

Kalen Coleman
Associate Corporate Counsel
Direct Dial: 317-219-8481
Email: kcoleman@misoenergy.org

November 24, 2025

VIA ELECTRONIC FILING

The Honorable Debbie-Anne A. Reese
Secretary
Federal Energy Regulatory Commission
888 First Street, N.E.
Washington, D.C. 20426

Re: Midcontinent Independent System Operator, Inc.
FERC Docket No. ER26-___-000

Dear Secretary Reese:

The Midcontinent Independent System Operator, Inc. ("MISO") hereby submits[1] a Generator Interconnection Agreement ("Interconnection Agreement") among Entergy Louisiana, LLC ("Interconnection Customer" with a Generating Facility), Entergy Louisiana, LLC ("Transmission Owner"), and MISO (collectively, the "Parties"). MISO has designated the Interconnection Agreement as Original Service Agreement No. 4596 under MISO's Tariff.[2] MISO has designated this project as Project No. E0014. Further, the Parties request waiver of the Commission's 60-day prior notice requirement and request an effective date of November 19, 2025, as discussed below.

I. OVERVIEW OF FILING

The body of the attached Interconnection Agreement conforms to the *pro forma* Generator Interconnection Agreement ("*pro forma* GIA"). As this Interconnection Agreement contains pending language, MISO asks that the Commission conditionally accept the Interconnection Agreement subject to any orders in Docket No. ER24-2046-000.

[1] *See* Section 205 of the Federal Power Act ("FPA"), 16 U.S.C. § 824d, and Section 35.12 of the Federal Energy Regulatory Commission's ("FERC" or "Commission") regulations, 18 C.F.R. § 35.12 (2025).

[2] MISO FERC Electric Tariff, Fifth Revised Vol. No. 1 ("Tariff").

II. DOCUMENTS SUBMITTED IN THIS FILING

The documents submitted with this filing include this transmittal letter and a public and non-public version of the Interconnection Agreement in accordance with the Parties' designation of the diagrams contained in this filing as Controlled Unclassified Information ("CUI") and Critical Energy Infrastructure Information ("CEII") under the Commission's rules. 18 C.F.R. § 388.113 (2025). Pursuant to the Commission's Notice Announcing New Combined Notice of Filings, issued on May 13, 2005, and the Commission's subsequent listing on its website, no form of notice is required under 18 C.F.R. § 35.11 (2025).[3] The Parties have designated diagrams of their interconnection in Exhibits A1-1 and A1-2 as CUI//CEII.

MISO hereby requests confidential treatment of the CEII contained in Exhibits A1-1 and A1-2 of the non-public version of the Interconnection Agreement enclosed pursuant to 18 C.F.R. § 388.113. The Parties assert that the information contained in Exhibits A1-1 and A1-2 qualify as CEII pursuant to 18 C.F.R. § 388.113(c)(1) for the following reasons: the diagrams attached to the Interconnection Agreement are system maps that provide specific detailed design information about existing critical transmission system infrastructure. The Exhibits are exempt from mandatory disclosure under the Freedom of Information Act, 5 U.S.C. § 552. Members of the public can obtain access to the Exhibits by complying with the Commission's procedures per 18 C.F.R. § 388.113.

The CEII information submitted with this filing will continue to be CEII while the facilities reported upon continue in operation. Due to the long-lived nature of utility facilities and their operation, this period is expected to be greater than the five-year period set out in 18 C.F.R § 388.113(e)(1). Upon any expiration of the CEII designation, the critical infrastructure information should therefore be treated as CEII and re-designated as such while the facilities remain in operation.

The non-public version of the Interconnection Agreement containing CEII information has been marked CUI//CEII – DO NOT RELEASE according to the Commission's instructions.

The documents submitted with this filing include this transmittal letter;

Tab A: Clean copy of the Non-Public Interconnection Agreement;

Tab A: Clean copy of the Public Interconnection Agreement

Tab B: Redlined copy of the Interconnection Agreement reflecting changes as compared to the *pro forma* GIA[4]; and

---

[3] *See* Documents and Filings, Notice Formats, available at http://www.ferc.gov/docs-filing/not-form.asp.

[4] Language currently pending before the Commission in MISO's Order Nos. 2023 and 2023-A compliance docket (ER24-2046-002) is highlighted in yellow. This language was accepted by the Commission on June 26, 2025, but is subject to further compliance. MISO has committed in that docket to make a filing to reconcile the language accepted in that docket with other effective language accepted by the Commission subsequent to MISO's Order Nos. 2023 and 2023-A compliance filing in Commission Docket No. ER24-2046-000 after the Commission issues

Tab C: Protective Agreement.

III. PROPOSED EFFECTIVE DATE

MISO respectfully requests that the Commission waive its sixty (60) day notice requirement[5] and make this Interconnection Agreement effective as of November 19, 2025. The Commission will ordinarily grant such waiver for a service agreement if the filing is submitted within 30 days of the service agreement's effective date.[6] The Parties have indicated their intention for and support of an effective date of November 19, 2025. MISO requests that the November 19, 2025 date be used to provide certainty to the Parties as to the status of the agreement. To the extent that the Commission determines that any requirements of 18 C.F.R. § 35 apply that have not been specifically addressed herein, the MISO respectfully requests waiver of such requirements.

IV. COMMUNICATIONS

All correspondence and communications in this matter should be addressed to:

Kalen Coleman*
Midcontinent Independent System Operator, Inc.
720 City Center Drive
Carmel, IN 46032
Telephone (317) 219-8481
kcoleman@misoenergy.org
agreements@misoenergy.org

*Persons authorized to receive service

V. NOTICE AND SERVICE

MISO notes that it has served a copy of this filing electronically, including attachments, upon all Tariff Customers under the Tariff, MISO Members, Member representatives of Transmission Owners and Non-Transmission Owners, as well as all state commissions within the Region. The filing has been posted electronically on MISO's website at https://www.misoenergy.org/legal/ferc-filings/ for other interested parties in this matter. In addition, MISO has served a copy of this filing electronically on all parties to this agreement.

---

a final order in Docket No. ER24-2046, including subdockets, accepting the pending language ("Reconciliation Filing"). MISO requests that the Commission treat the highlighted language in this agreement as subject to the outcome of ER24-2046-002. MISO commits to file any revisions to this highlighted language as necessary to comply with any Commission orders in this proceeding once the Commission accepts MISO's Reconciliation Filing.

5 18 C.F.R. § 35.3(a) (2025).

6 *See Prior Notice Filing Requirements Under Part II of the Federal Power Act*, 64 FERC ¶ 61,139 (1993). *See also International Transmission Company, et al.,* 139 FERC ¶ 61,022 (2012), P 14.

VI. CONCLUSION

For the foregoing reasons, MISO requests that the Commission accept this Interconnection Agreement for filing, grant the proposed effective date of November 19, 2025, and grant waiver of any Commission regulations not addressed herein that the Commission may deem applicable to this filing.

Respectfully submitted,

/s/ Kalen Coleman
Kalen Coleman

Attorney for the Midcontinent Independent System Operator, Inc.

Attachments

TAB A
PUBLIC

Document Accession #: 20251124-5333 Filed Date: 11/24/2025

SA 4596 ENTERGY LOUISIANA-ENTERGY LOUISIANA GIA VERSION 31.0.0

EFFECTIVE 11/19/2025

ORIGINAL SERVICE AGREEMENT NO. 4596

PUBLIC VERSION

Project E0014

GENERATOR INTERCONNECTION AGREEMENT

entered into by the

Midcontinent Independent System Operator, Inc.,

Entergy Louisiana, LLC

And

Entergy Louisiana, LLC

GENERATOR INTERCONNECTION AGREEMENT (GIA)

THIS GENERATOR INTERCONNECTION AGREEMENT ("GIA") is made and entered into this 19th day of November, 2025, by and between **Entergy Louisiana, LLC**, a limited liability company organized and existing under the laws of the State of Texas ("Interconnection Customer" with a Generating Facility), and **Entergy Louisiana, LLC**, a limited liability company organized and existing under the laws of the State of Texas ("Transmission Owner"), and the **Midcontinent Independent System Operator, Inc**., a non-profit, non-stock corporation organized and existing under the laws of the State of Delaware ("Transmission Provider"). Interconnection Customer, Transmission Owner and Transmission Provider each may be referred to as a "Party," or collectively as the "Parties."

RECITALS

WHEREAS, Transmission Provider has functional control of the operations of the Transmission System, as defined herein, and is responsible for providing Transmission Service and Interconnection Service on the transmission facilities under its control; and

WHEREAS, Interconnection Customer intends to own, lease and/or control and operate the Generating Facility identified as a Generating Facility in Appendix A to this GIA; and

WHEREAS, Transmission Owner owns or operates the Transmission System, whose operations are subject to the functional control of Transmission Provider, to which Interconnection Customer desires to connect the Generating Facility, and may therefore be required to construct certain Interconnection Facilities and Network Upgrades, as set forth in this GIA; and

WHEREAS, Interconnection Customer, Transmission Owner and Transmission Provider have agreed to enter into this GIA, and where applicable subject to Appendix H for a Provisional Generator Interconnection Agreement, for the purpose of interconnecting the Generating Facility with the Transmission System;

NOW, THEREFORE, in consideration of and subject to the mutual covenants contained herein, it is agreed:

ARTICLE 1. DEFINITIONS

When used in this GIA, terms with initial capitalization that are not defined in Article 1 shall have the meanings specified in the Article in which they are used. Those capitalized terms used in this GIA that are not otherwise defined in this GIA have the meaning set forth in the Tariff.

10 kW Inverter Process shall mean the procedure for evaluating an Interconnection Request for a certified inverter-based Small Generating Facility no larger than 10 kW that uses the screen set forth in Section 14.

Adverse System Impact shall mean the negative effects due to technical or operational limits on conductors or equipment being exceeded that may compromise the safety and reliability of the electric system.

Affected System(s) shall mean an electric transmission system or the electric system associated with an Existing Generating Facility or of a higher queued Generating Facility, which is an electric system other than the Transmission Provider's Transmission System that is affected by the Interconnection Request. An Affected System may or may not be subject to FERC jurisdiction.

Affected System Facilities Construction Agreement shall mean the agreement that is made between Transmission Provider and Interconnection Customer(s) to facilitate the construction of and to set forth cost responsibility for necessary Affected System Network Upgrades. This may or may not be a multi-party agreement, as determined by the Transmission Provider.

Affected System Interconnection Customer shall mean any entity that submits an interconnection request for a Generating Facility to a transmission system other than Transmission Provider's Transmission System that may cause the need for Affected System Network Upgrades on the Transmission Provider's Transmission System.

Affected System Network Upgrades shall mean the additions, modifications, and upgrades to Transmission Provider's Transmission System required to accommodate Affected System Interconnection Customer's proposed interconnection to a transmission System other than Transmission Provider's Transmission System.

Affected System Network Upgrade Facilities Study shall mean the facilities study performed by the Affected System Operator or Affected System Operator transmission owner to determine a list of facilities (including Affected System Interconnection Customer's interconnection facilities, transmission owner's interconnection facilities, system protection facilities, and if such upgrades have been determined, network upgrades, distribution upgrades, generator upgrades, common use upgrades, the cost of those facilities, and the time required to interconnect the generating facility(ies) with the Affected System Operator's transmission system.

Affected System Network Upgrade Facilities Study Report shall mean the report issued by the Affected System Operator following the completion of the Affected System Network Upgrade Facilities Study pursuant to Section 7.3.3 of the GIP.

Affected System Operator shall mean the entity that operates an Affected System.

Affected System Queue Position shall mean the queue position of an Affected System Interconnection Customer in Transmission Provider's interconnection queue relative to Transmission Provider's Interconnection Customers' Queue Position.

Affected System Study shall mean the evaluation of Affected System Interconnection Customers' proposed interconnection(s) to a transmission system other than the Transmission Provider's Transmission System that have an impact on Transmission Provider's Transmission System, as described in Section 8 of this GIP.

Affected System Study Agreement shall mean the agreement contained in Appendix 16 to the GIP that is made between Transmission Provider and host transmission provider, in absence of a JOA, JPA, or other agreement filed with the Commission, as noted in Section 8.

Affected System Study Report shall mean the report issued following completion of an Affected System Study.

Affiliate shall mean, with respect to a corporation, partnership or other entity, each such other corporation, partnership or other entity that directly or indirectly, through one or more intermediaries, controls, is controlled by, or is under common control with, such corporation, partnership or other entity.

Ancillary Services shall mean those services that are necessary to support the transmission of capacity and energy from resources to loads while maintaining reliable operation of the Transmission System in accordance with Good Utility Practice.

Applicable Laws and Regulations shall mean all duly promulgated applicable federal, state and local laws, regulations, rules, ordinances, codes, decrees, judgments, directives, or judicial or administrative orders, permits and other duly authorized actions of any Governmental Authority having jurisdiction over the Parties, their respective facilities and/or the respective services they provide.

Applicable Reliability Standards shall mean the requirements and guidelines of the Electric Reliability Organization and the Balancing Authority Area of the Transmission System to which the Generating Facility is directly interconnected.

Balancing Authority shall mean an entity that integrates resource plans ahead of time, maintains demand and resource balance within a Balancing Authority Area, and supports interconnection frequency in real time.

Balancing Authority Area shall mean the collection of generation, transmission, and

loads within the metered boundaries of the Balancing Authority. The Balancing Authority maintains load-resource balance within this area.

Base Case shall mean the base case power flow, short circuit, and stability databases used for the Interconnection Studies by Transmission Provider or Interconnection Customer.

Base Case Data shall mean base case power flow, short circuit and stability databases, including all underlying assumptions, and contingency lists. Such databases and lists, hereinafter referred to as Base Cases, shall include all (1) generation projects and (2) transmission projects, including merchant transmission projects that are proposed for the Transmission System for which a transmission expansion plan has been submitted and approved by the MISO Board.

Breach shall mean the failure of a Party to perform or observe any material term or condition of this GIA.

Breaching Party shall mean a Party that is in Breach of this GIA.

Business Day shall mean Monday through Friday, excluding Federal Holidays.

Calendar Day shall mean any day including Saturday, Sunday or a Federal Holiday. In the event that a period specified in this GIA is calculated in Calendar Days ends on a non-business day, such period shall be deemed to conclude on the following business day.

Cluster shall mean a group of one or more Interconnection Requests that are studied together for the purpose of conducting a Group Study.

Commercial Operation shall mean the status of a Generating Facility that has commenced generating electricity for sale, excluding electricity generated during Trial Operation.

Commercial Operation Date (COD) of a unit shall mean the date on which the Generating Facility commences Commercial Operation as agreed to by the Parties pursuant to Appendix E to this GIA.

Commitment Projection shall mean a projection of the number of MW expected to commit to the JTIQ Portfolio from ERAS and all DPP study clusters that already have passed DP1 as described in Section 9.4.2.e.ii of Rate Schedule 6 (MISO SPP-JOA).

Common Use Upgrade (CUU) shall mean an Interconnection Facility, Network Upgrade, System Protection Facility, or any other classified addition, alteration, or improvement on the Transmission System or the transmission system of an Affected System, not classified under Attachment FF as a Baseline Reliability Project, Market Efficiency Project, or Multi-Value Project, that is needed for the interconnection of multiple Interconnection Customers' Generating Facilities and which is the shared responsibility of such Interconnection Customers.

Confidential Information shall mean any proprietary or commercially or competitively

sensitive information, trade secret or information regarding a plan, specification, pattern, procedure, design, device, list, concept, policy or compilation relating to the present or planned business of a Party, or any other information as specified in Article 22, which is designated as confidential by the Party supplying the information, whether conveyed orally, electronically, in writing, through inspection, or otherwise, that is received by another Party.

Connection Facilities shall mean the Transmission Owner's Connection Facilities and the MHVDC Connection Customer's Connection Facilities, as defined in the MHCP.

Contingent Facilities shall mean those unbuilt Interconnection Facilities and Network Upgrades upon which the Interconnection Request's costs, timing and study findings are dependent, and if delayed or not built, could cause a need for restudies of the Interconnection Request or a reassessment of the Interconnection Facilities and/or Network Upgrades and/or costs and timing. Contingent Facilities may include facilities identified in MTEP that if delayed or not built could impact the timing of the Interconnection Request.

Customer Engagement Window shall mean the time period prior to the start of Definitive Planning Phase I set forth in Section 3.3.4 of the GIP.

Default shall mean the failure of a Breaching Party to cure its Breach in accordance with Article 17 of this GIA.

Definitive Planning Phase shall mean the Generator Interconnection Procedures process which leads to a Generator Interconnection Agreement. An Interconnection Customer enters the Definitive Planning Phase pursuant to GIP Section 7.2. The Definitive Planning Phase includes three distinct phases (Definitive Planning Phases I, II, and III) pursuant to Section 7 of the Generator Interconnection Procedures.

Definitive Planning Phase Queue Position shall mean the order of a valid Interconnection Request, relative to all other pending valid Interconnection Requests, in the Definitive Planning Phase. The Definitive Planning Phase Queue Position is established based upon the date Interconnection Customer satisfies all of the requirements of GIP Section 7.2 to enter the Definitive Planning Phase. All Interconnection Requests within the same Definitive Planning Phase cycle shall have equal priority (i.e. similarly queued).

Demonstrated Capability shall mean the continuous net real power output that the Generating Facility is required to demonstrate in compliance with Applicable Reliability Standards.

Dispute Resolution shall mean the procedure for resolution of a dispute between or among the Parties in which they will first attempt to resolve the dispute on an informal basis.

Distribution System shall mean the Transmission Owner's facilities and equipment, or the Distribution System of another party that is interconnected with the Transmission Owner's Transmission System, if any, connected to the Transmission System, over which facilities Transmission Service or Wholesale Distribution Service under the Tariff is available at the time

Interconnection Customer has requested interconnection of a Generating Facility for the purpose of either transmitting electric energy in interstate commerce or selling electric energy at wholesale in interstate commerce and which are used to transmit electricity to ultimate usage points such as homes and industries directly from nearby generators or from interchanges with higher voltage transmission networks which transport bulk power over longer distances. The voltage levels at which distribution systems operate differ among Local Balancing Authorities and other entities owning distribution facilities interconnected to the Transmission System.

Distribution Upgrades shall mean the additions, modifications, and upgrades to the Distribution System at or beyond the Point of Interconnection to facilitate interconnection of the Generating Facility and render the delivery service necessary to affect Interconnection Customer's wholesale sale of electricity in interstate commerce. Distribution Upgrades do not include Interconnection Facilities.

Effective Date shall mean the date on which this GIA becomes effective upon execution by the Parties subject to acceptance by the Commission, or if filed unexecuted, upon the date specified by the Commission.

Electric Reliability Organization shall mean the North American Electric Reliability Corporation or its successor organization.

Emergency Condition shall mean a condition or situation: (1) that in the reasonable judgment of the Party making the claim is imminently likely to endanger, or is contributing to the endangerment of, life, property, or public health and safety; or (2) that, in the case of either Transmission Provider or Transmission Owner, is imminently likely (as determined in a non-discriminatory manner) to cause a material adverse effect on the security of, or damage to the Transmission System, Transmission Owner's Interconnection Facilities or the electric systems of others to which the Transmission System is directly connected; or (3) that, in the case of Interconnection Customer, is imminently likely (as determined in a non-discriminatory manner) to cause a material adverse effect on the security of, or damage to, the Generating Facility or Interconnection Customer's Interconnection Facilities. System restoration and blackstart shall be considered Emergency Conditions; provided that Interconnection Customer is not obligated by this GIA to possess blackstart capability. Any condition or situation that results from lack of sufficient generating capacity to meet load requirements or that results solely from economic conditions shall not constitute an Emergency Condition, unless one of the enumerated conditions or situations identified in this definition also exists.

Energy Displacement Agreement shall mean an agreement between an Interconnection Customer with an Existing Generating Facility on the Transmission Provider's Transmission System and an Interconnection Customer with a proposed Generating Facility seeking to interconnect with Surplus Interconnection Service. The Energy Displacement Agreement specifies the term of operation, the Generating Facility Interconnection Service limit, and the mode of operation for energy production (common or singular operation).

Energy Resource Interconnection Service (ER Interconnection Service) shall mean an Interconnection Service that allows Interconnection Customer to connect its Generating

Facility to the Transmission System or Distribution System, as applicable, to be eligible to deliver the Generating Facility's electric output using the existing firm or non-firm capacity of the Transmission System on an as available basis. Energy Resource Interconnection Service does not convey transmission service.

Engineering & Procurement (E&P) Agreement shall mean an agreement that authorizes Transmission Owner to begin engineering and procurement of long lead-time items necessary for the establishment of the interconnection in order to advance the implementation of the Interconnection Request.

Environmental Law shall mean Applicable Laws or Regulations relating to pollution or protection of the environment or natural resources.

Existing Generating Facility shall mean a Generating Facility that is either under construction or is in service, and has an unsuspended interconnection agreement with its host transmission provider.

Expanded Scope Analysis shall mean the analysis described in Section 9.4.2.d.iv.a of Rate Schedule 6 (MISO-SPP JOA).

Expedited Resource Addition Study (ERAS) shall mean the temporary procedure for expediting interconnection projects identified for claimed resource adequacy and/or reliability needs.

Expedited Generator Interconnection Agreement (EGIA) shall mean the interconnection agreement for the Expedited Resource Addition Study established between the Transmission Provider and/or the Transmission Owner and the Interconnection Customer as set forth in Section 3.9 of this Attachment X. This agreement shall take the form of the Transmission Provider's *pro forma* Generator Interconnection Agreement modified for the Expedited Resource Addition Study. Unless otherwise provided in the GIP, all requirements applicable to the *pro forma* Generator Interconnection Agreement shall apply to the Expedited Generator Interconnection Agreement.

Facilities Construction Agreement (FCA) shall mean the form of facilities construction agreement, set forth in Appendix 8 to these Generator Interconnection Procedures. The FCA shall be used when an Interconnection Customer or an Affected System Interconnection Customer causes the need for the construction of Network Upgrades or System Protection Facilities on the transmission system of the Transmission Provider.

Fast Track Process shall mean the procedure for evaluating an Interconnection Request for a certified Small Generating Facility no larger than five MW that includes the screen set forth in Section 14, customer options meeting, and optional supplemental review.

Federal Holiday shall mean a Federal Reserve Bank holiday for a Party that has its principal place of business in the United States and a Canadian Federal or Provincial banking holiday for a Party that has its principal place of business located in Canada.

Federal Power Act shall mean the Federal Power Act, as amended, 16 U.S.C. §§ 791a *et seq*.

FERC shall mean the Federal Energy Regulatory Commission, also known as Commission, or its successor.

Final System Impact Study shall mean the Interconnection System Impact Study performed during Definitive Planning Phase III.

Force Majeure shall mean any act of God, labor disturbance, act of the public enemy, war, insurrection, riot, fire, storm or flood, explosion, breakage or accident to machinery or equipment, any order, regulation or restriction imposed by governmental, military or lawfully established civilian authorities, or any other cause beyond a Party's control. A Force Majeure event does not include an act of negligence or intentional wrongdoing by the Party claiming Force Majeure.

Generating Facility shall mean Interconnection Customer's device(s) for the production and/or storage for later injection of electricity identified in the Interconnection Request, but shall not include the Interconnection Customer's Interconnection Facilities. A Generating Facility consists of one or more generating unit(s) and/or storage device(s) which usually can operate independently and be brought online or taken offline individually.

Generating Facility Capacity shall mean the net capacity of the Generating Facility and the aggregate net capacity of the Generating Facility where it includes more than one device for the production and/or storage for later injection of electricity.

Generating Facility Modification shall mean modification to an Existing Generating Facility, including comparable replacement of only a portion of its equipment at the Existing Generating Facility.

Generating Facility Replacement shall mean replacement of one or more generating units and/or storage devices at the Existing Generating Facility with one or more new generating units or storage devices at the same electrical Point of Interconnection as the generating units and/or storage devices that is/are being decommissioned and electrically disconnected.

Generator Interconnection Agreement (GIA) shall mean the form of interconnection agreement, set forth herein.

Generator Interconnection Procedures (GIP) shall mean the interconnection procedures set forth in Attachment X of the Tariff.

Generator Upgrades shall mean the additions, modifications, and upgrades to the electric system of an Existing Generating Facility or of a higher queued Generating Facility at or beyond the Point of Interconnection to facilitate interconnection of the Generating Facility and render the Transmission Service necessary to affect Interconnection Customer's wholesale sale

of electricity in interstate commerce.

Good Utility Practice shall mean any of the practices, methods and acts engaged in or approved by a significant portion of the electric industry during the relevant time period, or any of the practices, methods and acts which, in the exercise of reasonable judgment in light of the facts known at the time the decision was made, could have been expected to accomplish the desired result at a reasonable cost consistent with good business practices, reliability, safety and expedition. Good Utility Practice is not intended to be limited to the optimum practice, method, or act to the exclusion of all others, but rather to be acceptable practices, methods, or acts generally accepted in the region.

Governmental Authority shall mean any federal, state, local or other governmental regulatory or administrative agency, court, commission, department, board, or other governmental subdivision, legislature, rulemaking board, tribunal, or other governmental authority having jurisdiction over the Parties, their respective facilities, or the respective services they provide, and exercising or entitled to exercise any administrative, executive, police, or taxing authority or power; provided, however, that such term does not include Interconnection Customer, Transmission Provider, Transmission Owner, or any Affiliate thereof.

Group Restudy shall mean a restudy of a Group Study conducted pursuant to Section 7.5 of the GIP

Group Study(ies) shall mean the evaluation of one or more Interconnection Requests within a Cluster as described in Section 7 of the GIP. Group Studies are divided into phases as described in section 7.3 of the GIP.

Hazardous Substances shall mean any chemicals, materials or substances defined as or included in the definition of "hazardous substances," "hazardous wastes," "hazardous materials," "hazardous constituents," "restricted hazardous materials," "extremely hazardous substances," "toxic substances," "radioactive substances," "contaminants," "pollutants," "toxic pollutants" or words of similar meaning and regulatory effect under any applicable Environmental Law, or any other chemical, material or substance, exposure to which is prohibited, limited or regulated by any applicable Environmental Law.

HVDC Facilities shall mean the high voltage direct current transmission facilities, including associated alternating current facilities, if any, that are subject to Section 27A of the Tariff and that are specifically identified in (i) any Agency Agreement pertaining to such facilities between Transmission Provider and Transmission Owner that owns or operates such facilities, or (ii) in any other arrangement that permits or will permit Transmission Provider to provide HVDC Service over such facilities as set forth in Section 27A of the Tariff.

HVDC Service shall mean Firm and Non-Firm Point-To-Point Transmission Service provided by Transmission Provider on HVDC Facilities pursuant to Section 27A of the Tariff.

Initial Synchronization Date shall mean the date upon which the Generating Facility is initially synchronized and upon which Trial Operation begins.

Injection Rights shall mean the Transmission Provider's pre-certification of the Transmission System's capability to receive capacity and energy from the MHVDC Transmission Line at the requested Point of Connection, and in the specified MW quantity, without degrading the reliability of the Transmission System, as described in Section 16 of the GIP and Section 3.2.3 of the MHCP.

In-Service Date (ISD) shall mean the date upon which Interconnection Customer reasonably expects it will be ready to begin use of the Transmission Owner's Interconnection Facilities to obtain backfeed power.

Interconnection Customer shall mean any entity, including Transmission Provider, Transmission Owner or any of the Affiliates or subsidiaries of either, that proposes to interconnect its Generating Facility with the Transmission System.

Interconnection Customer Decision Point I shall mean the time period beginning when the Interconnection Customer is provided the Preliminary System Impact Study results including cost estimates for upgrades and concludes after fifteen (15) Business Days.

Interconnection Customer Decision Point II shall mean the time period beginning when the Interconnection Customer is provided the Revised System Impact Study results including cost estimates for upgrades and concludes after fifteen (15) Business Days.

Interconnection Customer's Interconnection Facilities (ICIF) shall mean all facilities and equipment, as identified in Appendix A of this GIA, that are located between the Generating Facility and the Point of Change of Ownership, including any modification, addition, or upgrades to such facilities and equipment necessary to physically and electrically interconnect the Generating Facility to the Transmission System or Distribution System, as applicable. Interconnection Customer's Interconnection Facilities are sole use facilities.

Interconnection Facilities shall mean the Transmission Owner's Interconnection Facilities and the Interconnection Customer's Interconnection Facilities. Collectively, Interconnection Facilities include all facilities and equipment between the Generating Facility and the Point of Interconnection, including any modification, additions or upgrades that are necessary to physically and electrically interconnect the Generating Facility to the Transmission System. Interconnection Facilities shall not include Distribution Upgrades, Generator Upgrades, Stand Alone Network Upgrades or Network Upgrades.

Interconnection Facilities Study(ies) shall mean a study conducted by Transmission Owner, or its agent, for Interconnection Customer(s) to determine a list of facilities (including Interconnection Customer's Interconnection Facilities or Affected System Interconnection Customer's interconnection facilities, Transmission Owner's Interconnection Facilities, System Protection Facilities, and if such upgrades have been determined, Network Upgrades, Distribution Upgrades, Generator Upgrades, Common Use Upgrades, and Affected System Network Upgrades, as identified in the Interconnection System Impact Study), the cost of those facilities, and the time required to interconnect the Generating Facility(ies) with the

Transmission System.

Interconnection Facilities Study Agreement shall mean the form of agreement contained in Appendix 4 of the Generator Interconnection Procedures for conducting the Interconnection Facilities Study.

Interconnection Request shall mean (1) an Interconnection Customer's request, in the form of Appendix 1 to the Generator Interconnection Procedures, to interconnect a new Generating Facility, or a request for the Expedited Resource Addition Study for new generation capacity, or to increase the capacity of, or make a Material Modification to the operating characteristics of, an Existing Generating Facility that is interconnected with the Transmission System, or to interconnect an Existing Generating Facility that is external to the Transmission System, or to change Energy Resource Interconnection Service to Network Resource Interconnection Service for an Existing Generating Facility; or (2) an MHVDC Connection Customer's request, in the form of Appendix 1 to the Generator Interconnection Procedures, to obtain Injection Rights..

Interconnection Service shall mean the service provided by Transmission Provider associated with interconnecting the Generating Facility to the Transmission System, or external host transmission provider if applicable, and enabling it to receive electric energy and capacity from the Generating Facility at the Point of Interconnection pursuant to the terms of this Generator Interconnection Agreement or Point of Delivery as set forth in the Service Agreement for Network Resource Interconnection Service for an External Generating Facility and, if applicable, the Tariff.

Interconnection Study (or Study) shall mean any of the studies described in the Generator Interconnection Procedures.

Interconnection Study Agreement shall mean the form of agreement contained in Attachment B to Appendix 1 of the Generator Interconnection procedures for conducting all studies required by the Generator Interconnection Procedures.

Interconnection System Impact Study shall mean an engineering study that evaluates the impact of the proposed interconnection on the safety and reliability of Transmission System and, if applicable, an Affected System. The study shall identify and detail the system impacts that would result if the Generating Facility were interconnected without project modifications or system modifications, or to study potential impacts, including but not limited to those identified in the Scoping Meeting as described in the Generator Interconnection Procedures.

Interconnection Study Agreement shall mean the forms of agreement contained in Attachment B to Appendix 1 of the Generator Interconnection Procedures for conducting all studies required by the Generator Interconnection Procedures.

IRS shall mean the Internal Revenue Service.

Joint Operating Agreement ("JOA") shall mean an agreement between adjacent

balancing authorities or transmission providers for the coordination of operations.

Joint Operating Agreement between the Midcontinent Independent System Operator, Inc. and Southwest Power Pool, Inc. (MISO-SPP JOA) shall mean Rate Schedule 6 to the MISO Tariff.

Joint Planning Agreement ("JPA") shall mean an agreement between adjacent balancing authorities or transmission providers for the coordination of planning.

Joint Targeted Interconnection Queue (JTIQ) shall refer to the study and processes described in Section 9.4.2 of Rate Schedule 6 (MISO-SPP JOA).

Joint Targeted Interconnection Queue Study ("JTIQ Study") shall mean a transmission planning study conducted jointly by SPP and MISO to facilitate the interconnection of new generator capacity in both Parties' regions.

JTIQ Commitment Group Member shall mean any JTIQ Commitment Group Member included in a Commitment Group consistent with Section 9.4 of Rate Schedule 6 (MISO-SPP JOA).

JTIQ Commitment Group or Commitment Group shall mean a group of JTIQ Commitment Group Members that have executed a JTIQ Generator Interconnection Agreement within the twelve (12) month period ending April 30th of each year. The Commitment Group shall also include JTIQ Commitment Group Members for which a JTIQ Generator Interconnection Agreement has been filed unexecuted by SPP or the Transmission Provider and the Commission has accepted the agreement within the twelve (12) month period ending April 30th of each year.

JTIQ Generator Charge shall mean the charge to JTIQ Commitment Group Members to recover the JTIQ Commitment Group Member's share of the JTIQ Monthly Revenue Requirement for each of the JTIQ Upgrades in the JTIQ Portfolio in the Transmission Provider's Region.

JTIQ Participation Group shall mean the group of Interconnection Requests that shall consist of all interconnection customers included in the JTIQ Screening Groups whose interconnection request meets the distribution factor and impact criteria specified in Section 9.4.2(d)((ii) of Rate Schedule 6 (MISO-SPP JOA).

JTIQ Portfolio shall mean a group of JTIQ Upgrades identified pursuant to Section 9.4 of Rate Schedule 6 (MISO-SPP JOA).

JTIQ Screening Group shall mean a group of MISO Interconnection Customers and SPP interconnection customers whose Interconnection Requests will be screened for inclusion in a JTIQ Participation Group. The JTIQ Screening Group shall consist of all interconnection customers who have submitted interconnection requests into a MISO ERAS, SPP ERAS, DPP study cluster, or SPP DISIS study cluster that: (1) has a study commencement or kick off date

that is after the date that the Parties' respective Boards of Directors have approved a JTIQ Portfolio; and (2) has not commenced DPP Phase I, a MISO ERAS, the SPP ERAS or DISIS Phase One studies pursuant to each party's OATT as of the date that the Parties have declared the JTIQ Portfolio fully subscribed.

JTIQ Service Agreements shall mean the JTIQ Commitment Agreement attached to the MISO GIA as Appendix 17 and the SPP's *pro forma* agreement(s) that obligate interconnection customers to provide security for and pay the JTIQ Generator Charge for JTIQ Network Upgrades included in the applicable JTIQ Portfolio.

JTIQ Upgrade shall mean a Network Upgrade included in a JTIQ portfolio pursuant to Section 9.4 of Rate Schedule 6 (MISO-SPP JOA)**.**

Local Balancing Authority shall mean an operational entity or a Joint Registration Organization which is (i) responsible for compliance with the subset of Electric Reliability Organization Balancing Authority Reliability Standards defined in the Balancing Authority Agreement for their local area within the MISO Balancing Authority Area, (ii) a Party to Balancing Authority Agreement, excluding MISO, and (iii) provided in the Balancing Authority Agreement.

Local Resource Zone (LRZ) shall mean a geographic area within the Transmission Provider Region that is prescribed by the Transmission Provider, based upon the criteria in Section 68A.3, to address congestion that limits Planning Resource deliverability.

Loss shall mean any and all damages, losses, claims, including claims and actions relating to injury to or death of any person or damage to property, demand, suits, recoveries, costs and expenses, court costs, attorney fees, and all other obligations by or to third parties, arising out of or resulting from the other Party's performance, or non-performance of its obligations under this GIA on behalf of the indemnifying Party, except in cases of gross negligence or intentional wrongdoing, by the indemnified party.

Material Modification shall mean: (1) modification to an Interconnection Request in the queue, that has a material adverse impact on the cost or timing of any other Interconnection Request with an equal or later queue priority date; or Qualified Change.

Metering Equipment shall mean all metering equipment installed or to be installed at the Generating Facility, Interconnection Customer's Interconnection Facilities, and/or Transmission Owner's Interconnection Facilities pursuant to this GIA at the metering points, including but not limited to instrument transformers, MWh-meters, data acquisition equipment, transducers, remote terminal unit, communications equipment, phone lines, and fiber optics.

Monitoring and Consent Agreement shall mean an agreement that defines the terms and conditions applicable to a Generating Facility acquiring Surplus Interconnection Service. The Monitoring and Consent Agreement will list the roles and responsibilities of an Interconnection Customer seeking to interconnect with Surplus Interconnection Service and Transmission Owner to maintain the total output of the Generating Facility inside the parameters

delineated in the GIA.

Multi-Party Facilities Construction Agreement (MPFCA) shall mean the form of facilities construction agreement, set forth in Appendix 9 to these Generator Interconnection Procedures. The MPFCA shall be used when multiple Interconnection Requests or interconnection requests from Affected System Interconnection Customers cause the need for the construction of Common Use Upgrades on the Transmission System and share cost responsibility for such Common Use Upgrades.

Network Customer shall have that meaning as provided in the Tariff.

Network Resource shall mean any designated generating resource owned, purchased, or leased by a Network Customer under the Tariff. Network Resources do not include any resource, or any portion thereof, that is committed for sale to third parties or otherwise cannot be called upon to meet the Network Customer's Network Load on a non-interruptible basis.

Network Resource Interconnection Service (NR Interconnection Service) shall mean an Interconnection Service that allows Interconnection Customer to integrate its Generating Facility with the Transmission System in the same manner as for any Generating Facility being designated as a Network Resource. Network Resource Interconnection Service does not convey transmission service. Network Resource Interconnection Service shall include any network resource interconnection service established under an agreement with, or the tariff of, a Transmission Owner prior to integration into MISO, that is determined to be deliverable through the integration deliverability study process.

Network Upgrades shall mean the additions, modifications, and upgrades to the Transmission System required at or beyond the point at which the Interconnection Facilities connect to the Transmission System or Distribution System, as applicable, to accommodate the interconnection of the Generating Facility(ies) to the Transmission System. Network Upgrades shall not include any HVDC Facility Upgrades.

Notice of Dispute shall mean a written notice of a dispute or claim that arises out of or in connection with this GIA or its performance.

Optional Interconnection Study shall mean a sensitivity analysis based on assumptions specified by Interconnection Customer in the Optional Interconnection Study Agreement.

Optional Interconnection Study Agreement shall mean the form of agreement contained in Appendix 5 of the Generator Interconnection Procedures for conducting the Optional Interconnection Study.

Outage Transfer Distribution Factor (OTDF) Outage Transfer Distribution Factor, as defined by the Electric Reliability Organization.

Party or Parties shall mean Transmission Provider, Transmission Owner, Interconnection Customer, or any combination of the above.

Permissible Technological Advancement shall mean advancements to turbines, inverters, plant supervisory controls, excitation systems, or other technological advancements submitted to the Transmission Provider prior to the issuance of this draft Generator Interconnection Agreement for such project provided that such advancements does not: (1) degrade the electrical characteristics of the generating equipment; (2) does not cause any material adverse impact on the Transmission System with regard to short circuit capability limits, steady-state thermal and voltage limits, or dynamic system stability and response; (3) does not increase the installed capacity of the Generating Facility; or (4) change the fuel source of the proposed Generating Facility.

Point of Change of Ownership (PCO) shall mean the point, as set forth in Appendix A to the Generator Interconnection Agreement, where the Interconnection Customer's Interconnection Facilities connect to the Transmission Owner's Interconnection Facilities.

Point of Interconnection (POI) shall mean the point, as set forth in Appendix A of the GIA, where the Interconnection Facilities connect to the Transmission System.

Potential MW Total shall mean a projection of the number of MW that may commit to the JTIQ Portfolio from all ERAS and study clusters to date, including the current study cluster(s).

Preliminary System Impact Study shall mean the Interconnection System Impact Study performed during Definitive Planning Phase I.

Pre-Queue Phase shall mean Interconnection Customer outreach and education effort undertaken prior to the submission of the Interconnection Request.

Proportional Impact Method shall mean a technical analysis conducted by Transmission Provider to determine the degree to which each Generating Facility in the Group Study contributes to the need for a specific Network Upgrade.

Provisional Generator Interconnection Agreement shall mean the interconnection agreement for Provisional Interconnection Service established between the Transmission Provider and/or the Transmission Owner and the Interconnection Customer as set forth in Section 7.9 of this Attachment X. This agreement shall take the form of the Generator Interconnection Agreement modified for provisional purposes. Unless otherwise provided in the GIP, all requirements applicable to the Generator Interconnection Agreement shall apply to the Provisional Generator Interconnection Agreement.

Provisional Interconnection Service shall mean Interconnection Service provided by the Transmission Provider associated with interconnecting the Interconnection Customer's Generating Facility to the Transmission Provider's Transmission System and enabling that Transmission System to receive electric energy and capacity from the Generating Facility at the Point of Interconnection, pursuant to the terms of the Provisional Generator Interconnection Agreement and the Tariff.

Provisional Interconnection Study shall mean an engineering study, performed at Interconnection Customer's request, as a condition to entering into a Provisional Generator Interconnection Agreement, that evaluates the impact of the proposed interconnection on the safety and reliability of the Transmission System and, if applicable, any Affected System. The study shall identify and detail the impacts on the Transmission System and, if applicable, an Affected System, from stability, short circuit, and voltage issues that would result if the Generating Facility were interconnected without project modifications or system modifications.

Qualified Change shall mean a planned modification to an Existing Generating Facility that is undergoing evaluation for a Generating Facility Modification or Generating Facility Replacement, and has a material adverse impact on the Transmission System with respect to: i) steady-state thermal or voltage limits, ii) dynamic system stability and response, or iii) short-circuit capability limit; compared to the impacts of the Existing Generating Facility prior to the modification or replacement.

Queue Position shall mean the order of a valid Interconnection Request, relative to all other pending valid Interconnection Requests pursuant to Section 4.1 of the GIP.

Reasonable Efforts shall mean, with respect to an action required to be attempted or taken by a Party under this Generator Interconnection Agreement, efforts that are timely and consistent with Good Utility Practice and are otherwise substantially equivalent to those a Party would use to protect its own interests.

Relevant Electric Retail Regulatory Authority (RERRA) shall mean an entity that has jurisdiction over and establishes prices and/or policies for providers of retail electric service to end-customers, such as the city council for a municipal utility, the governing board of a cooperative utility, the state public utility commission or any such entity.

Reliability Assessment Study shall mean an engineering study that evaluates the impact of a proposed Generating Facility Replacement on the reliability of Transmission System during the time period between the date that the Existing Generating Facility ceases commercial operations and the Commercial Operation Date of the Replacement Generating Facility.

Replacement Generating Facility shall mean a Generating Facility that replaces an Existing Generating Facility, or a portion thereof, at the same electrical Point of Interconnection pursuant to Section 3.7 of this Attachment X.

Replacement Impact Study shall mean an engineering study that evaluates the impact of a proposed Generating Facility Replacement on the reliability of the Transmission System.

Revised System Impact Study shall mean the Interconnection System Impact Study performed during Definitive Planning Phase II.

Scoping Meeting shall mean the meeting between representatives of Interconnection Customer, Transmission Owner, Affected System Operator(s) and Transmission Provider

conducted for the purpose of discussing the proposed Interconnection Request and any alternative interconnection options, exchanging information including any transmission data and earlier study evaluations that would be reasonably expected to impact such interconnection options, refining information and models provided by Interconnection Customer(s), discussing the Group Study materials posted to OASIS pursuant to Section 3.4 of the GIP, and analyzing such information.

Shared Interconnection Request shall mean (1) multiple Interconnection Customer's request, in the form of Appendix 1 to the Generator Interconnection Procedures, to interconnect new Generating Facilities, or to increase the capacity of, or make a Material Modification to the operating characteristics of, Existing Generating Facilities that are interconnected with the Transmission System, or to interconnect Existing Generating Facilities that are external to the Transmission System, or to change Energy Resource Interconnection Service to Network Resource Interconnection Service for Existing Generating Facilities; or (2) multiple MHVDC Connection Customer's request, in the form of Appendix 1 to the Generator Interconnection Procedures, to obtain Injection Rights.

Shared Network Upgrade shall mean a Network Upgrade or Common Use Upgrade that is funded by an Interconnection Customer(s), including when the Transmission Owner elects to fund the capital cost of such a Network Upgrade or Common Use Upgrade under Section 11.3 of the GIA, and also benefits other Interconnection Customer(s) that are later identified as beneficiaries.

Site Control shall mean a documented right for one or more parcels of land for the purpose of constructing a Generating Facility, Interconnection Customer's Interconnection Facilities, and, if applicable (*i.e.*, when the Interconnection Customer is providing the site for such facilities), the Transmission Owner's Interconnection Facilities and Network Upgrades at the POI that the Interconnection Customer will develop. Such documented right shall be one of the following: (1) ownership of a site; (2) a leasehold interest in a site; or (3) an option to purchase or acquire a leasehold interest in a site; or (4) any other contractual or legal right to possess or occupy a site. Transmission Provider will maintain acreage requirements for each Generating Facility type on its OASIS or public website.

Small Generating Facility shall mean a Generating Facility that has an aggregate net Generating Facility Capacity of no more than five MW and meets the requirements of Section 14 and Appendix 3 of the GIP.

Southwest Power Pool (SPP) shall refer to the Southwest Power Pool, Inc. the Regional Transmission Organization that is the counterparty to Rate Schedule 6 (MISO-SPP JOA).

Special Protection System (SPS) shall mean an automatic protection system or remedial action scheme designed to detect abnormal or predetermined system conditions, and take corrective actions other than and/or in addition to the isolation of faulted components, to maintain system reliability. Such action may include changes in demand (MW and MVar), energy (MWh and MVarh), or system configuration to maintain system stability, acceptable voltage, or power flows. An SPS does not include (a) underfrequency or undervoltage load

shedding, (b) fault conditions that must be isolated, (c) out-of-step relaying not designed as an integral part of an SPS, or (d) Transmission Control Devices.

Stand Alone Network Upgrades shall mean Network Upgrades, that are not part of an Affected System or a JTIQ Upgrade, that Interconnection Customer may construct without affecting day-to-day operations of the Transmission System during their construction. Transmission Provider, Transmission Owner and Interconnection Customer must agree as to what constitutes Stand Alone Network Upgrades and identify them in Appendix A to this GIA. If the Transmission Provider or Transmission Owner and Interconnection Customer disagree about whether a particular Network Upgrade is a Stand Alone Network Upgrade, the Transmission Provider or Transmission Owner that disagrees with the Interconnection Customer must provide the Interconnection Customer a written technical explanation outlining why the Transmission Provider or Transmission Owner does not consider the Network Upgrade to be a Stand Alone Network Upgrade within fifteen (15) Business Days of its determination.

Substation Network Upgrades shall mean Network Upgrades that are required at or near the Point of Interconnection and are identified in the first portion of the Interconnection Facilities Study as described in GIP Section 7.3.2.5.

Supplemental Affected System Analysis shall mean **t**he affected systems analysis described in Section 7.3.2.3.1 of this GIP and Section 9.4.2.e.iii.a.i of the Rate Schedule 6 (MISO-SPP JOA) to determine if Supplemental Affected System Upgrades are required for one or more JTIQ Participation Group member(s).

Supplemental Affected System Upgrade shall mean a Network Upgrade in addition to those required to address the impact of interconnection requests in the current study cluster as described in Section 9.4.2.e.iii.a.i of Rate Schedule 6 (MISO-SPP-JOA).

Surplus Interconnection Service shall mean any Interconnection Service that is derived from the unneeded portion of Interconnection Service established in a GIA or in agreement with, or under the tariff of, a Transmission Owner prior to integration into MISO, such that if Surplus Interconnection Service is utilized the total amount of Interconnection Service at the Point of Interconnection would remain the same.

System Planning and Analysis Phase shall mean the phase of the Generator Interconnection Procedure process, prior to January 4, 2017, which consisted of an Interconnection System Impact Study for those Interconnection Requests that were studied in this phase.

System Protection Facilities shall mean the equipment, including necessary protection signal communications equipment, required to protect (1) the Transmission System or other delivery systems or other generating systems from faults or other electrical disturbances occurring at the Generating Facility and (2) the Generating Facility from faults or other electrical system disturbances occurring on the Transmission System or on other delivery systems or other generating systems to which the Transmission System is directly connected.

Target MW Value shall mean the projected new generation interconnection MW enabled by the JTIQ Portfolio. The Target MW Value for each JTIQ Portfolio shall be identified in Section 9.4 and related subsections of Rate Schedule 6.

Tariff shall mean the Transmission Provider's Tariff through which open access transmission service and Interconnection Service are offered, as filed with the Commission, and as amended or supplemented from time to time, or any successor tariff.

Threshold Charge shall mean the charge calculated using an estimate of plant in service value for the JTIQ Portfolio, excluding amounts funded under the GRIP Program, as described in Section 9.4.2 of Rate Schedule 6 (MISO-SPP JOA).

Transmission Control Devices shall mean a generally accepted transmission device that is planned and designed to provide dynamic control of electric system quantities, and are usually employed as solutions to specific system performance issues. Examples of such devices include fast valving, high response exciters, high voltage DC links, active or real power flow control and reactive compensation devices using power electronics (*e.g.*, unified power flow controllers), static var compensators, thyristor controlled series capacitors, braking resistors, and in some cases mechanically-switched capacitors and reactors. In general, such systems are not considered to be Special Protection Systems.

Transmission Owner shall mean that Transmission Owner as defined in the Tariff, which includes an entity that owns, leases or otherwise possesses an interest in the portion of the Transmission System at which Interconnection Customer proposes to interconnect or otherwise integrate the operation of the Generating Facility. Transmission Owner should be read to include any Independent Transmission Company that manages the transmission facilities of Transmission Owner and shall include, as applicable, the owner and/or operator of distribution facilities interconnected to the Transmission System, over which facilities transmission service or Wholesale Distribution Service under the Tariff is available at the time Interconnection Customer requests Interconnection Service and to which Interconnection Customer has requested interconnection of a Generating Facility for the purpose of either transmitting electric energy in interstate commerce or selling electric energy at wholesale in interstate commerce.

Transmission Provider shall mean the Midcontinent Independent System Operator, Inc. ("MISO"), the Regional Transmission Organization that controls or operates the transmission facilities of its transmission-owning members used for the transmission of electricity in interstate commerce and provides transmission service under the Tariff.

Transmission Owner's Interconnection Facilities (TOIF) shall mean all facilities and equipment owned by Transmission Owner from the Point of Change of Ownership to the Point of Interconnection as identified in Appendix A to this GIA, including any modifications, additions or upgrades to such facilities and equipment. Transmission Owner's Interconnection Facilities are sole use facilities and shall not include Distribution Upgrades, Generator Upgrades, Stand Alone Network Upgrades or Network Upgrades.

Transmission System shall mean the facilities owned by Transmission Owner and

controlled or operated by Transmission Provider or Transmission Owner that are used to provide Transmission Service (including HVDC Service) or Wholesale Distribution Service under the Tariff.

Trial Operation shall mean the period during which Interconnection Customer is engaged in on-site test operations and commissioning of the Generating Facility prior to Commercial Operation.

User-Defined Model shall mean any set of programming code created by equipment manufacturers or developers that captures the latest features of controllers that are mainly software-based and represent the entities' control strategy but does not necessarily correspond to any particular generic library model, as contained in Attachment A to Appendix 1 of the GIP.

Variable Energy Resource shall mean a device for the production of electricity that is characterized by an energy source that: (1) is renewable; (2) cannot be stored by the facility owner or operator; and (3) has variability that is beyond the control of the facility owner or operator.

Wholesale Distribution Service shall have that meaning as provided in the Tariff. Wherever the term "transmission delivery service" is used, Wholesale Distribution Service shall also be implied.

ARTICLE 2. EFFECTIVE DATE, TERM AND TERMINATION

2.1 Effective Date. This GIA shall become effective upon execution by the Parties subject to acceptance by FERC (if applicable), or if filed unexecuted, upon the date specified by FERC. Transmission Provider shall promptly file this GIA with FERC upon execution in accordance with Article 3.1, if required.

2.2 Term of Agreement. Subject to the provisions of Article 2.3, this GIA shall remain in effect for a period of thirty (30) years from the Effective Date and shall be automatically renewed for each successive one-year period thereafter on the anniversary of the Effective Date.

2.3 Termination Procedures. This GIA may be terminated as follows:

2.3.1 Written Notice. This GIA may be terminated by Interconnection Customer after giving Transmission Provider and Transmission Owner ninety (90) Calendar Days advance written notice. This GIA shall be terminated by Transmission Provider if the Generating Facility or a portion of the Generating Facility fails to achieve Commercial Operation by the Commercial Operation Date established in accordance with Section 4.4.4 of Attachment X, including any extension provided thereunder, or has ceased Commercial Operation for three (3) consecutive years, beginning with the last date of Commercial Operation for the Generating Facility, after giving Interconnection Customer ninety (90) Calendar Days advance written notice. Where only a portion of the Generating Facility fails to achieve Commercial Operation by the Commercial Operation Date established in accordance with Section 4.4.4 of Attachment X, including any extension provided thereunder, Transmission Provider shall only terminate that portion of the GIA. Notwithstanding the foregoing, in the limited circumstance that the Interconnection Request is served by a contingent Network Upgrade with an in-service date that is farther out than the Commercial Operation Date permitted under Section 4.4.4 of Attachment X, Transmission Provider shall only terminate this GIA for failure to achieve Commercial Operation by that later in-service date of the contingent Network Upgrade. The Generating Facility will not be deemed to have ceased Commercial Operation for purposes of this Article 2.3.1 if Interconnection Customer can document that it has taken other significant steps to maintain or restore operational readiness of the Generating Facility for the purpose of returning the Generating Facility to Commercial Operation as soon as possible.

2.3.1.1 Surplus Interconnection Service. Where this GIA provides for Surplus Interconnection Service and the Energy Displacement Agreement or the Monitoring and Consent Agreement required for Surplus Interconnection Service are no longer in effect, Interconnection Customer shall immediately cease Commercial Operation of the Generating Facility and this GIA shall be deemed terminated. In the event that the Existing Generating Facility retires and/or permanently ceases commercial

operation, the Surplus Interconnection Service provided under this GIA shall terminate except as provided in Section 3.3.1.3 of the GIP.

2.3.2 Default. Any Party may terminate this GIA in accordance with Article 17.

2.3.3 Notwithstanding Articles 2.3.1 and 2.3.2, no termination shall become effective until the Parties have complied with all Applicable Laws and Regulations applicable to such termination, including the filing with FERC of a notice of termination of this GIA, if required, which notice has been accepted for filing by FERC.

For EGIAs, no termination shall become effective until Interconnection Customer has provided all security as required by Section 2.4.

2.4 Termination Costs. If a Party elects to terminate this GIA pursuant to Article 2.3 above, each Party shall pay all costs incurred for which that Party is responsible (including any cancellation costs relating to orders or contracts for Interconnection Facilities, applicable upgrades, and related equipment) or charges assessed by the other Parties, as of the date of the other Parties' receipt of such notice of termination, under this GIA. In the event that this GIA is terminated by Interconnection Customer, Interconnection Customer is responsible for all financial impact that is caused as a result of this termination or the termination of Interconnection Customer's FCA(s) or MPFCA(s), such financial impact being determined through the financial impact analysis performed in accordance with Section 7.8 of Attachment X. In the event of termination by a Party, the Parties shall use commercially Reasonable Efforts to mitigate the costs, damages and charges arising as a consequence of termination. Upon termination of this GIA, unless otherwise ordered or approved by FERC:

In the event that this EGIA is terminated by Interconnection Customer that had an Interconnection Request studied in ERAS, Interconnection Customer is responsible for the full cost of all Network Upgrades identified in this EGIA as well as any Network Upgrades identified during the ERAS process that are to be memorialized in an agreement other that this EGIA, including any applicable FCA, MPFCA, or JTIQ Service Agreements. If the Network Upgrade costs for Network Upgrades subject to an FCA, MPFCA, or JTIQ Service Agreement have not been finalized or the Interconnection Customer has not made the payment under such agreement as of the date that termination of this EGIA is sought, Interconnection Customer shall provide the payment or security for such Network Upgrades in the amount required by the applicable agreement. If such agreement has not been executed and final costs are not available as of a date that termination is sought, Interconnection Customer shall provide such payment or security in an amount corresponding to the most recent estimate provided by the Transmission Provider during the ERAS process. Interconnection Customer shall pay or Transmission Provider shall refund, as applicable, to Interconnection Customer the difference between the amount of any estimated payment or security made pursuant to this Article and the final cost of such NU within ninety (90) Calendar Days after such final costs are invoiced to the Interconnection Customer.

2.4.1 With respect to any portion of the Transmission Owner's Interconnection Facilities, Network Upgrades, System Protection Facilities, Distribution Upgrades, Generator Upgrades, and if so determined and made a part of this GIA, upgrades on Affected Systems, that have not yet been constructed or installed, Transmission Owner shall to the extent possible and to the extent of Interconnection Customer's written notice under Article 2.3.1, cancel any pending orders of, or return, any materials or equipment for, or contracts for construction of, such facilities; provided that in the event Interconnection Customer elects not to authorize such cancellation, Interconnection Customer shall assume all payment obligations with respect to such materials, equipment, and contracts, and Transmission Owner shall deliver such material and equipment, and, if necessary, assign such contracts, to Interconnection Customer as soon as practicable, at Interconnection Customer's expense. To the extent that Interconnection Customer has already paid Transmission Owner for any or all such costs of materials or equipment not taken by Interconnection Customer or upgrades not yet constructed, Transmission Owner shall promptly transfer such amounts to Transmission Provider, less any costs, including penalties incurred by Transmission Owner to cancel any pending orders of or return such materials, equipment, or contracts. Transmission Provider will perform a financial impact analysis in accordance with Section 7.8 of Attachment X to determine the amount that should be refunded to Interconnection Customer. Transmission Provider shall refund such remaining amounts to Interconnection Customer, less the amount of Automatic Withdrawal Penalty funds received by the Interconnection Customer in accordance with Section 7.8.1 of the Attachment X and less any financial impact caused by the termination of this GIA or Interconnection Customer's FCA(s) or MPFCA(s), as determined through the analysis performed in accordance with Section 7.8 of Attachment X. If Interconnection Customer made its payment(s) through a letter of credit, surety bond, or parental guarantee, Transmission Owner will draw against that letter of credit, surety bond, or parental guarantee in an amount determined through the analysis performed in accordance with Section 7.8 of Attachment X plus the amount of any Automatic Withdrawal Penalty funds received by the Interconnection Customer in accordance with Section 7.8.1 of the Attachment X, and transfer that amount to Transmission Provider, unless Interconnection Customer funds the financial impact through another means.

If an Interconnection Customer terminates this GIA, it shall be responsible for all costs incurred in association with that Interconnection Customer's interconnection, including any cancellation costs relating to orders or contracts for Interconnection Facilities and equipment, and other expenses including any upgrades or related equipment for which Transmission Owner has incurred expenses and has not been reimbursed by Interconnection Customer.

2.4.2 Transmission Owner may, at its option, retain any portion of such materials, equipment, or facilities that Interconnection Customer chooses not to accept delivery of, in which case Transmission Owner shall be responsible for all costs

associated with procuring such materials, equipment, or facilities. If Transmission Owner does not so elect, then Interconnection Customer shall be responsible for such costs.

2.4.3 With respect to any portion of the Interconnection Facilities, and any other facilities already installed or constructed pursuant to the terms of this GIA, Interconnection Customer shall be responsible for all costs associated with the removal, relocation, reconfiguration or other disposition or retirement of such materials, equipment, or facilities, and such other expenses actually incurred by Transmission Owner necessary to return the Transmission, Distribution or Generator System, as applicable, to safe and reliable operation.

2.5 **Disconnection**. Upon termination of this GIA, the Parties will take all appropriate steps to disconnect the Generating Facility from the Transmission or Distribution System, as applicable. All costs required to effectuate such disconnection shall be borne by the terminating Party, unless such termination resulted from the non-terminating Party's Default of this GIA or such non-terminating Party otherwise is responsible for these costs under this GIA.

2.6 **Survival.** This GIA shall continue in effect after termination to the extent necessary to provide for final billings and payments and for costs incurred hereunder, including billings and payments pursuant to this GIA; to permit the determination and enforcement of liability and indemnification obligations arising from acts or events that occurred while this GIA was in effect; and to permit each Party to have access to the lands of the other Party pursuant to this GIA or other applicable agreements, to disconnect, remove or salvage its own facilities and equipment.

ARTICLE 3. REGULATORY FILINGS

3.1 **Filing.** Transmission Provider shall file this GIA (and any amendment hereto) with the appropriate Governmental Authority, if required. A Party may request that any information so provided be subject to the confidentiality provisions of Article 22. If that Party has executed this GIA, or any amendment thereto, the Party shall reasonably cooperate with Transmission Provider with respect to such filing and to provide any information reasonably requested by Transmission Provider needed to comply with applicable regulatory requirements.

ARTICLE 4. SCOPE OF SERVICE

4.1 **Interconnection Product Options**. Interconnection Customer has selected the following (checked) type of Interconnection Service:

Check: _____ SI or ____ ER and/or __X__ NR (See Appendix A for details)

4.1.1 Energy Resource Interconnection Service (ER Interconnection Service).

4.1.1.1 The Product. ER Interconnection Service allows Interconnection Customer to connect the Generating Facility to the Transmission or Distribution System, as applicable, and be eligible to deliver the Generating Facility's output using the existing firm or non-firm capacity of the Transmission System on an "as available" basis. To the extent Interconnection Customer wants to receive ER Interconnection Service, Transmission Owner shall construct facilities consistent with the studies identified in Appendix A.

An Interconnection Customer seeking ER Interconnection Service for new or added capacity at a Generating Facility may be granted conditional ER Interconnection Service status to the extent there is such capacity available on the Transmission System to accommodate the Interconnection Customer's Generating Facility. At the request of Interconnection Customer, conditional ER Interconnection Service status may be granted subject to the system being able to accommodate the interconnection without upgrades, until such time as a higher queued project(s) with a later service date affecting the same common elements is placed into service. The conditional ER Interconnection Service shall be terminated in the event Interconnection Customer fails to fund the necessary studies and the Network Upgrades necessary to grant the Interconnection Customer's ER Interconnection Service upon the completion of higher queued projects involving the same common elements.

4.1.1.2 Transmission Delivery Service Implications. Under ER Interconnection Service, Interconnection Customer will be eligible to inject power from the Generating Facility into and deliver power across the Transmission System on an "as available" basis up to the amount of MW identified in the applicable stability and steady state studies to the extent the upgrades initially required to qualify for ER Interconnection Service have been constructed. After that date FERC makes effective MISO's Energy Market Tariff filed in Docket No. ER04-691-000, Interconnection Customer may place a bid to sell into the market up to the maximum identified Generating Facility output, subject to any conditions specified in the Interconnection Service approval, and the Generating Facility will be dispatched to the extent the Interconnection Customer's bid clears. In all other instances, no transmission or other delivery service from the Generating Facility is assured, but Interconnection Customer may obtain Point-To-Point Transmission Service, Network Integration Transmission Service or be used for secondary network transmission service, pursuant to the Tariff, up to the maximum output identified in the stability and steady state studies. In those instances, in order for Interconnection Customer to obtain the right to deliver or inject energy beyond the Point of Interconnection or to improve its ability to do so, transmission delivery service must be

obtained pursuant to the provisions of the Tariff. The Interconnection Customer's ability to inject its Generating Facility output beyond the Point of Interconnection, therefore, will depend on the existing capacity of the Transmission or Distribution System as applicable, at such time as a Transmission Service request is made that would accommodate such delivery. The provision of Firm Point-To-Point Transmission Service or Network Integration Transmission Service may require the construction of additional Network or Distribution Upgrades.

4.1.2 Network Resource Interconnection Service (NR Interconnection Service).

4.1.2.1 The Product. Transmission Provider must conduct the necessary studies and Transmission Owner shall construct the facilities identified in Appendix A of this GIA, subject to the approval of Governmental Authorities, needed to integrate the Generating Facility in the same manner as for any Generating Facility being designated as a Network Resource.

4.1.2.2 Transmission Delivery Service Implications. NR Interconnection Service allows the Generating Facility to be designated by any Network Customer under the Tariff on the Transmission System as a Network Resource, up to the Generating Facility's full output, on the same basis as existing Network Resources that are interconnected to the Transmission or Distribution System, as applicable, and to be studied as a Network Resource on the assumption that such a designation will occur. Although NR Interconnection Service does not convey a reservation of Transmission Service, any Network Customer can utilize Network Integration Transmission Service under the Tariff to obtain delivery of energy from the Generating Facility in the same manner as it accesses Network Resources. A Generating Facility receiving NR Interconnection Service may also be used to provide Ancillary Services after technical studies and/or periodic analyses are performed with respect to the Generating Facility's ability to provide any applicable Ancillary Services, provided that such studies and analyses have been or would be required in connection with the provision of such Ancillary Services by any existing Network Resource. However, if the Generating Facility has not been designated as a Network Resource by any Network Customer, it cannot be required to provide Ancillary Services except to the extent such requirements extend to all generating facilities that are similarly situated. The provision of Network Integration Transmission Service or Firm Point-To-Point Transmission Service may require additional studies and the construction of additional upgrades. Because such studies and upgrades would be associated with a request for delivery service under the Tariff, cost responsibility for the studies and upgrades would be in accordance with FERC's policy for pricing transmission delivery services.

NR Interconnection Service does not necessarily provide Interconnection Customer with the capability to physically deliver the output of its Generating Facility to any particular load on the Transmission System without incurring congestion costs. In the event of transmission or distribution constraints on the Transmission or Distribution System, as applicable, the Generating Facility shall be subject to the applicable congestion management procedures in the Transmission System in the same manner as Network Resources.

There is no requirement either at the time of study or interconnection, or at any point in the future, that the Generating Facility be designated as a Network Resource by a Network Customer or that Interconnection Customer identify a specific buyer (or sink). To the extent a Network Customer does designate the Generating Facility as a Network Resource, it must do so pursuant to the Tariff.

Once an Interconnection Customer satisfies the requirements for obtaining NR Interconnection Service, any future Transmission Service request for delivery from the Generating Facility within the Transmission System of any amount of capacity and/or energy, up to the amount initially studied, will not require that any additional studies be performed or that any further upgrades associated with such Generating Facility be undertaken, regardless of whether such Generating Facility is ever designated by a Network Customer as a Network Resource and regardless of changes in ownership of the Generating Facility. To the extent Interconnection Customer enters into an arrangement for long term Transmission Service for deliveries from the Generating Facility to customers other than the studied Network Customers, or for any Point-To-Point Transmission Service, such request may require additional studies and upgrades in order for Transmission Provider to grant such request. However, the reduction or elimination of congestion or redispatch costs may require additional studies and the construction of additional upgrades.

To the extent Interconnection Customer enters into an arrangement for long term Transmission Service for deliveries from the Generating Facility outside the Transmission System, such request may require additional studies and upgrades in order for Transmission Provider to grant such request.

4.1.2.3 Conditional NR Interconnection Service. An Interconnection Customer seeking NR Interconnection Service for new or added capacity at a Generating Facility may be granted conditional NR Interconnection Service status to the extent there is such capacity available on the Transmission System to accommodate the Interconnection Customer's

Generating Facility. At the request of Interconnection Customer, conditional NR Interconnection Service status may be granted subject to the system being able to accommodate the interconnection without upgrades, until such time as higher queued project(s) with a later service date affecting the same common elements is placed into service. The conditional NR Interconnection Service status may be converted to ER Interconnection Service if either of the following occurs:

1) Interconnection Customer fails to fund necessary studies and Network Upgrades required to allow the Interconnection Customer's Generating Facility to receive NR Interconnection Service upon the completion of higher queued projects involving the same common elements; or

2) The higher queued project(s) or planned and required Network Upgrades are placed in service and the Network Upgrades required to provide NR Interconnection Service status to the Interconnection Customer's Generating Facility are not in service.

In the event Interconnection Customer fails to fund the necessary studies and Network Upgrades for NR Interconnection Service, the Interconnection Customer's conditional NR Interconnection Service status shall be converted to ER Interconnection Service status unless Interconnection Customer makes a new Interconnection Request. Such new Interconnection Request shall be evaluated in accordance with the GIP and its new queue position.

Some or all of the conditional NR Interconnection Service status may be temporarily revoked if the Network Upgrades are not in service when the higher queued project(s) are placed in service. The availability of conditional NR Interconnection Service status will be determined by Transmission Provider's studies. Upon funding and completion of the Network Upgrades required to establish the Generating Facility's NR Interconnection Service status, the Generating Facility will be granted NR Interconnection Service status.

The Parties agree that the portion of the Generating Facility classified as NR Interconnection Service is the first portion of the output of the combined output of all the units at the Generating Facility except in circumstances where Interconnection Customer otherwise elects this GIA, as amended, to allocate that portion to the output of specific unit(s) at the Generating Facility, the total of which will not exceed the output eligible for NR Interconnection Service as shown by the additional studies. To the extent Interconnection Customer desires to obtain NR Interconnection Service for any portion of the Generating Facility in addition to that supported by such additional studies, Interconnection Customer will be

required to request such additional NR Interconnection Service through a separate Interconnection Request in accordance with the GIP.

4.1.3 Surplus Interconnection Service (SI).

4.1.3.1 The Product. Surplus Interconnection Service is restricted Interconnection Service that allows an Interconnection Customer to increase the gross generating capability at the same Point of Interconnection of an Existing Generating Facility without increasing the total amount of Interconnection Service at the Point of Interconnection.

4.1.3.2 Transmission Delivery Service Implications. Surplus Interconnection Service does not convey any right to deliver electricity to any specific customer or Point of Delivery.

4.2 Provision of Service. Transmission Provider shall provide Interconnection Service for the Generating Facility at the Point of Interconnection.

4.3 Performance Standards. Each Party shall perform all of its obligations under this GIA in accordance with Applicable Laws and Regulations, Applicable Reliability Standards, and Good Utility Practice. To the extent a Party is required or prevented or limited in taking any action by such regulations and standards, or if the obligations of any Party may become limited by a change in Applicable Laws and Regulations, Applicable Reliability Standards, and Good Utility Practice after the execution of this GIA, that Party shall not be deemed to be in Breach of this GIA for its compliance therewith. The Party so limited shall notify the other Parties whereupon Transmission Provider shall amend this GIA in concurrence with the other Parties and submit the amendment to the Commission for approval.

4.4 No Transmission Delivery Service. The execution of this GIA does not constitute a request for, or the provision of, any transmission delivery service under the Tariff, and does not convey any right to deliver electricity to any specific customer or Point of Delivery.

4.5 Interconnection Customer Provided Services. The services provided by Interconnection Customer under this GIA are set forth in Article 9.6 and Article 13.4.1. Interconnection Customer shall be paid for such services in accordance with Article 11.7.

ARTICLE 5. INTERCONNECTION FACILITIES ENGINEERING, PROCUREMENT, AND CONSTRUCTION

5.1 Options. Unless otherwise mutually agreed to between the Parties, Interconnection Customer shall select: 1) the In-Service Date, Initial Synchronization Date, and Commercial Operation Date based on a reasonable construction schedule that will allow sufficient time for design, construction, equipment procurement, and permit acquisition of Transmission System equipment or right-of-way; and 2) either the Standard Option or

Alternate Option set forth below and such dates and selected option shall be set forth in Appendix B. If the dates designated by Interconnection Customer are not acceptable to Transmission Owner, Transmission Owner shall so notify Interconnection Customer within thirty (30) Calendar Days. Upon receipt of the notification that Interconnection Customer's designated dates are not acceptable to Transmission Owner, the Interconnection Customer shall notify Transmission Owner within thirty (30) Calendar Days whether it elects to exercise the Option to Build if it has not already elected to exercise the Option to Build.

5.1.1 Standard Option. Transmission Owner shall design, procure, and construct the Transmission Owner's Interconnection Facilities, Network Upgrades, System Protection Facilities, Distribution Upgrades, and Generator Upgrades using Reasonable Efforts to complete the Transmission Owner's Interconnection Facilities, Network Upgrades, System Protection Facilities, Distribution Upgrades and Generator Upgrades by the dates set forth in Appendix B, Milestones, subject to the receipt of all approvals required from Governmental Authorities and the receipt of all land rights necessary to commence construction of such facilities, and such other permits or authorizations as may be required. Transmission Provider or Transmission Owner shall not be required to undertake any action which is inconsistent with its standard safety practices, its material and equipment specifications, its design criteria and construction procedures, its labor agreements, Applicable Laws and Regulations and Good Utility Practice. In the event Transmission Owner reasonably expects that it will not be able to complete the Transmission Owner's Interconnection Facilities, Network Upgrades, System Protection Facilities, Distribution Upgrades and Generator Upgrades by the specified dates, Transmission Owner shall promptly provide written notice to Interconnection Customer and Transmission Provider and shall undertake Reasonable Efforts to meet the earliest dates thereafter.

5.1.2 Alternate Option. If the dates designated by Interconnection Customer are acceptable to Transmission Provider and Transmission Owner, Transmission Provider shall so notify Interconnection Customer within thirty (30) Calendar Days, and Transmission Owner shall assume responsibility for the design, procurement and construction of the Transmission Owner's Interconnection Facilities by the designated dates.

If Transmission Owner subsequently fails to complete the Transmission Owner's Interconnection Facilities by the In-Service Date, to the extent necessary to provide back feed power; or fails to complete Network Upgrades by the Initial Synchronization Date to the extent necessary to allow for Trial Operation at full power output, unless other arrangements are made by the Parties for such Trial Operation; or fails to complete the Network Upgrades by the Commercial Operation Date, as such dates are reflected in Appendix B, Milestones; Transmission Owner shall pay Interconnection Customer liquidated damages in accordance with Article 5.3, Liquidated Damages, provided, however, the dates designated by Interconnection Customer shall be extended day for day for each

Calendar Day that Transmission Provider refuses to grant clearances to install equipment.

Transmission Owner and Interconnection Customer may adopt an incentive payment schedule that is mutually agreeable to encourage Transmission Owner to meet specified accelerated dates. Such payment by Interconnection Customer is not subject to refund.

5.1.3 Option to Build. Pursuant to Section 7.3.2.5 & 7.3.3.5 of the GIP, Individual or Multiple Interconnection Customers shall have the option to assume responsibility for the design, procurement and construction of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades by the dates originally designated by Interconnection Customer under Article 5.1.2, if the requirements of this Article 5.1.3 are met. When multiple Interconnection Customers exercise this option, multiple Interconnection Customers may agree to exercise this option provided (1) all Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades constructed under this option are only required for Interconnection Customers in a single Cluster and (2) all impacted Interconnection Customers execute and provide to Transmission Provider an agreement regarding responsibilities, and payment for, the construction of Transmission Provider's Interconnection Facilities and Stand Alone Network Upgrades planned to be built under this option. The Parties must agree as to what constitutes Stand Alone Network Upgrades and identify such Stand Alone Network Upgrades in Appendix A. Except for Stand Alone Network Upgrades, Interconnection Customer shall have no right to construct Network Upgrades under this option.

5.1.4 Negotiated Option. If the dates designated by Interconnection Customer pursuant to Article 5.1 are not acceptable to Transmission Owner, the Parties shall in good faith attempt to negotiate terms and conditions (including revision of the specified dates and liquidated damages, the provision of incentives, or the procurement and construction of all facilities other than Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades if the Interconnection Customer elects to exercise the Option to Build under Article 5.1.3). If the Parties are unable to reach agreement on such terms and conditions, then, pursuant to Article 5.1.1 (Standard Option), Transmission Owner shall assume responsibility for the design, procurement and construction of all facilities other than Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades if Interconnection Customer has elected to exercise the Option to Build.

Transmission Owner and Interconnection Customer may adopt an incentive payment schedule that is mutually agreeable to encourage Transmission Owner to meet specified accelerated dates. Such payment by Interconnection Customer is not subject to refund.

5.2 General Conditions Applicable to Option to Build. If Interconnection Customer assumes responsibility for the design, procurement and construction of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades after receipt of all required approvals from Governmental Authorities necessary to commence construction,

(1) Interconnection Customer shall engineer, procure equipment, and construct the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades (or portions thereof) using Good Utility Practice and using standards and specifications provided in advance by Transmission Owner, or as required by any Governmental Authority;

(2) Interconnection Customer's engineering, procurement and construction of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades shall comply with all requirements of law or Governmental Authority to which Transmission Owner would be subject in the engineering, procurement or construction of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades;

(3) Transmission Provider, at Transmission Provider's option, and Transmission Owner shall be entitled to review and approve the engineering design, equipment acceptance tests(including witnessing of acceptance tests), and the construction (including monitoring of construction) of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades, and shall have the right to reject any design, procurement, construction or acceptance test of any equipment that does not meet the standards and specifications of Transmission Provider, Transmission Owner and any Governmental Authority;

(4) prior to commencement of construction, Interconnection Customer shall provide to Transmission Provider and Transmission Owner a schedule for construction of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades, and shall promptly respond to requests for information from Transmission Provider and Transmission Owner;

(5) at any time during construction, Transmission Provider and Transmission Owner shall have unrestricted access to the construction site for the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades and to conduct inspections of the same;

(6) at any time during construction, should any phase of the engineering, equipment procurement, or construction of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades not meet the standards and specifications provided by Transmission Owner, Interconnection Customer shall be obligated to remedy deficiencies in that portion of the Transmission Owner's Interconnection Facilities and Stand Alone Network

Upgrades to meet the standards and specifications provided by Transmission Provider and Transmission Owner;

(7) Interconnection Customer shall indemnify Transmission Provider and Transmission Owner for claims arising from the Interconnection Customer's construction of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades under the terms and procedures applicable to Article 18.1, Indemnity;

(8) Interconnection Customer shall transfer control of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades to Transmission Owner;

(9) Unless Parties otherwise agree, Interconnection Customer shall transfer ownership of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades to Transmission Owner in accordance with Appendix B;

(10) Transmission Provider, at Transmission Provider's option, and Transmission Owner shall approve and accept for operation and maintenance the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades to the extent engineered, procured, and constructed in accordance with this Article 5.2 only if the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades meet the standards and specifications of Transmission Provider, Transmission Owner and any Governmental Authority.

(11) Interconnection Customer shall deliver to Transmission Owner "as-built" drawings, information, and any other documents that are reasonably required by Transmission Owner to assure that the Interconnection Facilities and Stand-Alone Network Upgrades are built to the standards and specifications required by Transmission Owner.

(12) If Interconnection Customer exercises the Option to Build pursuant to Article 5.1.3, Interconnection Customer shall pay Transmission Owner the agreed upon amount of [$ PLACEHOLDER] for Transmission Owner to execute the responsibilities enumerated to Transmission Owner under Article 5.2. Transmission Owner shall invoice Interconnection Customer for this total amount to be divided on a monthly basis pursuant to Article 12.

(13) If Interconnection Customer exercises the Option to Build pursuant to Article 5.1.3, and the Transmission Owner has elected to fund the costs of Network Upgrades pursuant to Article 11.3, then prior to Interconnection Customer incurring any construction costs relating to the Option to Build and by the date specified in Appendix B, Interconnection Customer shall invoice the Transmission Owner for the estimated amount to be expended by the Interconnection Customer to construct any Stand Alone Network Upgrades for

which the Interconnection Customer has exercised its Option to Build in accordance with Appendix B. The Transmission Owner shall be required to reimburse Interconnection Customer for the full amount of such invoiced costs by the date specified in Appendix B, which shall be prior to the date by which Interconnection Customer must make any construction payment for such Stand Alone Network Upgrades. After completion of the construction of Stand Alone Network Upgrades by the Interconnection Customer and by the date specified in Appendix B for the Interconnection Customer to transfer such Stand Alone Network Upgrades to the Transmission Owner, Interconnection Customer shall provide an invoice of the final cost of the construction of Stand Alone Upgrades and shall set forth such costs in sufficient detail to enable the Transmission Owner to compare the actual costs with the estimates and to ascertain deviations, if any, from the cost estimates. In the event that the actual costs exceed the estimated costs previously invoiced by Interconnection Customer and paid by Transmission Owner, Transmission Owner shall pay to Interconnection Customer the difference between the amount previously paid and the actual costs within thirty (30) Calendar Days after receipt of a final construction invoice from Interconnection Customer. In the event that the actual costs are less than the estimated costs previously invoiced by Interconnection Customer and paid by Transmission Owner, Interconnection Customer shall refund, with interest (calculated in accordance with 18 C.F.R. Section 35.19a(a)(2)(iii), to Transmission Owner any amount by which the actual payment by Transmission Owner for estimated costs exceeds the actual costs of construction within thirty (30) Calendar Days of the issuance of such final construction invoice. Following the transfer of the Stand Alone Network Upgrades from the Interconnection Customer to the Transmission Owner, the Interconnection Customer shall make payments for such facilities to the Transmission Owner pursuant to an agreement between and among the Parties.

5.3 Liquidated Damages. The actual damages to Interconnection Customer, in the event the Transmission Owner's Interconnection Facilities or Network Upgrades are not completed by the dates designated by Interconnection Customer and accepted by Transmission Provider and Transmission Owner pursuant to subparagraphs 5.1.2 or 5.1.4, above, may include Interconnection Customer's fixed operation and maintenance costs and lost opportunity costs. Such actual damages are uncertain and impossible to determine at this time. Because of such uncertainty, any liquidated damages paid by Transmission Owner to Interconnection Customer in the event that Transmission Owner does not complete any portion of the Transmission Owner's Interconnection Facilities or Network Upgrades by the applicable dates, shall be an amount equal to ½ of 1 percent per day of the actual cost of the Transmission Owner's Interconnection Facilities and Network Upgrades, in the aggregate, for which Transmission Owner has assumed responsibility to design, procure and construct.

However, in no event shall the total liquidated damages exceed 20 percent of the actual cost of the Transmission Owner's Interconnection Facilities and Network Upgrades for which Transmission Owner has assumed responsibility to design, procure, and construct.

The foregoing payments will be made by Transmission Owner to Interconnection Customer as just compensation for the damages caused to Interconnection Customer, which actual damages are uncertain and impossible to determine at this time, and as reasonable liquidated damages, but not as a penalty or a method to secure performance of this GIA. Liquidated damages, when the Parties agree to them, are the exclusive remedy for the Transmission Owner's failure to meet its schedule.

No liquidated damages shall be paid to Interconnection Customer if: (1) Interconnection Customer is not ready to commence use of the Transmission Owner's Interconnection Facilities or Network Upgrades to take the delivery of power for the Generating Facility's Trial Operation or to export power from the Generating Facility on the specified dates, unless Interconnection Customer would have been able to commence use of the Transmission Owner's Interconnection Facilities or Network Upgrades to take the delivery of power for Generating Facility's Trial Operation or to export power from the Generating Facility, but for Transmission Owner's delay; (2) the Transmission Owner's failure to meet the specified dates is the result of the action or inaction of Transmission Provider, Interconnection Customer or any other earlier queued Interconnection Customer who has entered into an earlier GIA with Transmission Provider and/or a Transmission Owner or with an Affected System Operator, or any cause beyond Transmission Owner's reasonable control or reasonable ability to cure; (3) Interconnection Customer has assumed responsibility for the design, procurement and construction of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades; (4) the delay is due to the inability of Transmission Owner to obtain all required approvals from Governmental Authorities in a timely manner for the construction of any element of the Interconnection Facilities, Network Upgrades or Stand Alone Network Upgrades, or any other permit or authorization required, or any land rights or other private authorizations that may be required, and Transmission Owner has exercised Reasonable Efforts in procuring such approvals, permits, rights or authorizations; or (5) the Parties have otherwise agreed.

5.4 Power System Stabilizers. Interconnection Customer shall procure, install, maintain and operate power system stabilizers in accordance with the guidelines and procedures established by the Electric Reliability Organization. Transmission Provider and Transmission Owner reserve the right to reasonably establish minimum acceptable settings for any installed power system stabilizers, subject to the design and operating limitations of the Generating Facility. If the Generating Facility's power system stabilizers are removed from service or are not capable of automatic operation, Interconnection Customer shall immediately notify the Transmission Provider's system operator, or its designated representative. The requirements of this paragraph shall not apply to induction generators.

5.5 Equipment Procurement. If responsibility for construction of the Transmission Owner's Interconnection Facilities, Network Upgrades and/or Distribution Upgrades is to be borne by Transmission Owner, then Transmission Owner shall commence design of the Transmission Owner's Interconnection Facilities, Network Upgrades and/or Distribution Upgrades, and procure necessary equipment as soon as practicable after all

of the following conditions are satisfied, unless the Parties otherwise agree in writing:

5.5.1 Transmission Provider has completed the Interconnection Facilities Study pursuant to the Interconnection Facilities Study Agreement; and

5.5.2 Where applicable, Interconnection Customer has provided security to Transmission Owner in accordance with Article 11.6 by the dates specified in Appendix B, Milestones.

5.6 Construction Commencement. Transmission Owner shall commence construction of the Transmission Owner's Interconnection Facilities, Network Upgrades, Transmission Owner's System Protection Facilities, Distribution Upgrades, and Generator Upgrades for which it is responsible as soon as practicable after the following additional conditions are satisfied:

5.6.1 Approval of the appropriate Governmental Authority has been obtained for any facilities requiring regulatory approval; and

5.6.2 Where applicable, Interconnection Customer has provided security to Transmission Owner in accordance with Article 11.6 by the dates specified in Appendix B, Milestones.

5.7 Work Progress. Transmission Owner and Interconnection Customer will keep each other and Transmission Provider advised periodically as to the progress of their respective design, procurement and construction efforts. Either Transmission Owner or Interconnection Customer may, at any time, request a progress report from the other, with a copy to be provided to the other Parties. If, at any time, Interconnection Customer determines that the completion of the Transmission Owner's Interconnection Facilities, Network Upgrades, or Transmission Owner's System Protection Facilities will not be required until after the specified In-Service Date, Interconnection Customer will provide written notice to Transmission Provider and Transmission Owner of such later date upon which the completion of the Transmission Owner's Interconnection Facilities, Network Upgrades or Transmission Owner's System Protection Facilities will be required. Transmission Owner may delay the In-Service Date of its facilities accordingly.

5.8 Information Exchange. As soon as reasonably practicable after the Effective Date, the Parties shall exchange information regarding the design and compatibility of the Interconnection Facilities and compatibility of the Interconnection Facilities with the Transmission System or Distribution System, as applicable, and shall work diligently and in good faith to make any necessary design changes.

5.9 Other Interconnection Options.

5.9.1 Limited Operation. If any of the Transmission Owner's Interconnection Facilities, Network Upgrades, or Transmission Owner's System Protection Facilities, Distribution Upgrades or Generator Upgrades are not reasonably

expected to be completed prior to the Commercial Operation Date of the Generating Facility, Transmission Provider shall, upon the request and at the expense of Interconnection Customer, perform operating studies on a timely basis to determine the extent to which the Generating Facility and the Interconnection Customer's Interconnection Facilities may operate prior to the completion of the Transmission Owner's Interconnection Facilities, Network Upgrades, Transmission Owner's System Protection Facilities, Distribution Upgrades or Generator Upgrades consistent with Applicable Laws and Regulations, Applicable Reliability Standards, Good Utility Practice, and this GIA. Transmission Provider and Transmission Owner shall permit Interconnection Customer to operate the Generating Facility and the Interconnection Customer's Interconnection Facilities in accordance with the results of such studies; provided, however, such studies reveal that such operation may occur without detriment to the Transmission System as then configured and in accordance with the safety requirements of Transmission Owner and any Governmental Authority.

The maximum permissible output of the Generating Facility will be updated on a quarterly basis if the Network Upgrades necessary for the interconnection of the Generating Facility pursuant to this GIA are not in service within six (6) months following the Commercial Operation Date of the Generating Facility as specified in Appendix B of this GIA. These quarterly studies will be performed using the same methodology set forth in Section 11.5 of the GIP. These quarterly updates will end when all Network Upgrades necessary for the interconnection of the Generating Facility pursuant to this GIA are in service.

5.9.2 Provisional Interconnection Service.

Upon the request of Interconnection Customer, and prior to completion of requisite Interconnection Facilities, Network Upgrades, Distribution Upgrades, or System Protection Facilities Transmission Provider may execute a Provisional Generator Interconnection Agreement or Interconnection Customer may request the filing of an unexecuted Provisional Generator Interconnection Agreement with the Interconnection Customer for limited interconnection service at the discretion of Transmission Provider based upon an evaluation that will consider the results of available studies. Transmission Provider shall determine, through available studies or additional studies as necessary, whether stability, short circuit, thermal, and/or voltage issues would arise if Interconnection Customer interconnects without modifications to the Generating Facility or Transmission Provider's system. Transmission Provider shall determine whether any Interconnection Facilities, Network Upgrades, Distribution Upgrades, or System Protection Facilities that are necessary to meet the requirements of the Electric Reliability Organization, or any applicable Regional Entity for the interconnection of a new, modified and/or expanded Generating Facility are in place prior to the commencement of interconnection service from the Generating Facility. Where available studies indicate that such Interconnection Facilities, Network Upgrades, Distribution Upgrades, and/or System Protection Facilities that are required for the interconnection of a new, modified and/or expanded Generating Facility are

not currently in place, Transmission Provider will perform a study, at the Interconnection Customer's expense, to confirm the facilities that are required for Provisional Interconnection Service. The maximum permissible output of the Generating Facility in the Provisional Generator Interconnection Agreement shall be studied and updated on a quarterly basis. Interconnection Customer assumes all risk and liabilities with respect to changes between the Provisional Generator Interconnection Agreement and the Generator Interconnection Agreement, including changes in output limits and Interconnection Facilities, Network Upgrades, Distribution Upgrades, and/or System Protection Facilities cost responsibilities.

5.10 Interconnection Customer's Interconnection Facilities. Interconnection Customer shall, at its expense, design, procure, construct, own or control, and install the ICIF, as set forth in Appendix A.

5.10.1 Interconnection Customer's Interconnection Facility Specifications. Interconnection Customer shall submit initial design and specifications for the ICIF, including Interconnection Customer's System Protection Facilities, to Transmission Provider and Transmission Owner at least one hundred eighty (180) Calendar Days prior to the Initial Synchronization Date; and final design and specifications for review and comment at least ninety (90) Calendar Days prior to the Initial Synchronization Date. Transmission Provider at Transmission Provider's option, and Transmission Owner shall review such specifications to ensure that the ICIF are compatible with their respective technical specifications, operational control, and safety requirements and comment on such design and specifications within thirty (30) Calendar Days of Interconnection Customer's submission. All specifications provided hereunder shall be deemed confidential.

5.10.2 Transmission Provider's and Transmission Owner's Review. Transmission Provider's and Transmission Owner's review of Interconnection Customer's final specifications shall not be construed as confirming, endorsing, or providing a warranty as to the design, fitness, safety, durability or reliability of the Generating Facility, or the ICIF. Interconnection Customer shall make such changes to the ICIF as may reasonably be required by Transmission Provider and Transmission Owner, in accordance with Good Utility Practice, to ensure that the ICIF are compatible with the technical specifications, operational control and safety requirements of Transmission Provider and Transmission Owner.

5.10.3 ICIF Construction. The ICIF shall be designed and constructed in accordance with Good Utility Practice. Within one hundred twenty (120) Calendar Days after the Commercial Operation Date, unless the Parties agree on another mutually acceptable deadline, Interconnection Customer shall deliver to Transmission Provider and Transmission Owner "as-built" drawings, information and documents for the ICIF, such as: a one-line diagram, a site plan

showing the Generating Facility and the ICIF, plan and elevation drawings showing the layout of the ICIF, a relay functional diagram, relaying AC and DC schematic wiring diagrams and relay settings for all facilities associated with the Interconnection Customer's step-up transformers, the facilities connecting the Generating Facility to the step-up transformers and the ICIF, and the impedances (determined by factory tests) for the associated step-up transformers and the Generating Facility. Interconnection Customer shall provide Transmission Provider and Transmission Owner with Interconnection Customer's specifications for the excitation system, automatic voltage regulator, Generating Facility control and protection settings, transformer tap settings, and communications, if applicable.

5.11 Transmission Owner's Interconnection Facilities Construction. The Transmission Owner's Interconnection Facilities shall be designed and constructed in accordance with Good Utility Practice. Upon request, within one hundred twenty (120) Calendar Days after the Commercial Operation Date, unless the Parties agree on another mutually acceptable deadline, Transmission Owner shall deliver to Transmission Provider (if requested) and Interconnection Customer the "as-built" drawings, information and documents for the Transmission Owner's Interconnection Facilities specified in Appendix C to this GIA.

Such drawings, information and documents shall be deemed Confidential Information.

Upon completion, the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades shall be under the control of Transmission Provider or its designated representative.

5.12 Access Rights. Upon reasonable notice by a Party, and subject to any required or necessary regulatory approvals, a Party ("Granting Party") shall furnish *at no cost* to the other Party ("Access Party") any rights of use, licenses, rights of way and easements with respect to lands owned or controlled by the Granting Party, its agents (if allowed under the applicable agency agreement), or any Affiliate, that are necessary to enable the Access Party to obtain ingress and egress to construct, operate, maintain, repair, test (or witness testing), inspect, replace or remove facilities and equipment to: (i) interconnect the Generating Facility with the Transmission System; (ii) operate and maintain the Generating Facility, the Interconnection Facilities and the Transmission System; and (iii) disconnect or remove the Access Party's facilities and equipment upon termination of this GIA. In exercising such licenses, rights of way and easements, the Access Party shall not unreasonably disrupt or interfere with normal operation of the Granting Party's business and shall adhere to the safety rules and procedures established in advance, as may be changed from time to time, by the Granting Party and provided to the Access Party.

5.13 Lands of Other Property Owners. If any part of the Transmission Owner's Interconnection Facilities, Network Upgrades, and/or Distribution Upgrades is to be installed on property owned by persons other than Interconnection Customer or

Transmission Owner, Transmission Owner shall at Interconnection Customer's expense use efforts, similar in nature and extent to those that it typically undertakes on its own behalf or on behalf of its Affiliates, including use of its eminent domain authority to the extent permitted and consistent with Applicable Laws and Regulations and, to the extent consistent with such Applicable Laws and Regulations, to procure from such persons any rights of use, licenses, rights of way and easements that are necessary to construct, operate, maintain, test, inspect, replace or remove the Transmission Owner's Interconnection Facilities, Network Upgrades and/or Distribution Upgrades upon such property.

5.14 Permits. Transmission Provider or Transmission Owner and Interconnection Customer shall cooperate with each other in good faith in obtaining all permits, licenses and authorizations that are necessary to accomplish the interconnection in compliance with Applicable Laws and Regulations. With respect to this paragraph, Transmission Owner shall provide permitting assistance to Interconnection Customer comparable to that provided to the Transmission Owner's own, or an Affiliate's, generation to the extent that Transmission Owner or its Affiliate owns generation.

5.15 Early Construction of Base Case Facilities. (Includes facilities required for all queued projects with interconnection agreements).Interconnection Customer may request Transmission Owner to construct, and Transmission Owner shall construct, using Reasonable Efforts to accommodate Interconnection Customer's In-Service Date, all or any portion of any Network Upgrades, Transmission Owner's System Protection Facilities or Distribution Upgrades required for Interconnection Customer to be interconnected to the Transmission or Distribution System, as applicable, which are included in the Base Case of the Interconnection Facilities Study for Interconnection Customer, and which also are required to be constructed for another Interconnection Customer with a prior GIA, but where such construction is not scheduled to be completed in time to achieve Interconnection Customer's In-Service Date. Any such Network Upgrades, System Protection Facilities or Distribution Upgrades are included in the facilities to be constructed and as set forth in Appendix A to this GIA to the extent they are reasonably known.

5.16 Suspension.

5.16.1 Interconnection Customer's Right to Suspend for Force Majeure Event; Obligations. Provided that such suspension is permissible under the authorizations, permits or approvals granted for the construction of such Interconnection Facilities, Network Upgrades or Stand Alone Network Upgrades, Interconnection Customer will not suspend unless a Force Majeure event occurs.

Interconnection Customer must provide written notice of its request for suspension to Transmission Provider and Transmission Owner, and provide a description of the Force Majeure event that is acceptable to Transmission Provider. Suspension will only apply to Interconnection Customer milestones and Interconnection Facilities described in the Appendices of this GIA. Prior to

suspension, Interconnection Customer must also provide security acceptable to Transmission Owner, equivalent to the higher of $5 million or the total cost of all Network Upgrades, Transmission Owner's System Protection Facilities, and Distribution Upgrades listed in Appendix A of this GIA. Network Upgrades and Transmission Owner's Interconnection Facilities will be constructed on the schedule described in the Appendices of this GIA unless: (1) construction is prevented by the order of a Governmental Authority; (2) the Network Upgrades are not needed by any other project; or (3) Transmission Owner or Transmission Provider determines that a Force Majeure event prevents construction. In the event of (1), (2), or (3) security shall be released upon the determination that the Network Upgrades will no longer be constructed.

If suspension occurs, the Transmission or Distribution System, as applicable, shall be left in a safe and reliable condition in accordance with Good Utility Practice and the Transmission Provider's and Transmission Owner's safety and reliability criteria. In such event, Interconnection Customer shall be responsible for all reasonable and necessary costs which Transmission Provider and Transmission Owner (i) have incurred pursuant to this GIA prior to the suspension and (ii) incur in suspending such work, including any costs incurred to perform such work as may be necessary to ensure the safety of persons and property and the integrity of the Transmission or Distribution System, as applicable, during such suspension and, if applicable, any costs incurred in connection with the cancellation or suspension of material, equipment and labor contracts which Transmission Provider and Transmission Owner cannot reasonably avoid; provided, however, that prior to canceling or suspending any such material, equipment or labor contract, Transmission Provider and Transmission Owner shall obtain Interconnection Customer's authorization to do so.

Transmission Provider and Transmission Owner shall each invoice Interconnection Customer for such costs pursuant to Article 12 and shall use Reasonable Efforts to minimize its costs. In the event Interconnection Customer suspends work by Transmission Owner required under this GIA pursuant to this Article 5.16, and has not requested Transmission Owner to recommence the work required under this GIA on or before the expiration of three (3) years following commencement of such suspension, this GIA shall be deemed terminated. The three-year period shall begin on the date the suspension is requested, or the date of the written notice to Transmission Provider, if no effective date is specified.

5.16.2 Effect of Missed Interconnection Customer Milestones. If Interconnection Customer fails to provide notice of suspension pursuant to Article 5.16, and Interconnection Customer fails to fulfill or complete any Interconnection Customer Milestone provided in Appendix B ("Milestone"), this constitutes a Breach under this GIA. Depending upon the consequences of the Breach and effectiveness of the cure pursuant to Article 17, the Transmission Owner's Milestones may be revised, following consultation with Interconnection Customer, consistent with Reasonable Efforts, and in consideration of all relevant

circumstances. Parties shall employ Reasonable Efforts to maintain their remaining respective Milestones.

5.16.3 Effect of Suspension; Parties Obligations. In the event that Interconnection Customer suspends work pursuant to this Article 5.16, no construction duration, timelines and schedules set forth in Appendix B shall be suspended during the period of suspension unless ordered by a Governmental Authority, with such order being the Force Majeure event causing the suspension. Should Interconnection Customer request that work be recommenced, Transmission Owner shall be obligated to proceed with Reasonable Efforts and in consideration of all relevant circumstances including regional outage schedules, construction availability and material procurement in performing the work as described in Appendix A and Appendix B. Transmission Owner will provide Interconnection Customer with a revised schedule for the design, procurement, construction, installation and testing of the Transmission Owner's Interconnection Facilities and Network Upgrades. Upon any suspension by Interconnection Customer pursuant to Article 5.16, Interconnection Customer shall be responsible for only those costs specified in this Article 5.16.

5.17 Taxes.

5.17.1 Interconnection Customer Payments Not Taxable. The Parties intend that all payments or property transfers made by Interconnection Customer to Transmission Owner for the installation of the Transmission Owner's Interconnection Facilities, Network Upgrades, Transmission Owner's System Protection Facilities, Distribution Upgrades and Generator Upgrades shall be non-taxable, either as contributions to capital, or as an advance, in accordance with the Internal Revenue Code and any applicable state income tax laws and shall not be taxable as contributions in aid of construction or otherwise under the Internal Revenue Code and any applicable state income tax laws. To the extent that Transmission Owner is a limited liability company and not a corporation, and has elected to be taxed as a partnership, then the following shall apply: Transmission Owner represents, and the Parties acknowledge, that Transmission Owner is a limited liability company and is treated as a partnership for federal income tax purposes. Any payment made by Interconnection Customer to Transmission Owner for Network Upgrades is to be treated as an upfront payment in accordance with Rev Proc 2005-35. It is anticipated by the parties that any amounts paid by Interconnection Customer to Transmission Owner for Network Upgrades will be reimbursed to Interconnection Customer in accordance with the terms of this GIA, provided Interconnection Customer fulfills its obligations under this GIA.

5.17.2 Representations and Covenants. In accordance with IRS Notice 2016-36, Interconnection Customer represents and covenants that (i) ownership of the electricity generated at the Generating Facility will pass to another party prior to the transmission of the electricity on the Transmission System, (ii) for

income tax purposes, the amount of any payments and the cost of any property transferred to Transmission Owner for the Transmission Owner's Interconnection Facilities will be capitalized by Interconnection Customer as an intangible asset and recovered using the straight-line method over a useful life of twenty (20) years, and (iii) any portion of the Transmission Owner's Interconnection Facilities that is a "dual-use intertie," within the meaning of IRS Notice 2016-36, is reasonably expected to carry only a de minimis amount of electricity in the direction of the Generating Facility. For this purpose, "de minimis amount" means no more than 5 percent of the total power flows in both directions, calculated in accordance with the "5 percent test" set forth in IRS Notice 2016-36. This is not intended to be an exclusive list of the relevant conditions that must be met to conform to IRS requirements for non-taxable treatment.

At Transmission Owner's request, Interconnection Customer shall provide Transmission Owner with a report from an independent engineer confirming its representation in clause (iii), above, with a copy to Transmission Provider. Transmission Owner represents and covenants that the cost of the Transmission Owner's Interconnection Facilities paid for by Interconnection Customer will have no net effect on the base upon which rates are determined.

5.17.3 Indemnification for the Cost Consequences of Current Tax Liability Upon Transmission Owner. Notwithstanding Article 5.17.1 and to the extent permitted by law, Interconnection Customer shall protect, indemnify and hold harmless Transmission Owner from the cost consequences of any tax liability imposed against Transmission Owner as the result of payments or property transfers made by Interconnection Customer to Transmission Owner under this GIA for Interconnection Facilities, as well as any interest and penalties, other than interest and penalties attributable to any delay caused by Transmission Owner.

Transmission Owner shall not include a gross-up for the cost consequences of any current tax liability in the amounts it charges Interconnection Customer under this GIA unless (i) Transmission Owner has determined, in good faith, that the payments or property transfers made by Interconnection Customer to Transmission Owner should be reported as income subject to taxation or (ii) any Governmental Authority directs Transmission Owner to report payments or property as income subject to taxation; provided, however, that Transmission Owner may require Interconnection Customer to provide security for Interconnection Facilities, in a form reasonably acceptable to Transmission Owner (such as a parental guarantee or a letter of credit), in an amount equal to the cost consequences or any current tax liability under this Article 5.17. Interconnection Customer shall reimburse Transmission Owner for such costs on a fully grossed-up basis, in accordance with Article 5.17.4, within thirty (30) Calendar Days of receiving written notification from Transmission Owner of the amount due, including detail about how the amount was calculated.

The indemnification obligation shall terminate at the earlier of (1) the expiration of the ten-year testing period and the applicable statute of limitation, as it may be extended by Transmission Owner upon request of the IRS, to keep these years open for audit or adjustment, or (2) the occurrence of a subsequent taxable event and the payment of any related indemnification obligations as contemplated by this Article 5.17.

5.17.4 Tax Gross-Up Amount. Interconnection Customer's liability for the cost consequences of any current tax liability under this Article 5.17 shall be calculated on a fully grossed-up basis. Except as may otherwise be agreed to by the parties, this means that Interconnection Customer will pay Transmission Owner, in addition to the amount paid for the Interconnection Facilities, Network Upgrades, Transmission Owner's System Protection Facilities, and/or Distribution Upgrades, an amount equal to (1) the current taxes imposed on Transmission Owner ("Current Taxes") on the excess of (a) the gross income realized by Transmission Owner as a result of payments or property transfers made by Interconnection Customer to Transmission Owner under this GIA (without regard to any payments under this Article 5.17) (the "Gross Income Amount") over (b) the present value of future tax deductions for depreciation that will be available as a result of such payments or property transfers (the "Present Value Depreciation Amount"), plus (2) an additional amount sufficient to permit Transmission Owner to receive and retain, after the payment of all Current Taxes, an amount equal to the net amount described in clause (1).

For this purpose, (i) Current Taxes shall be computed based on Transmission Owner's composite federal and state tax rates at the time the payments or property transfers are received and Transmission Owner will be treated as being subject to tax at the highest marginal rates in effect at that time (the "Current Tax Rate"), and (ii) the Present Value Depreciation Amount shall be computed by discounting Transmission Owner's anticipated tax depreciation deductions as a result of such payments or property transfers by Transmission Owner's current weighted average cost of capital. Thus, the formula for calculating Interconnection Customer's liability to Transmission Owner pursuant to this Article 5.17.4 can be expressed as follows: (Current Tax Rate x (Gross Income Amount – Present Value of Tax Depreciation))/(1-Current Tax Rate). Interconnection Customer's estimated tax liability in the event taxes are imposed shall be stated in Appendix A, Interconnection Facilities, Network Upgrades and Distribution Upgrades.

5.17.5 Private Letter Ruling or Change or Clarification of Law. At Interconnection Customer's request and expense, Transmission Owner shall file with the IRS a request for a private letter ruling as to whether any property transferred or sums paid, or to be paid, by Interconnection Customer to Transmission Owner under this GIA are subject to federal income taxation. Interconnection Customer will prepare the initial draft of the request for a private letter ruling, and will certify

under penalties of perjury that all facts represented in such request are true and accurate to the best of Interconnection Customer's knowledge. Transmission Owner and Interconnection Customer shall cooperate in good faith with respect to the submission of such request.

Transmission Owner shall keep Interconnection Customer fully informed of the status of such request for a private letter ruling and shall execute either a privacy act waiver or a limited power of attorney, in a form acceptable to the IRS, that authorizes Interconnection Customer to participate in all discussions with the IRS regarding such request for a private letter ruling. Transmission Owner shall allow Interconnection Customer to attend all meetings with IRS officials about the request and shall permit Interconnection Customer to prepare the initial drafts of any follow-up letters in connection with the request.

5.17.6 Subsequent Taxable Events. If, within 10 years from the date on which the relevant Transmission Owner's Interconnection Facilities are placed in service, (i) Interconnection Customer breaches the covenant contained in Article 5.17.2, (ii) a "disqualification event" occurs within the meaning of IRS Notice 88-129, or (iii) this GIA terminates and Transmission Owner retains ownership of the Interconnection Facilities, Network Upgrades, Transmission Owner's System Protection Facilities, and/or Distribution Upgrades, Interconnection Customer shall pay a tax gross-up for the cost consequences of any current tax liability imposed on Transmission Owner, calculated using the methodology described in Article 5.17.4 and in accordance with IRS Notice 90-60.

5.17.7 Contests. In the event any Governmental Authority determines that Transmission Owner's receipt of payments or property constitutes income that is subject to taxation, Transmission Owner shall notify Interconnection Customer, in writing, within thirty (30) Calendar Days of receiving notification of such determination by a Governmental Authority. Upon the timely written request by Interconnection Customer and at Interconnection Customer's sole expense, Transmission Owner may appeal, protest, seek abatement of, or otherwise oppose such determination. Upon Interconnection Customer's written request and sole expense, Transmission Owner shall file a claim for refund with respect to any taxes paid under this Article 5.17, whether or not it has received such a determination. Transmission Owner reserves the right to make all decisions with regard to the prosecution of such appeal, protest, abatement or other contest, including the selection of counsel and compromise or settlement of the claim, but Transmission Owner shall keep Interconnection Customer informed, shall consider in good faith suggestions from Interconnection Customer about the conduct of the contest, and shall reasonably permit Interconnection Customer or an Interconnection Customer representative to attend contest proceedings.

Interconnection Customer shall pay to Transmission Owner on a periodic basis, as invoiced by Transmission Owner, Transmission Owner's documented

reasonable costs of prosecuting such appeal, protest, abatement or other contest. At any time during the contest, Transmission Owner may agree to a settlement either with Interconnection Customer's consent or after obtaining written advice from nationally-recognized tax counsel, selected by Transmission Owner, but reasonably acceptable to Interconnection Customer, that the proposed settlement represents a reasonable settlement given the hazards of litigation. Interconnection Customer's obligation shall be based on the amount of the settlement agreed to by Interconnection Customer, or if a higher amount, so much of the settlement that is supported by the written advice from nationally-recognized tax counsel selected under the terms of the preceding sentence. The settlement amount shall be calculated on a fully grossed-up basis to cover any related cost consequences of the current tax liability. Any settlement without Interconnection Customer's consent or such written advice will relieve Interconnection Customer from any obligation to indemnify Transmission Owner for the tax at issue in the contest.

5.17.8 Refund. In the event that (a) a private letter ruling is issued to Transmission Owner which holds that any amount paid or the value of any property transferred by Interconnection Customer to Transmission Owner under the terms of this GIA is not subject to federal income taxation, (b) any legislative change or administrative announcement, notice, ruling or other determination makes it reasonably clear to Transmission Owner in good faith that any amount paid or the value of any property transferred by Interconnection Customer to Transmission Owner under the terms of this GIA is not taxable to Transmission Owner, (c) any abatement, appeal, protest, or other contest results in a determination that any payments or transfers made by Interconnection Customer to Transmission Owner are not subject to federal income tax, or (d) if Transmission Owner receives a refund from any taxing authority for any overpayment of tax attributable to any payment or property transfer made by Interconnection Customer to Transmission Owner pursuant to this GIA, Transmission Owner shall promptly refund to Interconnection Customer the following:

any payment made by Interconnection Customer under this Article 5.17 for taxes that is attributable to the amount determined to be non-taxable, together with interest thereon,

(ii) interest on any amounts paid by Interconnection Customer to Transmission Owner for such taxes which Transmission Owner did not submit to the taxing authority, calculated in accordance with the methodology set forth in 18 C.F.R. Section 35.19a(a)(2)(iii) from the date payment was made by Interconnection Customer to the date Transmission Owner refunds such payment to Interconnection Customer, and

(iii) with respect to any such taxes paid by Transmission Owner, any refund or credit Transmission Owner receives or to which it may be

entitled from any Governmental Authority, interest (or that portion thereof attributable to the payment described in clause (i), above) owed to Transmission Owner for such overpayment of taxes (including any reduction in interest otherwise payable by Transmission Owner to any Governmental Authority resulting from an offset or credit); provided, however, that Transmission Owner will remit such amount promptly to Interconnection Customer only after and to the extent that Transmission Owner has received a tax refund, credit or offset from any Governmental Authority for any applicable overpayment of income tax related to the Transmission Owner's Interconnection Facilities.

The intent of this provision is to leave both parties, to the extent practicable, in the event that no taxes are due with respect to any payment for Interconnection Facilities and Network Upgrades hereunder, in the same position they would have been in had no such tax payments been made.

5.17.9 Taxes Other Than Income Taxes. Upon the timely request by Interconnection Customer, and at Interconnection Customer's sole expense, Transmission Owner shall appeal, protest, seek abatement of, or otherwise contest any tax (other than federal or state income tax) asserted or assessed against Transmission Owner for which Interconnection Customer may be required to reimburse Transmission Owner under the terms of this GIA. Interconnection Customer shall pay to Transmission Owner on a periodic basis, as invoiced by Transmission Owner, Transmission Owner's documented reasonable costs of prosecuting such appeal, protest, abatement, or other contest. Interconnection Customer and Transmission Owner shall cooperate in good faith with respect to any such contest. Unless the payment of such taxes is a prerequisite to an appeal or abatement or cannot be deferred, no amount shall be payable by Interconnection Customer to Transmission Owner for such taxes until they are assessed by a final, non-appealable order by any court or agency of competent jurisdiction. In the event that a tax payment is withheld and ultimately due and payable after appeal, Interconnection Customer will be responsible for all taxes, interest and penalties, other than penalties attributable to any delay caused by Transmission Owner.

5.18 Tax Status. Each Party shall cooperate with the other Parties to maintain each Party's tax status. Nothing in this GIA is intended to adversely affect any Party's tax-exempt status with respect to the issuance of bonds including, but not limited to, Local Furnishing Bonds.

5.19 Modification.

5.19.1 General. Either Party may undertake modifications to its facilities. If a Party plans to undertake a modification that reasonably may be expected to affect another Party's facilities, that Party shall provide to the other Parties sufficient

information regarding such modification so that the other Parties may evaluate the potential impact of such modification prior to commencement of the work. Such information shall be deemed to be Confidential Information hereunder and shall include information concerning the timing of such modifications and whether such modifications are expected to interrupt the flow of electricity from the Generating Facility. The Party desiring to perform such work shall provide the relevant drawings, plans, and specifications to the other Parties at least ninety (90) Calendar Days in advance of the commencement of the work or such shorter period upon which the Parties may agree, which agreement shall not unreasonably be withheld, conditioned or delayed.

In the case of Generating Facility modifications that do not require Interconnection Customer to submit an Interconnection Request, Transmission Provider shall provide, within thirty (30) Calendar Days (or such other time as the Parties may agree), an estimate of any additional modifications to the Transmission or Distribution System as applicable, Transmission Owner's Interconnection Facilities, Network Upgrades, Transmission Owner's System Protection Facilities, and/or Distribution Upgrades necessitated by such Interconnection Customer modification and a good faith estimate of the costs thereof which shall be the responsibility of Interconnection Customer.

5.19.2 Standards. Any additions, modifications, or replacements made to a Party's facilities shall be designed, constructed and operated in accordance with this GIA and Good Utility Practice.

5.19.3 Modification Costs. Interconnection Customer shall not be directly assigned the costs of any additions, modifications, or replacements that Transmission Owner makes to the Transmission Owner's Interconnection Facilities, Network Upgrades, Transmission Owner's System Protection Facilities, Distribution Upgrades, or the Transmission or Distribution System, as applicable, to facilitate the interconnection of a third party to the Transmission Owner's Interconnection Facilities or the Transmission or Distribution System, as applicable, or to provide transmission service to a third party under the Tariff. Interconnection Customer shall be responsible for the costs of any additions, modifications, or replacements to the Interconnection Customer's Interconnection Facilities that may be necessary to maintain or upgrade such Interconnection Customer's Interconnection Facilities consistent with Applicable Laws and Regulations, Applicable Reliability Standards or Good Utility Practice.

ARTICLE 6. TESTING AND INSPECTION

6.1 Pre-Commercial Operation Date Testing and Modifications. Prior to the Commercial Operation Date, Transmission Owner shall test the Transmission Owner's Interconnection Facilities, Network Upgrades, Transmission Owner's System Protection Facilities and Distribution Upgrades, and Interconnection Customer shall test each

electric production device at the Generating Facility, Interconnection Customer's System Protection Facilities, including control equipment to limit injection at the POI to the level of Interconnection Service set forth in Appendix A and the Interconnection Customer's Interconnection Facilities to ensure their safe and reliable operation. Similar testing may be required after initial operation. Transmission Owner and Interconnection Customer shall make any modifications to their respective facilities that are found to be necessary as a result of such testing. Interconnection Customer shall bear the cost of all such testing and modifications. Interconnection Customer shall generate test energy at the Generating Facility only if it has arranged for the delivery of such test energy.

6.2 Post-Commercial Operation Date Testing and Modifications. Each Party shall at its own expense perform routine inspection and testing of its facilities and equipment in accordance with Good Utility Practice as may be necessary to ensure the continued interconnection of the Generating Facility with the Transmission or Distribution System, as applicable, in a safe and reliable manner. Each Party shall have the right, upon advance written notice, to require reasonable additional testing of the Interconnection Facilities, at the requesting Party's expense, as may be in accordance with Good Utility Practice.

6.3 Right to Observe Testing. Each Party shall notify the other Parties in advance of its performance of tests of its Interconnection Facilities. The other Parties shall each have the right, at its own expense, to observe such testing.

6.4 Right to Inspect. Each Party shall have the right, but shall have no obligation to: (i) observe Transmission Owner's and Interconnection Customer's tests and/or inspection of any of their respective System Protection Facilities and other protective equipment, including power system stabilizers and control equipment; (ii) review the settings of the System Protection Facilities and other protective equipment; and (iii) review the maintenance records relative to the Interconnection Facilities, the System Protection Facilities and other protective equipment. A Party may exercise these rights from time to time as it deems necessary upon reasonable notice to the other Parties. The exercise or non-exercise by a Party of any such rights shall not be construed as an endorsement or confirmation of any element or condition of the Interconnection Facilities or the System Protection Facilities or other protective equipment or the operation thereof, or as a warranty as to the fitness, safety, desirability, or reliability of same. Any information that a Party obtains through the exercise of any of its rights under this Article 6.4 shall be deemed to be Confidential Information and treated pursuant to Article 22 of this GIA.

ARTICLE 7. METERING

7.1 General. Each Party shall comply with the Electric Reliability Organization requirements. Unless the Interconnection Customer is utilizing shared Interconnection Customer Interconnection Facilities, or unless otherwise agreed by the Parties, Transmission Owner, at its election, or otherwise Interconnection Customer, shall install Metering Equipment (the "Metering Party") at the Point of Interconnection prior to any operation of the Generating Facility. Transmission Owner, at its election, or otherwise

Interconnection Customer shall own, operate, test and maintain such Metering Equipment. Power flows to and from the Generating Facility shall be measured at or, at the Metering Party's option, compensated to, the Point of Interconnection. If Interconnection Customer will share Interconnection Facilities with any other projects, Interconnection Customer shall install Metering Equipment either on its own Generating Facility or its own non-shared facilities sufficient to measure the output of such Interconnection Customer's Generating Facility separately from any other Generating Facilities with which it will share Interconnection Facilities. The Metering Party shall provide metering quantities, in analog and/or digital form, to the other Parties upon request. Interconnection Customer shall bear all reasonable documented costs associated with the purchase, installation, operation, testing and maintenance of the Metering Equipment.

7.2 Check Meters. Interconnection Customer, at its option and expense, may install and operate, on its premises and on its side of the Point of Interconnection, one or more check meters to check the Metering Equipment owned by the Metering Party. Such check meters shall be for check purposes only and shall not be used for the measurement of power flows for purposes of this GIA, except as provided in Article 7.4 below. The check meters shall be subject at all reasonable times to inspection and examination by Transmission Provider, Transmission Owner or their designees. The installation, operation and maintenance thereof shall be performed entirely by Interconnection Customer in accordance with Good Utility Practice.

7.3 Standards. The Metering Party shall install, calibrate, and test revenue quality Metering Equipment in accordance with applicable ANSI standards.

7.4 Testing of Metering Equipment. The Metering Party shall inspect and test Metering Equipment upon installation and at least once every two (2) years thereafter. If requested to do so by a Party, the Metering Party shall, at the requesting Party's expense, inspect or test Metering Equipment more frequently than every two (2) years. The Metering Party shall give reasonable notice to the other Parties of the time when any inspection or test shall take place, and the other Parties may have representatives present at the test or inspection. If at any time Metering Equipment is found to be inaccurate or defective, it shall be adjusted, repaired or replaced at Interconnection Customer's expense, in order to provide accurate metering, unless the inaccuracy or defect is due to the Metering Party's failure to maintain, then the Metering Party shall pay. If Metering Equipment fails to register, or if the measurement made by Metering Equipment during a test varies by more than two percent (2%) from the measurement made by the standard meter used in the test, the Metering Party shall adjust the measurements by correcting all measurements for the period during which Metering Equipment was in error by using Interconnection Customer's check meters, if installed. If no such check meters are installed or if the period cannot be reasonably ascertained, the adjustment shall be for the period immediately preceding the test of the Metering Equipment equal to one-half the time from the date of the previous test of the Metering Equipment.

7.5 Metering Data. At Interconnection Customer's expense, the metered data shall be

telemetered to one or more locations designated by Transmission Provider and Transmission Owner and one or more locations designated by Interconnection Customer. Such telemetered data shall be used, under normal operating conditions, as the official measurement of the amount of energy delivered from the Generating Facility to the Point of Interconnection.

ARTICLE 8. COMMUNICATIONS

8.1 Interconnection Customer Obligations. Interconnection Customer shall maintain satisfactory operating communications with Transmission Provider's Transmission System dispatcher or representative designated by Transmission Provider. Interconnection Customer shall provide standard voice line, dedicated voice line and facsimile communications at its Generating Facility control room or central dispatch facility through use of either the public telephone system, or a voice communications system that does not rely on the public telephone system. Interconnection Customer shall also provide the dedicated data circuit(s) necessary to provide Interconnection Customer data to Transmission Provider as set forth in Appendix D, Security Arrangements Details. The data circuit(s) shall extend from the Generating Facility to the location(s) specified by Transmission Provider. Any required maintenance of such communications equipment shall be performed by and at the cost of Interconnection Customer. Operational communications shall be activated and maintained under, but not be limited to, the following events: system paralleling or separation, scheduled and unscheduled shutdowns, equipment clearances, and hourly and daily load data.

Unless the Generating Facility is an Intermittent Resource not relying on wind or solar as a fuel source, Interconnection Customer shall install communication and control equipment such that the Generating Facility can receive and respond to the appropriate dispatch signals while operating under the Tariff. Where applicable, the requirements of the communication and control equipment will be enumerated in Appendix C to this GIA.

8.2 Remote Terminal Unit (RTU). Prior to the Initial Synchronization Date of the Generating Facility, a remote terminal unit, or equivalent data collection and transfer equipment acceptable to both Parties, shall be installed by Interconnection Customer, or by Transmission Owner at Interconnection Customer's expense, to gather accumulated and instantaneous data to be telemetered to the location(s) designated by Transmission Owner and Transmission Provider through use of a dedicated point-to-point data circuit(s) as indicated in Article 8.1. The communication protocol for the data circuit(s) shall be specified by Transmission Owner and Transmission Provider. Instantaneous bi-directional analog real power and reactive power flow information must be telemetered directly to the location(s) specified by Transmission Provider and Transmission Owner.

Each Party will promptly advise the other Parties if it detects or otherwise learns of any metering, telemetry or communications equipment errors or malfunctions that require the attention and/or correction. The Party owning such equipment shall correct such error or malfunction as soon as reasonably feasible.

8.3 No Annexation. Any and all equipment placed on the premises of a Party shall be and remain the property of the Party providing such equipment regardless of the mode and manner of annexation or attachment to real property, unless otherwise mutually agreed by the Parties.

8.4 Provision of Data from a Variable Energy Resource. Interconnection Customer whose Generating Facility contains at least one Variable Energy Resource shall provide meteorological and forced outage data to the Transmission Provider to the extent necessary for the Transmission Provider's development and deployment of power production forecasts for that class of Variable Energy Resources. Interconnection Customer with a Variable Energy Resource having wind as the energy source will, upon request by the Transmission Provider, be required to provide Transmission Provider with site-specific meteorological data including: temperature, wind speed, wind direction, and atmospheric pressure. Interconnection Customer with a Variable Energy Resource having solar as the energy source will, upon request by the Transmission Provider, be required to provide the Transmission Provider with site-specific meteorological data including: temperature, atmospheric pressure, and irradiance. Transmission Provider and Interconnection Customer whose Generating Facility contains a Variable Energy Resource shall mutually agree to any additional meteorological data that are required for the development and deployment of a power production forecast. Interconnection Customer whose Generating Facility contains a Variable Energy Resource also shall submit data to Transmission Provider regarding all forced outages to the extent necessary for Transmission Provider's development and deployment of power production forecasts for that class of Variable Energy Resources. The exact specifications of the meteorological and forced outage data to be provided by Interconnection Customer to Transmission Provider, including the frequency and timing of data submittals, shall be made taking into account the size and configuration of the Variable Energy Resource, its characteristics, location, and its importance in maintaining generation resource adequacy and transmission system reliability in its area. All requirements for meteorological and forced outage data must be commensurate with the power production forecasting employed by Transmission Provider. Data requirements for meteorological and forced outage data will be negotiated by Transmission Provider and Interconnection Customer, and will be set forth in Appendix C, Interconnection Details, of this GIA.

ARTICLE 9. OPERATIONS

9.1 General. Each Party shall comply with the Electric Reliability Organization requirements. Each Party shall provide to any Party all information that may reasonably be required by that Party to comply with Applicable Laws and Regulations and Applicable Reliability Standards.

9.2 Local Balancing Authority Notification. At least three (3) months before Initial Synchronization Date, Interconnection Customer shall notify Transmission Provider and Transmission Owner in writing of the Local Balancing Authority in which the Generating Facility will be located. If Interconnection Customer elects to locate the Generating Facility through dynamic metering/scheduling in a Local Balancing Authority other than

the Local Balancing Authority in which the Generating Facility is physically located, and if permitted to do so by the relevant transmission tariffs, all necessary arrangements, including but not limited to those set forth in Article 7 and Article 8 of this GIA, and remote Local Balancing Authority generator interchange agreements, if applicable, and the appropriate measures under such agreements, shall be executed and implemented prior to the placement of the Generating Facility in the other Local Balancing Authority.

9.3 Transmission Provider and Transmission Owner Obligations. Transmission Provider shall cause the Transmission System and the Transmission Owner's Interconnection Facilities to be operated, maintained and controlled in a safe and reliable manner in accordance with this GIA. Transmission Provider, or its designee, may provide operating instructions to Interconnection Customer consistent with this GIA and the Tariff and, if applicable, Transmission Owner's operating protocols and procedures as they may change from time to time. Transmission Provider will consider changes to its operating protocols and procedures proposed by Interconnection Customer.

9.4 Interconnection Customer Obligations. Interconnection Customer shall at its own expense operate, maintain and control the Generating Facility and the Interconnection Customer's Interconnection Facilities in a safe and reliable manner and in accordance with this GIA. The Generating Facility must be operated in accordance with the operating limits, if any, in the Interconnection Facilities Study and specified in Appendix C of this GIA. Interconnection Customer shall operate the Generating Facility and the Interconnection Customer's Interconnection Facilities in accordance with all applicable requirements of Transmission Provider or its designated Local Balancing Authority Operator of which the Generating Facility is part, as such requirements are set forth in Appendix C, Interconnection Details, of this GIA. Appendix C, Interconnection Details, will be modified to reflect changes to the requirements as they may change from time to time. Any Party may request that a Party provide copies of the requirements set forth in Appendix C, Interconnection Details, of this GIA.

9.5 Start-Up and Synchronization. Consistent with the Parties' mutually acceptable procedures, Interconnection Customer is responsible for the proper synchronization of the Generating Facility to the Transmission or Distribution System, as applicable.

9.6 Reactive Power and Primary Frequency Response.

9.6.1 Power Factor Design Criteria.

9.6.1.1 Synchronous Generation. Interconnection Customer shall design the Generating Facility to be capable of maintaining a composite power delivery at continuous rated power output at the Point of Interconnection at all power factors over 0.95 leading to 0.95 lagging, unless the Transmission Provider has established different requirements that apply to all synchronous generators in the Local Balancing Authority on a comparable basis. The applicable Local Balancing Authority power factor requirements are listed on the Transmission Provider's website at

https://cdn.misoenergy.org/Reactive_Generator_Requirements108137.pdf

and may be referenced in the Appendices to this GIA. The Generating Facility shall be capable of continuous dynamic operation throughout the power factor design range as measured at the Point of Interconnection. Such operation shall account for the net effect of all energy production devices on the Interconnection Customer's side of the Point of Interconnection.

9.6.1.2 Inverter-Based Resource Plants. Interconnection Customer shall design the Generating Facility to be capable of maintaining a composite power delivery at continuous rated power output at the high-side of the generator substation at all power factors over 0.95 leading to 0.95 lagging, unless the Transmission Provider has established different requirements that apply to all inverter-based resource plants in the Local Balancing Authority on a comparable basis. The applicable Local Balancing Authority power factor requirements are listed on the Transmission Provider's website at

https://cdn.misoenergy.org/Reactive_Generator_Requirements108137.pdf

and may be referenced in the Appendices to this GIA. This power factor range standard shall be dynamic and can be met using, for example, power electronics designed to supply this level of reactive capability (taking into account any limitations due to voltage level, real power output, etc.) or fixed and switched capacitors, or a combination of the two. This requirement shall only apply to newly interconnecting inverter-based resource plants that have not yet completed a System Impact Study as of the effective date of the Final Rule establishing this requirement (Order No. 827). These requirements apply to existing inverter-based resource plants making upgrades that require a new Generator Interconnection Agreement only where the Transmission Provider's System Impact Study shows the need for reactive power as a result of an upgrade. If applicable, these requirements will be memorialized in Appendix C to this GIA.

Additional reactive power requirements for inverter-based resource plants are provided in Appendix G of this GIA.

9.6.2 Voltage Schedules. Once Interconnection Customer has synchronized the Generating Facility with the Transmission System, Transmission Provider shall require Interconnection Customer to operate the Generating Facility to produce or absorb reactive power within the design limitations of the Generating Facility set forth in Article 9.6.1 (Power Factor Design Criteria), to maintain the output voltage or power factor at the Point of Interconnection as specified by Transmission Provider. Transmission Provider's voltage schedules shall treat all sources of reactive power in the Local Balancing Authority in an equitable and not unduly discriminatory manner. Transmission Provider shall exercise

Reasonable Efforts to provide Interconnection Customer with such schedules at least one (1) Calendar Day in advance, and may make changes to such schedules as necessary to maintain the reliability of the Transmission or Distribution System as applicable. Interconnection Customer shall operate the Generating Facility to maintain the specified output voltage or power factor at the Point of Interconnection within the design limitations of the Generating Facility set forth in Article 9.6.1 (Power Factor Design Criteria). If Interconnection Customer is unable to maintain the specified voltage or power factor, it shall promptly notify Transmission Provider's system operator, or its designated representative.

9.6.2.1 Voltage Regulators. Whenever the Generating Facility is operated in parallel with the Transmission or Distribution System as applicable and voltage regulators are capable of operation, Interconnection Customer shall operate the Generating Facility with its speed governors and voltage regulators in automatic operation. If the Generating Facility's voltage regulators are not capable of such automatic operation, Interconnection Customer shall immediately notify Transmission Provider's system operator, or its designated representative, and ensure that such Generating Facility's reactive power production or absorption (measured in MVARs) are within the design capability of the Generating Facility's generating unit(s) and steady state stability limits. Interconnection Customer shall not cause its Generating Facility to disconnect automatically or instantaneously from the Transmission or Distribution System, as applicable, or trip any generating unit comprising the Generating Facility for an under or over frequency condition unless the abnormal frequency condition persists for a time period beyond the limits set forth in ANSI/IEEE Standard C37.106, or such other standard as applied to other generators in the Local Balancing Authority on a comparable basis.

9.6.3 Payment for Reactive Power. Payments for reactive power shall be pursuant to any tariff or rate schedule filed by Transmission Provider and approved by the FERC.

9.6.4 Primary Frequency Response. This Section 9.6.4 shall only apply in the event that the Interconnection Request for the Generating Facility completed Definitive Planning Phase Interconnection Customer Decision Point 2 after May 15, 2018.

Interconnection Customer shall ensure the primary frequency response capability of its Generating Facility by installing, maintaining, and operating a functioning governor or equivalent controls. The term "functioning governor or equivalent controls" as used herein shall mean the required hardware and/or software that provides frequency responsive real power control with the ability to sense changes in system frequency and autonomously adjust the Generating Facility's real power output in accordance with the droop and deadband parameters and in the direction needed to correct frequency deviations. Interconnection Customer is

required to install a governor or equivalent controls with the capability of operating: (1) with a maximum 5 percent droop and ±0.036 Hz deadband; or (2) in accordance with the relevant droop, deadband, and timely and sustained response settings from an approved Reliability Organization reliability standard providing for equivalent or more stringent parameters. The droop characteristic shall be: (1) based on the nameplate capacity of the Generating Facility, and shall be linear in the range of frequencies between 59 to 61 Hz that are outside of the deadband parameter; or (2) based on an approved Electric Reliability Organization reliability standard providing for an equivalent or more stringent parameter. The deadband parameter shall be: the range of frequencies above and below nominal (60 Hz) in which the governor or equivalent controls is not expected to adjust the Generating Facility's real power output in response to frequency deviations. The deadband shall be implemented: (1) without a step to the droop curve, that is, once the frequency deviation exceeds the deadband parameter, the expected change in the Generating Facility's real power output in response to frequency deviations shall start from zero and then increase (for under-frequency deviations) or decrease (for over-frequency deviations) linearly in proportion to the magnitude of the frequency deviation; or (2) in accordance with an approved Electric Reliability Organization Reliability Standard providing for an equivalent or more stringent parameter. Interconnection Customer shall notify Transmission Provider that the primary frequency response capability of the Generating Facility has been tested and confirmed during commissioning. Once Interconnection Customer has synchronized the Generating Facility with the Transmission System, Interconnection Customer shall operate the Generating Facility consistent with the provisions specified in Articles 9.6.4.1 and 9.6.4.2 of this GIA. The primary frequency response requirements contained herein shall apply to both synchronous and inverter-based resource plant Generating Facilities.

9.6.4.1 Governor or Equivalent Controls. Whenever the Generating Facility is operated in parallel with the Transmission System, Interconnection Customer shall operate the Generating Facility with its governor or equivalent controls in service and responsive to frequency. Interconnection Customer shall: (1) in coordination with Transmission Provider and/or the relevant balancing authority, set the deadband parameter to: (a) a maximum of ±0.036 Hz and set the droop parameter to a maximum of 5 percent; or (b) implement the relevant droop and deadband settings from an approved Regional Reliability Organization reliability standard that provides for equivalent or more stringent parameters. Interconnection Customer shall be required to provide the status and settings of the governor or equivalent controls to Transmission Provider and/or the relevant balancing authority upon request. If Interconnection Customer needs to operate the Generating Facility with its governor or equivalent controls not in service, Interconnection Customer shall immediately notify Transmission Provider and the relevant balancing authority, and provide both with the following information: (1) the operating status of the governor or

equivalent controls (i.e., whether it is currently out of service or when it will be taken out of service); (2) the reasons for removing the governor or equivalent controls from service; and (3) a reasonable estimate of when the governor or equivalent controls will be returned to service. Interconnection Customer shall make Reasonable Efforts to return its governor or equivalent controls into service as soon as practicable. Interconnection Customer shall make Reasonable Efforts to keep outages of the Generating Facility's governor or equivalent controls to a minimum whenever the Generating Facility is operated in parallel with the Transmission System.

9.6.4.2 Timely and Sustained Response. Interconnection Customer shall ensure that the Generating Facility's real power response to sustained frequency deviations outside of the deadband setting is automatically provided and shall begin immediately after frequency deviates outside of the deadband, and to the extent the Generating Facility has operating capability in the direction needed to correct the frequency deviation. Interconnection Customer shall not block or otherwise inhibit the ability of the governor or equivalent controls to respond and shall ensure that the response is not inhibited, except under certain operational constraints including, but not limited to, ambient temperature limitations, physical energy limitations, outages of mechanical equipment, or regulatory requirements. The Generating Facility shall sustain the real power response at least until system frequency returns to a value within the deadband setting of the governor or equivalent controls. A Commission-approved reliability standard with equivalent or more stringent requirements shall supersede the above requirements.

9.6.4.3 Exemptions. Generating Facilities that are regulated by the United States Nuclear Regulatory Commission shall be exempt from Articles 9.6.4, 9.6.4.1, and 9.6.4.2 of this GIA. Generating Facilities that are behind the meter generation that is sized-to-load (i.e., the thermal load and the generation are near-balanced in real-time operation and the generation is primarily controlled to maintain the unique thermal, chemical, or mechanical output necessary for the operating requirements of its host facility) shall be required to install primary frequency response capability in accordance with the droop and deadband capability requirements specified in Article 9.6.4, but shall be otherwise exempt from the operating requirements in Articles 9.6.4, 9.6.4.1, 9.6.4.2, and 9.6.4.4 of this GIA.

9.6.4.4 Electric Storage Resources. Interconnection Customer interconnecting an electric storage resource shall establish an operating range in Appendix C that specifies a minimum state of charge and a maximum state of charge between which the electric storage resource will be required to provide primary frequency response consistent with the

conditions set forth in Articles 9.6.4, 9.6.4.1, 9.6.4.2 and 9.6.4.3 of this GIA. Appendix C shall specify whether the operating range is static or dynamic, and shall consider (1) the expected magnitude of frequency deviations in the interconnection; (2) the expected duration that system frequency will remain outside of the deadband parameter in the interconnection; (3) the expected incidence of frequency deviations outside of the deadband parameter in the interconnection; (4) the physical capabilities of the electric storage resource; (5) operational limitations of the electric storage resource due to manufacturer specifications; and (6) any other relevant factors agreed to by Transmission Provider and Interconnection Customer, and in consultation with the relevant transmission owner or balancing authority as appropriate. If the operating range is dynamic, then Appendix C must establish how frequently the operating range will be reevaluated and the factors that may be considered during its reevaluation.

Interconnection Customer's electric storage resource is required to provide timely and sustained primary frequency response consistent with Article 9.6.4.2 of this GIA when it is online and dispatched to inject electricity to the Transmission System and/or receive electricity from the Transmission System. This excludes circumstances when the electric storage resource is not dispatched to inject electricity to the Transmission System and/or dispatched to receive electricity from the Transmission System.

9.6.4.5 Inverter-Based Resource Plants. Additional primary frequency response requirements for inverter-based resource plants, including electric storage resources, are provided in Appendix G of this GIA.

9.7 Outages and Interruptions.

9.7.1 Outages.

9.7.1.1 Outage Authority and Coordination. Interconnection Customer and Transmission Owner may each in accordance with Good Utility Practice in coordination with the other Party and Transmission Provider remove from service any of its respective Interconnection Facilities, System Protection Facilities, Network Upgrades, System Protection Facilities or Distribution Upgrades that may impact the other Party's facilities as necessary to perform maintenance or testing or to install or replace equipment. Absent an Emergency Condition, the Party scheduling a removal of such facility(ies) from service will use Reasonable Efforts to notify one another and schedule such removal on a date and time mutually acceptable to the Parties. In all circumstances, any Party planning to remove such facility(ies) from service shall use Reasonable Efforts to minimize the effect on the other Parties of such removal.

9.7.1.2 Outage Schedules. Transmission Provider shall post scheduled outages of transmission facilities on the OASIS. Interconnection Customer shall submit its planned maintenance schedules for the Generating Facility to Transmission Provider and Transmission Owner for a minimum of a rolling twenty-four (24) month period in accordance with the Transmission Provider's procedures. Interconnection Customer shall update its planned maintenance schedules as necessary. Transmission Provider may request Interconnection Customer to reschedule its maintenance as necessary to maintain the reliability of the Transmission System; provided, however, adequacy of generation supply shall not be a criterion in determining Transmission System reliability.

Transmission Provider shall compensate, pursuant to applicable Transmission Provider tariff or rate schedule, Interconnection Customer for any additional direct costs that Interconnection Customer incurs as a result of having to reschedule maintenance, including any additional overtime, breaking of maintenance contracts or other costs above and beyond the cost Interconnection Customer would have incurred absent the Transmission Provider's request to reschedule maintenance. Interconnection Customer will not be eligible to receive compensation, if during the twelve (12) months prior to the date of the scheduled maintenance, Interconnection Customer had modified its schedule of maintenance activities.

Costs shall be determined by negotiation between Transmission Provider and Interconnection Customer prior to implementation of the voluntary change in outage schedules, or if such request is made by or on behalf of a Transmission Customer requesting firm service, costs and recovery of costs shall be determined through a bilateral agreement between the Transmission Customer and Interconnection Customer. Voluntary changes to outage schedules under this Article 9.7.1.2 are separate from actions and compensation required under Article 13 and for which costs are recovered in accordance with Transmission Provider's applicable tariff or rate schedule.

9.7.1.3 Outage Restoration. If an outage on either the Interconnection Customer's or Transmission Owner's Interconnection Facilities, Network Upgrades, System Protection Facilities or Distribution Upgrades adversely affects a Party's operations or facilities, the Party that owns or controls the facility that is out of service shall use Reasonable Efforts to promptly restore such facility(ies) to a normal operating condition consistent with the nature of the outage. The Party that owns or controls the facility that is out of service shall provide the other Parties, to the extent such information is known, information on the nature of the Emergency Condition, an estimated time of restoration,

and any corrective actions required. Initial verbal notice shall be followed up as soon as practicable with written notice to the other Parties explaining the nature of the outage.

9.7.2 Interruption of Service. If required by Good Utility Practice to do so, Transmission Provider may require Interconnection Customer to interrupt or reduce deliveries of electricity if such delivery of electricity could adversely affect Transmission Provider's ability to perform such activities as are necessary to safely and reliably operate and maintain the Transmission System. The following provisions shall apply to any interruption or reduction permitted under this Article 9.7.2:

9.7.2.1 The interruption or reduction shall continue only for so long as reasonably necessary under Good Utility Practice;

9.7.2.2 Any such interruption or reduction shall be made on an equitable, non-discriminatory basis with respect to all generating facilities directly connected to the Transmission or Distribution System, as applicable;

9.7.2.3 When the interruption or reduction must be made under circumstances which do not allow for advance notice, Transmission Provider shall notify Interconnection Customer by telephone as soon as practicable of the reasons for the curtailment, interruption, or reduction, and, if known, its expected duration. Telephone notification shall be followed by written notification as soon as practicable;

9.7.2.4 Except during the existence of an Emergency Condition, when the interruption or reduction can be scheduled without advance notice, Transmission Provider shall notify Interconnection Customer in advance regarding the timing of such scheduling and further notify Interconnection Customer of the expected duration. Transmission Provider shall coordinate with Interconnection Customer using Good Utility Practice to schedule the interruption or reduction during periods of least impact to Interconnection Customer, Transmission Owner and Transmission Provider;

9.7.2.5 The Parties shall cooperate and coordinate with each other to the extent necessary in order to restore the Generating Facility, Interconnection Facilities, and the Transmission or Distribution System, as applicable to their normal operating state, consistent with system conditions and Good Utility Practice.

9.7.3 Ride Through Capability and Performance. The Transmission System is designed to automatically activate a load-shed program as required by the Electric Reliability Organization in the event of an underfrequency system disturbance. Interconnection Customer shall implement under-frequency and over-frequency

relay set points for the Generating Facility as required by the Electric Reliability Organization to ensure frequency "ride through" capability of the Transmission System. Generating Facility response to frequency deviations of pre-determined magnitudes, both under-frequency and over-frequency deviations, shall be studied and coordinated with Transmission Provider in accordance with Good Utility Practice. Interconnection Customer shall also implement under-voltage and over-voltage relay set points, or equivalent electronic controls, as required by the Electric Reliability Organization to ensure voltage "ride through" capability of the Transmission System. The term "ride through" as used herein shall mean the ability of a Generating Facility to stay connected to and synchronized with the Transmission System during system disturbances within a range of under-frequency, over-frequency, under-voltage, and over-voltage conditions, in accordance with Good Utility Practice and consistent with any standards and guidelines that are applied to other Generating Facilities in the Balancing Authority Area on a comparable basis. For abnormal frequency conditions and voltage conditions within the "no trip zone" defined by Reliability Standard PRC-024-3 or successor mandatory ride through reliability standards, the non-synchronous Generating Facility must ensure that, within any physical limitations of the Generating Facility, its control and protection settings are configured or set to (1) continue active power production during disturbance and post disturbance periods at pre-disturbance levels, unless providing primary frequency response or fast frequency response; (2) minimize reductions in active power and remain within dynamic voltage and current limits, if reactive power priority mode is enabled, unless providing primary frequency response or fast frequency response; (3) not artificially limit dynamic reactive power capability during disturbances; and (4) return to pre-disturbance active power levels without artificial ramp rate limits if active power is reduced, unless providing primary frequency response or fast frequency response.

9.7.4 System Protection and Other Control Requirements.

9.7.4.1 System Protection Facilities. Interconnection Customer shall, at its expense, install, operate and maintain its System Protection Facilities as a part of the Generating Facility or the Interconnection Customer's Interconnection Facilities. Transmission Owner shall install at Interconnection Customer's expense any Transmission Owner's System Protection Facilities that may be required on the Transmission Owner's Interconnection Facilities or the Transmission Owner's transmission or distribution facilities as a result of the interconnection of the Generating Facility and the Interconnection Customer's Interconnection Facilities.

9.7.4.2 Interconnection Customer's and Transmission Owner's System Protection Facilities shall be designed and coordinated with Affected Systems in accordance with Good Utility Practice.

9.7.4.3 Each Party shall be responsible for protection of its facilities consistent

with Good Utility Practice.

9.7.4.4 Each Party's protective relay design shall incorporate the necessary test switches to perform the tests required in Article 6. The required test switches will be placed such that they allow operation of lockout relays while preventing breaker failure schemes from operating and causing unnecessary breaker operations and/or the tripping of the Generating Facility.

9.7.4.5 Each Party will test, operate and maintain their respective System Protection Facilities in accordance with Good Utility Practice.

9.7.4.6 Prior to the In-Service Date, and again prior to the Commercial Operation Date, Interconnection Customer or Transmission Owner, or their respective agents, shall perform a complete calibration test and functional trip test of the System Protection Facilities. At intervals suggested by Good Utility Practice and following any apparent malfunction of the System Protection Facilities, Interconnection Customer or Transmission Owner shall each perform both calibration and functional trip tests of their respective System Protection Facilities. These tests do not require the tripping of any in-service generating unit. These tests do, however, require that all protective relays and lockout contacts be activated.

9.7.5 Requirements for Protection. In compliance with Good Utility Practice, Interconnection Customer shall provide, install, own, and maintain relays, circuit breakers and all other devices necessary to remove any fault contribution of the Generating Facility to any short circuit occurring on the Transmission or Distribution System, as applicable, not otherwise isolated by Transmission Owner's equipment, such that the removal of the fault contribution shall be coordinated with the protective requirements of the Transmission or Distribution System, as applicable. Such protective equipment shall include, without limitation, a disconnecting device or switch with load-interrupting capability located between the Generating Facility and the Transmission or Distribution System, as applicable, at a site selected upon mutual agreement (not to be unreasonably withheld, conditioned or delayed) of the Parties. Interconnection Customer shall be responsible for protection of the Generating Facility and Interconnection Customer's other equipment from such conditions as negative sequence currents, over- or under-frequency, sudden load rejection, over- or under-voltage, and generator loss-of-field. Interconnection Customer shall be solely responsible to disconnect the Generating Facility and Interconnection Customer's other equipment if conditions on the Transmission or Distribution System, as applicable, could adversely affect the Generating Facility.

9.7.6 Power Quality. Neither Party's facilities shall cause excessive voltage flicker nor introduce excessive distortion to the sinusoidal voltage or current waves as

defined by ANSI Standard C84.1, in accordance with IEEE Standard 519, or any applicable superseding electric industry standard. In the event of a conflict between ANSI Standard C84.1, and any applicable superseding electric industry standard, the applicable superseding electric industry standard shall control.

9.8 Switching and Tagging Rules. Prior to the Initial Synchronization Date, each Party shall provide the other Parties a copy of its switching and tagging rules that are applicable to the other Parties' activities. Such switching and tagging rules shall be developed on a non-discriminatory basis. The Parties shall comply with applicable switching and tagging rules, as amended from time to time, in obtaining clearances for work or for switching operations on equipment.

9.9 Use of Interconnection Facilities by Other Parties.

9.9.1 Purpose of Interconnection Facilities. Except as may be required by Applicable Laws and Regulations, or as otherwise agreed to among the Parties, the Interconnection Facilities shall be constructed for the sole purpose of interconnecting the Generating Facility to the Transmission or Distribution System, as applicable, and shall be used for no other purpose.

9.9.2 Other Users. If required by Applicable Laws and Regulations or if the Parties mutually agree, such agreement not to be unreasonably withheld or delayed, to allow one or more Parties to use the Transmission Owner's Interconnection Facilities, or any part thereof, Interconnection Customer will be entitled to compensation for the capital expenses it incurred in connection with the Interconnection Facilities based upon the pro rata use of the Interconnection Facilities by Transmission Owner, all non-Party users, and Interconnection Customer, in accordance with Applicable Laws and Regulations or upon some other mutually-agreed upon methodology. In addition, cost responsibility for ongoing costs, including operation and maintenance costs associated with the Interconnection Facilities, will be allocated between Interconnection Customer and any non-Party users based upon the pro rata use of the Interconnection Facilities by Transmission Owner, all non-Party users, and Interconnection Customer, in accordance with Applicable Laws and Regulations or upon some other mutually agreed upon methodology. If the issue of such compensation or allocation cannot be resolved through such negotiations, it shall be submitted to Dispute Resolution pursuant to Section 12 of the Tariff.

9.10 Disturbance Analysis Data Exchange. The Parties will cooperate with one another in the analysis of disturbances to either the Generating Facility or the Transmission System by gathering and providing access to any information relating to any disturbance, including information from oscillography, protective relay targets, breaker operations and sequence of events records, and any disturbance information required by Good Utility Practice.

ARTICLE 10. MAINTENANCE

10.1 Transmission Owner Obligations. Transmission Owner shall maintain the Transmission Owner's Interconnection Facilities in a safe and reliable manner and in accordance with this GIA and all Applicable Laws and Regulations.

10.2 Interconnection Customer Obligations. Interconnection Customer shall maintain the Generating Facility and the Interconnection Customer's Interconnection Facilities in a safe and reliable manner and in accordance with this GIA and all Applicable Laws and Regulations.

10.3 Coordination. The Parties shall confer regularly to coordinate the planning, scheduling and performance of preventive and corrective maintenance on the Generating Facility and the Interconnection Facilities.

10.4 Secondary Systems. Each Party shall cooperate with the other in the inspection, maintenance, and testing of control or power circuits that operate below 600 volts, AC or DC, including, but not limited to, any hardware, control or protective devices, cables, conductors, electric raceways, secondary equipment panels, transducers, batteries, chargers, and voltage and current transformers that directly affect the operation of a Party's facilities and equipment which may reasonably be expected to impact another Party. Each Party shall provide advance notice to the other Parties before undertaking any work on such circuits, especially on electrical circuits involving circuit breaker trip and close contacts, current transformers, or potential transformers.

10.5 Operating and Maintenance Expenses. Subject to the provisions herein addressing the use of facilities by others, and except for operations and maintenance expenses associated with modifications made for providing Interconnection Service or Transmission Service to a non-Party and such non-Party pays for such expenses, Interconnection Customer shall be responsible for all reasonable expenses including overheads, associated with: (1) owning, operating, maintaining, repairing, and replacing Interconnection Customer's Interconnection Facilities; and (2) operation, maintenance, repair and replacement of Transmission Owner's Interconnection Facilities to the extent required by Transmission Owner on a comparable basis.

ARTICLE 11. PERFORMANCE OBLIGATION

11.1 Interconnection Customer's Interconnection Facilities. Interconnection Customer shall design, procure, construct, install, own and/or control the Interconnection Customer's Interconnection Facilities described in Appendix A at its sole expense.

11.2 Transmission Owner's Interconnection Facilities. Transmission Owner shall design, procure, construct, install, own and/or control the Transmission Owner's Interconnection Facilities described in Appendix A at the sole expense of Interconnection Customer.

11.3 Network Upgrades, System Protection Facilities and Distribution Upgrades.

Transmission Owner shall design, procure, construct, install, and own the Network Upgrades, Transmission Owner's System Protection Facilities and Distribution Upgrades described in Appendix A. Interconnection Customer shall be responsible for all costs related to Distribution Upgrades and/or Generator Upgrades. As required by Section 7.3.2.1 and 7.3.3.1 of Attachment X, Transmission Owner shall have provided Transmission Provider with written notice if Transmission Owner elects to fund the capital for the Network Upgrades and Transmission Owner's System Protection Facilities; otherwise, such facilities, if any, shall be solely funded by Interconnection Customer. In the event that the Transmission Owner elects to fund the capital costs of the Network Upgrades and/or Transmission Owner's System Protection Facilities, then the Parties shall enter into a Facilities Service Agreement. The Facilities Service Agreement shall take the form of the *pro forma* Facilities Service Agreement that is included as Appendix 14 of Attachment X to the MISO Tariff .

11.3.1 Contingencies Affecting Network Upgrades, System Protection Facilities and Distribution Upgrades. Network Upgrades, System Protection Facilities and Distribution Upgrades that are required to accommodate the Generating Facility may be modified because (1) a higher queued Interconnection Request withdrew or was deemed to have withdrawn, (2) the interconnection agreement associated with a higher queued Interconnection Request was terminated prior to the project's In-Service Date, (3) the Commercial Operation Date for a higher queued Interconnection Request is delayed, or the project itself is delayed (including due to suspension) such that facilities required to accommodate lower queued projects or the project itself may be altered, (4) the queue position is reinstated for a higher-queued Interconnection Request whose queue position was subject to dispute resolution, (5) changes occur in Transmission Provider or Transmission Owner equipment design standards or reliability criteria giving rise to the need for restudy, (6) the facilities required to accommodate a higher queued Interconnection Request were modified constituting a Material Modification pursuant to Section 4.4 of the GIP, (7) a GIA with an effective date prior to this GIA is terminated, (8) when ordered to restudy by FERC, or (9) the Network Upgrade Facilities Study for a Network Upgrade, which is to be included in this GIA, is completed after execution of this GIA. The higher queued Interconnection Requests that could impact the Network Upgrades, System Protection Facilities and Distribution Upgrades required to accommodate the Generating Facility, and possible Modifications that may result from the above listed events affecting the higher queued Interconnection Requests, to the extent such modifications are reasonably known and can be determined, and estimates of the costs associated with such required Network Upgrades, System Protection Facilities and Distribution Upgrades, are provided in Appendix A.

11.3.2 Agreement to Restudy and Cost Reallocation. In the event that one of the contingencies listed in Article 11.3.1 occurs, at any time before the Network Upgrades, Common Use Upgrades, Shared Network Upgrades, System Protection Facilities and/or Distribution Upgrades associated with higher queued Interconnection Requests with GIA in effect prior to this GIA are completed,

Transmission Provider may determine, in its discretion, that a restudy is required. If a restudy is required, Transmission Provider will provide notice to Interconnection Customer and Interconnection Customer agrees to enter into an Interconnection Study Agreement for such restudy. Transmission Provider will reevaluate the need for any Common Use Upgrade(s) and/or Shared Network Upgrade(s), and if still required, reallocate the cost and responsibility for any Common Use Upgrade and/or Shared Network Upgrade, without a restudy when possible, or with a restudy if the Transmission Provider deems it necessary in order to ensure reliability of the Transmission System. The Parties agree to amend Appendix A to this GIA in accordance with Article 30.10 to reflect the results of any cost reallocation required under this Article 11.3.2.

11.3.3 Agreement to Fund Shared Network Upgrades. Interconnection Customer agrees to fund Shared Network Upgrades, as determined by Transmission Provider. Where applicable, payments to fund Shared Network Upgrade(s) that are made to Transmission Provider by Interconnection Customer will be disbursed by Transmission Provider to the appropriate entities that funded the Shared Network Upgrades in accordance with Attachment X and Attachment FF of the Tariff. In the event that Interconnection Customer fails to meet its obligation to fund Shared Network Upgrades, Transmission Owner and Transmission Provider shall not be responsible for the Interconnection Customer's funding obligation.

11.4 Transmission Credits.

11.4.1 Repayment of Amounts Advanced for Network Upgrades. Interconnection Customer shall be entitled to a cash repayment by Transmission Owner(s) and the Affected System Owner(s) that own the Network Upgrades, of the amount paid respectively to Transmission Owner and Affected System Operator, if any, for the Network Upgrades, as provided under Attachment FF of this Tariff and including any tax gross-up or other tax-related payments associated with the repayable portion of the Network Upgrades, and not repaid to Interconnection Customer pursuant to Article 5.17.8 or otherwise, to be paid to Interconnection Customer on a dollar-for-dollar basis for the non-usage sensitive portion of transmission charges, as payments are made under the Tariff and Affected System's Tariff for Transmission Services with respect to the Generating Facility. Any repayment shall include interest calculated in accordance with the methodology set forth in FERC's regulations at 18 C.F.R. § 35.19 (a)(2)(iii) from the date of any payment for Network Upgrades through the date on which Interconnection Customer receives a repayment of such payment pursuant to this subparagraph. Interest shall not accrue during periods in which Interconnection Customer has suspended construction pursuant to Article 11 or the Network Upgrades have been determined not to be needed pursuant to this Article 11.4.1. Interconnection Customer may assign such repayment rights to any person.

If the Generating Facility is designated a Network Resource under the Tariff, or

if there are otherwise no incremental payments for Transmission Service resulting from the use of the Generating Facility by Transmission Customer, and in the absence of another mutually agreeable payment schedule any repayments provided under Attachment FF shall be established equal to the applicable rate for Firm Point-To-Point Transmission Service for the pricing zone where the Network Load is located multiplied by the portion of the demonstrated output of the Generating Facility designated as a Network Resource by the Network Customer(s) or in the absence of such designation, equal to the monthly firm single system-wide rate defined under Schedule 7 of the Tariff multiplied by the portion of the demonstrated output of the Generating Facility under contract to Network Customer(s) and consistent with studies pursuant to Section 3.2.2.2 of the GIP.

Notwithstanding the foregoing, as applicable and consistent with the provisions of Attachment FF of this Tariff, Interconnection Customer, Transmission Provider, Transmission Owner, and Affected System Operator may adopt any alternative payment schedule that is mutually agreeable so long as Transmission Owner and Affected System Operator take one of the following actions no later than five (5) years from the Commercial Operation Date: (1) return to Interconnection Customer any amounts advanced for Network Upgrades not previously repaid, or (2) declare in writing that Transmission Owner or Affected System Operator will continue to provide payments to Interconnection Customer on a dollar-for-dollar basis for the non-usage sensitive portion of transmission charges, or develop an alternative schedule that is mutually agreeable and provides for the return of all amounts advanced for Network Upgrades not previously repaid; however, full reimbursement shall not extend beyond twenty (20) years from the Commercial Operation Date.

If the Generating Facility is installed in phases, the amount eligible for refund as each phase achieves Commercial Operation will be reduced by the proportional amount of generation capacity not yet installed. However, all facilities in Appendix A other than the Generating Facility shall be built without consideration for the phasing of the Generating Facility as though the entire Generating Facility will be placed in Commercial Operation for the full output or increased output of the Generating Facility constructed by Interconnection Customer under this GIA.

If the Generating Facility fails to achieve Commercial Operation, but it or another generating facility is later constructed and makes use of the Network Upgrades, Transmission Owner and Affected System Operator shall at that time reimburse Interconnection Customer for the remaining applicable amounts that may be refundable pursuant to Attachment FF of this Tariff that were advanced for the Network Upgrades on their respective systems as described above. Before any such reimbursement can occur, Interconnection Customer, or the entity that ultimately constructs the Generating Facility, if different, is responsible for identifying the entity to which the reimbursement must be made.

11.4.2 Special Provisions for Transmission Provider as an Affected System to be covered under Separate Agreements. When the Transmission Owner's Transmission or Distribution System (including for this Article 11.4.2 independent distribution systems connected to the Transmission System) is an Affected System for an interconnection in another electric system, Transmission Provider will coordinate the performance of Interconnection Studies with the other system. Transmission Provider will determine if any Network Upgrades or Distribution Upgrades, which may be required on the Transmission System as a result of the interconnection, would not have been needed but for the interconnection. Unless Transmission Owner provides, under the interconnection agreement between Interconnection Customer and the other system, for the repayment of amounts advanced to Transmission Provider or an impacted Transmission Owner for Network Upgrades, Interconnection Customer, Transmission Provider, and the impacted Transmission Owner(s) shall enter into an agreement that provides for such repayment by Transmission Owner(s) as directed by Transmission Provider. The agreement shall specify the terms governing payments to be made by Interconnection Customer to the Affected System Operator as well as the payment of refunds by the Affected System Operator.

11.4.3 Notwithstanding any other provision of this GIA, nothing herein shall be construed as relinquishing or foreclosing any rights, including but not limited to firm transmission rights, capacity rights, transmission congestion rights, or transmission credits, that Interconnection Customer, shall be entitled to, now or in the future under any other agreement or tariff as a result of, or otherwise associated with, the transmission capacity, if any, created by the Network Upgrades, including the right to obtain cash reimbursement or transmission credits for transmission service that is not associated with the Generating Facility.

11.5 Initial Payment. For upgrades that the Transmission Owner has elected to self-fund, the Interconnection Customer is responsible for making the initial payment for the total cost of Network Upgrades (excluding JTIQ Upgrades) or Transmission Owner's System Protection Facilities in the form of security pursuant to Article 11.6. For upgrades where the Transmission Owner did not elect to self-fund, the Interconnection Customer shall elect (and provide its election to the Transmission Provider within five days of the commencement of negotiation of the GIA pursuant to Section 11.2 of the GIP) to make either 1) an initial payment equal to twenty (20) percent of the total cost of Network Upgrades (excluding JTIQ Upgrades), Transmission Owner Interconnection Facilities, Transmission Owner's System Protection Facilities, Distribution Upgrades and/or Generator Upgrades (if the In-Service Date is less than or equal to five (5) years of the initial payment date); or 2) an initial payment equal to ten (10) percent of the total cost of Network Upgrades (excluding JTIQ Upgrades), Transmission Owner Interconnection Facilities, Transmission Owner's System Protection Facilities, Distribution Upgrades and/or Generator Upgrades (if the In-Service Date exceeds the initial payment date by

more than five (5) years); or 3) the total cost of Network Upgrades (excluding JTIQ Upgrades), Transmission Owner Interconnection Facilities, Transmission Owner's System Protection Facilities, Distribution Upgrades and/or Generator Upgrades in the form of security pursuant to Article 11.6. The initial payment shall be provided to Transmission Owner by Interconnection Customer pursuant to this Article 11.5 within the later of a) forty-five (45) Calendar Days of the execution of the GIA by all Parties, or b) forty-five (45) Calendar Days of acceptance by FERC if the GIA is filed unexecuted and the payment is being protested by Interconnection Customer, or c) forty-five (45) Calendar Days of the filing if the GIA is filed unexecuted and the initial payment is not being protested by Interconnection Customer. If the Interconnection Customer made its milestone payments in the form of cash and the Interconnection Customer elects a cash initial payment, then the Transmission Provider shall transfer those funds to the Transmission Owner on the Interconnection Customer's behalf.

11.6 Provision of Security. Unless a milestone cash payment schedule is provided in Appendix B, Interconnection Customer shall, at least forty-five (45) Calendar Days prior to the commencement of the design, procurement, installation, or construction of a discrete portion of a facility, not otherwise funded under Article 11.5, provide additional security. Additionally, the Interconnection Customer will be required to provide security more than forty-five (45) Calendar Days in advance if requested by Transmission Owner because regulatory approvals are required for the construction of such facilities. Interconnection Customer shall provide Transmission Owner, at Interconnection Customer's selection, a guarantee, a surety bond, letter of credit or other form of security that is reasonably acceptable to Transmission Owner and is consistent with the Uniform Commercial Code of the jurisdiction identified in Article 14.2.1. Such security for payment, as specified in Appendix B of this GIA, shall be in an amount sufficient to cover the applicable costs and cost commitments, in addition to those funded under Article 11.5, required of the Party responsible for building the facilities pursuant to the construction schedule developed in Appendix B for designing, engineering, seeking regulatory approval from any Governmental Authority, constructing, procuring and installing the applicable portion of the Transmission Owner's Interconnection Facilities, Transmission Owner's System Protection Facilities, Network Upgrades, Distribution Upgrades or Stand-Alone Network Upgrades and shall be reduced on a dollar-for-dollar basis for payments made to Transmission Owner for these purposes. Transmission Owner must use the milestone payments required under the GIP before requiring Interconnection Customer to submit additional security. Transmission Owner must specify, in Appendix B of this GIA, the dates for which Interconnection Customer must provide additional security for construction of each discrete portion of Transmission Owner's Interconnection Facilities, Network Upgrades, or Distribution Upgrades and Interconnection Customer must provide such additional security.

In addition:

11.6.1 The guarantee must be made by an entity that meets the creditworthiness requirements of Transmission Owner, and contain terms and conditions that guarantee payment of any amount that may be due from Interconnection

Customer, up to an agreed-to maximum amount.

11.6.2 The letter of credit must be issued by a financial institution reasonably acceptable to Transmission Owner and must specify a reasonable expiration date.

11.6.3 The surety bond must be issued by an insurer reasonably acceptable to Transmission Owner and must specify a reasonable expiration date.

11.6.4 If the Shared Network Upgrade is not in service, Interconnection Customer will not be required to make a payment under Schedule 26-B until the Shared Network Upgrade is in service, but Interconnection Customer will provide, as applicable, an Irrevocable Letter of Credit to fund any Shared Network Upgrade pursuant to Attachment FF of the Tariff. The Irrevocable Letter of Credit shall be in an amount sufficient to cover the Interconnection Customer's share of the applicable costs and cost commitments associated with the Shared Network Upgrades. Transmission Provider may periodically adjust the Interconnection Customer's share of the applicable costs and cost commitment of Shared Network Upgrades and may require Interconnection Customer to adjust the amount of the Irrevocable Letter of Credit accordingly.

11.7 Interconnection Customer Compensation. If Transmission Provider requests or directs Interconnection Customer to provide a service pursuant to Article 13.4 of this GIA, Transmission Provider shall compensate Interconnection Customer in accordance with any tariff or rate schedule filed by Transmission Provider and approved by the FERC.

11.8 Provision of Security for JTIQ Upgrades. If the Transmission Provider determines that the Interconnection Request meets the distribution factor and impact criteria specified in Section 9.4.2(d)((ii) of Rate Schedule 6 (MISO SPP JOA) and is included in the JTIQ Participation Group, Interconnection Customer shall be required to provide security in accordance with Attachment X, Appendix 18 (MISO JTIQ Commitment Agreement) and SPP's JTIQ Service Agreement.

ARTICLE 12. INVOICE

12.1 General. Each Party shall submit to the other Party, on a monthly basis, invoices of amounts due, if any, for the preceding month. Each invoice shall state the month to which the invoice applies and fully describe the services and equipment provided. The Parties may discharge mutual debts and payment obligations due and owing to each other on the same date through netting, in which case all amounts a Party owes to the other Party under this GIA, including interest payments or credits, shall be netted so that only the net amount remaining due shall be paid by the owing Party.

12.2 Final Invoice. Within six (6) months after completion of the construction of the Transmission Owner's Interconnection Facilities, Transmission Owner's System Protection Facilities, Distribution Upgrades and the Network Upgrades, Transmission

Owner shall provide an invoice of the final cost of the construction of the Transmission Owner's Interconnection Facilities, Transmission Owner's System Protection Facilities, Distribution Upgrades and the Network Upgrades and shall set forth such costs in sufficient detail to enable Interconnection Customer to compare the actual costs with the estimates and to ascertain deviations, if any, from the cost estimates. Transmission Owner shall refund, with interest (calculated in accordance with 18 C.F.R. Section 35.19a(a)(2)(iii), to Interconnection Customer any amount by which the actual payment by Interconnection Customer for estimated costs exceeds the actual costs of construction within thirty (30) Calendar Days of the issuance of such final construction invoice.

12.3 Payment. Invoices shall be rendered to the paying Party at the address specified in Appendix F. The Party receiving the invoice shall pay the invoice within thirty (30) Calendar Days of receipt. All payments shall be made in immediately available funds payable to the other Party, or by wire transfer to a bank named and account designated by the invoicing Party. Payment of invoices by a Party will not constitute a waiver of any rights or claims that Party may have under this GIA.

12.4 Disputes. In the event of a billing dispute among the Parties, Transmission Provider shall continue to provide Interconnection Service under this GIA as long as Interconnection Customer: (i) continues to make all payments not in dispute; and (ii) pays to Transmission Provider or Transmission Owner or into an independent escrow account the portion of the invoice in dispute, pending resolution of such dispute. If Interconnection Customer fails to meet these two requirements for continuation of service, then Transmission Provider may or, at Transmission Owner's request upon Interconnection Customer's failure to pay, Transmission Owner, shall provide notice to Interconnection Customer of a Default pursuant to Article 17. Within thirty (30) Calendar Days after the resolution of the dispute, the Party that owes money to another Party shall pay the amount due with interest calculated in accord with the methodology set forth in 18 C.F.R. § 35.19a(a)(2)(iii).

ARTICLE 13. EMERGENCIES

13.1 Obligations. Each Party shall comply with the Emergency Condition procedures of Transmission Provider, the Electric Reliability Organization, and Applicable Laws and Regulations.

13.2 Notice. Transmission Provider or Transmission Owner shall notify the other Parties promptly when it becomes aware of an Emergency Condition that affects the Transmission Owner's Interconnection Facilities or the Transmission or Distribution System, as applicable, that may reasonably be expected to affect Interconnection Customer's operation of the Generating Facility or the Interconnection Customer's Interconnection Facilities.

Interconnection Customer shall notify Transmission Provider and Transmission Owner, which includes by definition if applicable, the operator of a Distribution System, promptly when it becomes aware of an Emergency Condition that affects the Generating

Facility or the Interconnection Customer's Interconnection Facilities that may reasonably be expected to affect the Transmission or Distribution System, as applicable, or the Transmission Owner's Interconnection Facilities.

To the extent information is known, the notification shall describe the Emergency Condition, the extent of the damage or deficiency, the expected effect on the operation of Interconnection Customer's or Transmission Provider's or Transmission Owner's facilities and operations, its anticipated duration and the corrective action taken and/or to be taken. The initial notice shall be followed as soon as practicable with written notice.

13.3 Immediate Action. Unless, in a Party's reasonable judgment, immediate action is required, the Party exercising such judgment shall notify and obtain the consent of the other Parties, such consent to not be unreasonably withheld, prior to performing any manual switching operations at the Generating Facility or the Interconnection Customer's Interconnection Facilities in response to an Emergency Condition either declared by Transmission Provider or otherwise regarding the Transmission or Distribution System, as applicable.

13.4 Transmission Provider and Transmission Owner Authority.

13.4.1 General. Transmission Provider or Transmission Owner may take whatever actions or inactions with regard to the Transmission System or the Transmission Owner's Interconnection Facilities it deems necessary during an Emergency Condition in order to (i) preserve public health and safety, (ii) preserve the reliability of the Transmission System or the Transmission Owner's Interconnection Facilities, (iii) limit or prevent damage, and (iv) expedite restoration of service.

Transmission Provider or Transmission Owner shall use Reasonable Efforts to minimize the effect of such actions or inactions on the Generating Facility or the Interconnection Customer's Interconnection Facilities. Transmission Provider or Transmission Owner may, on the basis of technical considerations, require the Generating Facility to mitigate an Emergency Condition by taking actions necessary and limited in scope to remedy the Emergency Condition, including, but not limited to, directing Interconnection Customer to shut-down, start-up, increase or decrease the real or reactive power output of the Generating Facility; implementing a reduction or disconnection pursuant to Article 13.4.2; directing Interconnection Customer to assist with blackstart (if available) or restoration efforts; or altering the outage schedules of the Generating Facility and the Interconnection Customer's Interconnection Facilities. Interconnection Customer shall comply with all of Transmission Provider's or Transmission Owner's operating instructions concerning Generating Facility real power and reactive power output within the manufacturer's design limitations of the Generating Facility's equipment that is in service and physically available for operation at the time, in compliance with Applicable Laws and Regulations.

13.4.2 Reduction and Disconnection. Transmission Provider or Transmission Owner may reduce Interconnection Service or disconnect the Generating Facility or the Interconnection Customer's Interconnection Facilities, when such reduction or disconnection is necessary under Good Utility Practice due to Emergency Conditions. These rights are separate and distinct from any right of curtailment of Transmission Provider pursuant to the Tariff. When Transmission Provider can schedule the reduction or disconnection in advance, Transmission Provider shall notify Interconnection Customer of the reasons, timing and expected duration of the reduction or disconnection. Transmission Provider shall coordinate with Interconnection Customer and Transmission Owner using Good Utility Practice to schedule the reduction or disconnection during periods of least impact to Interconnection Customer, Transmission Owner and Transmission Provider. Any reduction or disconnection shall continue only for so long as reasonably necessary pursuant to Good Utility Practice. The Parties shall cooperate with each other to restore the Generating Facility, the Interconnection Facilities, and the Transmission System to their normal operating state as soon as practicable consistent with Good Utility Practice.

13.5 Interconnection Customer Authority. Consistent with Good Utility Practice and this GIA and the GIP, Interconnection Customer may take whatever actions or inactions with regard to the Generating Facility or the Interconnection Customer's Interconnection Facilities during an Emergency Condition in order to (i) preserve public health and safety, (ii) preserve the reliability of the Generating Facility or the Interconnection Customer's Interconnection Facilities, (iii) limit or prevent damage, and (iv) expedite restoration of service. Interconnection Customer shall use Reasonable Efforts to minimize the effect of such actions or inactions on the Transmission System and the Transmission Owner's Interconnection Facilities. Transmission Provider and Transmission Owner shall use Reasonable Efforts to assist Interconnection Customer in such actions.

13.6 Limited Liability. Except as otherwise provided in Article 11.6 of this GIA, no Party shall be liable to any other for any action it takes in responding to an Emergency Condition so long as such action is made in good faith and is consistent with Good Utility Practice.

13.7 Audit. In accordance with Article 25.3, any Party may audit the performance of another Party when that Party declared an Emergency Condition.

ARTICLE 14. REGULATORY REQUIREMENTS AND GOVERNING LAW

14.1 Regulatory Requirements. Each Party's obligations under this GIA shall be subject to its receipt of any required approval or certificate from one or more Governmental Authorities in the form and substance satisfactory to the applying Party, or the Party making any required filings with, or providing notice to, such Governmental Authorities, and the expiration of any time period associated therewith. Each Party shall in good faith seek, and if necessary assist the other Party and use its Reasonable Efforts to obtain such

other approvals. Nothing in this GIA shall require Interconnection Customer to take any action that could result in its inability to obtain, or its loss of, status or exemption under the Federal Power Act, the Public Utility Holding Company Act of 2005, as amended, or the Public Utility Regulatory Policies Act of 1978.

14.2 Governing Law.

14.2.1 The validity, interpretation and performance of this GIA and each of its provisions shall be governed by the laws of the state where the Point of Interconnection is located, without regard to its conflicts of law principles.

14.2.2 This GIA is subject to all Applicable Laws and Regulations.

14.2.3 Each Party expressly reserves the right to seek changes in, appeal, or otherwise contest any laws, orders, rules, or regulations of a Governmental Authority.

ARTICLE 15. NOTICES

15.1 General. Unless otherwise provided in this GIA, any notice, demand or request required or permitted to be given by any Party to the other Parties and any instrument required or permitted to be tendered or delivered by a Party in writing to the other Parties shall be effective when delivered and may be so given, tendered or delivered, by recognized national courier, or by depositing the same with the United States Postal Service with postage prepaid, for delivery by certified or registered mail, addressed to the Party, or personally delivered to the Party, at the address set out in Appendix F, Addresses for Delivery of Notices and Billings.

Either Party may change the notice information in this GIA by giving five (5) Business Days written notice prior to the effective date of the change.

15.2 Billings and Payments. Billings and payments shall be sent to the addresses set out in Appendix F.

15.3 Alternative Forms of Notice. Any notice or request required or permitted to be given by any Party to the other and not required by this GIA to be given in writing may be so given by telephone, facsimile or email to the telephone numbers and email addresses set out in Appendix F.

15.4 Operations and Maintenance Notice. Each Party shall notify the other Parties in writing of the identity of the person(s) that it designates as the point(s) of contact with respect to the implementation of Articles 9 and 10.

ARTICLE 16. FORCE MAJEURE

16.1 Force Majeure.

16.1.1 Economic hardship is not considered a Force Majeure event.

16.1.2 A Party shall not be considered to be in Default with respect to any obligation hereunder, (including obligations under Article 4 and 5), other than the obligation to pay money when due, if prevented from fulfilling such obligation by Force Majeure. A Party unable to fulfill any obligation hereunder (other than an obligation to pay money when due) by reason of Force Majeure shall give notice and the full particulars of such Force Majeure to the other Parties in writing or by telephone as soon as reasonably possible after the occurrence of the cause relied upon. Telephone, facsimile or email notices given pursuant to this Article shall be confirmed in writing as soon as reasonably possible and shall specifically state full particulars of the Force Majeure, the time and date when the Force Majeure occurred and when the Force Majeure is reasonably expected to cease. The Party affected shall exercise Reasonable Efforts to remove such disability with reasonable dispatch, but shall not be required to accede or agree to any provision not satisfactory to it in order to settle and terminate a strike or other labor disturbance.

ARTICLE 17. DEFAULT

17.1 Default

17.1.1 General. No Default shall exist where such failure to discharge an obligation (other than the payment of money) is the result of Force Majeure as defined in this GIA or the result of an act or omission of another Party. Upon a Breach, the non-Breaching Party or Parties shall give written notice of such Breach to the Breaching Party with a copy to the other Party if one Party gives notice of such Breach. Except as provided in Article 17.1.2, the Breaching Party shall have thirty (30) Calendar Days from receipt of the Breach notice within which to cure such Breach; provided however, if such Breach is not capable of cure within thirty (30) Calendar Days, the Breaching Party shall commence such cure within thirty (30) Calendar Days after notice and continuously and diligently complete such cure within ninety (90) Calendar Days from receipt of the Breach notice; and, if cured within such time, the Breach specified in such notice shall cease to exist.

17.1.2 Termination. If a Breach is not cured as provided in this Article, or if a Breach is not capable of being cured within the period provided for herein, the non-Breaching Party or Parties shall terminate this GIA, subject to Article 2.3.2 of this GIA, by written notice to the Breaching Party, with a copy to the other Party if one Party gives notice of termination, and be relieved of any further obligation hereunder and, whether or not that Party(ies) terminates this GIA, to recover from the Breaching Party all amounts due hereunder, plus all other damages and remedies to which it is (they are) entitled at law or in equity. The provisions of this Article will survive termination of this GIA.

17.1.3 Cross-Default. Pursuant to Article 11.3 of this GIA, the Parties shall enter into a

Facilities Service Agreement if the Transmission Owner has elected to fund the capital for the Network Upgrades and/or Transmission Owner's System Protection Facilities. Notwithstanding anything to the contrary contained in this GIA, a breach by Interconnection Customer of any provision, covenant, or other term or condition contained in the Facilities Service Agreement shall be considered a breach under this GIA. Such breach shall be subject to the terms of Article 17 of this GIA. If a default under this GIA results from the Interconnection Customer's breach of the Facilities Service Agreement and subsequent failure to cure, the Transmission Owner and Transmission Provider shall be entitled, but in no event required, to apply all rights and remedies available by reason of default under the Facilities Service Agreement and this GIA.

Pursuant to Section 11.3 of the GIP, an Interconnection Customer included in a JTIQ Participation Group shall execute or request the unexecuted filing both of the Transmission Provider's JTIQ Commitment Agreement and the JTIQ Service Agreement included in SPP's tariff. Notwithstanding anything to the contrary contained in this GIA, a breach by Interconnection Customer of any provision, covenant, or other term or condition contained in the JTIQ Commitment Agreement or SPP's JTIQ Service Agreement shall be considered a breach under this GIA. Such breach shall be subject to the terms of Article 17 of this GIA provided, however, that the manner and timing of cure of such breach shall adhere to the requirements of the applicable agreement and cure in accordance with the provisions of such agreement shall also cure the breach of this GI. If a default under this GIA results from the Interconnection Customer's breach of the JTIQ Commitment Agreement or SPP JTIQ Service Agreement and subsequent failure to cure, the Transmission Owner and Transmission Provider shall be entitled, but in no event required, to apply all rights and remedies available by reason of default under the JTIQ Commitment Agreement, SPP JTIQ Service Agreement, and this GIA.

17.2 Violation of Operating Assumptions for Generating Facilities. If Transmission Provider requires Interconnection Customer to memorialize the operating assumptions for the charging behavior of the Generating Facility that includes at least one electric storage resource in Appendix A of this GIA, Transmission Provider may consider Interconnection Customer to be in Breach of the GIA if Interconnection Customer fails to operate the Generating Facility in accordance with those operating assumptions for charging behavior. However, if Interconnection Customer operates contrary to the operating assumptions for charging behavior specified in Appendix A of this GIA at the direction of Transmission Provider, Transmission Provider shall not consider Interconnection Customer in Breach of this GIA.

ARTICLE 18. LIMITATION OF LIABILITY, INDEMNITY, CONSEQUENTIAL DAMAGES AND INSURANCE

18.1 Limitation of Liability. A Party shall not be liable to another Party or to any third party or other person for any damages arising out of actions under this GIA, including, but not limited to, any act or omission that results in an interruption, deficiency or imperfection of Interconnection Service, except as provided in this Tariff. The provisions set forth in the Tariff shall be additionally applicable to any Party acting in good faith to implement or comply with its obligations under this GIA, regardless of whether the obligation is preceded by a specific directive.

18.2 Indemnity. To the extent permitted by law, an Indemnifying Party shall at all times indemnify, defend and hold the other Parties harmless from Loss.

18.2.1 Indemnified Party. If an Indemnified Party is entitled to indemnification under this Article 18 as a result of a claim by a non-Party, and the Indemnifying Party fails, after notice and reasonable opportunity to proceed under Article 18.2, to assume the defense of such claim, such Indemnified Party may at the expense of the Indemnifying Party contest, settle or consent to the entry of any judgment with respect to, or pay in full, such claim.

18.2.2 Indemnifying Party. If an Indemnifying Party is obligated to indemnify and hold any Indemnified Party harmless under this Article 18, the amount owing to the Indemnified Party shall be the amount of such Indemnified Party's actual Loss, net of any insurance or other recovery.

18.2.3 Indemnity Procedures. Promptly after receipt by an Indemnified Party of any claim or notice of the commencement of any action or administrative or legal proceeding or investigation as to which the indemnity provided for in Article 18.2 may apply, the Indemnified Party shall notify the Indemnifying Party of such fact. Any failure of or delay in such notification shall not affect a Party's indemnification obligation unless such failure or delay is materially prejudicial to the Indemnifying Party.

The Indemnifying Party shall have the right to assume the defense thereof with counsel designated by such Indemnifying Party and reasonably satisfactory to the Indemnified Party. If the defendants in any such action include one or more Indemnified Parties and the Indemnifying Party and if the Indemnified Party reasonably concludes that there may be legal defenses available to it and/or other Indemnified Parties which are different from or additional to those available to the Indemnifying Party, the Indemnified Party shall have the right to select separate counsel to assert such legal defenses and to otherwise participate in the defense of such action on its own behalf. In such instances, the Indemnifying Party shall only be required to pay the fees and expenses of one additional attorney to represent an Indemnified Party or Indemnified Parties having such differing or additional legal defenses.

The Indemnified Party shall be entitled, at its expense, to participate in any such action, suit or proceeding, the defense of which has been assumed by the

Indemnifying Party. Notwithstanding the foregoing, the Indemnifying Party (i) shall not be entitled to assume and control the defense of any such action, suit or proceedings if and to the extent that, in the opinion of the Indemnified Party and its counsel, such action, suit or proceeding involves the potential imposition of criminal liability on the Indemnified Party, or there exists a conflict or adversity of interest between the Indemnified Party and the Indemnifying Party, in such event the Indemnifying Party shall pay the reasonable expenses of the Indemnified Party, and (ii) shall not settle or consent to the entry of any judgment in any action, suit or proceeding without the consent of the Indemnified Party, which shall not be reasonably withheld, conditioned or delayed.

18.3 Consequential Damages. Other than the Liquidated Damages heretofore described, in no event shall either Party be liable under any provision of this GIA for any losses, damages, costs or expenses for any special, indirect, incidental, consequential, or punitive damages, including but not limited to loss of profit or revenue, loss of the use of equipment, cost of capital, cost of temporary equipment or services, whether based in whole or in part in contract, in tort, including negligence, strict liability, or any other theory of liability; provided; however, that damages for which a Party may be liable to the other Party under another agreement will not be considered to be special, indirect, incidental, or consequential damages hereunder.

18.4 Insurance. Transmission Owner and Interconnection Customer shall, at their own expense, maintain in force throughout the period of this GIA pursuant to 18.4.9, and until released by the other Party, the following minimum insurance coverages, with insurers authorized to do business or an approved surplus lines carrier in the state where the Point of Interconnection is located:

18.4.1 Employers' Liability and Workers' Compensation Insurance providing statutory benefits in accordance with the laws and regulations of the state in which the Point of Interconnection is located.

18.4.2 Commercial General Liability Insurance including premises and operations, personal injury, broad form property damage, broad form blanket contractual liability coverage (including coverage for the contractual indemnification) products and completed operations coverage, coverage for explosion, collapse and underground hazards, independent contractors coverage, coverage for pollution to the extent normally available and punitive damages to the extent normally available and a cross liability endorsement, with minimum limits of One Million Dollars ($1,000,000) per occurrence/One Million Dollars ($1,000,000) aggregate combined single limit for personal injury, bodily injury, including death and property damage.

18.4.3 Comprehensive Automobile Liability Insurance, for coverage of owned and non-owned and hired vehicles, trailers or semi-trailers licensed for travel on public roads, with a minimum combined single limit of One Million Dollars

($1,000,000) each occurrence for bodily injury, including death, and property damage.

18.4.4 Excess Public Liability Insurance over and above the Employer's Liability, Commercial General Liability and Comprehensive Automobile Liability Insurance coverage, with a minimum combined single limit of Twenty Million Dollars ($20,000,000) per occurrence/Twenty Million Dollars ($20,000,000) aggregate.

18.4.5 The Commercial General Liability Insurance, Comprehensive Automobile Insurance and Excess Public Liability Insurance policies shall name the other Parties, their parents, associated and Affiliate companies and their respective directors, officers, agents, servants and employees ("Other Party Group") as additional insured. All policies shall contain provisions whereby the insurers waive all rights of subrogation in accordance with the provisions of this GIA against the Other Party Groups and provide thirty (30) Calendar Days' advance written notice to the Other Party Groups prior to anniversary date of cancellation or any material change in coverage or condition.

18.4.6 The Commercial General Liability Insurance, Comprehensive Automobile Liability Insurance and Excess Public Liability Insurance policies shall contain provisions that specify that the policies are primary and shall apply to such extent without consideration for other policies separately carried and shall state that each insured is provided coverage as though a separate policy had been issued to each, except the insurer's liability shall not be increased beyond the amount for which the insurer would have been liable had only one insured been covered. Each Party shall be responsible for its respective deductibles or retentions.

18.4.7 The Commercial General Liability Insurance, Comprehensive Automobile Liability Insurance and Excess Public Liability Insurance policies, if written on a Claims First Made Basis, shall be maintained in full force and effect for two (2) years after termination of this GIA, which coverage may be in the form of tail coverage or extended reporting period coverage if agreed by Transmission Owner and Interconnection Customer.

18.4.8 The requirements contained herein as to the types and limits of all insurance to be maintained by Transmission Owner and Interconnection Customer are not intended to and shall not in any manner, limit or qualify the liabilities and obligations assumed by Transmission Owner and Interconnection Customer under this GIA.

18.4.9 As of the date set forth in Appendix B, Milestones, and as soon as practicable after the end of each fiscal year or at the renewal of the insurance policy and in any event within ninety (90) Calendar Days thereafter, Interconnection Customer and Transmission Owner shall provide the other Party with

certification of all insurance required in this GIA, executed by each insurer or by an authorized representative of each insurer.

18.4.10 Notwithstanding the foregoing, Transmission Owner or Interconnection Customer may self-insure to meet the minimum insurance requirements of Articles 18.4.1 through 18.4.8, to the extent it maintains a self-insurance program; provided that, Transmission Owner's or Interconnection Customer's senior secured debt is rated at investment grade, or better, by Standard & Poor's and that its self-insurance program meets minimum insurance requirements under Articles 18.4.1 through 18.4.8. For any period of time that a Transmission Owner's or Interconnection Customer's senior secured debt is unrated by Standard & Poor's or is rated at less than investment grade by Standard & Poor's, such Party shall comply with the insurance requirements applicable to it under Articles 18.4.1 through 18.4.9. In the event that Transmission Owner or Interconnection Customer is permitted to self-insure pursuant to this article, it shall notify the other Party that it meets the requirements to self-insure and that its self-insurance program meets the minimum insurance requirements in a manner consistent with that specified in Article 18.4.9.

18.4.11 Transmission Owner and Interconnection Customer agree to report to each other in writing as soon as practical all accidents or occurrences resulting in injuries to any person, including death, and any property damage arising out of this GIA.

ARTICLE 19. ASSIGNMENT

19.1 Assignment. This GIA may be assigned by any Party only with the written consent of the other Parties; provided that a Party may assign this GIA without the consent of the other Parties to any Affiliate of the assigning Party with an equal or greater credit rating and with the legal authority and operational ability to satisfy the obligations of the assigning Party under this GIA; and provided further that Interconnection Customer shall have the right to assign this GIA, without the consent of either Transmission Provider or Transmission Owner, for collateral security purposes to aid in providing financing for the Generating Facility, provided that Interconnection Customer will promptly notify Transmission Provider of any such assignment. Any financing arrangement entered into by Interconnection Customer pursuant to this Article will provide that prior to or upon the exercise of the secured party's, trustee's or mortgagee's assignment rights pursuant to said arrangement, the secured creditor, the trustee or mortgagee will notify Transmission Provider of the date and particulars of any such exercise of assignment right(s), including providing Transmission Provider and Transmission Owner with proof that it meets the requirements of Article 11.5 and 18.4. Any attempted assignment that violates this Article is void and ineffective. Any assignment under this GIA shall not relieve a Party of its obligations, nor shall a Party's obligations be enlarged, in whole or in part, by reason thereof. Where required, consent to assignment will not be unreasonably withheld, conditioned or delayed.

ARTICLE 20. SEVERABILITY

20.1 **Severability**. If any provision in this GIA is finally determined to be invalid, void or unenforceable by any court or other Governmental Authority having jurisdiction, such determination shall not invalidate, void or make unenforceable any other provision, agreement or covenant of this GIA; provided that if Interconnection Customer (or any non-Party, but only if such non-Party is not acting at the direction of either Transmission Provider or Transmission Owner) seeks and obtains such a final determination with respect to any provision of the Alternate Option (Article 5.1.2), or the Negotiated Option (Article 5.1.4), then none of these provisions shall thereafter have any force or effect and the Parties' rights and obligations shall be governed solely by the Standard Option (Article 5.1.1).

ARTICLE 21. COMPARABILITY

21.1 **Comparability**. The Parties will comply with all applicable comparability and code of conduct laws, rules and regulations including such laws, rules and regulations of Governmental Authorities establishing standards of conduct, as amended from time to time.

ARTICLE 22. CONFIDENTIALITY

22.1 **Confidentiality.** Confidential Information shall include, without limitation, all information relating to a Party's technology, research and development, business affairs, and pricing, and any information supplied by a Party to another Party prior to the execution of this GIA.

Information is Confidential Information only if it is clearly designated or marked in writing as confidential on the face of the document, or, if the information is conveyed orally or by inspection, if the Party providing the information orally informs the Party receiving the information that the information is confidential. The Parties shall maintain as confidential any information that is provided and identified by a Party as Critical Energy Infrastructure Information (CEII), as that term is defined in 18 C.F.R. Section 388.113(c). Such confidentiality will be maintained in accordance with this Article 22.

If requested by the receiving Party, the disclosing Party shall provide in writing, the basis for asserting that the information referred to in this Article warrants confidential treatment, and the requesting Party may disclose such writing to the appropriate Governmental Authority. Each Party shall be responsible for the costs associated with affording confidential treatment to its information.

22.1.1 Term**.** During the term of this GIA, and for a period of three (3) years after the expiration or termination of this GIA, except as otherwise provided in this Article 22 or with regard to CEII, each Party shall hold in confidence and shall not disclose to any person Confidential Information. CEII shall be treated in

accordance with Commission policy and regulations.

22.1.2 Scope. Confidential Information shall not include information that the receiving Party can demonstrate: (1) is generally available to the public other than as a result of a disclosure by the receiving Party; (2) was in the lawful possession of the receiving Party on a non-confidential basis before receiving it from the disclosing Party; (3) was supplied to the receiving Party without restriction by a non-Party, who, to the knowledge of the receiving Party after due inquiry, was under no obligation to the disclosing Party to keep such information confidential; (4) was independently developed by the receiving Party without reference to Confidential Information of the disclosing Party; (5) is, or becomes, publicly known, through no wrongful act or omission of the receiving Party or Breach of this GIA; or (6) is required, in accordance with Article 22.1.7 of this GIA, Order of Disclosure, to be disclosed by any Governmental Authority or is otherwise required to be disclosed by law or subpoena, or is necessary in any legal proceeding establishing rights and obligations under this GIA. Information designated as Confidential Information will no longer be deemed confidential if the Party that designated the information as confidential notifies the receiving Party that it no longer is confidential.

22.1.3 Release of Confidential Information. No Party shall release or disclose Confidential Information to any other person, except to its Affiliates (limited by the Standards of Conduct requirements), subcontractors, employees, agents, consultants, or to non-parties who may be or are considering providing financing to or equity participation with Interconnection Customer, or to potential purchasers or assignees of Interconnection Customer, on a need-to-know basis in connection with this GIA, unless such person has first been advised of the confidentiality provisions of this Article 22 and has agreed to comply with such provisions. Notwithstanding the foregoing, a Party providing Confidential Information to any person shall remain primarily responsible for any release of Confidential Information in contravention of this Article 22.

22.1.4 Rights. Each Party retains all rights, title, and interest in the Confidential Information that it discloses to the receiving Party. The disclosure by a Party to the receiving Party of Confidential Information shall not be deemed a waiver by the disclosing Party or any other person or entity of the right to protect the Confidential Information from public disclosure.

22.1.5 No Warranties. By providing Confidential Information, no Party makes any warranties or representations as to its accuracy or completeness. In addition, by supplying Confidential Information, no Party obligates itself to provide any particular information or Confidential Information to another Party nor to enter into any further agreements or proceed with any other relationship or joint venture.

22.1.6 Standard of Care. Each Party shall use at least the same standard of care to

protect Confidential Information it receives as it uses to protect its own Confidential Information from unauthorized disclosure, publication or dissemination. Each Party may use Confidential Information solely to fulfill its obligations to another Party under this GIA or its regulatory requirements.

22.1.7 Order of Disclosure. If a court or a Governmental Authority or entity with the right, power, and apparent authority to do so requests or requires any Party, by subpoena, oral deposition, interrogatories, requests for production of documents, administrative order, or otherwise, to disclose Confidential Information, that Party shall provide the disclosing Party with prompt notice of such request(s) or requirement(s) so that the disclosing Party may seek an appropriate protective order or waive compliance with the terms of this GIA. Notwithstanding the absence of a protective order or waiver, the Party may disclose such Confidential Information which, in the opinion of its counsel, the Party is legally compelled to disclose. Each Party will use Reasonable Efforts to obtain reliable assurance that confidential treatment will be accorded any Confidential Information so furnished.

22.1.8 Termination of Agreement. Upon termination of this GIA for any reason, each Party shall, within ten (10) Calendar Days of receipt of a written request from another Party, use Reasonable Efforts to destroy, erase, or delete (with such destruction, erasure, and deletion certified in writing to the requesting Party) or return to the requesting Party, without retaining copies thereof, any and all written or electronic Confidential Information received from the requesting Party, except that each Party may keep one copy for archival purposes, provided that the obligation to treat it as Confidential Information in accordance with this Article 22 shall survive such termination.

22.1.9 Remedies**.** The Parties agree that monetary damages would be inadequate to compensate a Party for another Party's Breach of its obligations under this Article 22. Each Party accordingly agrees that the disclosing Party shall be entitled to equitable relief, by way of injunction or otherwise, if the receiving Party Breaches or threatens to Breach its obligations under this Article 22, which equitable relief shall be granted without bond or proof of damages, and the Breaching Party shall not plead in defense that there would be an adequate remedy at law. Such remedy shall not be deemed an exclusive remedy for the Breach of this Article 22, but shall be in addition to all other remedies available at law or in equity. The Parties further acknowledge and agree that the covenants contained herein are necessary for the protection of legitimate business interests and are reasonable in scope. No Party, however, shall be liable for indirect, incidental, or consequential or punitive damages of any nature or kind resulting from or arising in connection with this Article 22.

22.1.10 Disclosure to FERC, its Staff or a State**.** Notwithstanding anything in this Article 22 to the contrary, and pursuant to 18 CFR § 1b.20, if FERC or its staff, during the course of an investigation or otherwise, requests information from a

Party that is otherwise required to be maintained in confidence pursuant to this GIA, the Party shall provide the requested information to FERC or its staff, within the time provided for in the request for information. In providing the information to FERC or its staff, the Party must, consistent with 18 CFR § 388.112, request that the information be treated as confidential and non-public by FERC and its staff and that the information be withheld from public disclosure. Parties are prohibited from notifying the other Parties to this GIA prior to the release of the Confidential Information to FERC or its staff. The Party shall notify the other Parties to this GIA when it is notified by FERC or its staff that a request to release Confidential Information has been received by FERC, at which time any of the Parties may respond before such information would be made public, pursuant to 18 CFR § 388.112. Requests from a state regulatory body conducting a confidential investigation shall be treated in a similar manner if consistent with the applicable state rules and regulations.

22.1.11 Subject to the exception in Article 22.1.10, any information that a disclosing Party claims is competitively sensitive, commercial or financial information under this GIA shall not be disclosed by the receiving Party to any person not employed or retained by the receiving Party, except to the extent disclosure is (i) required by law; (ii) reasonably deemed by the receiving Party to be required to be disclosed in connection with a dispute between or among the Parties, or the defense of litigation or dispute; (iii) otherwise permitted by consent of the disclosing Party, such consent not to be unreasonably withheld; or (iv) necessary to fulfill its obligations under this GIA or as the Regional Transmission Organization or a Local Balancing Authority operator including disclosing the Confidential Information to a regional or national reliability organization. The Party asserting confidentiality shall notify the receiving Party in writing of the information that Party claims is confidential. Prior to any disclosures of that Party's Confidential Information under this subparagraph, or if any non-Party or Governmental Authority makes any request or demand for any of the information described in this subparagraph, the Party who received the Confidential Information from the disclosing Party agrees to promptly notify the disclosing Party in writing and agrees to assert confidentiality and cooperate with the disclosing Party in seeking to protect the Confidential Information from public disclosure by confidentiality agreement, protective order or other reasonable measures.

ARTICLE 23. ENVIRONMENTAL RELEASES

23.1 Each Party shall notify the other Parties, first orally and then in writing, of the release of any Hazardous Substances, any asbestos or lead abatement activities, or any type of remediation activities related to the Generating Facility or the Interconnection Facilities, each of which may reasonably be expected to affect another Party. The notifying Party shall: (i) provide the notice as soon as practicable, provided such Party makes a good faith effort to provide the notice no later than twenty-four hours after such Party becomes aware of the occurrence; and (ii) promptly furnish to the other Parties copies of any

publicly available reports filed with any Governmental Authorities addressing such events.

ARTICLE 24. INFORMATION REQUIREMENTS

24.1 Information Acquisition. Transmission Provider, Transmission Owner and Interconnection Customer shall submit specific information regarding the electrical characteristics of their respective facilities to each other as described below and in accordance with Applicable Reliability Standards.

24.2 Information Submission by Transmission Provider and Transmission Owner The initial information submission by Transmission Provider to Interconnection Customer, with copy provided to Transmission Owner, shall occur no later than one hundred eighty (180) Calendar Days prior to Trial Operation and shall include Transmission or Distribution System information, as applicable and available, necessary to allow Interconnection Customer to select equipment and meet any system protection and stability requirements, unless otherwise mutually agreed to by the Parties. On a monthly basis, Transmission Owner shall provide Interconnection Customer a status report on the construction and installation of Transmission Owner's Interconnection Facilities, Transmission Owner's System Protection Facilities, Distribution Upgrades and Network Upgrades, including, but not limited to, the following information: (1) progress to date; (2) a description of the activities since the last report (3) a description of the action items for the next period; and (4) the delivery status of equipment ordered.

24.3 Updated Information Submission by Interconnection Customer. The updated information submission by Interconnection Customer to Transmission Provider, with copy to Transmission Owner, including manufacturer information, shall occur no later than one hundred eighty (180) Calendar Days prior to the Trial Operation. Interconnection Customer shall submit to Transmission Provider and Transmission Owner a completed copy of the Generating Facility data requirements contained in Appendix 1 to the GIP. It shall also include any additional information provided to Transmission Provider for the Interconnection Facilities Study. Information in this submission shall be the most current Generating Facility design or expected performance data. Information submitted for stability models shall be compatible with Transmission Provider standard models. If there is no compatible model, Interconnection Customer will work with a consultant mutually agreed to by Transmission Provider and Interconnection Customer to develop and supply a standard model and associated information.

If the Interconnection Customer's data is materially different from what was originally provided to Transmission Provider pursuant to the Interconnection Study Agreement between Transmission Provider and Interconnection Customer, then Transmission Provider will conduct appropriate studies to determine the impact on the Transmission System based on the actual data submitted pursuant to this Article 24.3. Interconnection Customer shall not begin Trial Operation until such studies are completed.

24.4 Information Supplementation. Prior to the Commercial Operation Date, the Parties shall supplement their information submissions described above in this Article 24 with any and all "as-built" Generating Facility information or "as-tested" performance information that differs from the initial submissions or, alternatively, written confirmation that no such differences exist. Interconnection Customer shall conduct tests on the Generating Facility as required by Good Utility Practice, such as an open circuit "step voltage" test on the Generating Facility to verify proper operation of the Generating Facility's automatic voltage regulator.

Unless otherwise agreed, the test conditions shall include: (1) Generating Facility at synchronous speed; (2) automatic voltage regulator on and in voltage control mode; and (3) a five percent (5 %) change in Generating Facility terminal voltage initiated by a change in the voltage regulators reference voltage. Interconnection Customer shall provide validated test recordings showing the responses in Generating Facility terminal and field voltages. In the event that direct recordings of these voltages is impractical, recordings of other voltages or currents that mirror the response of the Generating Facility's terminal or field voltage are acceptable if information necessary to translate these alternate quantities to actual Generating Facility terminal or field voltages is provided. Generating Facility testing shall be conducted and results provided to Transmission Provider and Transmission Owner for each individual generating unit in a station.

Subsequent to the Commercial Operation Date, Interconnection Customer shall provide Transmission Provider and Transmission Owner any information changes due to equipment replacement, repair, or adjustment. Transmission Owner shall provide Interconnection Customer, with copy to Transmission Provider, any information changes due to equipment replacement, repair or adjustment in the directly connected substation or any adjacent Transmission Owner substation that may affect the Interconnection Customer's Interconnection Facilities equipment ratings, protection or operating requirements. The Parties shall provide such information no later than thirty (30) Calendar Days after the date of the equipment replacement, repair or adjustment.

ARTICLE 25. INFORMATION ACCESS AND AUDIT RIGHTS

25.1 Information Access. Each Party (the "disclosing Party") shall make available to the other Parties information that is in the possession of the disclosing Party and is necessary in order for the other Parties to: (i) verify the costs incurred by the disclosing Party for which another Party is responsible under this GIA; and (ii) carry out its obligations and responsibilities under this GIA. The Parties shall not use such information for purposes other than those set forth in this Article 25.1 and to enforce their rights under this GIA.

25.2 Reporting of Non-Force Majeure Events. A Party (the "notifying Party") shall notify the other Parties when the notifying Party becomes aware of its inability to comply with the provisions of this GIA for a reason other than a Force Majeure event. The Parties agree to cooperate with each other and provide necessary information regarding such inability to comply, including the date, duration, reason for the inability to comply, and

corrective actions taken or planned to be taken with respect to such inability to comply. Notwithstanding the foregoing, notification, cooperation or information provided under this Article shall not entitle any Party receiving such notification to allege a cause for anticipatory breach of this GIA.

25.3 Audit Rights. Subject to the requirements of confidentiality under Article 22 of this GIA, each Party shall have the right, during normal business hours, and upon prior reasonable notice to the other Parties, to audit at its own expense the other Parties' accounts and records pertaining to the Parties' performance or the Parties' satisfaction of obligations under this GIA. Such audit rights shall include audits of the other Parties' costs, calculation of invoiced amounts, the Transmission Provider's efforts to allocate responsibility for the provision of reactive support to the Transmission or Distribution System, as applicable, the Transmission Provider's efforts to allocate responsibility for interruption or reduction of generation, and each Party's actions in an Emergency Condition. Any audit authorized by this Article shall be performed at the offices where such accounts and records are maintained and shall be limited to those portions of such accounts and records that relate to each Party's performance and satisfaction of obligations under this GIA. Each Party shall keep such accounts and records for a period equivalent to the audit rights periods described in Article 25.4.

25.4 Audit Rights Periods.

25.4.1 Audit Rights Period for Construction-Related Accounts and Records. Accounts and records related to the design, engineering, procurement, and construction of the Transmission Owner's Interconnection Facilities, Transmission Owner's System Protection Facilities, Distribution Upgrades and Network Upgrades shall be subject to audit for a period of twenty-four months following Transmission Owner's issuance of a final invoice in accordance with Article 12.2.

25.4.2 Audit Rights Period for All Other Accounts and Records. Accounts and records related to a Party's performance or satisfaction of all obligations under this GIA other than those described in Article 25.4.1 shall be subject to audit as follows: (i) for an audit relating to cost obligations, the applicable audit rights period shall be twenty-four (24) months after the auditing Party's receipt of an invoice giving rise to such cost obligations; and (ii) for an audit relating to all other obligations, the applicable audit rights period shall be twenty-four (24) months after the event for which the audit is sought.

25.5 Audit Results. If an audit by a Party determines that an overpayment or an underpayment has occurred, a notice of such overpayment or underpayment shall be given to the Party or from whom the overpayment or underpayment is owed together with those records from the audit which support such determination.

ARTICLE 26. SUBCONTRACTORS

26.1 General. Nothing in this GIA shall prevent a Party from utilizing the services of any subcontractor as it deems appropriate to perform its obligations under this GIA; provided, however, that each Party shall require its subcontractors to comply with all applicable terms and conditions of this GIA in providing such services and each Party shall remain primarily liable to the other Parties for the performance of such subcontractor.

26.2 Responsibility of Principal. The creation of any subcontract relationship shall not relieve the hiring Party of any of its obligations under this GIA. The hiring Party shall be fully responsible to the other Parties for the acts or omissions of any subcontractor the hiring Party hires as if no subcontract had been made; provided, however, that in no event shall Transmission Provider or Transmission Owner be liable for the actions or inactions of Interconnection Customer or its subcontractors with respect to obligations of Interconnection Customer under Article 5 of this GIA. Any applicable obligation imposed by this GIA upon the hiring Party shall be equally binding upon, and shall be construed as having application to, any subcontractor of such Party.

26.3 No Limitation by Insurance. The obligations under this Article 26 will not be limited in any way by any limitation of subcontractor's insurance.

ARTICLE 27. DISPUTES

27.1 Submission. In the event any Party has a dispute, or asserts a claim, that arises out of or in connection with this GIA or its performance, such Party (the "disputing Party") shall provide the other Parties with written notice of the dispute or claim ("Notice of Dispute"). Such dispute or claim shall be referred to a designated senior representative of each Party for resolution on an informal basis as promptly as practicable after receipt of the Notice of Dispute by the non-disputing Parties. In the event the designated representatives are unable to resolve the claim or dispute through unassisted or assisted negotiations within thirty (30) Calendar Days of the non-disputing Parties' receipt of the Notice of Dispute, such claim or dispute shall be submitted for resolution in accordance with the dispute resolution procedures of the Tariff.

ARTICLE 28. REPRESENTATIONS, WARRANTIES AND COVENANTS

28.1 General. Each Party makes the following representations, warranties and covenants:

28.1.1 Good Standing. Such Party is duly organized, validly existing and in good standing under the laws of the state in which it is organized, formed, or incorporated, as applicable; that it is qualified to do business in the state or states in which the Generating Facility, Interconnection Facilities and Network Upgrades owned by such Party, as applicable, are located; and that it has the corporate power and authority to own its properties, to carry on its business as now being conducted and to enter into this GIA and carry out the transactions contemplated hereby and perform and carry out all covenants and obligations on

its part to be performed under and pursuant to this GIA.

28.1.2 Authority**.** Such Party has the right, power and authority to enter into this GIA, to become a Party hereto and to perform its obligations hereunder. This GIA is a legal, valid and binding obligation of such Party, enforceable against such Party in accordance with its terms, except as the enforceability thereof may be limited by applicable bankruptcy, insolvency, reorganization or other similar laws affecting creditors' rights generally and by general equitable principles (regardless of whether enforceability is sought in a proceeding in equity or at law).

28.1.3 No Conflict. The execution, delivery and performance of this GIA does not violate or conflict with the organizational or formation documents, or bylaws or operating agreement, of such Party, or any judgment, license, permit, order, material agreement or instrument applicable to or binding upon such Party or any of its assets.

28.1.4 Consent and Approval. Such Party has sought or obtained, or, in accordance with this GIA will seek or obtain, each consent, approval, authorization, order, or acceptance by any Governmental Authority in connection with the execution, delivery and performance of this GIA, and it will provide to any Governmental Authority notice of any actions under this GIA that are required by Applicable Laws and Regulations.

ARTICLE 29. {RESERVED}

ARTICLE 30. MISCELLANEOUS

30.1 Binding Effect. This GIA and the rights and obligations hereof, shall be binding upon and shall inure to the benefit of the successors and assigns of the Parties hereto.

30.1.1 Reversion. If offered pursuant to an Agency Agreement under which this GIA is executed by Transmission Provider as agent for the relevant Transmission Owner, in the event that the relevant Agency Agreement terminates, any HVDC Service offered by Transmission Provider under this GIA shall revert to the relevant Transmission Owner and Transmission Provider shall be released from all obligations and responsibilities under this GIA.

30.2 Conflicts. In the event of a conflict between the body of this GIA and any attachment, appendices or exhibits hereto, the terms and provisions of the body of this GIA shall prevail and be deemed the final intent of the Parties.

30.3 Rules of Interpretation. This GIA, unless a clear contrary intention appears, shall be construed and interpreted as follows: (1) the singular number includes the plural number and vice versa; (2) reference to any person includes such person's successors and assigns but, in the case of a Party, only if such successors and assigns are permitted by this GIA,

and reference to a person in a particular capacity excludes such person in any other capacity or individually; (3) reference to any agreement (including this GIA), document, instrument or tariff means such agreement, document, instrument, or tariff as amended or modified and in effect from time to time in accordance with the terms thereof and, if applicable, the terms hereof; (4) reference to any Applicable Laws and Regulations means such Applicable Laws and Regulations as amended, modified, codified, or reenacted, in whole or in part, and in effect from time to time, including, if applicable, rules and regulations promulgated thereunder; (5) unless expressly stated otherwise, reference to any Article, Section or Appendix means such Article of this GIA or such Appendix to this GIA, or such Section to the GIP or such Appendix to the GIP, as the case may be; (6) "hereunder", "hereof", "herein", "hereto" and words of similar import shall be deemed references to this GIA as a whole and not to any particular Article or other provision hereof or thereof; (7) "including" (and with correlative meaning "include") means including without limiting the generality of any description preceding such term; and (8) relative to the determination of any period of time, "from" means "from and including", "to" means "to but excluding" and "through" means "through and including."

30.4 Entire Agreement. This GIA, including all Appendices and attachments hereto, constitutes the entire agreement between the Parties with reference to the subject matter hereof, and supersedes all prior and contemporaneous understandings or agreements, oral or written, between the Parties with respect to the subject matter of this GIA. There are no other agreements, representations, warranties, or covenants, which constitute any part of the consideration for, or any condition to, any Party's compliance with its obligations under this GIA.

30.5 No Third Party Beneficiaries. This GIA is not intended to and does not create rights, remedies, or benefits of any character whatsoever in favor of any persons, corporations, associations, or entities other than the Parties, and the obligations herein assumed are solely for the use and benefit of the Parties, their successors in interest and, where permitted, their assigns.

30.6 Waiver. The failure of a Party to this GIA to insist, on any occasion, upon strict performance of any provision of this GIA will not be considered a waiver of any obligation, right, or duty of, or imposed upon, such Party.

Any waiver at any time by any Party of its rights with respect to this GIA shall not be deemed a continuing waiver or a waiver with respect to any other failure to comply with any other obligation, right, duty of this GIA. Termination or Default of this GIA for any reason by Interconnection Customer shall not constitute a waiver of the Interconnection Customer's legal rights to obtain Interconnection Service from Transmission Provider. Any waiver of this GIA shall, if requested, be provided in writing.

30.7 Headings. The descriptive headings of the various Articles of this GIA have been inserted for convenience of reference only and are of no significance in the interpretation or construction of this GIA.

30.8 Multiple Counterparts. This GIA may be executed in two or more counterparts, each of which is deemed an original but all constitute one and the same instrument.

30.9 Amendment. The Parties may by mutual agreement amend this GIA by a written instrument duly executed by all of the Parties.

30.10 Modification by the Parties. The Parties may by mutual agreement amend the Appendices to this GIA by a written instrument duly executed by all of the Parties. Such amendment shall become effective and a part of this GIA upon satisfaction of all Applicable Laws and Regulations.

30.11 Reservation of Rights. Transmission Provider shall have the right to make a unilateral filing with FERC to modify this GIA with respect to any rates, terms and conditions, charges, classifications of service, rule or regulation under Section 205 or any other applicable provision of the Federal Power Act and FERC's rules and regulations thereunder, and Transmission Owner and Interconnection Customer shall have the right to make a unilateral filing with FERC to modify this GIA pursuant to Section 206 or any other applicable provision of the Federal Power Act and FERC's rules and regulations thereunder; provided that each Party shall have the right to protest any such filing and to participate fully in any proceeding before FERC in which such modifications may be considered. Nothing in this GIA shall limit the rights of the Parties or of FERC under Sections 205 or 206 of the Federal Power Act and FERC's rules and regulations thereunder, except to the extent that the Parties otherwise mutually agree as provided herein.

30.12 No Partnership. This GIA shall not be interpreted or construed to create an association, joint venture, agency relationship, or partnership among or between the Parties or to impose any partnership obligation or partnership liability upon any Party. No Party shall have any right, power or authority to enter into any agreement or undertaking for, or act on behalf of, or to act as or be an agent or representative of, or to otherwise bind, the other Parties.

IN WITNESS WHEREOF, the Parties have executed this GIA in multiple originals; each of which shall constitute and be an original GIA among the Parties.

Transmission Provider
Midcontinent Independent System Operator, Inc.

By: _____ DMK 11/17/2025
Name: Aubrey Johnson
Title: Vice President, System Planning

Transmission Owner
Entergy Louisiana, LLC

By: John T. Anderson
Name: John T. Anderson
Title: VP - Project & Portfolio Development

Interconnection Customer
Entergy Louisiana, LLC

By: _____
Name: Phillip R. May
Title: President and CEO

APPENDICES TO GIA

Appendix A	Interconnection Facilities, System Protection Facilities, Distribution Upgrades, Generator Upgrades and Network Upgrades
Appendix B	Milestones
Appendix B-1	Pre-Certification Generation Test Notification Form
Appendix C	Interconnection Details
Appendix D	Security Arrangements Details
Appendix E	Commercial Operation Date
Appendix F	Addresses for Delivery of Notices and Billings
Appendix G	Interconnection Requirements for Inverter-Based Resource Plants
Appendix H	Interconnection Requirements for Provisional GIA
Appendix I	Requirements Applicable to Surplus Interconnection Service

Appendix A to GIA
Interconnection Facilities, System Protection Facilities, Distribution Upgrades, Generator Upgrades and Network Upgrades

1. Description of Generating Facility

Interconnection Customer shall install a 1,928 MVA facility, rated at 1,640 MW gross and 1,536 MW net, with all studies performed at or below these outputs. The Generating Facility is composed of two (2) Mitsubishi gas turbine generation units rated at 562 MVA / 478 MW each and two (2) Mitsubishi heat recovery steam generators rated at 402 MVA / 342 MW in a combined cycle plant. Interconnection Service provided under this agreement is 1,536 MW of conditional ERIS and/or NRIS that will become 1,536 MW of NRIS upon completion of all Network Upgrades, Common Use Upgrades, and Affected System Upgrades under this GIA and transmission assumptions listed in Table A10-1 of Exhibit A10.

Interconnection Customer shall install a switchyard with the appropriate protection equipment coordinated per Appendix C to this GIA. The Switchyard shall contain two (2) generator step-up transformers 230/23.5 kV 360/600 MVA, two (2) generator step-up transformers 230/21 kV 252/420 MVA, four (4) 4000 A 80kA circuit breakers connected as illustrated in Exhibit A1-1.

The Generating Facility shall provide reactive compensation as necessary to meet the FERC Order 827.

2. Interconnection Facilities

(a) Point of Interconnection.

i. The Point of Interconnection (POI) shall be at the point where the E0014 lead line connects to the Transmission Owner's Smalling 230kV yard substation bus.
ii. The Point of Change of Ownership (PCO) shall be at the Interconnection Customer's dead-end structure within the generation step-up yard.
iii. The Metering Equipment will be located on the Transmission Owner Interconnection Facilities and compensated to the Point of Interconnection. Refer to Exhibit A2 one-line diagram for the demarcation points of these facilities.

(b) Interconnection Facilities (including metering equipment) to be constructed by Interconnection Customer.

Interconnection Customer shall construct and own the Customer Interconnection Facilities. These facilities shall include:

- Two (2) approximately 0.28 mile of 230 kV generator lead lines using 954 ACSS Cardinal conductors.
- A servitude agreement will need to be executed between Interconnection Customer and Entergy for the transmission line connecting the PCO to

POI, and access road(s). Actual size and final location will be determined after detail design is complete. Below is a list of the servitudes and their preliminary dimensions:

- One PCO to POI servitude will be approximately 125 feet wide x 1800 feet long, approximately 5.15 acres and a second PCO to POI servitude will be approximately 125 feet wide x 1650 feet long, approximately 4.72 acres.

- The first underground servitude for E0014 ADSS fiber will be approximately 0.25 miles long between PCO and POI. The second underground servitude for E0014 ADSS fiber will be approximately 0.21 miles long between the PCO and POI. Total size and location will be determined after detail design is complete.
- The Interconnection Customer will provide to Transmission Owner a copy of wetland delineation for the new switching station site, access road and transmission line ROW, ESA Phase I report, and cultural resources constraint analysis/archeological survey, if required
- Interconnection Customer is responsible for coordinating and obtaining station service supply for the Interconnection Customer Interconnection Facilities and the Generating Facility. The Interconnection Customer will coordinate station supply with the local service territory provider to address normal and emergency back-up station power needs for Interconnection Customer Interconnection Facilities and for Generating Facility during construction and operation of those facilities. Net metering of Station Service power may be obtained per the requirements of Transmission Provider's Schedule 20

(c) Transmission Owner Interconnection Facilities (including metering equipment) to be constructed by Transmission Owner. Transmission Owner Interconnection Facilities shall consist of the following equipment:

i. Smalling 500/230 kV Substation

General

a) Customer will transmit generator breaker status, telemetering data including MW, MVAR, MWhr and MVARhrs to Entergy's Smalling 500/230kV Substation Remote Terminal Unit (RTU) utilizing underground fiber optic cable.
b) Customer will design line protection compatible with the line relaying installed at Entergy's Smalling 500/230kV Substation.

Site

a) Installation of 5/8'' x 10' ground rods shall be installed near major equipment such as surge arresters.

Foundations

a) Drilled pier and pad foundations will be used for all equipment support structure.
b) The foundation scope of work includes design and construction of the following:

- Install twenty-nine (29) 36-inch diameter 17-foot-long drilled pier foundations for 230kV single phase, low bus support insulators.
- Install six (6) 42 inch diameter 22-foot-long drilled pier foundations for 230kV single phase, high bus support insulators.
- Install six (6) 36-inch diameter 20-foot-long drilled pier foundations for 230kV surge arrester structures.
- Install six (6) 36-inch diameter 20-foot-long drilled pier foundations for 230kV CCVT structures.
- Install two (2) set of four (4) 72-inch diameter 30-foot-long drilled pier foundations for 230kV deadend structure.

Electrical

a) Steel Structures
- Six (6) single-phase 230kV high bus support structure.
- Twenty-nine (29) single-phase 230kV low bus support structure.
- Six (6) 230kV surge arrester structures.
- Six (6) 230kV CCVT structures.
- Two (2) three-phase 230kV deadend structure.

b) 230 kV Station Post Insulators
- Forty-one (41) polymer insulators rated for nominal system voltage of 230 kV.
- Installation includes fitting accessories.

c) 230 kV Suspension Insulators
- Six (6) 230 kV polymer suspension insulators installed on the H-frame.
- Installation includes fitting accessories.

d) 230 kV Surge Arresters
- Six (6) station class surge arrester rated for nominal system voltage.

e) Conductors
- The horizontal bus will be 4” aluminum schedule 40 rigid tubular bus.
- The equipment jumpers from the horizontal bus to the string bus shall be bundled 1780 ACSR “Chukar,” two conductors per phase.
- The equipment jumpers for switches to breakers shall be 1780 ACSR “Chukar,” two conductors per phase.
- The equipment jumpers from the horizontal bus to the coupling capacitor voltage transformers and surge arresters shall be 1780 ACSR “Chukar,” one conductor per phase.
- Include all necessary fittings.

f) Raceway & Conduit
- 2” PVC conduit with couplings, bends, adapters, liquid-tight fittings, and related hardware for CCVTs.
- All conduit at road crossings and running outside station fence will be encased in concrete.

g) Existing Control Building

- Includes installing connection of control cable wiring checkout and commissioning of the associated systems.

Relay

a) The relay protection scheme is subject to change during detailed design considering the long procurement duration.
b) Two (2) new relay panels are required for the protective relays associated with the Gen-Tie lines coming from Franklin Farms powerplant at the Smalling 500/230kV substation.
   - One (1) protection panel shall include two (2) SEL-411L relays using a line current differential scheme for the new 230kV single gen-tie line from Unit#1 (CTG1-STG1) of the Franklin Farms powerplant. Entergy Standard for breaker control PM1803 OPT C5.
   - One (1) protection panel shall include two (2) SEL-411L relays using a line current differential scheme for the new 230kV single gen-tie line from Unit#2 (CTG2-STG2) of the Franklin Farms powerplant. Entergy Standard for breaker control PM1803 OPT C5.
   - Relay communication between terminals shall be established via fiber optic cables. Refer to the project telecommunications plan for circuit routing and connection details.
   - Includes installing the panels inside the control building, de-terminating existing control cable wiring, reconnecting existing shielded control cable wiring, installing and connecting any additional control cable wiring as required, checkout and commissioning of the associated systems.

Relay Settings

a) Refer to Network Upgrade section.

Communications and SCADA

a) Refer to Network Upgrade section.

Metering

a) No metering upgrades required.

ii. Transmission Owner's 230kV Transmission Line

General

a) The transmission line scope consists of two spans of conductor located between the Franklin Farms Generation and Smalling Substation on the new single-circuit 230kV Interconnection Customer transmission line.
b) New double-bundle 954kcmil Cardinal ACSS and DNO-12776 & Alumoweld 7#7 shield wires will be installed on the interconnection span.

Structures and Foundations

a) Install (6) self-supported steel monopole dead-end structures
b) Install (2) direct embed steel monopole 0-1.5º suspension braced post structure
c) Foundation analysis to be performed during Detailed Design.

Conductor and Insulators

a) Install approximately 23,000’ of 954 kcmil ACSS Cardinal (double-bundle) for main conductor
b) Install strain insulators for (6) new structures and (6) new substation terminals
c) Install braced post insulators for (2) new structures.

Shield Wire

a) Install approximately 3,000’ of DNO-12776 OPGW
b) Install approximately 3,200’ of Alumoweld 7#7

The estimated costs for these facilities are in year 2025 dollars, with an intended accuracy of +/- 20%, and are detailed in Exhibit A6.

3. Network Upgrades

(a) Stand-Alone Network Upgrades to be installed by Transmission Owner. None.

(b) Network Upgrades to be installed by Transmission Owner. The Network Upgrades were developed for installing two new 562 MVA CTG and 402 MVA STG generating facility lines connected at the Transmission Owners’ Smalling 500/230kV substation. Upgrades will include yard equipment upgrades, installation of relay panels and telecom upgrades at Smalling 500/230kV substation.

i. Smalling 500/230kV Substation

General

a) Customer will transmit generator breaker status, telemetering data including MW, MVAR, MWhr and MVARhrs to Transmission Owner’s Smalling 500/230kV Substation Remote Terminal Unit (RTU) utilizing underground fiber optic cable.
b) Customer will design line protection compatible with the line relaying installed at the Transmission Owner’s Smalling 500/230kV Substation.

Site

a) Installation of 5/8’’ x 10’ ground rods shall be installed near major equipment such as surge arresters.

Foundations

a) Drilled pier and pad foundations will be used for all equipment support structure.
b) The foundation scope of work includes design and construction of the following:
   - Install thirty-four (34) 42 inch diameter 22-foot-long drilled pier foundations for 230kV single phase, low bus support insulators and structure.
   - Install twelve (12) set of two (2) 42 inch diameter 22-foot long drilled pier foundations for 230kV low switch structures.

- Install four (4) 10'L X 10'W X 2'H slab foundations for 230kV breakers.
- Install four (4) 8'L X 6'W X 2'H slab foundations for 230kV breaker access pad.

Electrical

a) Steel Structures
- Thirty-four (34) single-phase 230kV low bus support structure.
- Eight (8) 230kV low switch structures.
- Four (4) 230kV low switch bypass structures.

b) 230 kV Station Post Insulators
- Fifty-six (56) polymer insulators rated for nominal system voltage of 230 kV.
- Installation includes fitting accessories.

c) Gas Circuit Breakers
- Four (4) 245 kV, SF6 gas circuit breakers rated 3000 A, 63 kA interrupting capability, three (3) sets of bushing CTs, designed as per Transmission Owner specification SD0202.
- Includes installing control conduit to the circuit breakers, jumpers to the associated disconnect switches, and control cable to the control building.

d) 230 kV Disconnect Switches
- Six (6) three-phase vertical break disconnect switch is required to allow isolation of the circuit breaker that comprise the 230 kV main bus.
- Two (2) three-phase vertical break disconnect switch, with mechanical interlocked ground switch attachment, is required to allow isolation of the circuit breaker that comprise the 230 kV line terminals to the breaker for remote line isolation.
- All switches to be rated 230 kV, 3000 A continuous, 63 kA short term withstand capacity, 900 kV BIL.

e) Conductors
- The horizontal bus will be 4” aluminum schedule 40 rigid tubular bus.
- The equipment jumpers from the horizontal bus to the string bus shall be bundled 1780 ACSR “Chukar,” two conductors per phase.
- The equipment jumpers for switches to breakers shall be 1780 ACSR “Chukar,” two conductors per phase.
- The equipment jumpers from the horizontal bus to the coupling capacitor voltage transformers and surge arresters shall be 1780 ACSR “Chukar,” one conductor per phase.
- Include all necessary fittings.

f) Raceway & Conduit
- Four (4) new, two-inch (2”) conduits for the Transmission Owner-Interconnection fiber optic cable, routed from the new control house to the Interconnect Customer PCO Pole Location/POI.

i. Handhole / pull box installed at the PCO structure, according to Transmission Owner design specs.
ii. ADSS fiber between Smalling control house and the handhole / pull box installed at the PCO structure, including all associated fiber splicing.
iii. Excess slack of ADSS fiber left in the handhole / pull box located at the PCO structure such that the Interconnect Customer may pull to the generation control house.

- 2" PVC conduit with couplings, bends, adapters, liquid-tight fittings, and related hardware for breakers and switches.
- All conduit at road crossings and running outside station fence will be encased in concrete.

h) Existing Control Building
- Includes installing the panels in the control building, connection of control cable wiring checkout and commissioning of the associated systems.

Relay

a) Instrument Transformer
- Six (6) coupling capacitor voltage transformers (CCVTs), each with two (2) secondary windings, shall be installed. Scope includes installation of conduits to the CCVTs, jumpers to the associated bus, and control cables to the control building.

b) Miscellaneous equipment shall include:
- Two (2) three-phase CCVT/PT outdoor junction boxes capable of accommodating two (2) secondary windings.

c) Four (4) new relay panels are required for the new breakers in the Bay 5 & 8 at the Smalling 500/230kV substation.
- Four (4) breaker control panels for breakers RX311, RX312, RX316, and RX317 shall be provided with one (1) SEL-451 relay configured for breaker control, monitoring, and backup protection functions.
- Includes installing the panels inside the control building, de-terminating existing control cable wiring, reconnecting existing shielded control cable wiring, installing and connecting any additional control cable wiring as required, checkout and commissioning of the associated systems.

Relay Settings

a) Study and apply NERC/SERC Regulatory compliance requirements (FAC-008-3, PRC-027, PRC-023, PRC-025). Perform analysis based on Transmission Owner Standard compliance procedure for setting revisions and updates.

b) Develop new relay settings for two (2) new line protection panels associated with the 230kV interconnection gen-tie line coming from Unit#1 & Unit#2, incorporating two (2) SEL-411L relays utilizing a line current differential protection scheme.

c) Develop new relay settings for four (4) new breaker control panels associated with the 230kV breakers RX311, RX312, RX316, and RX317 incorporating one (1) SEL-451 relay for control and backup protection.
d) Develop revised relay settings for eight (8) bus protection panels associated with the 230kV Bus#1-4, each incorporating two (2) SEL-487B relays.
e) Prepare and support test plans for all newly developed and revised relay settings, ensuring complete functional and protection validation.
f) Provide both off-site and on-site support during the construction and commissioning phases, addressing relay setting database issues, relay software compatibility, and firmware version alignment.
g) Upgrade existing relays to the latest approved firmware in accordance with Transmission Owner standards and verify compatibility with relay settings and communication protocols.
h) Perform relay settings logistics and documentation tasks, including maintenance of relay database files (.rdbs), generation of viewable relay setting documents (.xls), organization of project folders for web posting (IPS), and relay model development in CAPE®.
i) All relay settings work shall be completed in strict accordance with Transmission Owner protection standards, project-specific design drawings, and applicable system studies.

Communications and SCADA

a) Provision underground (UG) fiber connections between Smalling 500/230kV Substation and the Franklin Farms Plant. Fiber shall be routed via dedicated conduits and splice points as coordinated with Transmission Owner IT Telecom.
b) Install one (1) 96-strand single mode fiber cable from Smalling Substation to the Plant Process Data Centers (PDCs), including link or fiber tie through the Admin Building to the Plant Control Building.
c) Provide a 144-strand fiber cable through the Admin Building for redundancy and future expansion.
d) Install Optical Ground Wire (OPGW) on the Gen-Tie line to provide a redundant telecommunications path between Smalling Substation and the Franklin Farms Plant, ensuring diverse and reliable routing.
e) Provide fiber panels and fiber connectors in the Smalling 500/230-kV Substation Electrical Building and Plant Electrical Building to maintain continuity of the fiber ring design.
f) Establish fully redundant singlemode direct fiber relay paths from Smalling 230kV Substation to both Plant relaying, ensuring physically diverse redundant routes for reliability.
g) Coordinate with Transmission Owner Telecom and Relay Design to define patching, port assignments, and multiplexed channel usage consistent with Transmission Owner standards.
h) Transmission Owner will complete fiber installation and splicing at the Smalling 230kV substation.

i) Complete fiber installation and splicing at the Smalling 230-kV Substation in coordination with Transmission Owner Telecom standards.
j) Transmission Owner Telecom's responsibility is to provide Direct Fiber assignments for Relay-Channels, Relay and Power Generation counterparts (on Power Gen side of Transmission) install relay communications via these channels. Transmission Owner Telecom (internal) will splice/OTDR test fibers and provide results to Relay/Power Gen. Relay and Power Gen resources responsible for testing Relays themselves. Update RTU configuration files as required to support new relay communication paths.
k) Perform SCADA integration and testing for all new fiber channels, including relay communications, telemetry, and alarm/status points.

Metering

a) No metering upgrades required.

ii. Underground ADSS Fiber

General

a) New underground fiber to be installed on this T-line section between the Franklin Farms CCCT and Smalling 500/230 kV substation.

UG Fiber

a) Approximately a total of 0.3 miles shall be installed between the Franklin Farms CCCT and Smalling 500/230 kV substation to provide communications to both stations.

(c) Shared Network Upgrade(s) to be funded by Interconnection Customer.
None.

(d) Substation Network Upgrades to be installed by Transmission Owner.
None.

4. System Protection Facilities

(a) System Protection Facilities not listed in Section 2 or 3 to be constructed by Interconnection Customer. None.

(b) System Protection Facilities not listed in 2 or 3 to be constructed by Transmission Owner.

Smalling 500 kV Substation

a) Develop new relay settings for one (1) line protection panel associated with the 500 kV Smalling–Baxter Wilson Line, incorporating two (2) SEL-411L relays utilizing a line current differential protection scheme.
b) Develop new relay settings for three (3) line protection panels associated with the 500 kV Smalling–Car Gas Rd Lines #1, #2, and #3, each incorporating two (2) SEL-411L relays utilizing a line current differential protection scheme.

Car Gas Rd 500 kV Substation

a) Develop new relay settings for three (3) line protection panels associated with the 500 kV Car Gas Rd–Smalling Lines #1, #2, and #3, each incorporating two (2) SEL-411L relays.
b) Develop new relay settings for three (3) line protection panels associated with the 500 kV Car Gas Rd–Perryville Lines #1, #2, and #3, each incorporating two (2) SEL-411L relays.
c) Develop new relay settings for two (2) line protection panels associated with the 500 kV Car Gas Rd–Sterlington Lines #1 and #2, each incorporating two (2) SEL-411L relays.
d) Develop new relay settings for one (1) line protection panel associated with the 500 kV Car Gas Rd–Mt Olive Line, incorporating two (2) SEL-411L relays.

Perryville 500 kV Substation

a) Develop new relay settings for three (3) line protection panels associated with the 500 kV Perryville–Car Gas Rd Lines #1, #2, and #3, each incorporating two (2) SEL-411L relays.
b) Develop new relay settings for one (1) backup protection panel associated with Perryville Unit #1, incorporating one (1) SEL-311C relay.
c) Develop new relay settings for one (1) backup protection panel associated with Perryville Unit #2, incorporating one (1) SEL-311C relay.

Sterlington 500 kV Substation

a) Develop new relay settings for two (2) line protection panels associated with the 500 kV Sterlington–Car Gas Rd Lines #1 and #2, each incorporating two (2) SEL-411L relays.
b) Develop new relay settings for one (1) line protection panel associated with the 500 kV Sterlington–Ouachita Line, incorporating two (2) SEL-411L relays.
c) Develop new relay settings for one (1) line protection panel associated with the 500 kV Sterlington–Ouachita Line, incorporating one (1) SEL-321 relay with POTT/DTT scheme.
d) Develop new relay settings for one (1) line protection panel associated with the 500 kV Sterlington–El Dorado Line, incorporating one (1) SEL-411L relay (OPT Modified C5).
e) Develop new relay settings for one (1) line protection panel associated with the 500 kV Sterlington–El Dorado Line, incorporating SEL-421 and SEL-311C relays.

Ouachita 500 kV Substation

a) Develop new relay settings for two (2) line protection panels associated with the 500 kV Ouachita–Sterlington Line (three-terminal configuration), each incorporating two (2) SEL-411L relays.
b) Develop new relay settings for one (1) line protection panel associated with the 500 kV Ouachita–Sterlington Line (three-terminal configuration), incorporating one (1) SEL-321 relay.

El Dorado 500 kV Substation

a) Develop new relay settings for one (1) line protection panel associated with the 500 kV El Dorado–Sterlington Line, incorporating one (1) SEL-411L relay (OPT Modified C5).
b) Develop new relay settings for one (1) line protection panel associated with the 500 kV El Dorado–Sterlington Line, incorporating SEL-421 and SEL-321 relays.

Baxter Wilson 500 kV Substation

a) Develop new relay settings for one (1) line protection panel associated with the 500 kV Baxter Wilson–Smalling Line, incorporating two (2) SEL-411L relays.

Catahoula 230 kV Substation

a) Develop new relay settings for two (2) line protection panels associated with the 230 kV Catahoula–Smalling Lines #1 and #2, each incorporating two (2) SEL-411L relays.

Eagle 230 kV Substation

a) Develop new relay settings for one (1) line protection panel associated with the 230 kV Eagle–Smalling Line, incorporating two (2) SEL-411L relays.
b) Develop new relay settings for one (1) line protection panel associated with the 230 kV Eagle–Chotard Line, incorporating two (2) SEL-411L relays.

Chotard 230 kV Substation

a) Develop new relay settings for one (1) line protection panel associated with the 230 kV Chotard–Smalling Line, incorporating two (2) SEL-411L relays.
b) Develop new relay settings for one (1) line protection panel associated with the 230 kV Chotard–Eagle Line, incorporating two (2) SEL-411L relays.

Yucatan 230 kV Substation

a) Develop new relay settings for one (1) line protection panel associated with the 230 kV Yucatan–Smalling Line #1, incorporating two (2) SEL-411L relays.
b) Develop new relay settings for one (1) line protection panel associated with the 230 kV Yucatan–Smalling Line #2, incorporating two (2) SEL-411L relays.

Concordia 230 kV Substation

a) Develop new relay settings for one (1) line protection panel associated with the 230 kV Concordia–Smalling Line, incorporating two (2) SEL-411L relays.
b) Develop new relay settings for one (1) line protection panel associated with the 230 kV Concordia–Marengo Line, incorporating two (2) SEL-411L relays.

Marengo 230 kV Substation

a) Develop new relay settings for one (1) line protection panel associated with the 230 kV Marengo–Smalling Line, incorporating two (2) SEL-411L relays.
b) Develop new relay settings for one (1) line protection panel associated with the 230 kV Marengo–Concordia Line, incorporating two (2) SEL-411L relays.

5. Distribution Upgrades.

(a) Distribution Upgrades to be constructed by Transmission Owner. None.

6. Contingency List. See Exhibit A10.

7. Affected System Upgrades List.
Affected Systems Studies have not concluded as of the date of this EGIA. Interconnection Customer is responsible for executing and fulfilling the obligations of any agreements for the study, construction, or funding of Affected System network upgrades identified by the Affected System after execution of this GIA.

8. JTIQ Upgrades.
None.

9. Common Use Upgrades. Interconnection Customer is responsible for entering into Facilities Construction Agreements and/or Multi-Party Facilities Construction Agreement with transmission owner for Interconnection Customer's share of the following upgrades:

10. Exhibits – The following exhibits are included:

A1. Interconnection Customer One-Line & Site Map
A1-1: Interconnection Customer One-Line Diagram (1 of 2)
A1-2: Interconnection Customer One-Line Diagram (2 of 2)
A1-3: Interconnection Project Site Map
A2. Transmission Owner One-Lines
A2-1: Transmission Owner One-Line
A3. Transmission Owner Substation General Arrangement
A3-1: General Arrangement Drawing
A4. Transmission Line Plan and Profile
A4-1: Tangent Structure Type
A4-2: Dead End Structure Types
A4-3: 3-D Interconnection Layout
A5. Facilities to be Constructed by Transmission Owner
A6. Detailed Cost of Facilities to be Constructed by Transmission Owner
A7. Facilities to be Constructed by Interconnection Customer
A8. Detailed Cost of Facilities to be Constructed by Interconnection Customer
A9. Facilities Subject to Transmission Owner Reimbursement
A10. Contingent Facilities
A11. Interconnection Customer Milestones
A12. Construction & Coordination Schedules
A13. Permits, Licenses, Regulatory Approvals and Authorization
A14. Interconnection and Operating Guidelines

Exhibit A1. Interconnection Customer One-Line & Site Map

A1-1: Interconnection Customer One-Line Diagram (1 of 2)

CUI//CEII MATERIAL – DO NOT RELEASE

A1-2: Interconnection Customer One-Line Diagram (2 of 2)

CUI//CEII MATERIAL – DO NOT RELEASE

A1-3: Interconnection Project Site Map




Exhibit A2. Transmission Owner One-Lines
A2-1: Transmission Owner One-Line




Exhibit A3. Transmission Owner Substation General Arrangement
A3-1: General Arrangement Drawing






Exhibit A4. Transmission Line Plan and Profile
A4-1: Tangent Structure Type



A4-2: Dead End Structure Types

0°–5°, SELF SUPPORTING, DE, JUMPER, VERTICAL, SINGLE CIRCUIT, DE POLYMER, STEEL 230kV



ASSEMBLY LIST		
ITEM	QTY.	ASSEMBLY/DRAWING
1	3	BLT–P–S
2	6	DEP/TRB–230–XX
3	3	JLP–230–XX
4	2	OHG–DE–XX
REFERENCE DRAWINGS		
7	1	SGN–S
8	–	GND–S–XX
9	–	POLE INDEX
10	1	FOOTING
11	–	PVO, SHT 1, VW PV–19
12	–	ANODE–XX (IF REQ.)

NOTES:

1) All dimensions are to Centerline of top attachment or BLT–XX.
2) See Pole Fabricator's drawings for attachment details.
3) See Staking Sheet and CU Drawings for line angles, pole, footing, grounding, and sign requirements.
4) Refer to Assembly drawings for part details.
5) Conductor attachment vangs shall be placed within 5 degrees of Ahead and Back locations.
6) This structure shall not be used for single insulator bundled conductor applications unless the combined phase tension is less than 19.4 kips. For two insulator attachment bundled conductor applications, use the appropriate bundled framing.

Set:Phase

NO.	DATE:	REVISION	BY:	APPR:

SDJA–V–DEP–S 230

ENTERGY STANDARD DWG.

DESIGN APPROVAL	STANDARDS APPROVAL
SIGNED / DATE	SIGNED / DATE

DEADEND STEEL 230kV
0°–5° SINGLE CIRCUIT

APPROVED BY:	DATE: 8–15–03
CHECKED BY:	SCALE: NONE
DRAWN BY: LINESOFT	ESI NO. TDS559A0


Entergy

No.

PLOT 1=130 SH. 1 OF 1

70'–120', SELF SUPPORTING, DE, VERTICAL,
SINGLE CIRCUIT, DE POLMER, STEEL 230kV

ASSEMBLY LIST		
ITEM	QTY.	ASSEMBLY/DRAWING
1	6	DEP/TRB–230–XX
2	2	OHG–DE–XX
REFERENCE DRAWINGS		
7	1	SGN–S
8	–	GND–S–XX
9	–	POLE INDEX
10	1	FOOTING
11	–	PVO, SHT 2, VW PV–15
12	–	ANODE–XX (IF REQ.)



NOTES:

1) All dimensions are to Centerline of top attachment.
2) See Pole Fabricator's drawings for attachment details.
3) See Staking Sheet and CU Drawings for line angles, pole, footing, grounding, and sign requirements.
4) Refer to Assembly drawings for part details.
5) Conductor attachment vangs shall be placed within 5 degrees of Ahead and Back locations.
6) This structure shall not be used for single insulator bundled conductor applications unless the combined phase tension is less than 19.4 kips. For two insulator attachment bundled conductor applications, use the appropriate bundled framing.

Set:Phase

NO.	DATE:	REVISION	BY:	APPR:
2	8–18–04	REVISED DIMENSION FOR SIGN	ITRON	
1	4–28–03	REV., DIM., GND., NOTE 1, ADD ITEM 12, NOTE 6	ITRON	

SD–V–DEP–S 230

ENTERGY STANDARD DWG.

DESIGN APPROVAL	STANDARDS APPROVAL
SIGNED / DATE	SIGNED / DATE

DEADEND STEEL 230kV
70'–120' SINGLE CIRCUIT

APPROVED BY:	DATE:	10–18–96
CHECKED BY:	SCALE:	NONE
DRAWN BY:	ESI NO.	TDS419A2

Entergy

No.

PLOT 1=130 SH. 1 OF 1

A4-3: 3-D Interconnection Layout




Exhibit A5. Facilities to be Constructed by Transmission Owner

Description of Upgrade	Upgrade Classification	Estimated Cost*
J3841 500/230 kV Substation: Transmission Owner Interconnection Facilities shall consist of a high bus dead-end structure, a section of tubular bus tapping off the breaker and a half bay, a disconnect switch with a ground switch attachment, (3) 230 kV surge arresters, and (6) coupling capacitor voltage transformers, and (1) Line Protection Panel with associated wiring . The facilities shall include associated support structures and associated foundations, as shown on Exhibit A4 which is a preliminary electrical profile view of the TOIFs.	TOIF	$875,000
J3842 500/230 kV Substation: Transmission Owner Interconnection Facilities shall consist of a high bus dead-end structure, a section of tubular bus tapping off the breaker and a half bay, a disconnect switch with a ground switch attachment, (3) 230 kV surge arresters, (6) coupling capacitor voltage transformer, and (1) Line Protection Panel with associated wiring. The facilities shall include associated support structures and associated foundations, as shown on Exhibit A4 which is a preliminary electrical profile view of the TOIFs.	TOIF	$865,000
J3841 Transmission Line: Entergy's Interconnection Facilities shall consist on installing new 954 ACSS "Cardinal", DNO-12776 OPGW 96, and 7#7 Alumowled shield wires, along with all attachment hardware. Self supported steel monopole tangent (1) and dead-end (3) structures, along with all attachment hardware.	TOIF	$1,765,000
J3842 Transmission Line: Entergy's Interconnection Facilities shall consist on installing new 954 ACSS "Cardinal", DNO-12776 OPGW 96, and 7#7 Alumowled shield wires, along with all attachment hardware. Self supported steel monopole tangent (1) and dead-end (3) structures, along with all attachment hardware.	TOIF	$1,735,000
J3841 500/230 kV Substation Equipment Upgrade(s): Network upgrade shall include (2) 245 kV, 63kA Circuit, Breakers, (4) 230kV, 3000A Switches, (17) 230 kV Bus Supports, (2) Breaker Control Panels and associated wiring.	NU	$4,263,300

J3842 500/230 kV Substation Equipment Upgrade(s): Network upgrade shall include (2) 245 kV, 63kA Circuit, Breakers, (4) 230kV, 3000A Switches, (17) 230 kV Bus Supports, (2) Breaker Control Panels and associated wiring.	NU	$4,263,300
J3841/J3842 Telecom: Installation of new UG fiber to establish redundant communication paths, including all materials, engineering, technician labor, fiber termination panels, and transition splicing at Smalling Substation and Franklin Farms Plant.	NU	$213,400
	Total Cost:	**$13,980,000**

***Estimated Costs are in 2025 dollars**

Exhibit A6. Detailed Cost of Facilities to be Constructed by Transmission Owner

Table A6-1: Detailed Cost Estimate*

Item Description	Estimated Total	TOIF	SANU	NU
Contract Construction	$7,290,000	$2,990,000	$0	$4,300,000
Contract Project Management	$570,000	$0	$0	$570,000
ROW, Permitting Support & Environmental	$0	$0	$0	$0
Materials	$3,510,000	$1,530,000	$0	$1,980,000
Contract Engineering	$590,000	$210,000	$0	$380,000
Telecom	$200,000	$0	$0	$200,000
Payroll	$500,000	$0	$0	$500,000
Distribution	$0	$0	$0	$0
Expense	$40,000	$20,000	$0	$20,000
Total Direct Cost:	**$12,700,000**	**$4,750,000**	**$0**	**$7,950,000**
Capital Suspense:	$850,000	$320,000	$0	$530,000
AFUDC:	$390,000	$150,000	$0	$250,000
Other Overheads:	$40,000	$20,000	$0	$10,000
Total In-direct Cost:	**$1,280,000**	**$490,000**	**$0**	**$790,000**
Total Cost:	**$13,980,000**	**$5,240,000**	**$0**	**$8,740,000**

***Estimated Costs are in 2025 dollars**

Exhibit A7. Facilities to be Constructed by Interconnection Customer

Interconnection Customer facilities are not included in this Facilities Study report. To be provided by the Interconnection Customer.

Exhibit A8. Detailed Cost of Facilities to be Constructed by Interconnection Customer

Interconnection Customer facilities are not included in this Facilities Study report. To be provided by the Interconnection Customer.

Exhibit A9. Facilities Subject to Transmission Owner Reimbursement

There is no transmission owner reimbursable scope associated with this project.

A10 Contingent Facilities

Table A10-1 describes transmission assumptions modeled in the studies that were deemed necessary to allow for the Interconnection Service as described in Appendix A of this GIA and is not related to Article 11.3.1, i.e., does not describe projects associated with a higher queued and/or similarly queued ERAS Interconnection Request. Nevertheless, if the transmission assumptions are not completed or significantly modified, the Interconnection Service granted under this GIA may be restricted until such time as the Interconnection Customer funds a study to determine the applicable ERIS and NRIS level that results due to the changes in Table A10-1.

A list of higher-queued and/or similarly queued ERAS study projects are in Tables A10-2 and A10-3. A project inclusion in this GIA does not necessarily mean that these facilities would be contingencies for the Interconnection Customer's Generating Facility. If any of the higher queued and/or same cycle ERAS generators were to drop out, then the Interconnection Customer may be subject to restudy pursuant to Article 11.3.2.

Table A10-1: Transmission Assumptions

MTEP ID	Facility ID	Facility	Description	Expected Completion Date	Status
25242	28277	WEBRE- COMMODORE 500kV Circuit 1	Amite South Reliability Project Phase 1 - alternative	8/1/2028	M2 - Appendix A Approved
15654	23667	DELHI-TALLULAH 115 kV Circuit 1	Delhi to Tallulah Rebuild	12/1/2026	M2 - Appendix A Approved
15654	23668	DELHI-DEHIL RX 115 kV Circuit 1	Delhi to Tallulah Rebuild	12/1/2026	M2 - Appendix A Approved
50093	50139	CHALKBLUFFPV – GALET 500kV Circuit 1	Galet 500/230kV New Substation	2/26/2027	M2 - Appendix A Approved

50093	50139	W.MEMPHIS – GALET 500 kV Circuit 1	Galet 500/230kV New Substation	2/26/2027	M2 - Appendix A Approved
17974	24744	STILLEYS – WEST FRANK FORT EAST 345kV Circuit 1	Crab Orchard: Install 345-138 kV transformer. Tap the Shawnee-West Frankfort east-4564 line and install 345kV ring bus to make the connection.	12/1/2026	M2 - Appendix A Approved
17974	24744	STILLEYS – SHAWNEE 345 kV Circuit 1	Crab Orchard: Install 345-138 kV transformer. Tap the Shawnee-West Frankfort east-4564 line and install 345kV ring bus to make the connection.	12/1/2026	M2 - Appendix A Approved
50556	50936	S HILLS - EAST ADAIR 345 kV Circuit T2	LRTP 23 – Lakefield Junction – East Adair	6/1/2034	M2 - Appendix A Approved
50556	50931	ORIENT - EAST ADAIR 345 kV Circuit T2	LRTP 23 – Lakefield Junction – East Adair	6/1/2034	M2 - Appendix A Approved
AFS	AFS	SPP	Build New Beckham to Potter 345 kV Line	TBD	TBD

Table A10-2: Prior Queued Projects

MISO Higher Queued Project #	Service Type	TO	County, State	Point Of Interconnection	Pmax (MW)	Fuel Type
None						

Table A10-3: Similarly Queued Projects

MISO Queue Project #	Service Type	TO	County, State	Point Of Interconnection	ERIS MW	Fuel Type
None						

Exhibit A11. Interconnection Customer Milestones

This exhibit is provided for reference only. Binding dates are in Appendix B.

The customer milestones include, but are not limited to those shown in the table below:

Table A11-1: Milestone Schedule

IC Milestone Schedule	
Task Name	**Proposed Finish**
GIA Execution:	TBD
GIA Payment:	TBD
Landowner Access Approval (soil borings):	N/A
Site Acquisition (servitude agreements):	N/A
Receipt of Environmental Permitting:	Complete

Exhibit A12. Construction & Coordination Schedules

This exhibit is provided for reference only. Binding dates are in Appendix B.

The proposed schedule is dependent on obtaining a suitable substation site, on timely receipt of all approvals associated with constructing the Transmission Owner interconnection substation and lines, outage availability, equipment lead-time, and resource availability. This schedule does not include upgrades that may be required because of the system impact studies. An Engineering and Procurement Agreement between the parties could potentially be utilized to begin work before the generation interconnection agreement is executed.
A detailed schedule will be prepared subsequent to customer approval to proceed with the project. Based on the Task duration schedules listed below, the overall project in-service date is projected to be Feb 2028.

Table A12-1: Milestone Schedule

Task Name	Proposed Start	Proposed Finish
GIA Execution:	TBD	
Customer Approval & Funding:	TBD	
Complete Project Execution Plan:	Complete	
Update/ Baseline Schedule:	Complete	
Detail Design:	Complete	Complete
Order Material:	Complete	Complete
Receive Material:	Complete	Complete
Issue for Construction Design Packages:	Complete	Complete
Environmental Permits:	Complete	
Construction:	Oct 2025	Oct 2026
In-Service:	Feb 2028	

Milestone Schedule Notes:

1. This schedule does not account for adverse weather conditions or major weather events.
2. All construction work requiring outages will be performed during acceptable periods of system load, which most often is the off-peak load season. Line outages will be discussed with the SOC and TCC and the assumption is made that line outages will be executed as planned. However, last minute denial of outages by the SOC/TCC along with resulting schedule delay is possible.
3. Substation construction will be coordinated with the transmission line outages when possible.
4. The above milestone schedule assumes construction resources will be available when required.

Exhibit A13. Permits, Licenses, Regulatory Approvals and Authorization

Permits, licenses, and approvals required to construct the Transmission Owner facilities may include, but are not limited to:

1. MISO questionnaire to be submitted to MISO, TCC, and TOP for review and approval
2. Revised station one line to be submitted to MISO, TCC, and TOP for review and approval
3. Wetland delineation of servitudes and proposed construction access points
4. US Corps of Engineers permitting/approval for wetlands
5. US Corps of Engineers permitting/approval for river/levee permits
6. Environmental sampling and disposal of displaced soils
7. Develop and implement a Storm Water Pollution Prevention Plan (SWPPP)
8. Temporary landowner easements
9. Pipeline Letters of No Objection
10. Access Road Permits for Public Roads

Exhibit A14. Interconnection and Operating Guidelines / Requirement

A14.1 Interconnection

The Interconnection Customer will comply with the Interconnection Guidelines for Transmission Interconnection Producer-Owned Generation Greater Than 20 MW dated March 2007, as amended from time to time and available at: https://www.entergy.com/transmission/requirements ("ENTERGY FACILITY CONNECTION REQUIREMENTS").

A14.2 Power Factor

In accordance with FERC Order No. 827, all newly-interconnected generators (synchronous or non-synchronous) are required to provide dynamic reactive power support within the range of +/- 0.95 power factor at the transmission voltage side of the generator step-up transformer at all dispatch levels. Static reactive power devices can only be used to make up for reactive losses that occur between the inverters and the transmission voltage side of the generator step-up transformer. Any additional reactive power must be supplied by a dynamic reactive power device.

The +/-0.95 power factor requirement corresponds to a triangle-shaped reactive power capability with proportional reduction in reactive power capability at lower active power (i.e. real power) output, as shown in Figure 14.1. However, reactive power capability outside the triangular-shaped requirement yet within the reactive power capability of the plant should be utilized to the greatest extent possible. Inverters shall not have artificial settings imposed to limit reactive power output to the triangular boundary.




Figure A14-1: Inverter-based Resource Plant Reactive Power Capability

A14.3 Primary Frequency Response

In accordance with FERC Order No. 842, the Interconnection Customer shall ensure the primary frequency response capability of its Generating Facility by installing, maintaining, and operating a functioning governor or equivalent controls. The hardware and/or software that provides frequency responsive active power control shall be able to sense changes in system frequency and autonomously adjust the Generating Facility's power output in accordance with the droop and deadband parameters provided by Entergy Transmission and to the extent the Generating Facility has operating capability in the direction needed to correct the frequency deviation. The Interconnection Customer is required to install a governor or equivalent controls with the

capability of operating with a maximum 5% droop and a maximum ± 0.036 Hz deadband. This response must be timely and sustained rather than injected for a short period and then withdrawn. The primary frequency response requirements shall apply to all inverter-based generating resources including energy storage during both charging and discharging states.

The Generator Owner shall provide the status and settings of the governor or equivalent controls to Entergy Transmission upon request. If the Generator Owner needs to operate the Generating Facility with its governor or equivalent controls not in service, the Generator Owner shall immediately notify Entergy Transmission and make reasonable efforts to return its governor or equivalent controls to service as soon as practical.

A14.3.1 Dynamic Frequency Response Requirements for Inverter-Based Resources

For a step change in frequency at the Point of Interconnection (POI), inverter-based resources (IBR) shall have the capability to meet the dynamic characteristics shown in Table A14.1. The active power-frequency response shall be sustained by the resource until such time that the control signals (e.g., Balancing Authority automatic generation control (AGC)) return the generator to a new set point value.

Table A14.1: Dynamic Active Power-Frequency Performance

Parameter	Description	Performance Requirement
Reaction Time	Time between the step change in frequency and the time when the IBR's active power output begins responding to the change.	< 500 ms
Rise Time	Time in which the IBR has reached 90% of the new steady-state (target) active power output command.	< 4 s
Settling Time	Time in which the IBR has entered into, and remains within, the settling band of the new steady-state active power output command.	< 10 s
Overshoot	Percentage of rated active power output that the IBR can exceed while reaching the settling band.	< 5%
Settling Band	Percentage of rated active power output that the resource should settle to within the settling time.	< 2.5%

A14.4 Frequency and Voltage Ride Through

The frequency and voltage ride-through curves described in NERC Reliability Standard PRC-024 and PRC-029 apply to the POI and not the inverter terminals themselves. The Interconnection Customer, in coordination with their inverter manufacturer, shall reflect the ride-through requirements at the POI to the inverter terminals to ensure that the inverters can ride through and continue current injection during disturbances.

The PRC-024 and PRC-029 voltage and frequency ride-through curves specify a "No Trip Zone". Operations outside of the "No Trip Zone" shall not be interpreted as a "Must Trip Zone" but rather a "May Trip Zone".

A14.4.1 Frequency Measurements and Protection

Frequency shall be calculated over a period of time (no less than 6 cycles) and filtered to

take control action on the fundamental frequency component of the calculated signal. Calculated frequency shall not be susceptible to spikes caused by phase jumps on the Bulk Electric System (BES).

Inverter-based resources shall also inhibit frequency tripping during and immediately after low voltage conditions. Inverter-based resources shall ensure that the frequency measurement and protection settings are set such that these resources are able to ride through and not trip for phase jumps or other grid disturbances where calculated frequency is affected but grid frequency is within the ride-through curves of PRC-024 and PRC-029.

A14.4.2 Momentary Cessation

Inverter-based resources interconnected to the transmission system are expected to continue current injection inside the "No Trip" zone of the PRC-024 and PRC-029 frequency and voltage ride through curves. Newly interconnecting inverter-based resources should eliminate the use of momentary cessation unless necessary in areas of the BES with low short circuit strength (SCR < 3).

A14.5 Voltage Control

BES-connected resources are required to operate in automatic voltage control mode as per NERC Reliability Standard VAR-002. All resources, including inverter-based resources, shall operate in a closed-loop, automatic voltage control mode to maintain voltage at the POI to within the specified voltage schedule tolerance band provided by the Transmission Operator as per NERC Reliability Standard VAR-002.

A14.5.1 Small Disturbance Reactive Power-Voltage Control Performance

Individual inverters shall always operate in automatic voltage control to support BES voltage schedules, post-contingency voltage recovery, and voltage stability. Each inverter shall continually respond to all changes in terminal voltage in a closed loop fashion to maintain the set point voltage level.

Inverter-based resources shall have the capability to meet the performance characteristics shown in Table A14.2. These characteristics are specified for the response of reactive power of the overall closed-loop response of the inverter-based resource plant.

Table A14.2: Dynamic Reactive Power-Voltage Performance for Small Disturbance

Parameter	Description	Performance Requirement
Reaction Time	Time between the step change in voltage and when the IBR's reactive power output begins responding to the change. Shall not include any intentional time delay.	< 500 ms
Rise Time	Time between a step change in control signal input (reference voltage) and when the reactive power output changes by 90% of its final value.	< 2-30 s
Overshoot	Percentage of rated reactive power output that the IBR can exceed while reaching the settling band.	< 5%

A14.5.2 Large Disturbance Reactive Power-Voltage Performance

The reactive power-voltage control shall be stable over all expected operating and grid conditions and be tuned to provide this stable response. The dynamic response of inverter-based resources shall be programmable by the Interconnection Customer (in coordination with the inverter manufacturer) to enable changes based on changing grid conditions once installed in the field.

Inverter response to fault events on the BES shall abide by the following principles:

- **Fault Inception**: During the inception of a fault, priority shall be given to delivering as much current to the system as quickly as possible to support protective relay systems to detect and clear the fault.
- **On-Fault Current Injection**: For the remaining on-fault period after the first couple cycles up to fault clearing, priority shall be given to accurately detecting and controlling the type of current needed based on terminal conditions and providing a combination of active and reactive current as necessary.
- **Post Fault Current Injection**: Priority shall be given to ensuring sufficient local voltage support before attempting to maintain or return to pre-disturbance active current injection.
- **Post-Fault Voltage Overshoot Mitigation**: Inverter reactive current response shall not exacerbate transient overvoltage conditions on the BES.

Inverters shall be designed to have the capability to meet the performance specifications shown in Table A14.3.

Table A14.3: Dynamic Reactive Power-Voltage Performance for Large Disturbance

Parameter	Description	Performance Requirement
Reaction Time	Time between the step change in voltage and when the IBR's reactive power output begins responding to the change.	< 200 ms
Rise Time	Time between a step change in control signal input (reference voltage) and when the reactive power output changes by 90% of its final value.	< 30 s

A14.6 Transmission System Studies

NERC Reliability Standard FAC-002 requires each Transmission Planner to assess the reliability impact of interconnecting new generation as well as any material modifications to existing interconnections of generation. Steady-state, dynamic, and short circuit studies are performed as part of the MISO Definitive Planning Phase (DPP) process. However, there are other considerations that may need to be assessed based on the interconnection location, IBR control functionality, and nearby resources (SVCs, series capacitors, synchronous generation, IBR generation, etc.).

A14.6.1 Controls Interactions and Controls Instability

Inter-plant coordination is increasingly important as the penetration of inverter-based resources continues to grow. When multiple resources attempt to control the same location on the BES (e.g., controlling voltage at the same POI or close proximity), their control systems need to be coordinated with one another to avoid reactive power output imbalance,

circular reactive power flows, controls overshoot, voltage control hunting, and unstable oscillations. Coordination issues shall be evaluated prior to the resource connecting to the BES. Prior to performing this analysis, the consultant selected by the Interconnection Customer shall be approved by Entergy Transmission. This analysis shall be performed during the plant design phase prior to plant backfeed. The results of the analysis shall be provided to Entergy Transmission with the cost of the study borne by the Interconnection Customer.

A14.6.2 Weak Grid Analysis (SCR < 3)

The changing nature of the electric grid and the growing complexity of IBR control systems can impact the performance of inverter-based resources and shall be assessed to ensure reliable operation of the BES. One of these changes is the continued reduction of short circuit levels in areas of high penetration of inverter-based resources. For interconnections with a short circuit ratio < 3, an EMTP study is required to assess potential SSR/SSCI and the proposed control design. Prior to performing this analysis, the consultant selected by the Interconnection Customer shall be approved by Entergy Transmission. This analysis shall be performed during the plant design phase prior to plant backfeed. The results of the analysis shall be provided to Entergy Transmission with the cost of the study borne by the Interconnection Customer.

A14.6.3 Power Quality

A14.6.3.1 Harmonic Distortion

Due to converter characteristics associated with IBR generation, there is an increased possibility of generating harmonic currents; therefore, Entergy shall install power quality monitoring devices at the POI. Entergy will install CCVTs with PQ sensors or Harmonic Measuring Devices (HMDs) to enhance accuracy of the Power Quality measurements. The harmonic current distortion at the POI shall be monitored for compliance with the IEEE 2800-2022 standard with the proposed generation. The harmonic distortion voltages at the POI shall also be monitored for compliance with the IEEE 519 standard with the proposed generation. Entergy will use IEEE 519, Table 1 to evaluate compliance with the voltage distortion limits. The table below is excerpted from the IEEE 519 standard for the transmission supply voltage levels. Entergy's evaluation of compliance with harmonic voltage distortion limits at the POI considers both the proposed generation and background harmonics present at the POI.

Table A14.4: Weekly 95th percentile (10 mins) Voltage Distortion Limits

Bus Voltage, V, at the POI	Individual harmonic (%) h ≤ 50	Total harmonic distortion THD (%)
1 kV < V ≤ 69 kV	3.0	5.0
69 kV < V ≤ 161 kV	1.5	2.5
161 kV < V	1.0	1.5[a]

[a] High-voltage systems are allowed to have up to 2.0% THD where the cause is an HVDC terminal whose effects are found to be attenuated at points in the network where future users may be connected.

If the PQ meter at the POI records harmonic voltage distortions that exceed the limits of the IEEE 519-2022, and if such conditions result in customer complaints or Entergy equipment performance issues attributable to the interconnection customer generator, Entergy may impose operating restrictions on the IBR until the issue is resolved. In the event that further studies are required, the costs to conduct such studies will be the responsibility of the Interconnection Customer.

A14.6.3.2 Flicker

Entergy has adopted subclause 8.1.3 (Flicker), including Table 16, of the IEEE Standard 2800-2022, without modification. The IBR plant contribution to the flicker at the POI shall not exceed EPst and EPlt of 0.35 and 0.25 respectively based on the 95th percentile value for a one-week measurements period. Assessment and measurement methods for flicker are defined in IEEE Std 1453 (subclause 6.3) and IEC 61000-3-7 (subclause 6.3). Entergy will monitor the flicker at the POI and work with the customer to take corrective action when this limit is exceeded.

A14.6.3.3 Rapid Voltage Changes (RVC)

The IBR plant shall not cause the rapid voltage changes at the POI to exceed 2.5% of nominal voltage.

This RVC limit shall apply to sudden changes due to frequent energization of transformers, frequent switching of capacitors, or from abrupt output variations caused by IBR plant misoperation. These RVC limits shall not apply to infrequent events such as switching, unplanned tripping, or transformer energization related to commissioning, fault restoration, or maintenance.

A14.7 Modeling

The steady-state and dynamic models used to represent inverter-based resources shall accurately capture the small and large disturbance aspects of the resource. The following modeling information shall be provided to Entergy Transmission within 60 calendar days prior to plant backfeed.

- Steady state model including collector system equivalent as recommended by NREL, collector station transformer, padmount transformer, and transmission gen-tie line.
- Dynamic models using the 2nd Generation Renewable Energy Models [PSS/E Models REPC, REGC, and REEC].
- Frequency and voltage ride through characteristics and corresponding dynamic models [PSS/E VTGTPA, FRQTPA]. The low-voltage ride-through capability of the PV plant shall be demonstrated either through detailed modeling of the PV controls or by field/ factory tests.
- Inverter PQ curve.
- CAPE short circuit model using a Voltage Controlled Current Source Model or short circuit modeling documentation from the inverter manufacturer.
- PSCAD model of the IBR plant.

Model verification shall be performed in compliance with NERC Reliability Standards MOD-026 and MOD-027 and transmitted to the Transmission Planner within 365 calendar days after the commissioning date.

A14.8 Inverter Negative Sequence Requirements

For unbalanced faults, in addition to increased positive sequence reactive current, the IBR unit shall inject negative sequence:

- Dependent on the IBR unit terminal (POI) negative sequence voltage, and
- Leads the IBR unit terminal (POI) negative sequence voltage by an allowable range as specified below. The allowable range is provided in lieu of tolerance band specified in the definition of a settling time.
    - 90-100 degrees, for full converter-based IBR Units
    - 90-150 degrees, for type III WTGs

A14.9 Disturbance Monitoring

The IBR owner is required to comply with the disturbance monitoring and reporting requirements in PRC-028-1.

A14.10 Communication Paths

The Interconnection Customer shall coordinate with the Transmission Owner to ensure that Transmission Owner's microwave paths are not obstructed by wind turbines, as applicable, associated with the Generating Facility. Obstruction shall be defined as any encroachment on the 3D cylindrical ellipse, as determined by the Worst-Case Fresnel Zone calculation, that would interfere with communication signals propagating between the transmitter and receiver. At a minimum, this coordination shall consist of one of the following:

The Interconnection Customer shall provide the Transmission Owner with geographical coordinates, along with tower heights and blade diameters, of each proposed wind turbine associated with the Generating Facility for review against the Transmission Owner's Licensed Microwave Paths. The Transmission Owner may elect to hire an RF Consultant to determine whether the proposed turbine locations will obstruct its Licensed Microwave Paths Costs, such a study shall be allocated to the Interconnection Customer and shall not be subject to reimbursement.

The Interconnection Customer shall provide the Transmission Owner with a microwave path study, including evaluation of the Transmission Owner's Licensed Microwave Paths. The Transmission Owner will review and approve or deny the completed study within 10 business days after the study is submitted, where the approval of the Transmission Owner is not to be unreasonably withheld or denied. The Interconnection Customer shall gain approval of the submitted study prior to constructing the Generating Facility.

A14.11 Generic Requirements for Fiber Optic Construction in Support of MISO Generation Projects

- All fiber shall be single mode, and its performance shall meet or exceed ITU-TG.657A1 specifications for Single-mode Optical Fiber, Dispersion Unshifted, with Low Water Peak.

- Minimum per-cable fiber count shall be forty-eight (48) strands.
    - To facilitate inter-company splicing, this count shall be incorporated into the fiber optic cable in four (4) bundles/tubes of twelve (12) fibers each, for a total of 48 fibers.
    - Higher count cables may be coordinated with Entergy.
- Fiber cable design shall be appropriate for the intended purpose (OPGW versus ADSS versus all-dielectric duct).
- All fiber optic joinery shall be accomplished via fusion splicing. Minimum standards for finished fusion splice performance are found in Table 1, below.
    - Mechanical fiber splicing is not permitted.
    - All fibers in the cable shall be spliced through at all intermediate splice points.
- Fiber termination connector type shall be SC ultra-polished physical contact or LC ultra-polished physical contact.
    - Mechanical fiber terminations are not permitted.
    - Connector Pigtails shall be attached to entrance cable via fusion splicing.
    - All fibers in the cable shall be terminated.
- At the designated meet point(s), Entergy will provide an all-dielectric fiber optic cable stub of sufficient length, to which the customer shall splice their fiber optic cable in a customer-provided splice enclosure appropriate to the cable and construction type.
    - This interface will be the point of demarcation for ownership and operational responsibility of the new fiber optic cable construction.
    - All fibers in the cable shall be spliced through at the point of demarcation.
- Entergy reserves the right to inspect customer-owned fiber optic facilities for compliance with these minimum requirements to ensure reliable operation of inter-company relay and communication systems.

- T**able A14.5: Summarized Fiber Optic Splice Performance Grid**

Summarized Fiber Optic Splice Performance Grid (all measurements to be recorded at 1550 nm)		
Parameter	**Measured Value**	**Action Required**
Splice Loss as estimated by Fusion Splicer:	loss ≤0.05 dB*loss ≤0.05 dB*	TARGET
	0.05 dB<loss<0.10 dB*0.05 dB<loss<0.10 dB*	acceptable
	loss ≥0.10 dB*loss ≥0.10 dB*	Break and re-splice up to three times; if no improvement, note the splice location and the fiber number for communication to Entergy.
Splice Loss as measured by OTDR:	loss ≤0.05 dB*loss ≤0.05 dB*	TARGET
	0.05 dB<loss<0.10 dB*0.05 dB<loss<0.10 dB*	acceptable
	loss ≥0.10 dB*loss ≥0.10 dB*	Note the splice location and fiber number for communication to Entergy.

Appendix B to GIA
Milestones

1. Selected Option pursuant to Article 5.1: Interconnection Customer selects the Standard Option as described in Article 5.1.1. Articles 5.1.2, 5.1.3, and 5.1.4 shall not apply to this GIA.

2. Milestones: The description and date entries listed in the following tables are provided solely for the convenience of the Parties in establishing their applicable Milestones consistent with the provisions of this GIA and the GIP.

A. Interconnection Customer Milestones

No.	Description	Date
1a.	Provide initial payment to Transmission Owner (GIA 11.5) in form of security for $ 13,980,000 (100% of total cost of Transmission Owner Interconnection Facilities and Network Upgrades). Coordinate Initial Payment confirmation with Transmission Owner and notify Transmission Provider via email notice to gifinance@misoenergy.org.	Because Interconnection Customer and Transmission Owner are the same Party, no security is being transferred . -Completed.
1b.	Provide security, *i.e.*, a guarantee, surety bond, letter of credit or other reasonably acceptable form of security to Transmission Owner (GIA 11.6).	Not Applicable.
1c.	Enter into a Facilities Service Agreement ("FSA") as may be applicable, with Transmission Owner for the Network Upgrades associated with this GIA.	Not Applicable.
1d.	Enter into amendment of this GIA, if required, for Interconnection Requests that did not elect optional negotiation period adjustment for Interconnection Facilities Study pursuant to GIA Section 11.3.1.	Within 90 days of the posting of the final Interconnection Facilities report.
1e.	Enter into SPP JTIQ Service Agreement (if included in JTIQ Participation Group) pursuant to GIP Section 11.1.	Not Applicable.
1f.	Enter into any agreement required by an Affected System for the study, construction, or funding of a network upgrade to mitigate impacts (for Interconnection Requests processed through ERAS) pursuant to GIP Section 3.5.2.	Within 15 Calendar Days after tender.
1g.	Demonstrate 100% Site Control (if not provided earlier due to qualifying regulatory limitations) or the GIA may be terminated per Article 2 of this GIA and the Interconnection Customer may be subject to Withdrawal Penalties per Section 7.6.2.1.1 of the GIP (Calculation of the Automatic Withdrawal Penalty).	Within 180 Calendar Days of the Effective Date.
2.	Provide Certificate of Insurance (GIA 18.4.9).	The earlier of the construction work

		commencement date or the milestone date; thereafter, within 90 Calendar Days of end of fiscal year or insurance renewal date.
3.	Provide evidence of one or more of the following milestones being achieved: (1) execution of contract for (a) fuel supply or transport; (b) cooling water supply; (c) engineering procurement of major equipment or construction; (d) execution of a contract for the sale of electric energy or capacity from the Generating Facility, or a statement signed by an officer or authorized agent of Interconnection Customer attesting that the Generating Facility is included in an applicable state resource adequacy plan; or other information that Transmission Provider deems to be reasonable evidence that the Generating Facility will qualify as a designated network resource; or (2) documentation of application for state or local air, water, land, or federal nuclear or hydroelectric permits and that the application is proceeding per regulations (GIP 11.3).	Within 180 Calendar Days of Effective Date.
4.	Cash Payment and security obligations are subject to quarterly review and update by Transmission Owner; who will take into account actual costs, updated cost projections and schedule revisions and make changes to the Interconnection Customer's Cash Payments and security obligations as required.	Because Interconnection Customer and Transmission Owner are the same Party, no security or cash is being provided.
5.	Invoice Transmission Owner for the estimated amount to be expended by the Interconnection Customer to construct any Stand Alone Network Upgrades for which the Interconnection Customer has exercised its Option to Build if the Transmission Owner has elected to Self Fund (GIA 5.2.13).	Not Applicable.
6.	Pre-construction meeting.	As may be agreed to by the Parties.
7.	Provide initial design and specifications for Interconnection Customer's Interconnection Facilities to Transmission Owner and Transmission Provider for comment (GIA 5.10.1).	180 Calendar Days prior to initial synchronization date.
8.	Provide final design and specifications for Interconnection Customer's Interconnection Facilities to Transmission Owner and Transmission Provider for comment (GIA 5.10.1).	90 Calendar Days prior to initial synchronization date.
9.	Deliver to Transmission Owner and Transmission Provider "as-built" drawings, information and documents	Within 120 Calendar Days of Commercial Operation

	regarding Interconnection Customer's Interconnection Facilities (GIA 5.10.3).	Date.
10.	Provide Transmission Owner final cost invoices to construct Stand Alone Network Upgrades for which the Interconnection Customer has exercised its Option to Build if the Transmission Owner has elected to Self Fund (GIA 5.2.13).	Not Applicable.
11.	Notify Transmission Provider and Transmission Owner in writing of Local Balancing Authority where Generating Facility is located (GIA 9.2).	Nine months prior to Initial Synchronization Date.
12.	Pre-energization meeting.	As may be agreed to by the Parties.
13.	Initial Synchronization Date.	08/05/2028
14.	Commercial Operation Date.	08/06/2028
15.	Interconnection Customer shall provide the Parties with notice on the status of the Generating Facility, including COD, under Article 15 of this GIA and shall also send such notice by email to ResourceIntegration@misoenergy.org. Notification shall include Interconnection Customer's name, and as applicable Market Participant(s) name(s), and project number.	6 months prior to Initial Synchronization Date.
16.	Interconnection Customer shall provide notice to the Parties of a test plan in advance of conducting tests for the Generating Facility. The notice shall be in the form below and should be provided under Article 15 of this GIA, and a copy of such notice should be emailed to ResourceIntegration@misoenergy.org**.**	5 Business Days prior to testing.
17.	In the event the Interconnection Customer makes any modifications to the design of the site layouts or interconnection facility routes after execution of this GIA, Interconnection Customer shall notify the Parties of such changes immediately upon identifying the need for such changes. After providing such notification, the Interconnection Customer shall provide to Transmission Provider evidence of continued Site Control for land sufficient to accommodate the changes in site layouts and/or interconnection facility routes (GIP 7.2.2).	90 Calendar Days after Interconnection Customer provides notice to Parties.

18.	Provide TO a PSCAD Model and a PSCAD Model Parameter Verification Report. This report shall provide evidence that tunable parameters match what is implemented in the field. Evidence can take the form of screenshots, nameplate photographs, signed manufacturer commissioning reports, parameter dump file, etc. All of these must be cross referenced with the settings in the PSCAD model. Field tunable parameters should be identified by the manufacturer but should include at a minimum, protection settings, ride through settings and any tunable control gains. Evidence must also be provided that proves the PSCAD PPC model has all communication delays, any sample and hold type outputs and all gains that are in the field. This must be confirmed with voltage step tests in the field and in PSCAD. The PPC must be tuned to work over a range of expected SCRs.	30 days prior to Commercial Operation Date.

B. Transmission Owner Milestones

No.	Description	Date
0.	Transmission Owner to enter Network Upgrade information into Transmission Provider's MTEP database and model on demand.	10 Business Days after Effective Date.
1.	Provide Certificate of Insurance (GIA 18.4.9).	The earlier of the construction work commencement date or the milestone date; within 90 Calendar Days of end of fiscal year or insurance renewal date.
2.	• Commence design of Interconnection Facilities (GIA 5.5 et seq.). • Commence equipment procurement.	As agreed to by the Parties (after completion of Interconnection Facilities Study, receipt of written authorization from Interconnection Customer and Interconnection Customer's deposit of security.
3.	Commence construction of Interconnection Facilities (GIA 5.6 et seq.).	As agreed to by the Parties (after receiving approval of

		Governmental Authority, receipt of written authorization and security from Interconnection Customer).
4.	Comment on Interconnection Customer's final design and specifications.	Within 30 Calendar Days of Interconnection Customer's submission of final design and specifications.
5.	Deliver to Interconnection Customer and Transmission Provider "as-built" drawings, information and documents regarding Transmission Owner's Interconnection Facilities (GIA 5.11).	Within 120 Calendar Days of Commercial Operation Date.
6.	Provide payment for invoiced estimated costs to construct for which the Interconnection Customer has exercised its Option to Build if the Transmission Owner has elected to Self Fund (GIA 5.2.13).	Not Applicable.
7.	Provide Interconnection Customer final cost invoices (GIA 12.2 *et seq.*).	Within (6) six months of completion.
8.	Refund overpayment of estimated costs (GIA 12.2).	Refunds within 30 Calendar Days after final invoice.
9.	In-Service Date/Backfeed Date.	08/04/2028

C. Affected System Owner Milestones

No.	Description	Date
1	Affected Systems Studies have not concluded as of the date of this EGIA. Interconnection Customer is responsible for executing and fulfilling the obligations of any agreements for the study, construction, or funding of Affected System network upgrades identified by the Affected System after execution of this GIA.	Execute agreements tendered by the affected system within fifteen (15) Calendar Days of tender.

Appendix B-1 to GIA
Pre-Certification Generation Test Notification Form

The following form would need to be submitted to MISO Real Time Operations at least five (5) Business Days prior to the first date of testing.

Project Number:

Project Name:

Point of Interconnection:

Dispatcher Contact Information:

Date	Start Time (in EST)	End Time (in EST)	Expected MW Output	Expected MVAR Output (Only needed if beyond normal power factor)

Appendix C to GIA
Interconnection Details

This Appendix C is a part of this GIA among Interconnection Customer, Transmission Owner and Transmission Provider.

1. The unique requirements of each generation interconnection will dictate the establishment of mutually agreeable Interconnection and/or Operating Guidelines that further define the requirements of this GIA. The Interconnection and/or Operating Guidelines applicable to this GIA consist of the following information. Additional detail may be provided through attachment to this Appendix C or through electronic means via the web address specified.

    (a) System Protection Facilities;
    (b) Communication requirements;
    (c) Metering requirements;
    (d) Grounding requirements;
    (e) Transmission Line and Substation Connection configurations;
    (f) Unit Stability requirements;
    (g) Equipment ratings;
    (h) Short Circuit requirements;
    (i) Synchronizing requirements;
    (j) Generation and Operation Control requirements;
    (k) Data provisions;
    (l) Energization inspection and testing requirements; and
    (m) Control equipment, if any.

    Entergy Facility Connection Requirements website:
    http://www.entergy.com/energydelivery/facility_requirements.aspx

    Reference material regarding the Entergy Facility Connection Requirements can be found on the two (2) links below located on the above mentioned web address.

    (1) Entergy Facilities Connection Requirements Document, March 2007; and
    (2) Entergy Facilities Connection Spreadsheet, October 2008.

    In the event that the Interconnection and/or Operating Guidelines conflict with this GIA, this GIA will govern.

2. Information required pursuant to Section 8.4 for Variable Energy Resource Generating Facilities: _____. Not Applicable

Appendix D to GIA
Security Arrangements Details

Infrastructure security of Transmission or Distribution System equipment and operations, as applicable, and control hardware and software is essential to ensure day-to-day Transmission and Distribution System reliability and operational security. The Commission will expect all Transmission Providers, market participants, and Interconnection Customers interconnected to the Transmission or Distribution System, as applicable, to comply with the recommendations provided by Governmental Authorities regarding Critical Energy Infrastructure Information ("CEII") as that term is defined in 18 C.F.R. Section 388.113(c) and best practice recommendations from the electric reliability authority. All public utilities will be expected to meet basic standards for system infrastructure and operational security, including physical, operational, and cyber-security practices.

Appendix E to GIA
Commercial Operation Date

This Appendix E is a part of this GIA between Transmission Provider, Transmission Owner and Interconnection Customer.

[Date]

Midcontinent Independent System Operator, Inc.
Attn: Director, Transmission Access Planning
720 City Center Drive
Carmel, IN 46032

Re: _____ Generating Facility

Dear _____:

On **[Date] [Interconnection Customer]** has completed Trial Operation of Unit No. ___. This letter confirms that **[Interconnection Customer]** commenced commercial operation of Unit No. ___ at the Generating Facility, effective as of **[Date plus one Calendar Day]**.

Thank you.

[Signature]

[Interconnection Customer Representative]

cc: Transmission Owner

Appendix F to GIA
Addresses for Delivery of Notices and Billings

Notices:

Transmission Provider:

MISO
Attn: Director, Transmission Access Planning
720 City Center Drive
Carmel, IN 46032

Transmission Owner:

Entergy Services, LLC
Attn: Sr Manager, Interconnection Planning and Customer Service
9585 Pecue Blvd
Baton Rouge, LA 70818

Interconnection Customer:

Entergy Services, LLC
Attn: Power Development/Jonathan Alvis
2107 Research Forest Drive
The Woodlands, TX 77380

Billings and Payments:

Transmission Provider:

MISO
Attn: Director, Transmission Access Planning
720 City Center Drive
Carmel, IN 46032

Transmission Owner:

Entergy Louisiana, LLC
P.O. Box 679505
Dallas, TX 75267-9505

Interconnection Customer:

Entergy Louisiana, LLC
Attn: Miscellaneous Accounts Receivable
P.O. Box 679505
Dallas, TX 75267-9505

Alternative Forms of Delivery of Notices (telephone, facsimile or email):

Transmission Provider:

Phone: (317) 249-5700
Email: misotap@misoenergy.org or
MISOTransmissionAccessPlanning@misoenergy.org

Transmission Owner:

Entergy Services, LLC
Voice telephone: (504)-576-7940
Email address: GIA@entergy.com

Interconnection Customer:

Entergy Louisiana, LLC
Voice telephone: (281) 719-7109
Email: jalvis@entergy.com

Entergy Louisiana, LLC
Attn: Sr Manager, Resource Planning
4809 Jefferson Highway
Jefferson LA 70121

Appendix G to GIA
Interconnection Requirements for Inverter-Based Resource Plants

Appendix G sets forth requirements and provisions specific to inverter-based resource (IBR) plants. Transmission Owner Local Planning Criteria for IBR performance may differ from Appendix G requirements. In such cases, Transmission Owner Local Planning Criteria shall supersede the Appendix G requirements and be documented in Appendix C of this GIA[1]. All other requirements of this GIA also apply to IBR plant interconnections. *IBR plants* shall meet both Applicable Reliability Standards and Appendix G requirements. Battery energy storage systems required to furnish grid-forming controls shall be exempt from specific IEEE 2800 requirements as outlined in the BPM for Generator Interconnection. Italicized terms indicate IEEE 2800-2022 defined terms[2]. IEEE 2800-2022's definitions will govern these italicized terms unless otherwise defined herein.

A. General

The *IBR plant* shall adhere to IEEE 2800-2022 Clause 4 requirements, except for subclauses 4.1 (introduction), 4.5 (operational measurement and communication capability), 4.6 (control capability requirements), 4.8 (isolation devices), 4.9 (inadvertent energization of TS), 4.11 (interconnection integrity), and 4.12 (integration with TS grounding).

Within the adopted IEEE 2800-2022 Subclauses, the following requirements shall be incorporated as Transmission Provider and Transmission Owner[3] specification options noted in IEEE 2800-2022.

- Subclause 4.2.1: The *reference point of applicability* (RPA) shall be at the *point of measurement* (POM) bus with the exception of requirements specified in Clauses 7.2.2.3.4 and 7.2.2.3.5 of the standard to have the RPA at the *point of connection* (POC).

- Subclause 4.3: The Transmission Owner shall specify the nominal voltage and frequency at the RPA in Appendix C of this GIA.

- Subclause 4.10.2: The *enter service* criteria shall use the default values for *applicable voltages* and *applicable frequency* specified in the table below unless otherwise specified in Appendix C of this GIA[4].

---

[1] IEEE 2800-2022 points to "weak grid" issues requiring exceptions to default values and ranges of available settings for various types of performance. IEEE 2800-2022 Annex C.2 contains discussion on characterizing weak grid areas.

[2] "IEEE Standard for Interconnection and Interoperability of Inverter-Based Resources (IBRs) Interconnecting with Associated Transmission Electric Power Systems," in IEEE Std 2800-2022 , vol., no., pp.1-180, 22 April 2022, doi: 10.1109/IEEESTD.2022.9762253.

[3] For the purpose of this GIA, the IEEE 2800 term of *TS operator* is synonymous with Transmission Owner and the IEEE 2800 term of *TS owner* is synonymous with Transmission Planner or Transmission Owner, as applicable.

[4] MISO default values may be modified within the IEEE 2800 range of allowable settings by Transmission Owner Local Planning Criteria.

Enter service criteria	Default setting
Applicable voltage, minimum value	0.9 p.u.
Applicable voltage, maximum value	1.05 p.u.
Applicable frequency, minimum value	58.8 Hz
Applicable frequency, maximum value	60.12 Hz.

- Subclause 4.10.3: The performance during *enter service* shall use the default values specified below unless otherwise specified in Appendix C of this GIA.
    - The minimum intentional delay performance, as defined in Subclause 4.10.3, b), shall be 0 seconds.
    - The duration of the *enter service* period, as defined in Subclause 4.10.3, c), shall be 300 seconds.

B. Response to Abnormal Conditions

The *IBR plant* shall adhere to IEEE 2800-2022 Clause 7 requirements, except for subclauses 7.2.1 (voltage protection) and 7.3.1 (mandatory frequency tripping). Where Applicable Reliability Standards require more stringent ride-through requirements compared to IEEE 2800-2022 Clause 7 requirements, those standards shall take precedence[5].

Within the adopted IEEE 2800-2022 Subclauses, the following requirements shall be incorporated as the Transmission Provider and Transmission Owner decision points[6] noted in IEEE 2800-2022.

- Subclause 7.2.2.1: The Transmission Owner shall specify the nominal voltage for use by this clause. Nominal voltages may include nominal transmission system voltages that are different from standard ANSI C84.1-2016 voltages.
- Subclause 7.2.2.2: If the *IBR plant* cannot deliver both active and reactive power due to its current limit (or apparent power limit), when the *applicable voltage* is below 95%, then preference shall be given to reactive power while minimizing any reductions in active power.
- Subclause 7.2.2.3: The *IBR plant* shall give preference to reactive power unless otherwise specified in Appendix C of this GIA. In addition, the *IBR plant* shall minimize reductions in active power while carrying out the reactive current priority mode response.

[5] More stringent ride-through requirements include, but are not limited to, expanded voltage and frequency conditions or extended cumulative times under which *IBR plants* must ride-through.

[6] Decision points refer to language in the IEEE 2800-2022 standard that leaves default values, application of requirements, and other details open for the *TS Owner* or *TS Operator* to define.

- Subclause 7.2.2.3.4: The Interconnection Customer shall submit the *IBR plant* controls default relationship between the magnitude of incremental positive and negative sequence reactive currents. The Transmission Provider and Transmission Owner, through this agreement, may specify a required *IBR plant* response relationship between the incremental positive and negative sequence reactive currents.

C. Reactive Power

The *IBR plant* shall adhere to IEEE 2800-2022 Clause 5 requirements.

Within the adopted IEEE 2800-2022 Subclauses, the following requirements shall be incorporated as the Transmission Provider and Transmission Owner decision points noted in IEEE 2800-2022.

- Subclause 5.1: The *IBR plant* shall have the reactive power capabilities outlined in this clause. Consistent with section 9.6.1 of this GIA, an *IBR plant* shall maintain a power factor within the range of 0.95 leading to 0.95 lagging, unless Transmission Provider has established different requirements that apply to all Generating Facilities in the Local Balancing Authority on a comparable basis, measured at the high side of the generator substation.

- Subclause 5.2.2: The voltage control dynamic performance requirements in Table 5 shall apply when the system short-circuit strength at the RPA is equal to or above the minimum short-circuit strength identified by the Transmission Provider or Transmission Owner.

- Subclause 5.2.2: The *reaction time*, as defined in Subclause 5.2.2 Table 5, shall be 250 milliseconds or less.

- Subclause 5.2.2: The maximum *step response time*, as defined in Subclause 5.2.2 Table 5, shall be 30 seconds.

- Subclause 5.2.3: The power factor control mode shall appropriately operate at all active power levels from the Inverter Based Resource Continuous Rating ("ICR") down to, but not including, zero.

D. Primary Frequency Response

The *IBR plant* shall adhere to IEEE 2800-2022 Clause 6 requirements, except for Subclause 6.2 (fast frequency response).

Within the adopted IEEE 2800-2022 Subclauses, the following requirements shall be incorporated as the Transmission Provider and Transmission Owner decision points noted in IEEE 2800-2022.

- Subclause 6.1.1: The use of primary frequency response capabilities shall be required for all *IBR plants.*
- Subclause 6.1.1: Frequency droop shall be based on the difference between nameplate capacity and zero output such that the slopes of the droop curves are always constant.
- Subclause 6.1.2: The *settling band* default value in Table 8 shall be based on the maximum of 2.5% of change or 0.5% of nameplate capacity.

The exceptions to primary frequency response requirements provided to electric storage resources in Article 9.6.4.4 of this GIA shall still apply.

TABLE 2. SUMMARY OF ADOPTION TREATMENT OF IEEE 2800-2022 SUBCLAUSES

IEEE 2800-2022 Subclause	Required by Appendix G for DPP-2022 and later	Required by Appendix G for DPP-2023 and later	Exception
4.1 Introduction			**X**
4.2 Reference Point of Applicability	**X**		
4.3 Applicable Voltages and Frequencies	**X**		
4.4 Measurement Accuracy	**X**		
4.5 Operational Measurement and Communication Capability			**X**
4.6 Control Capability			**X**
4.7 Prioritization of IBR Responses	**X**		
4.8 Isolation Devices			**X**
4.9 Inadvertent Energization of TS			**X**
4.10 Enter Service	**X**		
4.11 Interconnection Integrity			**X**
4.12 Integration with TS grounding			**X**
5.1 Reactive Power Capability		**X**	
5.2 Voltage and Reactive Power Modes		**X**	
6.1 Primary Frequency Response		**X**	
6.2 Fast Frequency Response			**X**
7.1 Introduction	**X**		
7.2.1 Voltage protection			**X**
7.2.2.1 Voltage disturbance ride-through: General	**X**		
7.2.2.2 Voltage disturbances within continuous operation	**X**		

7.2.2.3 Low- and high-voltage ride-through	**X**		
7.2.2.4 Consecutive voltage deviations ride-through		**X**	
7.2.2.5 Dynamic voltage support	**X**		
7.2.2.6 Restore output after voltage ride-through	**X**		
7.2.3 Transient overvoltage	**X**		
7.3.1 Mandatory frequency tripping			**X**
7.3.2 Frequency disturbance ride-through	**X**		
7.4 Return to service	**X**		

E. Supervisory Control and Data Acquisition (SCADA) Capability

The *IBR plant* shall provide SCADA capability to transmit data and receive instructions from Transmission Provider to protect system reliability. Transmission Provider and Interconnection Customer shall determine what SCADA information is essential for the proposed *IBR plant*, taking into account the size of the plant and its characteristics, location, and importance in maintaining generation resource adequacy and transmission system reliability in its area.

F. Disturbance Monitoring and Reporting Requirements

IBR plants with generating capacities of more than 20 MW must monitor and record data for all frequency ride-through events, transient low-voltage disturbances that initiated reactive current injection, reactive current injection or momentary cessation for transient high-voltage disturbances, and inverter trips. Dynamic Disturbance Recording ("DDR") data must be recorded continuously. The data may be recorded and stored in a central plant control system. The following data must be recorded:

Plant Level

(1) Plant three-phase voltage, current and power factor

(2) Status of ancillary reactive devices

(3) Status of all plant circuit breakers

(4) Status of plant controller

(5) Plant control set points

(6) Status of main plant transformer no load taps

(7) Status of main plant transformer tap changer (if applicable)

(8) Protective relay trips (relay target data)

Inverter Level Data

(1) Frequency, current, and voltage during frequency ride-through events

(2) Voltage and current during momentary cessation for transient high-voltage events (when used)

(3) Voltage and current during reactive current injection for transient low or high-voltage events

(4) Inverter alarm and fault codes

(5) DC current

(6) DC voltage

DDR Data – Plant Level

(1) One phase-to-neutral or positive sequence voltage on high-side of the main power transformer(s)

(2) Positive sequence current or phase current for the same phase as (1)

(3) Real and reactive power flows expressed on a three-phase basis corresponding to each main power transformer(s) where current measurements are required

(4) Frequency of any one of the voltages in (1)

The data must be time synchronized to a one millisecond level of resolution. All data except DDR data must be sampled at least every 10 milliseconds. DDR data must have an input sampling rate of at least 960 samples per second and an output recording rate of electrical quantities of at least 60 times per second.

The *IBR plant* shall store this data for a minimum of 60 calendar days. The *IBR plant*, upon request from MISO or the transmission owner, shall make this data available within 10 calendar days of the request.

Phasor measurement unit ("PMU") capabilities shall be used to facilitate the DDR data.

G. Applicability

IBR plants that are, or have been, interconnected to the network at the effective date of the Appendix G abnormal voltage ride-through standard are exempt from meeting the Appendix G abnormal voltage ride-through standard for the remaining life of the existing generation

equipment. Except for *IBR plants* actively undergoing a Generating Facility Replacement at the effective date of this GIA that have equipment on order where the OEM has documented performance that differs from what is required in this GIA, all individual IBR units that are replaced are required to meet the Appendix G performance requirements.

The IEEE 2800-2022 requirements cited in Section A (IEEE 2800-2022 Clause 4) and Section B (IEEE 2800-2022 Clause 7, except Subclause 7.2.2.4) of Appendix G shall apply to *IBR plants* in the DPP-2022-Cycle and beyond. For the DPP-2022-Cycle, Interconnection Customers may request exceptions confined to these sections only if specific limitations or uncertainties of equipment or plant capabilities prevent implementation of these requirements. GIAs signed or amended with inverter changes on or after January 1, 2025, are not eligible for requirement exceptions. Further, the process for establishing exceptions for these requirements shall not apply beyond the DPP-2022-Cycle.

The IEEE 2800-2022 requirements cited in Section B (IEEE 2800-2022 Subclause 7.2.2.4), Section C (IEEE 2800-2022 Clause 5), and Section D (IEEE 2800.2022 Clause 6) of Appendix G shall apply to *IBR plants* in the DPP-2023-Cycle and beyond. For the DPP-2023-Cycle, Generating Facilities Replacements, and Surplus Interconnections, Interconnection Customers may request exceptions confined to these sections only if specific limitations or uncertainties of equipment or plant capabilities prevent implementation of these requirements. GIAs signed or amended with inverter changes on or after January 1, 2026, are not eligible for requirement exceptions. Further, the process for establishing exceptions for these requirements shall not apply beyond the DPP-2023-Cycle.

Interconnection Customers requesting exceptions shall submit documentation to the Transmission Provider outlining the specific IEEE 2800-2022 subclauses pertinent to the request along with information from the manufacturer regarding the nature of the issue conforming to or assessing conformance with requirements herein. The Transmission Provider will, in good faith, accept Original Equipment Manufacturer (OEM)-documented requirement exceptions and document these exceptions in Appendix C of this GIA.

If the performance or capability exception can be mitigated through equipment firmware upgrades still under development, the Interconnection Customer shall use commercially reasonable efforts to implement the firmware upgrade within sixty (60) calendar days of commercial availability of such firmware.

The DDR and PMU requirements in the Section F, Disturbance Monitoring and Reporting Requirements of Appendix G shall apply to *IBR plants* in the DPP-2023-Cycle and beyond.

Appendix H to GIA – Not Applicable
Interconnection Requirements for Provisional GIA

Provisional Agreement

This GIA is being provided in accordance with Section 11.5 of the Transmission Provider's GIP, which provides among other things, that an Interconnection Customer may request that Transmission Provider provide Interconnection Customer with a Provisional Generator Interconnection Agreement that limits the transfer of energy by Interconnection Customer commensurate with that allowed for Energy Resource Interconnection Service. Interconnection Customer requested Transmission Provider to provide a Provisional Generator Interconnection Agreement for limited operation at the discretion of Transmission Provider based upon the results of available studies (by Interconnection Customer and by Transmission Provider).

A Provisional Interconnection Study, the results of which are posted on the confidential portion of the Transmission Provider's internet website, was performed by Transmission Provider in order to confirm the facilities that are required for provisional Interconnection Service and to require them to be in place prior to commencement of service under the GIA.

Interconnection Customer represents that the Interconnection Customer facilities (including Network Upgrades, Interconnection Facilities, Distribution Upgrades, System Protection Upgrades and/or Generator Upgrades) that are necessary to commence provisional Interconnection Service and meet the requirements of the Electric Reliability Organization, or any applicable regional entity for the interconnection of a new generator are in place prior to the commencement of generation from the Generating Facility and will remain in place during the term of the service. The requisite Interconnection Studies were performed for the Generating Facility. Interconnection Customer shall meet any additional requirements (including reactive power requirements) pursuant to the results of applicable future Interconnection System Impact Studies. Until such time as the applicable Interconnection Studies and any identified facilities are completed, the output of the Generating Facility will operate within the output limit prescribed in a future, if applicable, operating guide.

The maximum permissible output of the Generating Facility under Appendix A will be updated by Transmission Provider on a quarterly basis, determined in accordance with Section 11.5 of the GIP, by finding the transfer limit of energy commensurate with the analysis for Energy Resource Interconnection Service ("ERIS"). This study shall be performed assuming the system topology represented by the base cases used to calculate Available Flowgate Capability, as described in Attachment C of the Tariff, with dispatch and optimization algorithms posted on the MISO internet site and operation above those limits will be deemed as unauthorized use of the Transmission System and subject to provisions in the Tariff surrounding that use.

Use of interim operating guide

Implementation of interim operating guide, if applicable, will constitute an interim solution that will permit Interconnection Customer to operate the Generating Facility under conditional Interconnection Service until planned Network Upgrades are constructed. Any interim operating

guide will be subject to the approval of Transmission Owner and Transmission Provider. Minimum requirements for an interim operating guide are as indicated below.

* Transmission Operator will have control of breaker(s) dedicated to the Generating Facility and will be able to trip the Interconnection Customer's Generating Facility
* Protection schemes must be tested and operative
* Interconnection Customer will provide continuous communication capability with the Generator Operator
* Interconnection Customer and the owner of the Existing Generating Facility will enter into an operating agreement or similar agreement which designates, among other things, the responsibilities and authorities of each of the parties and shall be subject to the acceptance of Transmission Provider and Transmission Owner.
* A termination date consistent with completion of construction of Network Upgrades will be included as part of all operating guides accepted by Transmission Owner and Transmission Provider.

Interconnection Customer assumes all risks and liabilities with respect to changes, which may impact the Generator Interconnection Agreement including, but not limited to, change in output limits and responsibilities for future Network Upgrade and cost responsibilities that have not yet been identified on the direct connect Transmission System as well as all affected Transmission, Distribution or Generation System(s) including non-Transmission Provider Systems. Such upgrades will be determined pursuant to the Tariff and Policies in effect at the time of the Interconnection Studies.

Appendix I to GIA – Not Applicable
Requirements Applicable to Surplus Interconnection Service

Where this GIA provides for Surplus Interconnection Service, Interconnection Customer acknowledges, agrees to, and will be required to operate under the following conditions:

1) The combined Real-Time Offers, including Energy and Operating Reserves, of the Generating Facility and the Existing Generating Facility with which Interconnection Customer has an executed Energy Displacement Agreement must be less than or equal to Interconnection Service limit (MW, MVAR, MVA output) provided in Exhibit I-1 (Monitoring and Consent Agreement) (hereinafter, "Interconnection Service limit"). In the event that the sum of the simultaneous energy output of the Surplus Interconnection Service Generating Facility and the Existing Generating Facility exceeds such Interconnection Service limit, MISO reserves the right to curtail and/or disconnect the Generating Facility immediately.

   In the event that the sum of the emergency and/or economic maximum offer limits of the Generating Facility and the Existing Generating Facility exceeds the Interconnection Service limit, MISO reserves the right to curtail and/or disconnect the Generating Facility immediately.
2) The total MW, MVAR, MVA output at the Point of Interconnection resulting from the combined output of the Generating Facility with Surplus Interconnection Service and the Existing Generating Facility with which Interconnection Customer has an executed Energy Displacement Agreement shall not at any time exceed the Interconnection Service limit.

3) The Existing Generating Facility with which Interconnection Customer has an executed Energy Displacement Agreement is not relieved of any applicable requirements under the RAR of the Tariff.

4) The Interconnection Customer shall submit to the Transmission Provider a report by the seventh Calendar Day of each month showing the prior month's output, by 15 minute increment, the combined real-time offers and cleared energy injection. The Existing Generating Facility and the Interconnection Customer shall cooperate consistent with other provisions in the Tariff to the extent necessary to ensure accuracy of the report. Transmission Provider shall provide a template for this report.

Exhibit I-1 (Completed Monitoring and Consent Agreement - Appendix 11 of the GIP)

Exhibit I-2 (Completed Energy Displacement Agreement - Appendix 12 of the GIP)

TAB B
PUBLIC

GENERATOR INTERCONNECTION AGREEMENT (GIA)

THIS GENERATOR INTERCONNECTION AGREEMENT ("GIA") is made and entered into this ____ day of _____ ~~20__~~,2025, by and between _____,**Entergy Louisiana, LLC,** a _____limited liability company organized and existing under the laws of the State~~/Commonwealth~~ of _____Texas ("Interconnection Customer" with a Generating Facility), and _____,**Entergy Louisiana, LLC,** a ~~[corporation]~~limited liability company organized and existing under the laws of the State~~/Commonwealth~~ of _____Texas ("Transmission Owner"), and the **Midcontinent Independent System Operator, Inc**., a non-profit, non-stock corporation organized and existing under the laws of the State of Delaware ("Transmission Provider"). Interconnection Customer, Transmission Owner and Transmission Provider each may be referred to as a "Party," or collectively as the "Parties."

RECITALS

WHEREAS, Transmission Provider has functional control of the operations of the Transmission System, as defined herein, and is responsible for providing Transmission Service and Interconnection Service on the transmission facilities under its control; and

WHEREAS, Interconnection Customer intends to own, lease and/or control and operate the Generating Facility identified as a Generating Facility in Appendix A to this GIA; and

WHEREAS, Transmission Owner owns or operates the Transmission System, whose operations are subject to the functional control of Transmission Provider, to which Interconnection Customer desires to connect the Generating Facility, and may therefore be required to construct certain Interconnection Facilities and Network Upgrades, as set forth in this GIA; and

WHEREAS, Interconnection Customer, Transmission Owner and Transmission Provider have agreed to enter into this GIA, and where applicable subject to Appendix H for a Provisional Generator Interconnection Agreement, for the purpose of interconnecting the Generating Facility with the Transmission System;

NOW, THEREFORE, in consideration of and subject to the mutual covenants contained herein, it is agreed:

ARTICLE 1. DEFINITIONS

When used in this GIA, terms with initial capitalization that are not defined in Article 1 shall have the meanings specified in the Article in which they are used. Those capitalized terms used in this GIA that are not otherwise defined in this GIA have the meaning set forth in the Tariff.

10 kW Inverter Process shall mean the procedure for evaluating an Interconnection Request for a certified inverter-based Small Generating Facility no larger than 10 kW that uses the screen set forth in Section 14.

Adverse System Impact shall mean the negative effects due to technical or operational limits on conductors or equipment being exceeded that may compromise the safety and reliability of the electric system.

Affected System(s) shall mean an electric transmission system or the electric system associated with an Existing Generating Facility or of a higher queued Generating Facility, which is an electric system other than the Transmission Provider's Transmission System that is affected by the Interconnection Request. An Affected System may or may not be subject to FERC jurisdiction.

Affected System Facilities Construction Agreement shall mean the agreement that is made between Transmission Provider and Interconnection Customer(s) to facilitate the construction of and to set forth cost responsibility for necessary Affected System Network Upgrades. This may or may not be a multi-party agreement, as determined by the Transmission Provider.

Affected System Interconnection Customer shall mean any entity that submits an interconnection request for a Generating Facility to a transmission system other than Transmission Provider's Transmission System that may cause the need for Affected System Network Upgrades on the Transmission Provider's Transmission System.

Affected System Network Upgrades shall mean the additions, modifications, and upgrades to Transmission Provider's Transmission System required to accommodate Affected System Interconnection Customer's proposed interconnection to a transmission System other than Transmission Provider's Transmission System.

Affected System Network Upgrade Facilities Study shall mean the facilities study performed by the Affected System Operator or Affected System Operator transmission owner to determine a list of facilities (including Affected System Interconnection Customer's interconnection facilities, transmission owner's interconnection facilities, system protection facilities, and if such upgrades have been determined, network upgrades, distribution upgrades, generator upgrades, common use upgrades, the cost of those facilities, and the time required to interconnect the generating facility(ies) with the Affected System Operator's transmission system.

Affected System Network Upgrade Facilities Study Report shall mean the report issued by the Affected System Operator following the completion of the Affected System Network Upgrade Facilities Study pursuant to Section 7.3.3 of the GIP.

Affected System Operator shall mean the entity that operates an Affected System.

Affected System Queue Position shall mean the queue position of an Affected System Interconnection Customer in Transmission Provider's interconnection queue relative to Transmission Provider's Interconnection Customers' Queue Position.

Affected System Study shall mean the evaluation of Affected System Interconnection Customers' proposed interconnection(s) to a transmission system other than the Transmission Provider's Transmission System that have an impact on Transmission Provider's Transmission System, as described in Section 8 of this GIP.

Affected System Study Agreement shall mean the agreement contained in Appendix 16 to the GIP that is made between Transmission Provider and host transmission provider, in absence of a JOA, JPA, or other agreement filed with the Commission, as noted in Section 8.

Affected System Study Report shall mean the report issued following completion of an Affected System Study.

Affiliate shall mean, with respect to a corporation, partnership or other entity, each such other corporation, partnership or other entity that directly or indirectly, through one or more intermediaries, controls, is controlled by, or is under common control with, such corporation, partnership or other entity.

Ancillary Services shall mean those services that are necessary to support the transmission of capacity and energy from resources to loads while maintaining reliable operation of the Transmission System in accordance with Good Utility Practice.

Applicable Laws and Regulations shall mean all duly promulgated applicable federal, state and local laws, regulations, rules, ordinances, codes, decrees, judgments, directives, or judicial or administrative orders, permits and other duly authorized actions of any Governmental Authority having jurisdiction over the Parties, their respective facilities and/or the respective services they provide.

Applicable Reliability Standards shall mean the requirements and guidelines of the Electric Reliability Organization and the Balancing Authority Area of the Transmission System to which the Generating Facility is directly interconnected.

Balancing Authority shall mean an entity that integrates resource plans ahead of time, maintains demand and resource balance within a Balancing Authority Area, and supports interconnection frequency in real time.

Balancing Authority Area shall mean the collection of generation, transmission, and

loads within the metered boundaries of the Balancing Authority. The Balancing Authority maintains load-resource balance within this area.

Base Case shall mean the base case power flow, short circuit, and stability databases used for the Interconnection Studies by Transmission Provider or Interconnection Customer.

Base Case Data shall mean base case power flow, short circuit and stability databases, including all underlying assumptions, and contingency lists. Such databases and lists, hereinafter referred to as Base Cases, shall include all (1) generation projects and (2) transmission projects, including merchant transmission projects that are proposed for the Transmission System for which a transmission expansion plan has been submitted and approved by the MISO Board.

Breach shall mean the failure of a Party to perform or observe any material term or condition of this GIA.

Breaching Party shall mean a Party that is in Breach of this GIA.

Business Day shall mean Monday through Friday, excluding Federal Holidays.

Calendar Day shall mean any day including Saturday, Sunday or a Federal Holiday. In the event that a period specified in this GIA is calculated in Calendar Days ends on a non-business day, such period shall be deemed to conclude on the following business day.

Cluster shall mean a group of one or more Interconnection Requests that are studied together for the purpose of conducting a Group Study.

Commercial Operation shall mean the status of a Generating Facility that has commenced generating electricity for sale, excluding electricity generated during Trial Operation.

Commercial Operation Date (COD) of a unit shall mean the date on which the Generating Facility commences Commercial Operation as agreed to by the Parties pursuant to Appendix E to this GIA.

Commitment Projection shall mean a projection of the number of MW expected to commit to the JTIQ Portfolio from ERAS and all DPP study clusters that already have passed DP1 as described in Section 9.4.2.e.ii of Rate Schedule 6 (MISO SPP-JOA).

Common Use Upgrade (CUU) shall mean an Interconnection Facility, Network Upgrade, System Protection Facility, or any other classified addition, alteration, or improvement on the Transmission System or the transmission system of an Affected System, not classified under Attachment FF as a Baseline Reliability Project, Market Efficiency Project, or Multi-Value Project, that is needed for the interconnection of multiple Interconnection Customers' Generating Facilities and which is the shared responsibility of such Interconnection Customers.

Confidential Information shall mean any proprietary or commercially or competitively

sensitive information, trade secret or information regarding a plan, specification, pattern, procedure, design, device, list, concept, policy or compilation relating to the present or planned business of a Party, or any other information as specified in Article 22, which is designated as confidential by the Party supplying the information, whether conveyed orally, electronically, in writing, through inspection, or otherwise, that is received by another Party.

Connection Facilities shall mean the Transmission Owner's Connection Facilities and the MHVDC Connection Customer's Connection Facilities, as defined in the MHCP.

Contingent Facilities shall mean those unbuilt Interconnection Facilities and Network Upgrades upon which the Interconnection Request's costs, timing and study findings are dependent, and if delayed or not built, could cause a need for restudies of the Interconnection Request or a reassessment of the Interconnection Facilities and/or Network Upgrades and/or costs and timing. Contingent Facilities may include facilities identified in MTEP that if delayed or not built could impact the timing of the Interconnection Request.

Customer Engagement Window shall mean the time period prior to the start of Definitive Planning Phase I set forth in Section 3.3.4 of the GIP.

Default shall mean the failure of a Breaching Party to cure its Breach in accordance with Article 17 of this GIA.

Definitive Planning Phase shall mean the Generator Interconnection Procedures process which leads to a Generator Interconnection Agreement. An Interconnection Customer enters the Definitive Planning Phase pursuant to GIP Section 7.2. The Definitive Planning Phase includes three distinct phases (Definitive Planning Phases I, II, and III) pursuant to Section 7 of the Generator Interconnection Procedures.

Definitive Planning Phase Queue Position shall mean the order of a valid Interconnection Request, relative to all other pending valid Interconnection Requests, in the Definitive Planning Phase. The Definitive Planning Phase Queue Position is established based upon the date Interconnection Customer satisfies all of the requirements of GIP Section 7.2 to enter the Definitive Planning Phase. All Interconnection Requests within the same Definitive Planning Phase cycle shall have equal priority (i.e. similarly queued).

Demonstrated Capability shall mean the continuous net real power output that the Generating Facility is required to demonstrate in compliance with Applicable Reliability Standards.

Dispute Resolution shall mean the procedure for resolution of a dispute between or among the Parties in which they will first attempt to resolve the dispute on an informal basis.

Distribution System shall mean the Transmission Owner's facilities and equipment, or the Distribution System of another party that is interconnected with the Transmission Owner's Transmission System, if any, connected to the Transmission System, over which facilities Transmission Service or Wholesale Distribution Service under the Tariff is available at the time

Interconnection Customer has requested interconnection of a Generating Facility for the purpose of either transmitting electric energy in interstate commerce or selling electric energy at wholesale in interstate commerce and which are used to transmit electricity to ultimate usage points such as homes and industries directly from nearby generators or from interchanges with higher voltage transmission networks which transport bulk power over longer distances. The voltage levels at which distribution systems operate differ among Local Balancing Authorities and other entities owning distribution facilities interconnected to the Transmission System.

Distribution Upgrades shall mean the additions, modifications, and upgrades to the Distribution System at or beyond the Point of Interconnection to facilitate interconnection of the Generating Facility and render the delivery service necessary to affect Interconnection Customer's wholesale sale of electricity in interstate commerce. Distribution Upgrades do not include Interconnection Facilities.

Effective Date shall mean the date on which this GIA becomes effective upon execution by the Parties subject to acceptance by the Commission, or if filed unexecuted, upon the date specified by the Commission.

Electric Reliability Organization shall mean the North American Electric Reliability Corporation or its successor organization.

Emergency Condition shall mean a condition or situation: (1) that in the reasonable judgment of the Party making the claim is imminently likely to endanger, or is contributing to the endangerment of, life, property, or public health and safety; or (2) that, in the case of either Transmission Provider or Transmission Owner, is imminently likely (as determined in a non-discriminatory manner) to cause a material adverse effect on the security of, or damage to the Transmission System, Transmission Owner's Interconnection Facilities or the electric systems of others to which the Transmission System is directly connected; or (3) that, in the case of Interconnection Customer, is imminently likely (as determined in a non-discriminatory manner) to cause a material adverse effect on the security of, or damage to, the Generating Facility or Interconnection Customer's Interconnection Facilities. System restoration and blackstart shall be considered Emergency Conditions; provided that Interconnection Customer is not obligated by this GIA to possess blackstart capability. Any condition or situation that results from lack of sufficient generating capacity to meet load requirements or that results solely from economic conditions shall not constitute an Emergency Condition, unless one of the enumerated conditions or situations identified in this definition also exists.

Energy Displacement Agreement shall mean an agreement between an Interconnection Customer with an Existing Generating Facility on the Transmission Provider's Transmission System and an Interconnection Customer with a proposed Generating Facility seeking to interconnect with Surplus Interconnection Service. The Energy Displacement Agreement specifies the term of operation, the Generating Facility Interconnection Service limit, and the mode of operation for energy production (common or singular operation).

Energy Resource Interconnection Service (ER Interconnection Service) shall mean an Interconnection Service that allows Interconnection Customer to connect its Generating

Facility to the Transmission System or Distribution System, as applicable, to be eligible to deliver the Generating Facility's electric output using the existing firm or non-firm capacity of the Transmission System on an as available basis. Energy Resource Interconnection Service does not convey transmission service.

Engineering & Procurement (E&P) Agreement shall mean an agreement that authorizes Transmission Owner to begin engineering and procurement of long lead-time items necessary for the establishment of the interconnection in order to advance the implementation of the Interconnection Request.

Environmental Law shall mean Applicable Laws or Regulations relating to pollution or protection of the environment or natural resources.

Existing Generating Facility shall mean a Generating Facility that is either under construction or is in service, and has an unsuspended interconnection agreement with its host transmission provider.

Expanded Scope Analysis shall mean the analysis described in Section 9.4.2.d.iv.a of Rate Schedule 6 (MISO-SPP JOA).

Expedited Resource Addition Study (ERAS) shall mean the temporary procedure for expediting interconnection projects identified for claimed resource adequacy and/or reliability needs.

Expedited Generator Interconnection Agreement (EGIA) shall mean the interconnection agreement for the Expedited Resource Addition Study established between the Transmission Provider and/or the Transmission Owner and the Interconnection Customer as set forth in Section 3.9 of this Attachment X. This agreement shall take the form of the Transmission Provider's *pro forma* Generator Interconnection Agreement modified for the Expedited Resource Addition Study. Unless otherwise provided in the GIP, all requirements applicable to the *pro forma* Generator Interconnection Agreement shall apply to the Expedited Generator Interconnection Agreement.

Facilities Construction Agreement (FCA) shall mean the form of facilities construction agreement, set forth in Appendix 8 to these Generator Interconnection Procedures. The FCA shall be used when an Interconnection Customer or an Affected System Interconnection Customer causes the need for the construction of Network Upgrades or System Protection Facilities on the transmission system of the Transmission Provider.

Fast Track Process shall mean the procedure for evaluating an Interconnection Request for a certified Small Generating Facility no larger than five MW that includes the screen set forth in Section 14, customer options meeting, and optional supplemental review.

Federal Holiday shall mean a Federal Reserve Bank holiday for a Party that has its principal place of business in the United States and a Canadian Federal or Provincial banking holiday for a Party that has its principal place of business located in Canada.

Federal Power Act shall mean the Federal Power Act, as amended, 16 U.S.C. §§ 791a *et seq*.

FERC shall mean the Federal Energy Regulatory Commission, also known as Commission, or its successor.

Final System Impact Study shall mean the Interconnection System Impact Study performed during Definitive Planning Phase III.

Force Majeure shall mean any act of God, labor disturbance, act of the public enemy, war, insurrection, riot, fire, storm or flood, explosion, breakage or accident to machinery or equipment, any order, regulation or restriction imposed by governmental, military or lawfully established civilian authorities, or any other cause beyond a Party's control. A Force Majeure event does not include an act of negligence or intentional wrongdoing by the Party claiming Force Majeure.

Generating Facility shall mean Interconnection Customer's device(s) for the production and/or storage for later injection of electricity identified in the Interconnection Request, but shall not include the Interconnection Customer's Interconnection Facilities. A Generating Facility consists of one or more generating unit(s) and/or storage device(s) which usually can operate independently and be brought online or taken offline individually.

Generating Facility Capacity shall mean the net capacity of the Generating Facility and the aggregate net capacity of the Generating Facility where it includes more than one device for the production and/or storage for later injection of electricity.

Generating Facility Modification shall mean modification to an Existing Generating Facility, including comparable replacement of only a portion of its equipment at the Existing Generating Facility.

Generating Facility Replacement shall mean replacement of one or more generating units and/or storage devices at the Existing Generating Facility with one or more new generating units or storage devices at the same electrical Point of Interconnection as the generating units and/or storage devices that is/are being decommissioned and electrically disconnected.

Generator Interconnection Agreement (GIA) shall mean the form of interconnection agreement, set forth herein.

Generator Interconnection Procedures (GIP) shall mean the interconnection procedures set forth in Attachment X of the Tariff.

Generator Upgrades shall mean the additions, modifications, and upgrades to the electric system of an Existing Generating Facility or of a higher queued Generating Facility at or beyond the Point of Interconnection to facilitate interconnection of the Generating Facility and render the Transmission Service necessary to affect Interconnection Customer's wholesale sale

of electricity in interstate commerce.

Good Utility Practice shall mean any of the practices, methods and acts engaged in or approved by a significant portion of the electric industry during the relevant time period, or any of the practices, methods and acts which, in the exercise of reasonable judgment in light of the facts known at the time the decision was made, could have been expected to accomplish the desired result at a reasonable cost consistent with good business practices, reliability, safety and expedition. Good Utility Practice is not intended to be limited to the optimum practice, method, or act to the exclusion of all others, but rather to be acceptable practices, methods, or acts generally accepted in the region.

Governmental Authority shall mean any federal, state, local or other governmental regulatory or administrative agency, court, commission, department, board, or other governmental subdivision, legislature, rulemaking board, tribunal, or other governmental authority having jurisdiction over the Parties, their respective facilities, or the respective services they provide, and exercising or entitled to exercise any administrative, executive, police, or taxing authority or power; provided, however, that such term does not include Interconnection Customer, Transmission Provider, Transmission Owner, or any Affiliate thereof.

Group Restudy shall mean a restudy of a Group Study conducted pursuant to Section 7.5 of the GIP

Group Study(ies) shall mean the evaluation of one or more Interconnection Requests within a Cluster as described in Section 7 of the GIP. Group Studies are divided into phases as described in section 7.3 of the GIP.

Hazardous Substances shall mean any chemicals, materials or substances defined as or included in the definition of "hazardous substances," "hazardous wastes," "hazardous materials," "hazardous constituents," "restricted hazardous materials," "extremely hazardous substances," "toxic substances," "radioactive substances," "contaminants," "pollutants," "toxic pollutants" or words of similar meaning and regulatory effect under any applicable Environmental Law, or any other chemical, material or substance, exposure to which is prohibited, limited or regulated by any applicable Environmental Law.

HVDC Facilities shall mean the high voltage direct current transmission facilities, including associated alternating current facilities, if any, that are subject to Section 27A of the Tariff and that are specifically identified in (i) any Agency Agreement pertaining to such facilities between Transmission Provider and Transmission Owner that owns or operates such facilities, or (ii) in any other arrangement that permits or will permit Transmission Provider to provide HVDC Service over such facilities as set forth in Section 27A of the Tariff.

HVDC Service shall mean Firm and Non-Firm Point-To-Point Transmission Service provided by Transmission Provider on HVDC Facilities pursuant to Section 27A of the Tariff.

Initial Synchronization Date shall mean the date upon which the Generating Facility is initially synchronized and upon which Trial Operation begins.

Injection Rights shall mean the Transmission Provider's pre-certification of the Transmission System's capability to receive capacity and energy from the MHVDC Transmission Line at the requested Point of Connection, and in the specified MW quantity, without degrading the reliability of the Transmission System, as described in Section 16 of the GIP and Section 3.2.3 of the MHCP.

In-Service Date (ISD) shall mean the date upon which Interconnection Customer reasonably expects it will be ready to begin use of the Transmission Owner's Interconnection Facilities to obtain backfeed power.

Interconnection Customer shall mean any entity, including Transmission Provider, Transmission Owner or any of the Affiliates or subsidiaries of either, that proposes to interconnect its Generating Facility with the Transmission System.

Interconnection Customer Decision Point I shall mean the time period beginning when the Interconnection Customer is provided the Preliminary System Impact Study results including cost estimates for upgrades and concludes after fifteen (15) Business Days.

Interconnection Customer Decision Point II shall mean the time period beginning when the Interconnection Customer is provided the Revised System Impact Study results including cost estimates for upgrades and concludes after fifteen (15) Business Days.

Interconnection Customer's Interconnection Facilities (ICIF) shall mean all facilities and equipment, as identified in Appendix A of this GIA, that are located between the Generating Facility and the Point of Change of Ownership, including any modification, addition, or upgrades to such facilities and equipment necessary to physically and electrically interconnect the Generating Facility to the Transmission System or Distribution System, as applicable. Interconnection Customer's Interconnection Facilities are sole use facilities.

Interconnection Facilities shall mean the Transmission Owner's Interconnection Facilities and the Interconnection Customer's Interconnection Facilities. Collectively, Interconnection Facilities include all facilities and equipment between the Generating Facility and the Point of Interconnection, including any modification, additions or upgrades that are necessary to physically and electrically interconnect the Generating Facility to the Transmission System. Interconnection Facilities shall not include Distribution Upgrades, Generator Upgrades, Stand Alone Network Upgrades or Network Upgrades.

Interconnection Facilities Study(ies) shall mean a study conducted by Transmission Owner, or its agent, for Interconnection Customer(s) to determine a list of facilities (including Interconnection Customer's Interconnection Facilities or Affected System Interconnection Customer's interconnection facilities, Transmission Owner's Interconnection Facilities, System Protection Facilities, and if such upgrades have been determined, Network Upgrades, Distribution Upgrades, Generator Upgrades, Common Use Upgrades, and Affected System Network Upgrades, as identified in the Interconnection System Impact Study), the cost of those facilities, and the time required to interconnect the Generating Facility(ies) with the

Transmission System.

Interconnection Facilities Study Agreement shall mean the form of agreement contained in Appendix 4 of the Generator Interconnection Procedures for conducting the Interconnection Facilities Study.

Interconnection Request shall mean (1) an Interconnection Customer's request, in the form of Appendix 1 to the Generator Interconnection Procedures, to interconnect a new Generating Facility, or a request for the Expedited Resource Addition Study for new generation capacity, or to increase the capacity of, or make a Material Modification to the operating characteristics of, an Existing Generating Facility that is interconnected with the Transmission System, or to interconnect an Existing Generating Facility that is external to the Transmission System, or to change Energy Resource Interconnection Service to Network Resource Interconnection Service for an Existing Generating Facility; or (2) an MHVDC Connection Customer's request, in the form of Appendix 1 to the Generator Interconnection Procedures, to obtain Injection Rights..

Interconnection Service shall mean the service provided by Transmission Provider associated with interconnecting the Generating Facility to the Transmission System, or external host transmission provider if applicable, and enabling it to receive electric energy and capacity from the Generating Facility at the Point of Interconnection pursuant to the terms of this Generator Interconnection Agreement or Point of Delivery as set forth in the Service Agreement for Network Resource Interconnection Service for an External Generating Facility and, if applicable, the Tariff.

Interconnection Study (or Study) shall mean any of the studies described in the Generator Interconnection Procedures.

Interconnection Study Agreement shall mean the form of agreement contained in Attachment B to Appendix 1 of the Generator Interconnection procedures for conducting all studies required by the Generator Interconnection Procedures.

Interconnection System Impact Study shall mean an engineering study that evaluates the impact of the proposed interconnection on the safety and reliability of Transmission System and, if applicable, an Affected System. The study shall identify and detail the system impacts that would result if the Generating Facility were interconnected without project modifications or system modifications, or to study potential impacts, including but not limited to those identified in the Scoping Meeting as described in the Generator Interconnection Procedures.

Interconnection Study Agreement shall mean the forms of agreement contained in Attachment B to Appendix 1 of the Generator Interconnection Procedures for conducting all studies required by the Generator Interconnection Procedures.

IRS shall mean the Internal Revenue Service.

Joint Operating Agreement ("JOA") shall mean an agreement between adjacent

balancing authorities or transmission providers for the coordination of operations.

Joint Operating Agreement between the Midcontinent Independent System Operator, Inc. and Southwest Power Pool, Inc. (MISO-SPP JOA) shall mean Rate Schedule 6 to the MISO Tariff.

Joint Planning Agreement ("JPA") shall mean an agreement between adjacent balancing authorities or transmission providers for the coordination of planning.

Joint Targeted Interconnection Queue (JTIQ) shall refer to the study and processes described in Section 9.4.2 of Rate Schedule 6 (MISO-SPP JOA).

Joint Targeted Interconnection Queue Study ("JTIQ Study") shall mean a transmission planning study conducted jointly by SPP and MISO to facilitate the interconnection of new generator capacity in both Parties' regions.

JTIQ Commitment Group Member shall mean any JTIQ Commitment Group Member included in a Commitment Group consistent with Section 9.4 of Rate Schedule 6 (MISO-SPP JOA).

JTIQ Commitment Group or Commitment Group shall mean a group of JTIQ Commitment Group Members that have executed a JTIQ Generator Interconnection Agreement within the twelve (12) month period ending April 30th of each year. The Commitment Group shall also include JTIQ Commitment Group Members for which a JTIQ Generator Interconnection Agreement has been filed unexecuted by SPP or the Transmission Provider and the Commission has accepted the agreement within the twelve (12) month period ending April 30th of each year.

JTIQ Generator Charge shall mean the charge to JTIQ Commitment Group Members to recover the JTIQ Commitment Group Member's share of the JTIQ Monthly Revenue Requirement for each of the JTIQ Upgrades in the JTIQ Portfolio in the Transmission Provider's Region.

JTIQ Participation Group shall mean the group of Interconnection Requests that shall consist of all interconnection customers included in the JTIQ Screening Groups whose interconnection request meets the distribution factor and impact criteria specified in Section 9.4.2(d)((ii) of Rate Schedule 6 (MISO-SPP JOA).

JTIQ Portfolio shall mean a group of JTIQ Upgrades identified pursuant to Section 9.4 of Rate Schedule 6 (MISO-SPP JOA).

JTIQ Screening Group shall mean a group of MISO Interconnection Customers and SPP interconnection customers whose Interconnection Requests will be screened for inclusion in a JTIQ Participation Group. The JTIQ Screening Group shall consist of all interconnection customers who have submitted interconnection requests into a MISO ERAS, SPP ERAS, DPP study cluster, or SPP DISIS study cluster that: (1) has a study commencement or kick off date

that is after the date that the Parties' respective Boards of Directors have approved a JTIQ Portfolio; and (2) has not commenced DPP Phase I, a MISO ERAS, the SPP ERAS or DISIS Phase One studies pursuant to each party's OATT as of the date that the Parties have declared the JTIQ Portfolio fully subscribed.

JTIQ Service Agreements shall mean the JTIQ Commitment Agreement attached to the MISO GIA as Appendix 17 and the SPP's *pro forma* agreement(s) that obligate interconnection customers to provide security for and pay the JTIQ Generator Charge for JTIQ Network Upgrades included in the applicable JTIQ Portfolio.

JTIQ Upgrade shall mean a Network Upgrade included in a JTIQ portfolio pursuant to Section 9.4 of Rate Schedule 6 (MISO-SPP JOA)**.**

Local Balancing Authority shall mean an operational entity or a Joint Registration Organization which is (i) responsible for compliance with the subset of Electric Reliability Organization Balancing Authority Reliability Standards defined in the Balancing Authority Agreement for their local area within the MISO Balancing Authority Area, (ii) a Party to Balancing Authority Agreement, excluding MISO, and (iii) provided in the Balancing Authority Agreement.

Local Resource Zone (LRZ) shall mean a geographic area within the Transmission Provider Region that is prescribed by the Transmission Provider, based upon the criteria in Section 68A.3, to address congestion that limits Planning Resource deliverability.

Loss shall mean any and all damages, losses, claims, including claims and actions relating to injury to or death of any person or damage to property, demand, suits, recoveries, costs and expenses, court costs, attorney fees, and all other obligations by or to third parties, arising out of or resulting from the other Party's performance, or non-performance of its obligations under this GIA on behalf of the indemnifying Party, except in cases of gross negligence or intentional wrongdoing, by the indemnified party.

Material Modification shall mean: (1) modification to an Interconnection Request in the queue, that has a material adverse impact on the cost or timing of any other Interconnection Request with an equal or later queue priority date; or Qualified Change.

Metering Equipment shall mean all metering equipment installed or to be installed at the Generating Facility, Interconnection Customer's Interconnection Facilities, and/or Transmission Owner's Interconnection Facilities pursuant to this GIA at the metering points, including but not limited to instrument transformers, MWh-meters, data acquisition equipment, transducers, remote terminal unit, communications equipment, phone lines, and fiber optics.

Monitoring and Consent Agreement shall mean an agreement that defines the terms and conditions applicable to a Generating Facility acquiring Surplus Interconnection Service. The Monitoring and Consent Agreement will list the roles and responsibilities of an Interconnection Customer seeking to interconnect with Surplus Interconnection Service and Transmission Owner to maintain the total output of the Generating Facility inside the parameters

delineated in the GIA.

Multi-Party Facilities Construction Agreement (MPFCA) shall mean the form of facilities construction agreement, set forth in Appendix 9 to these Generator Interconnection Procedures. The MPFCA shall be used when multiple Interconnection Requests or interconnection requests from Affected System Interconnection Customers cause the need for the construction of Common Use Upgrades on the Transmission System and share cost responsibility for such Common Use Upgrades.

Network Customer shall have that meaning as provided in the Tariff.

Network Resource shall mean any designated generating resource owned, purchased, or leased by a Network Customer under the Tariff. Network Resources do not include any resource, or any portion thereof, that is committed for sale to third parties or otherwise cannot be called upon to meet the Network Customer's Network Load on a non-interruptible basis.

Network Resource Interconnection Service (NR Interconnection Service) shall mean an Interconnection Service that allows Interconnection Customer to integrate its Generating Facility with the Transmission System in the same manner as for any Generating Facility being designated as a Network Resource. Network Resource Interconnection Service does not convey transmission service. Network Resource Interconnection Service shall include any network resource interconnection service established under an agreement with, or the tariff of, a Transmission Owner prior to integration into MISO, that is determined to be deliverable through the integration deliverability study process.

Network Upgrades shall mean the additions, modifications, and upgrades to the Transmission System required at or beyond the point at which the Interconnection Facilities connect to the Transmission System or Distribution System, as applicable, to accommodate the interconnection of the Generating Facility(ies) to the Transmission System. Network Upgrades shall not include any HVDC Facility Upgrades.

Notice of Dispute shall mean a written notice of a dispute or claim that arises out of or in connection with this GIA or its performance.

Optional Interconnection Study shall mean a sensitivity analysis based on assumptions specified by Interconnection Customer in the Optional Interconnection Study Agreement.

Optional Interconnection Study Agreement shall mean the form of agreement contained in Appendix 5 of the Generator Interconnection Procedures for conducting the Optional Interconnection Study.

Outage Transfer Distribution Factor (OTDF) Outage Transfer Distribution Factor, as defined by the Electric Reliability Organization.

Party or Parties shall mean Transmission Provider, Transmission Owner, Interconnection Customer, or any combination of the above.

Permissible Technological Advancement shall mean advancements to turbines, inverters, plant supervisory controls, excitation systems, or other technological advancements submitted to the Transmission Provider prior to the issuance of this draft Generator Interconnection Agreement for such project provided that such advancements does not: (1) degrade the electrical characteristics of the generating equipment; (2) does not cause any material adverse impact on the Transmission System with regard to short circuit capability limits, steady-state thermal and voltage limits, or dynamic system stability and response; (3) does not increase the installed capacity of the Generating Facility; or (4) change the fuel source of the proposed Generating Facility.

Point of Change of Ownership (PCO) shall mean the point, as set forth in Appendix A to the Generator Interconnection Agreement, where the Interconnection Customer's Interconnection Facilities connect to the Transmission Owner's Interconnection Facilities.

Point of Interconnection (POI) shall mean the point, as set forth in Appendix A of the GIA, where the Interconnection Facilities connect to the Transmission System.

Potential MW Total shall mean a projection of the number of MW that may commit to the JTIQ Portfolio from all ERAS and study clusters to date, including the current study cluster(s).

Preliminary System Impact Study shall mean the Interconnection System Impact Study performed during Definitive Planning Phase I.

Pre-Queue Phase shall mean Interconnection Customer outreach and education effort undertaken prior to the submission of the Interconnection Request.

Proportional Impact Method shall mean a technical analysis conducted by Transmission Provider to determine the degree to which each Generating Facility in the Group Study contributes to the need for a specific Network Upgrade.

Provisional Generator Interconnection Agreement shall mean the interconnection agreement for Provisional Interconnection Service established between the Transmission Provider and/or the Transmission Owner and the Interconnection Customer as set forth in Section 7.9 of this Attachment X. This agreement shall take the form of the Generator Interconnection Agreement modified for provisional purposes. Unless otherwise provided in the GIP, all requirements applicable to the Generator Interconnection Agreement shall apply to the Provisional Generator Interconnection Agreement.

Provisional Interconnection Service shall mean Interconnection Service provided by the Transmission Provider associated with interconnecting the Interconnection Customer's Generating Facility to the Transmission Provider's Transmission System and enabling that Transmission System to receive electric energy and capacity from the Generating Facility at the Point of Interconnection, pursuant to the terms of the Provisional Generator Interconnection Agreement and the Tariff.

Provisional Interconnection Study shall mean an engineering study, performed at Interconnection Customer's request, as a condition to entering into a Provisional Generator Interconnection Agreement, that evaluates the impact of the proposed interconnection on the safety and reliability of the Transmission System and, if applicable, any Affected System. The study shall identify and detail the impacts on the Transmission System and, if applicable, an Affected System, from stability, short circuit, and voltage issues that would result if the Generating Facility were interconnected without project modifications or system modifications.

Qualified Change shall mean a planned modification to an Existing Generating Facility that is undergoing evaluation for a Generating Facility Modification or Generating Facility Replacement, and has a material adverse impact on the Transmission System with respect to: i) steady-state thermal or voltage limits, ii) dynamic system stability and response, or iii) short-circuit capability limit; compared to the impacts of the Existing Generating Facility prior to the modification or replacement.

Queue Position shall mean the order of a valid Interconnection Request, relative to all other pending valid Interconnection Requests pursuant to Section 4.1 of the GIP.

Reasonable Efforts shall mean, with respect to an action required to be attempted or taken by a Party under this Generator Interconnection Agreement, efforts that are timely and consistent with Good Utility Practice and are otherwise substantially equivalent to those a Party would use to protect its own interests.

Relevant Electric Retail Regulatory Authority (RERRA) shall mean an entity that has jurisdiction over and establishes prices and/or policies for providers of retail electric service to end-customers, such as the city council for a municipal utility, the governing board of a cooperative utility, the state public utility commission or any such entity.

Reliability Assessment Study shall mean an engineering study that evaluates the impact of a proposed Generating Facility Replacement on the reliability of Transmission System during the time period between the date that the Existing Generating Facility ceases commercial operations and the Commercial Operation Date of the Replacement Generating Facility.

Replacement Generating Facility shall mean a Generating Facility that replaces an Existing Generating Facility, or a portion thereof, at the same electrical Point of Interconnection pursuant to Section 3.7 of this Attachment X.

Replacement Impact Study shall mean an engineering study that evaluates the impact of a proposed Generating Facility Replacement on the reliability of the Transmission System.

Revised System Impact Study shall mean the Interconnection System Impact Study performed during Definitive Planning Phase II.

Scoping Meeting shall mean the meeting between representatives of Interconnection Customer, Transmission Owner, Affected System Operator(s) and Transmission Provider

conducted for the purpose of discussing the proposed Interconnection Request and any alternative interconnection options, exchanging information including any transmission data and earlier study evaluations that would be reasonably expected to impact such interconnection options, refining information and models provided by Interconnection Customer(s), discussing the Group Study materials posted to OASIS pursuant to Section 3.4 of the GIP, and analyzing such information.

Shared Interconnection Request shall mean (1) multiple Interconnection Customer's request, in the form of Appendix 1 to the Generator Interconnection Procedures, to interconnect new Generating Facilities, or to increase the capacity of, or make a Material Modification to the operating characteristics of, Existing Generating Facilities that are interconnected with the Transmission System, or to interconnect Existing Generating Facilities that are external to the Transmission System, or to change Energy Resource Interconnection Service to Network Resource Interconnection Service for Existing Generating Facilities; or (2) multiple MHVDC Connection Customer's request, in the form of Appendix 1 to the Generator Interconnection Procedures, to obtain Injection Rights.

Shared Network Upgrade shall mean a Network Upgrade or Common Use Upgrade that is funded by an Interconnection Customer(s), including when the Transmission Owner elects to fund the capital cost of such a Network Upgrade or Common Use Upgrade under Section 11.3 of the GIA, and also benefits other Interconnection Customer(s) that are later identified as beneficiaries.

Site Control shall mean a documented right for one or more parcels of land for the purpose of constructing a Generating Facility, Interconnection Customer's Interconnection Facilities, and, if applicable (*i.e.*, when the Interconnection Customer is providing the site for such facilities), the Transmission Owner's Interconnection Facilities and Network Upgrades at the POI that the Interconnection Customer will develop. Such documented right shall be one of the following: (1) ownership of a site; (2) a leasehold interest in a site; or (3) an option to purchase or acquire a leasehold interest in a site; or (4) any other contractual or legal right to possess or occupy a site. Transmission Provider will maintain acreage requirements for each Generating Facility type on its OASIS or public website.

Small Generating Facility shall mean a Generating Facility that has an aggregate net Generating Facility Capacity of no more than five MW and meets the requirements of Section 14 and Appendix 3 of the GIP.

Southwest Power Pool (SPP) shall refer to the Southwest Power Pool, Inc. the Regional Transmission Organization that is the counterparty to Rate Schedule 6 (MISO-SPP JOA).

Special Protection System (SPS) shall mean an automatic protection system or remedial action scheme designed to detect abnormal or predetermined system conditions, and take corrective actions other than and/or in addition to the isolation of faulted components, to maintain system reliability. Such action may include changes in demand (MW and MVar), energy (MWh and MVarh), or system configuration to maintain system stability, acceptable voltage, or power flows. An SPS does not include (a) underfrequency or undervoltage load

shedding, (b) fault conditions that must be isolated, (c) out-of-step relaying not designed as an integral part of an SPS, or (d) Transmission Control Devices.

Stand Alone Network Upgrades shall mean Network Upgrades, that are not part of an Affected System or a JTIQ Upgrade, that Interconnection Customer may construct without affecting day-to-day operations of the Transmission System during their construction. Transmission Provider, Transmission Owner and Interconnection Customer must agree as to what constitutes Stand Alone Network Upgrades and identify them in Appendix A to this GIA. If the Transmission Provider or Transmission Owner and Interconnection Customer disagree about whether a particular Network Upgrade is a Stand Alone Network Upgrade, the Transmission Provider or Transmission Owner that disagrees with the Interconnection Customer must provide the Interconnection Customer a written technical explanation outlining why the Transmission Provider or Transmission Owner does not consider the Network Upgrade to be a Stand Alone Network Upgrade within fifteen (15) Business Days of its determination.

Substation Network Upgrades shall mean Network Upgrades that are required at or near the Point of Interconnection and are identified in the first portion of the Interconnection Facilities Study as described in GIP Section 7.3.2.5.

Supplemental Affected System Analysis shall mean **t**he affected systems analysis described in Section 7.3.2.3.1 of this GIP and Section 9.4.2.e.iii.a.i of the Rate Schedule 6 (MISO-SPP JOA) to determine if Supplemental Affected System Upgrades are required for one or more JTIQ Participation Group member(s).

Supplemental Affected System Upgrade shall mean a Network Upgrade in addition to those required to address the impact of interconnection requests in the current study cluster as described in Section 9.4.2.e.iii.a.i of Rate Schedule 6 (MISO-SPP-JOA).

Surplus Interconnection Service shall mean any Interconnection Service that is derived from the unneeded portion of Interconnection Service established in a GIA or in agreement with, or under the tariff of, a Transmission Owner prior to integration into MISO, such that if Surplus Interconnection Service is utilized the total amount of Interconnection Service at the Point of Interconnection would remain the same.

System Planning and Analysis Phase shall mean the phase of the Generator Interconnection Procedure process, prior to January 4, 2017, which consisted of an Interconnection System Impact Study for those Interconnection Requests that were studied in this phase.

System Protection Facilities shall mean the equipment, including necessary protection signal communications equipment, required to protect (1) the Transmission System or other delivery systems or other generating systems from faults or other electrical disturbances occurring at the Generating Facility and (2) the Generating Facility from faults or other electrical system disturbances occurring on the Transmission System or on other delivery systems or other generating systems to which the Transmission System is directly connected.

Target MW Value shall mean the projected new generation interconnection MW enabled by the JTIQ Portfolio. The Target MW Value for each JTIQ Portfolio shall be identified in Section 9.4 and related subsections of Rate Schedule 6.

Tariff shall mean the Transmission Provider's Tariff through which open access transmission service and Interconnection Service are offered, as filed with the Commission, and as amended or supplemented from time to time, or any successor tariff.

Threshold Charge shall mean the charge calculated using an estimate of plant in service value for the JTIQ Portfolio, excluding amounts funded under the GRIP Program, as described in Section 9.4.2 of Rate Schedule 6 (MISO-SPP JOA).

Transmission Control Devices shall mean a generally accepted transmission device that is planned and designed to provide dynamic control of electric system quantities, and are usually employed as solutions to specific system performance issues. Examples of such devices include fast valving, high response exciters, high voltage DC links, active or real power flow control and reactive compensation devices using power electronics (*e.g.*, unified power flow controllers), static var compensators, thyristor controlled series capacitors, braking resistors, and in some cases mechanically-switched capacitors and reactors. In general, such systems are not considered to be Special Protection Systems.

Transmission Owner shall mean that Transmission Owner as defined in the Tariff, which includes an entity that owns, leases or otherwise possesses an interest in the portion of the Transmission System at which Interconnection Customer proposes to interconnect or otherwise integrate the operation of the Generating Facility. Transmission Owner should be read to include any Independent Transmission Company that manages the transmission facilities of Transmission Owner and shall include, as applicable, the owner and/or operator of distribution facilities interconnected to the Transmission System, over which facilities transmission service or Wholesale Distribution Service under the Tariff is available at the time Interconnection Customer requests Interconnection Service and to which Interconnection Customer has requested interconnection of a Generating Facility for the purpose of either transmitting electric energy in interstate commerce or selling electric energy at wholesale in interstate commerce.

Transmission Provider shall mean the Midcontinent Independent System Operator, Inc. ("MISO"), the Regional Transmission Organization that controls or operates the transmission facilities of its transmission-owning members used for the transmission of electricity in interstate commerce and provides transmission service under the Tariff.

Transmission Owner's Interconnection Facilities (TOIF) shall mean all facilities and equipment owned by Transmission Owner from the Point of Change of Ownership to the Point of Interconnection as identified in Appendix A to this GIA, including any modifications, additions or upgrades to such facilities and equipment. Transmission Owner's Interconnection Facilities are sole use facilities and shall not include Distribution Upgrades, Generator Upgrades, Stand Alone Network Upgrades or Network Upgrades.

Transmission System shall mean the facilities owned by Transmission Owner and

controlled or operated by Transmission Provider or Transmission Owner that are used to provide Transmission Service (including HVDC Service) or Wholesale Distribution Service under the Tariff.

Trial Operation shall mean the period during which Interconnection Customer is engaged in on-site test operations and commissioning of the Generating Facility prior to Commercial Operation.

User-Defined Model shall mean any set of programming code created by equipment manufacturers or developers that captures the latest features of controllers that are mainly software-based and represent the entities' control strategy but does not necessarily correspond to any particular generic library model, as contained in Attachment A to Appendix 1 of the GIP.

Variable Energy Resource shall mean a device for the production of electricity that is characterized by an energy source that: (1) is renewable; (2) cannot be stored by the facility owner or operator; and (3) has variability that is beyond the control of the facility owner or operator.

Wholesale Distribution Service shall have that meaning as provided in the Tariff. Wherever the term "transmission delivery service" is used, Wholesale Distribution Service shall also be implied.

ARTICLE 2. EFFECTIVE DATE, TERM AND TERMINATION

2.1 Effective Date. This GIA shall become effective upon execution by the Parties subject to acceptance by FERC (if applicable), or if filed unexecuted, upon the date specified by FERC. Transmission Provider shall promptly file this GIA with FERC upon execution in accordance with Article 3.1, if required.

2.2 Term of Agreement. Subject to the provisions of Article 2.3, this GIA shall remain in effect for a period of ~~———~~thirty (30) years from the Effective Date and shall be automatically renewed for each successive one-year period thereafter on the anniversary of the Effective Date.

2.3 Termination Procedures. This GIA may be terminated as follows:

2.3.1 Written Notice. This GIA may be terminated by Interconnection Customer after giving Transmission Provider and Transmission Owner ninety (90) Calendar Days advance written notice. This GIA shall be terminated by Transmission Provider if the Generating Facility or a portion of the Generating Facility fails to achieve Commercial Operation by the Commercial Operation Date established in accordance with Section 4.4.4 of Attachment X, including any extension provided thereunder, or has ceased Commercial Operation for three (3) consecutive years, beginning with the last date of Commercial Operation for the Generating Facility, after giving Interconnection Customer ninety (90) Calendar Days advance written notice. Where only a portion of the Generating Facility fails to achieve Commercial Operation by the Commercial Operation Date established in accordance with Section 4.4.4 of Attachment X, including any extension provided thereunder, Transmission Provider shall only terminate that portion of the GIA. Notwithstanding the foregoing, in the limited circumstance that the Interconnection Request is served by a contingent Network Upgrade with an in-service date that is farther out than the Commercial Operation Date permitted under Section 4.4.4 of Attachment X, Transmission Provider shall only terminate this GIA for failure to achieve Commercial Operation by that later in-service date of the contingent Network Upgrade. The Generating Facility will not be deemed to have ceased Commercial Operation for purposes of this Article 2.3.1 if Interconnection Customer can document that it has taken other significant steps to maintain or restore operational readiness of the Generating Facility for the purpose of returning the Generating Facility to Commercial Operation as soon as possible.

2.3.1.1 Surplus Interconnection Service. Where this GIA provides for Surplus Interconnection Service and the Energy Displacement Agreement or the Monitoring and Consent Agreement required for Surplus Interconnection Service are no longer in effect, Interconnection Customer shall immediately cease Commercial Operation of the Generating Facility and this GIA shall be deemed terminated. In the event that the Existing Generating Facility retires and/or permanently ceases commercial

operation, the Surplus Interconnection Service provided under this GIA shall terminate except as provided in Section 3.3.1.3 of the GIP.

2.3.2 Default. Any Party may terminate this GIA in accordance with Article 17.

2.3.3 Notwithstanding Articles 2.3.1 and 2.3.2, no termination shall become effective until the Parties have complied with all Applicable Laws and Regulations applicable to such termination, including the filing with FERC of a notice of termination of this GIA, if required, which notice has been accepted for filing by FERC.

For EGIAs, no termination shall become effective until Interconnection Customer has provided all security as required by Section 2.4.

2.4 Termination Costs. If a Party elects to terminate this GIA pursuant to Article 2.3 above, each Party shall pay all costs incurred for which that Party is responsible (including any cancellation costs relating to orders or contracts for Interconnection Facilities, applicable upgrades, and related equipment) or charges assessed by the other Parties, as of the date of the other Parties' receipt of such notice of termination, under this GIA. In the event that this GIA is terminated by Interconnection Customer, Interconnection Customer is responsible for all financial impact that is caused as a result of this termination or the termination of Interconnection Customer's FCA(s) or MPFCA(s), such financial impact being determined through the financial impact analysis performed in accordance with Section 7.8 of Attachment X. In the event of termination by a Party, the Parties shall use commercially Reasonable Efforts to mitigate the costs, damages and charges arising as a consequence of termination. Upon termination of this GIA, unless otherwise ordered or approved by FERC:

In the event that this EGIA is terminated by Interconnection Customer that had an Interconnection Request studied in ERAS, Interconnection Customer is responsible for the full cost of all Network Upgrades identified in this EGIA as well as any Network Upgrades identified during the ERAS process that are to be memorialized in an agreement other that this EGIA, including any applicable FCA, MPFCA, or JTIQ Service Agreements. If the Network Upgrade costs for Network Upgrades subject to an FCA, MPFCA, or JTIQ Service Agreement have not been finalized or the Interconnection Customer has not made the payment under such agreement as of the date that termination of this EGIA is sought, Interconnection Customer shall provide the payment or security for such Network Upgrades in the amount required by the applicable agreement. If such agreement has not been executed and final costs are not available as of a date that termination is sought, Interconnection Customer shall provide such payment or security in an amount corresponding to the most recent estimate provided by the Transmission Provider during the ERAS process. Interconnection Customer shall pay or Transmission Provider shall refund, as applicable, to Interconnection Customer the difference between the amount of any estimated payment or security made pursuant to this Article and the final cost of such NU within ninety (90) Calendar Days after such final costs are invoiced to the Interconnection Customer.

2.4.1 With respect to any portion of the Transmission Owner's Interconnection Facilities, Network Upgrades, System Protection Facilities, Distribution Upgrades, Generator Upgrades, and if so determined and made a part of this GIA, upgrades on Affected Systems, that have not yet been constructed or installed, Transmission Owner shall to the extent possible and to the extent of Interconnection Customer's written notice under Article 2.3.1, cancel any pending orders of, or return, any materials or equipment for, or contracts for construction of, such facilities; provided that in the event Interconnection Customer elects not to authorize such cancellation, Interconnection Customer shall assume all payment obligations with respect to such materials, equipment, and contracts, and Transmission Owner shall deliver such material and equipment, and, if necessary, assign such contracts, to Interconnection Customer as soon as practicable, at Interconnection Customer's expense. To the extent that Interconnection Customer has already paid Transmission Owner for any or all such costs of materials or equipment not taken by Interconnection Customer or upgrades not yet constructed, Transmission Owner shall promptly transfer such amounts to Transmission Provider, less any costs, including penalties incurred by Transmission Owner to cancel any pending orders of or return such materials, equipment, or contracts. Transmission Provider will perform a financial impact analysis in accordance with Section 7.8 of Attachment X to determine the amount that should be refunded to Interconnection Customer. Transmission Provider shall refund such remaining amounts to Interconnection Customer, less the amount of Automatic Withdrawal Penalty funds received by the Interconnection Customer in accordance with Section 7.8.1 of the Attachment X and less any financial impact caused by the termination of this GIA or Interconnection Customer's FCA(s) or MPFCA(s), as determined through the analysis performed in accordance with Section 7.8 of Attachment X. If Interconnection Customer made its payment(s) through a letter of credit, surety bond, or parental guarantee, Transmission Owner will draw against that letter of credit, surety bond, or parental guarantee in an amount determined through the analysis performed in accordance with Section 7.8 of Attachment X plus the amount of any Automatic Withdrawal Penalty funds received by the Interconnection Customer in accordance with Section 7.8.1 of the Attachment X, and transfer that amount to Transmission Provider, unless Interconnection Customer funds the financial impact through another means.

If an Interconnection Customer terminates this GIA, it shall be responsible for all costs incurred in association with that Interconnection Customer's interconnection, including any cancellation costs relating to orders or contracts for Interconnection Facilities and equipment, and other expenses including any upgrades or related equipment for which Transmission Owner has incurred expenses and has not been reimbursed by Interconnection Customer.

2.4.2 Transmission Owner may, at its option, retain any portion of such materials, equipment, or facilities that Interconnection Customer chooses not to accept delivery of, in which case Transmission Owner shall be responsible for all costs

associated with procuring such materials, equipment, or facilities. If Transmission Owner does not so elect, then Interconnection Customer shall be responsible for such costs.

2.4.3 With respect to any portion of the Interconnection Facilities, and any other facilities already installed or constructed pursuant to the terms of this GIA, Interconnection Customer shall be responsible for all costs associated with the removal, relocation, reconfiguration or other disposition or retirement of such materials, equipment, or facilities, and such other expenses actually incurred by Transmission Owner necessary to return the Transmission, Distribution or Generator System, as applicable, to safe and reliable operation.

2.5 **Disconnection**. Upon termination of this GIA, the Parties will take all appropriate steps to disconnect the Generating Facility from the Transmission or Distribution System, as applicable. All costs required to effectuate such disconnection shall be borne by the terminating Party, unless such termination resulted from the non-terminating Party's Default of this GIA or such non-terminating Party otherwise is responsible for these costs under this GIA.

2.6 **Survival.** This GIA shall continue in effect after termination to the extent necessary to provide for final billings and payments and for costs incurred hereunder, including billings and payments pursuant to this GIA; to permit the determination and enforcement of liability and indemnification obligations arising from acts or events that occurred while this GIA was in effect; and to permit each Party to have access to the lands of the other Party pursuant to this GIA or other applicable agreements, to disconnect, remove or salvage its own facilities and equipment.

ARTICLE 3. REGULATORY FILINGS

3.1 **Filing.** Transmission Provider shall file this GIA (and any amendment hereto) with the appropriate Governmental Authority, if required. A Party may request that any information so provided be subject to the confidentiality provisions of Article 22. If that Party has executed this GIA, or any amendment thereto, the Party shall reasonably cooperate with Transmission Provider with respect to such filing and to provide any information reasonably requested by Transmission Provider needed to comply with applicable regulatory requirements.

ARTICLE 4. SCOPE OF SERVICE

4.1 **Interconnection Product Options**. Interconnection Customer has selected the following (checked) type of Interconnection Service:

Check: _____ SI or ____ ER and/or ____ X__ NR (See Appendix A for details)

4.1.1 Energy Resource Interconnection Service (ER Interconnection Service).

4.1.1.1 The Product. ER Interconnection Service allows Interconnection Customer to connect the Generating Facility to the Transmission or Distribution System, as applicable, and be eligible to deliver the Generating Facility's output using the existing firm or non-firm capacity of the Transmission System on an "as available" basis. To the extent Interconnection Customer wants to receive ER Interconnection Service, Transmission Owner shall construct facilities consistent with the studies identified in Appendix A.

An Interconnection Customer seeking ER Interconnection Service for new or added capacity at a Generating Facility may be granted conditional ER Interconnection Service status to the extent there is such capacity available on the Transmission System to accommodate the Interconnection Customer's Generating Facility. At the request of Interconnection Customer, conditional ER Interconnection Service status may be granted subject to the system being able to accommodate the interconnection without upgrades, until such time as a higher queued project(s) with a later service date affecting the same common elements is placed into service. The conditional ER Interconnection Service shall be terminated in the event Interconnection Customer fails to fund the necessary studies and the Network Upgrades necessary to grant the Interconnection Customer's ER Interconnection Service upon the completion of higher queued projects involving the same common elements.

4.1.1.2 Transmission Delivery Service Implications. Under ER Interconnection Service, Interconnection Customer will be eligible to inject power from the Generating Facility into and deliver power across the Transmission System on an "as available" basis up to the amount of MW identified in the applicable stability and steady state studies to the extent the upgrades initially required to qualify for ER Interconnection Service have been constructed. After that date FERC makes effective MISO's Energy Market Tariff filed in Docket No. ER04-691-000, Interconnection Customer may place a bid to sell into the market up to the maximum identified Generating Facility output, subject to any conditions specified in the Interconnection Service approval, and the Generating Facility will be dispatched to the extent the Interconnection Customer's bid clears. In all other instances, no transmission or other delivery service from the Generating Facility is assured, but Interconnection Customer may obtain Point-To-Point Transmission Service, Network Integration Transmission Service or be used for secondary network transmission service, pursuant to the Tariff, up to the maximum output identified in the stability and steady state studies. In those instances, in order for Interconnection Customer to obtain the right to deliver or inject energy beyond the Point of Interconnection or to improve its ability to do so, transmission delivery service must be

obtained pursuant to the provisions of the Tariff. The Interconnection Customer's ability to inject its Generating Facility output beyond the Point of Interconnection, therefore, will depend on the existing capacity of the Transmission or Distribution System as applicable, at such time as a Transmission Service request is made that would accommodate such delivery. The provision of Firm Point-To-Point Transmission Service or Network Integration Transmission Service may require the construction of additional Network or Distribution Upgrades.

4.1.2 Network Resource Interconnection Service (NR Interconnection Service).

4.1.2.1 The Product. Transmission Provider must conduct the necessary studies and Transmission Owner shall construct the facilities identified in Appendix A of this GIA, subject to the approval of Governmental Authorities, needed to integrate the Generating Facility in the same manner as for any Generating Facility being designated as a Network Resource.

4.1.2.2 Transmission Delivery Service Implications. NR Interconnection Service allows the Generating Facility to be designated by any Network Customer under the Tariff on the Transmission System as a Network Resource, up to the Generating Facility's full output, on the same basis as existing Network Resources that are interconnected to the Transmission or Distribution System, as applicable, and to be studied as a Network Resource on the assumption that such a designation will occur. Although NR Interconnection Service does not convey a reservation of Transmission Service, any Network Customer can utilize Network Integration Transmission Service under the Tariff to obtain delivery of energy from the Generating Facility in the same manner as it accesses Network Resources. A Generating Facility receiving NR Interconnection Service may also be used to provide Ancillary Services after technical studies and/or periodic analyses are performed with respect to the Generating Facility's ability to provide any applicable Ancillary Services, provided that such studies and analyses have been or would be required in connection with the provision of such Ancillary Services by any existing Network Resource. However, if the Generating Facility has not been designated as a Network Resource by any Network Customer, it cannot be required to provide Ancillary Services except to the extent such requirements extend to all generating facilities that are similarly situated. The provision of Network Integration Transmission Service or Firm Point-To-Point Transmission Service may require additional studies and the construction of additional upgrades. Because such studies and upgrades would be associated with a request for delivery service under the Tariff, cost responsibility for the studies and upgrades would be in accordance with FERC's policy for pricing transmission delivery services.

NR Interconnection Service does not necessarily provide Interconnection Customer with the capability to physically deliver the output of its Generating Facility to any particular load on the Transmission System without incurring congestion costs. In the event of transmission or distribution constraints on the Transmission or Distribution System, as applicable, the Generating Facility shall be subject to the applicable congestion management procedures in the Transmission System in the same manner as Network Resources.

There is no requirement either at the time of study or interconnection, or at any point in the future, that the Generating Facility be designated as a Network Resource by a Network Customer or that Interconnection Customer identify a specific buyer (or sink). To the extent a Network Customer does designate the Generating Facility as a Network Resource, it must do so pursuant to the Tariff.

Once an Interconnection Customer satisfies the requirements for obtaining NR Interconnection Service, any future Transmission Service request for delivery from the Generating Facility within the Transmission System of any amount of capacity and/or energy, up to the amount initially studied, will not require that any additional studies be performed or that any further upgrades associated with such Generating Facility be undertaken, regardless of whether such Generating Facility is ever designated by a Network Customer as a Network Resource and regardless of changes in ownership of the Generating Facility. To the extent Interconnection Customer enters into an arrangement for long term Transmission Service for deliveries from the Generating Facility to customers other than the studied Network Customers, or for any Point-To-Point Transmission Service, such request may require additional studies and upgrades in order for Transmission Provider to grant such request. However, the reduction or elimination of congestion or redispatch costs may require additional studies and the construction of additional upgrades.

To the extent Interconnection Customer enters into an arrangement for long term Transmission Service for deliveries from the Generating Facility outside the Transmission System, such request may require additional studies and upgrades in order for Transmission Provider to grant such request.

4.1.2.3 Conditional NR Interconnection Service. An Interconnection Customer seeking NR Interconnection Service for new or added capacity at a Generating Facility may be granted conditional NR Interconnection Service status to the extent there is such capacity available on the Transmission System to accommodate the Interconnection Customer's

Generating Facility. At the request of Interconnection Customer, conditional NR Interconnection Service status may be granted subject to the system being able to accommodate the interconnection without upgrades, until such time as higher queued project(s) with a later service date affecting the same common elements is placed into service. The conditional NR Interconnection Service status may be converted to ER Interconnection Service if either of the following occurs:

1) Interconnection Customer fails to fund necessary studies and Network Upgrades required to allow the Interconnection Customer's Generating Facility to receive NR Interconnection Service upon the completion of higher queued projects involving the same common elements; or

2) The higher queued project(s) or planned and required Network Upgrades are placed in service and the Network Upgrades required to provide NR Interconnection Service status to the Interconnection Customer's Generating Facility are not in service.

In the event Interconnection Customer fails to fund the necessary studies and Network Upgrades for NR Interconnection Service, the Interconnection Customer's conditional NR Interconnection Service status shall be converted to ER Interconnection Service status unless Interconnection Customer makes a new Interconnection Request. Such new Interconnection Request shall be evaluated in accordance with the GIP and its new queue position.

Some or all of the conditional NR Interconnection Service status may be temporarily revoked if the Network Upgrades are not in service when the higher queued project(s) are placed in service. The availability of conditional NR Interconnection Service status will be determined by Transmission Provider's studies. Upon funding and completion of the Network Upgrades required to establish the Generating Facility's NR Interconnection Service status, the Generating Facility will be granted NR Interconnection Service status.

The Parties agree that the portion of the Generating Facility classified as NR Interconnection Service is the first portion of the output of the combined output of all the units at the Generating Facility except in circumstances where Interconnection Customer otherwise elects this GIA, as amended, to allocate that portion to the output of specific unit(s) at the Generating Facility, the total of which will not exceed the output eligible for NR Interconnection Service as shown by the additional studies. To the extent Interconnection Customer desires to obtain NR Interconnection Service for any portion of the Generating Facility in addition to that supported by such additional studies, Interconnection Customer will be

required to request such additional NR Interconnection Service through a separate Interconnection Request in accordance with the GIP.

4.1.3 Surplus Interconnection Service (SI).

4.1.3.1 The Product. Surplus Interconnection Service is restricted Interconnection Service that allows an Interconnection Customer to increase the gross generating capability at the same Point of Interconnection of an Existing Generating Facility without increasing the total amount of Interconnection Service at the Point of Interconnection.

4.1.3.2 Transmission Delivery Service Implications. Surplus Interconnection Service does not convey any right to deliver electricity to any specific customer or Point of Delivery.

4.2 Provision of Service. Transmission Provider shall provide Interconnection Service for the Generating Facility at the Point of Interconnection.

4.3 Performance Standards. Each Party shall perform all of its obligations under this GIA in accordance with Applicable Laws and Regulations, Applicable Reliability Standards, and Good Utility Practice. To the extent a Party is required or prevented or limited in taking any action by such regulations and standards, or if the obligations of any Party may become limited by a change in Applicable Laws and Regulations, Applicable Reliability Standards, and Good Utility Practice after the execution of this GIA, that Party shall not be deemed to be in Breach of this GIA for its compliance therewith. The Party so limited shall notify the other Parties whereupon Transmission Provider shall amend this GIA in concurrence with the other Parties and submit the amendment to the Commission for approval.

4.4 No Transmission Delivery Service. The execution of this GIA does not constitute a request for, or the provision of, any transmission delivery service under the Tariff, and does not convey any right to deliver electricity to any specific customer or Point of Delivery.

4.5 Interconnection Customer Provided Services. The services provided by Interconnection Customer under this GIA are set forth in Article 9.6 and Article 13.4.1. Interconnection Customer shall be paid for such services in accordance with Article 11.7.

ARTICLE 5. INTERCONNECTION FACILITIES ENGINEERING, PROCUREMENT, AND CONSTRUCTION

5.1 Options. Unless otherwise mutually agreed to between the Parties, Interconnection Customer shall select: 1) the In-Service Date, Initial Synchronization Date, and Commercial Operation Date based on a reasonable construction schedule that will allow sufficient time for design, construction, equipment procurement, and permit acquisition of Transmission System equipment or right-of-way; and 2) either the Standard Option or

Alternate Option set forth below and such dates and selected option shall be set forth in Appendix B. If the dates designated by Interconnection Customer are not acceptable to Transmission Owner, Transmission Owner shall so notify Interconnection Customer within thirty (30) Calendar Days. Upon receipt of the notification that Interconnection Customer's designated dates are not acceptable to Transmission Owner, the Interconnection Customer shall notify Transmission Owner within thirty (30) Calendar Days whether it elects to exercise the Option to Build if it has not already elected to exercise the Option to Build.

5.1.1 Standard Option. Transmission Owner shall design, procure, and construct the Transmission Owner's Interconnection Facilities, Network Upgrades, System Protection Facilities, Distribution Upgrades, and Generator Upgrades using Reasonable Efforts to complete the Transmission Owner's Interconnection Facilities, Network Upgrades, System Protection Facilities, Distribution Upgrades and Generator Upgrades by the dates set forth in Appendix B, Milestones, subject to the receipt of all approvals required from Governmental Authorities and the receipt of all land rights necessary to commence construction of such facilities, and such other permits or authorizations as may be required. Transmission Provider or Transmission Owner shall not be required to undertake any action which is inconsistent with its standard safety practices, its material and equipment specifications, its design criteria and construction procedures, its labor agreements, Applicable Laws and Regulations and Good Utility Practice. In the event Transmission Owner reasonably expects that it will not be able to complete the Transmission Owner's Interconnection Facilities, Network Upgrades, System Protection Facilities, Distribution Upgrades and Generator Upgrades by the specified dates, Transmission Owner shall promptly provide written notice to Interconnection Customer and Transmission Provider and shall undertake Reasonable Efforts to meet the earliest dates thereafter.

5.1.2 Alternate Option. If the dates designated by Interconnection Customer are acceptable to Transmission Provider and Transmission Owner, Transmission Provider shall so notify Interconnection Customer within thirty (30) Calendar Days, and Transmission Owner shall assume responsibility for the design, procurement and construction of the Transmission Owner's Interconnection Facilities by the designated dates.

If Transmission Owner subsequently fails to complete the Transmission Owner's Interconnection Facilities by the In-Service Date, to the extent necessary to provide back feed power; or fails to complete Network Upgrades by the Initial Synchronization Date to the extent necessary to allow for Trial Operation at full power output, unless other arrangements are made by the Parties for such Trial Operation; or fails to complete the Network Upgrades by the Commercial Operation Date, as such dates are reflected in Appendix B, Milestones; Transmission Owner shall pay Interconnection Customer liquidated damages in accordance with Article 5.3, Liquidated Damages, provided, however, the dates designated by Interconnection Customer shall be extended day for day for each

Calendar Day that Transmission Provider refuses to grant clearances to install equipment.

Transmission Owner and Interconnection Customer may adopt an incentive payment schedule that is mutually agreeable to encourage Transmission Owner to meet specified accelerated dates. Such payment by Interconnection Customer is not subject to refund.

5.1.3 Option to Build. Pursuant to Section 7.3.2.5 & 7.3.3.5 of the GIP, Individual or Multiple Interconnection Customers shall have the option to assume responsibility for the design, procurement and construction of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades by the dates originally designated by Interconnection Customer under Article 5.1.2, if the requirements of this Article 5.1.3 are met. When multiple Interconnection Customers exercise this option, multiple Interconnection Customers may agree to exercise this option provided (1) all Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades constructed under this option are only required for Interconnection Customers in a single Cluster and (2) all impacted Interconnection Customers execute and provide to Transmission Provider an agreement regarding responsibilities, and payment for, the construction of Transmission Provider's Interconnection Facilities and Stand Alone Network Upgrades planned to be built under this option. The Parties must agree as to what constitutes Stand Alone Network Upgrades and identify such Stand Alone Network Upgrades in Appendix A. Except for Stand Alone Network Upgrades, Interconnection Customer shall have no right to construct Network Upgrades under this option.

5.1.4 Negotiated Option. If the dates designated by Interconnection Customer pursuant to Article 5.1 are not acceptable to Transmission Owner, the Parties shall in good faith attempt to negotiate terms and conditions (including revision of the specified dates and liquidated damages, the provision of incentives, or the procurement and construction of all facilities other than Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades if the Interconnection Customer elects to exercise the Option to Build under Article 5.1.3). If the Parties are unable to reach agreement on such terms and conditions, then, pursuant to Article 5.1.1 (Standard Option), Transmission Owner shall assume responsibility for the design, procurement and construction of all facilities other than Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades if Interconnection Customer has elected to exercise the Option to Build.

Transmission Owner and Interconnection Customer may adopt an incentive payment schedule that is mutually agreeable to encourage Transmission Owner to meet specified accelerated dates. Such payment by Interconnection Customer is not subject to refund.

5.2 General Conditions Applicable to Option to Build. If Interconnection Customer assumes responsibility for the design, procurement and construction of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades after receipt of all required approvals from Governmental Authorities necessary to commence construction,

(1) Interconnection Customer shall engineer, procure equipment, and construct the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades (or portions thereof) using Good Utility Practice and using standards and specifications provided in advance by Transmission Owner, or as required by any Governmental Authority;

(2) Interconnection Customer's engineering, procurement and construction of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades shall comply with all requirements of law or Governmental Authority to which Transmission Owner would be subject in the engineering, procurement or construction of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades;

(3) Transmission Provider, at Transmission Provider's option, and Transmission Owner shall be entitled to review and approve the engineering design, equipment acceptance tests(including witnessing of acceptance tests), and the construction (including monitoring of construction) of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades, and shall have the right to reject any design, procurement, construction or acceptance test of any equipment that does not meet the standards and specifications of Transmission Provider, Transmission Owner and any Governmental Authority;

(4) prior to commencement of construction, Interconnection Customer shall provide to Transmission Provider and Transmission Owner a schedule for construction of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades, and shall promptly respond to requests for information from Transmission Provider and Transmission Owner;

(5) at any time during construction, Transmission Provider and Transmission Owner shall have unrestricted access to the construction site for the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades and to conduct inspections of the same;

(6) at any time during construction, should any phase of the engineering, equipment procurement, or construction of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades not meet the standards and specifications provided by Transmission Owner, Interconnection Customer shall be obligated to remedy deficiencies in that portion of the Transmission Owner's Interconnection Facilities and Stand Alone Network

Upgrades to meet the standards and specifications provided by Transmission Provider and Transmission Owner;

(7) Interconnection Customer shall indemnify Transmission Provider and Transmission Owner for claims arising from the Interconnection Customer's construction of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades under the terms and procedures applicable to Article 18.1, Indemnity;

(8) Interconnection Customer shall transfer control of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades to Transmission Owner;

(9) Unless Parties otherwise agree, Interconnection Customer shall transfer ownership of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades to Transmission Owner in accordance with Appendix B;

(10) Transmission Provider, at Transmission Provider's option, and Transmission Owner shall approve and accept for operation and maintenance the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades to the extent engineered, procured, and constructed in accordance with this Article 5.2 only if the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades meet the standards and specifications of Transmission Provider, Transmission Owner and any Governmental Authority.

(11) Interconnection Customer shall deliver to Transmission Owner "as-built" drawings, information, and any other documents that are reasonably required by Transmission Owner to assure that the Interconnection Facilities and Stand-Alone Network Upgrades are built to the standards and specifications required by Transmission Owner.

(12) If Interconnection Customer exercises the Option to Build pursuant to Article 5.1.3, Interconnection Customer shall pay Transmission Owner the agreed upon amount of [$ PLACEHOLDER] for Transmission Owner to execute the responsibilities enumerated to Transmission Owner under Article 5.2. Transmission Owner shall invoice Interconnection Customer for this total amount to be divided on a monthly basis pursuant to Article 12.

(13) If Interconnection Customer exercises the Option to Build pursuant to Article 5.1.3, and the Transmission Owner has elected to fund the costs of Network Upgrades pursuant to Article 11.3, then prior to Interconnection Customer incurring any construction costs relating to the Option to Build and by the date specified in Appendix B, Interconnection Customer shall invoice the Transmission Owner for the estimated amount to be expended by the Interconnection Customer to construct any Stand Alone Network Upgrades for

which the Interconnection Customer has exercised its Option to Build in accordance with Appendix B. The Transmission Owner shall be required to reimburse Interconnection Customer for the full amount of such invoiced costs by the date specified in Appendix B, which shall be prior to the date by which Interconnection Customer must make any construction payment for such Stand Alone Network Upgrades. After completion of the construction of Stand Alone Network Upgrades by the Interconnection Customer and by the date specified in Appendix B for the Interconnection Customer to transfer such Stand Alone Network Upgrades to the Transmission Owner, Interconnection Customer shall provide an invoice of the final cost of the construction of Stand Alone Upgrades and shall set forth such costs in sufficient detail to enable the Transmission Owner to compare the actual costs with the estimates and to ascertain deviations, if any, from the cost estimates. In the event that the actual costs exceed the estimated costs previously invoiced by Interconnection Customer and paid by Transmission Owner, Transmission Owner shall pay to Interconnection Customer the difference between the amount previously paid and the actual costs within thirty (30) Calendar Days after receipt of a final construction invoice from Interconnection Customer. In the event that the actual costs are less than the estimated costs previously invoiced by Interconnection Customer and paid by Transmission Owner, Interconnection Customer shall refund, with interest (calculated in accordance with 18 C.F.R. Section 35.19a(a)(2)(iii), to Transmission Owner any amount by which the actual payment by Transmission Owner for estimated costs exceeds the actual costs of construction within thirty (30) Calendar Days of the issuance of such final construction invoice. Following the transfer of the Stand Alone Network Upgrades from the Interconnection Customer to the Transmission Owner, the Interconnection Customer shall make payments for such facilities to the Transmission Owner pursuant to an agreement between and among the Parties.

5.3 Liquidated Damages. The actual damages to Interconnection Customer, in the event the Transmission Owner's Interconnection Facilities or Network Upgrades are not completed by the dates designated by Interconnection Customer and accepted by Transmission Provider and Transmission Owner pursuant to subparagraphs 5.1.2 or 5.1.4, above, may include Interconnection Customer's fixed operation and maintenance costs and lost opportunity costs. Such actual damages are uncertain and impossible to determine at this time. Because of such uncertainty, any liquidated damages paid by Transmission Owner to Interconnection Customer in the event that Transmission Owner does not complete any portion of the Transmission Owner's Interconnection Facilities or Network Upgrades by the applicable dates, shall be an amount equal to ½ of 1 percent per day of the actual cost of the Transmission Owner's Interconnection Facilities and Network Upgrades, in the aggregate, for which Transmission Owner has assumed responsibility to design, procure and construct.

However, in no event shall the total liquidated damages exceed 20 percent of the actual cost of the Transmission Owner's Interconnection Facilities and Network Upgrades for which Transmission Owner has assumed responsibility to design, procure, and construct.

The foregoing payments will be made by Transmission Owner to Interconnection Customer as just compensation for the damages caused to Interconnection Customer, which actual damages are uncertain and impossible to determine at this time, and as reasonable liquidated damages, but not as a penalty or a method to secure performance of this GIA. Liquidated damages, when the Parties agree to them, are the exclusive remedy for the Transmission Owner's failure to meet its schedule.

No liquidated damages shall be paid to Interconnection Customer if: (1) Interconnection Customer is not ready to commence use of the Transmission Owner's Interconnection Facilities or Network Upgrades to take the delivery of power for the Generating Facility's Trial Operation or to export power from the Generating Facility on the specified dates, unless Interconnection Customer would have been able to commence use of the Transmission Owner's Interconnection Facilities or Network Upgrades to take the delivery of power for Generating Facility's Trial Operation or to export power from the Generating Facility, but for Transmission Owner's delay; (2) the Transmission Owner's failure to meet the specified dates is the result of the action or inaction of Transmission Provider, Interconnection Customer or any other earlier queued Interconnection Customer who has entered into an earlier GIA with Transmission Provider and/or a Transmission Owner or with an Affected System Operator, or any cause beyond Transmission Owner's reasonable control or reasonable ability to cure; (3) Interconnection Customer has assumed responsibility for the design, procurement and construction of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades; (4) the delay is due to the inability of Transmission Owner to obtain all required approvals from Governmental Authorities in a timely manner for the construction of any element of the Interconnection Facilities, Network Upgrades or Stand Alone Network Upgrades, or any other permit or authorization required, or any land rights or other private authorizations that may be required, and Transmission Owner has exercised Reasonable Efforts in procuring such approvals, permits, rights or authorizations; or (5) the Parties have otherwise agreed.

5.4 Power System Stabilizers. Interconnection Customer shall procure, install, maintain and operate power system stabilizers in accordance with the guidelines and procedures established by the Electric Reliability Organization. Transmission Provider and Transmission Owner reserve the right to reasonably establish minimum acceptable settings for any installed power system stabilizers, subject to the design and operating limitations of the Generating Facility. If the Generating Facility's power system stabilizers are removed from service or are not capable of automatic operation, Interconnection Customer shall immediately notify the Transmission Provider's system operator, or its designated representative. The requirements of this paragraph shall not apply to induction generators.

5.5 Equipment Procurement. If responsibility for construction of the Transmission Owner's Interconnection Facilities, Network Upgrades and/or Distribution Upgrades is to be borne by Transmission Owner, then Transmission Owner shall commence design of the Transmission Owner's Interconnection Facilities, Network Upgrades and/or Distribution Upgrades, and procure necessary equipment as soon as practicable after all

of the following conditions are satisfied, unless the Parties otherwise agree in writing:

5.5.1 Transmission Provider has completed the Interconnection Facilities Study pursuant to the Interconnection Facilities Study Agreement; and

5.5.2 Where applicable, Interconnection Customer has provided security to Transmission Owner in accordance with Article 11.6 by the dates specified in Appendix B, Milestones.

5.6 Construction Commencement. Transmission Owner shall commence construction of the Transmission Owner's Interconnection Facilities, Network Upgrades, Transmission Owner's System Protection Facilities, Distribution Upgrades, and Generator Upgrades for which it is responsible as soon as practicable after the following additional conditions are satisfied:

5.6.1 Approval of the appropriate Governmental Authority has been obtained for any facilities requiring regulatory approval; and

5.6.2 Where applicable, Interconnection Customer has provided security to Transmission Owner in accordance with Article 11.6 by the dates specified in Appendix B, Milestones.

5.7 Work Progress. Transmission Owner and Interconnection Customer will keep each other and Transmission Provider advised periodically as to the progress of their respective design, procurement and construction efforts. Either Transmission Owner or Interconnection Customer may, at any time, request a progress report from the other, with a copy to be provided to the other Parties. If, at any time, Interconnection Customer determines that the completion of the Transmission Owner's Interconnection Facilities, Network Upgrades, or Transmission Owner's System Protection Facilities will not be required until after the specified In-Service Date, Interconnection Customer will provide written notice to Transmission Provider and Transmission Owner of such later date upon which the completion of the Transmission Owner's Interconnection Facilities, Network Upgrades or Transmission Owner's System Protection Facilities will be required. Transmission Owner may delay the In-Service Date of its facilities accordingly.

5.8 Information Exchange. As soon as reasonably practicable after the Effective Date, the Parties shall exchange information regarding the design and compatibility of the Interconnection Facilities and compatibility of the Interconnection Facilities with the Transmission System or Distribution System, as applicable, and shall work diligently and in good faith to make any necessary design changes.

5.9 Other Interconnection Options.

5.9.1 Limited Operation. If any of the Transmission Owner's Interconnection Facilities, Network Upgrades, or Transmission Owner's System Protection Facilities, Distribution Upgrades or Generator Upgrades are not reasonably

expected to be completed prior to the Commercial Operation Date of the Generating Facility, Transmission Provider shall, upon the request and at the expense of Interconnection Customer, perform operating studies on a timely basis to determine the extent to which the Generating Facility and the Interconnection Customer's Interconnection Facilities may operate prior to the completion of the Transmission Owner's Interconnection Facilities, Network Upgrades, Transmission Owner's System Protection Facilities, Distribution Upgrades or Generator Upgrades consistent with Applicable Laws and Regulations, Applicable Reliability Standards, Good Utility Practice, and this GIA. Transmission Provider and Transmission Owner shall permit Interconnection Customer to operate the Generating Facility and the Interconnection Customer's Interconnection Facilities in accordance with the results of such studies; provided, however, such studies reveal that such operation may occur without detriment to the Transmission System as then configured and in accordance with the safety requirements of Transmission Owner and any Governmental Authority.

The maximum permissible output of the Generating Facility will be updated on a quarterly basis if the Network Upgrades necessary for the interconnection of the Generating Facility pursuant to this GIA are not in service within six (6) months following the Commercial Operation Date of the Generating Facility as specified in Appendix B of this GIA. These quarterly studies will be performed using the same methodology set forth in Section 11.5 of the GIP. These quarterly updates will end when all Network Upgrades necessary for the interconnection of the Generating Facility pursuant to this GIA are in service.

5.9.2 Provisional Interconnection Service.

Upon the request of Interconnection Customer, and prior to completion of requisite Interconnection Facilities, Network Upgrades, Distribution Upgrades, or System Protection Facilities Transmission Provider may execute a Provisional Generator Interconnection Agreement or Interconnection Customer may request the filing of an unexecuted Provisional Generator Interconnection Agreement with the Interconnection Customer for limited interconnection service at the discretion of Transmission Provider based upon an evaluation that will consider the results of available studies. Transmission Provider shall determine, through available studies or additional studies as necessary, whether stability, short circuit, thermal, and/or voltage issues would arise if Interconnection Customer interconnects without modifications to the Generating Facility or Transmission Provider's system. Transmission Provider shall determine whether any Interconnection Facilities, Network Upgrades, Distribution Upgrades, or System Protection Facilities that are necessary to meet the requirements of the Electric Reliability Organization, or any applicable Regional Entity for the interconnection of a new, modified and/or expanded Generating Facility are in place prior to the commencement of interconnection service from the Generating Facility. Where available studies indicate that such Interconnection Facilities, Network Upgrades, Distribution Upgrades, and/or System Protection Facilities that are required for the interconnection of a new, modified and/or expanded Generating Facility are

not currently in place, Transmission Provider will perform a study, at the Interconnection Customer's expense, to confirm the facilities that are required for Provisional Interconnection Service. The maximum permissible output of the Generating Facility in the Provisional Generator Interconnection Agreement shall be studied and updated on a quarterly basis. Interconnection Customer assumes all risk and liabilities with respect to changes between the Provisional Generator Interconnection Agreement and the Generator Interconnection Agreement, including changes in output limits and Interconnection Facilities, Network Upgrades, Distribution Upgrades, and/or System Protection Facilities cost responsibilities.

5.10 Interconnection Customer's Interconnection Facilities. Interconnection Customer shall, at its expense, design, procure, construct, own or control, and install the ICIF, as set forth in Appendix A.

5.10.1 Interconnection Customer's Interconnection Facility Specifications. Interconnection Customer shall submit initial design and specifications for the ICIF, including Interconnection Customer's System Protection Facilities, to Transmission Provider and Transmission Owner at least one hundred eighty (180) Calendar Days prior to the Initial Synchronization Date; and final design and specifications for review and comment at least ninety (90) Calendar Days prior to the Initial Synchronization Date. Transmission Provider at Transmission Provider's option, and Transmission Owner shall review such specifications to ensure that the ICIF are compatible with their respective technical specifications, operational control, and safety requirements and comment on such design and specifications within thirty (30) Calendar Days of Interconnection Customer's submission. All specifications provided hereunder shall be deemed confidential.

5.10.2 Transmission Provider's and Transmission Owner's Review. Transmission Provider's and Transmission Owner's review of Interconnection Customer's final specifications shall not be construed as confirming, endorsing, or providing a warranty as to the design, fitness, safety, durability or reliability of the Generating Facility, or the ICIF. Interconnection Customer shall make such changes to the ICIF as may reasonably be required by Transmission Provider and Transmission Owner, in accordance with Good Utility Practice, to ensure that the ICIF are compatible with the technical specifications, operational control and safety requirements of Transmission Provider and Transmission Owner.

5.10.3 ICIF Construction. The ICIF shall be designed and constructed in accordance with Good Utility Practice. Within one hundred twenty (120) Calendar Days after the Commercial Operation Date, unless the Parties agree on another mutually acceptable deadline, Interconnection Customer shall deliver to Transmission Provider and Transmission Owner "as-built" drawings, information and documents for the ICIF, such as: a one-line diagram, a site plan

showing the Generating Facility and the ICIF, plan and elevation drawings showing the layout of the ICIF, a relay functional diagram, relaying AC and DC schematic wiring diagrams and relay settings for all facilities associated with the Interconnection Customer's step-up transformers, the facilities connecting the Generating Facility to the step-up transformers and the ICIF, and the impedances (determined by factory tests) for the associated step-up transformers and the Generating Facility. Interconnection Customer shall provide Transmission Provider and Transmission Owner with Interconnection Customer's specifications for the excitation system, automatic voltage regulator, Generating Facility control and protection settings, transformer tap settings, and communications, if applicable.

5.11 Transmission Owner's Interconnection Facilities Construction. The Transmission Owner's Interconnection Facilities shall be designed and constructed in accordance with Good Utility Practice. Upon request, within one hundred twenty (120) Calendar Days after the Commercial Operation Date, unless the Parties agree on another mutually acceptable deadline, Transmission Owner shall deliver to Transmission Provider (if requested) and Interconnection Customer the "as-built" drawings, information and documents for the Transmission Owner's Interconnection Facilities specified in Appendix C to this GIA.

Such drawings, information and documents shall be deemed Confidential Information.

Upon completion, the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades shall be under the control of Transmission Provider or its designated representative.

5.12 Access Rights. Upon reasonable notice by a Party, and subject to any required or necessary regulatory approvals, a Party ("Granting Party") shall furnish *at no cost* to the other Party ("Access Party") any rights of use, licenses, rights of way and easements with respect to lands owned or controlled by the Granting Party, its agents (if allowed under the applicable agency agreement), or any Affiliate, that are necessary to enable the Access Party to obtain ingress and egress to construct, operate, maintain, repair, test (or witness testing), inspect, replace or remove facilities and equipment to: (i) interconnect the Generating Facility with the Transmission System; (ii) operate and maintain the Generating Facility, the Interconnection Facilities and the Transmission System; and (iii) disconnect or remove the Access Party's facilities and equipment upon termination of this GIA. In exercising such licenses, rights of way and easements, the Access Party shall not unreasonably disrupt or interfere with normal operation of the Granting Party's business and shall adhere to the safety rules and procedures established in advance, as may be changed from time to time, by the Granting Party and provided to the Access Party.

5.13 Lands of Other Property Owners. If any part of the Transmission Owner's Interconnection Facilities, Network Upgrades, and/or Distribution Upgrades is to be installed on property owned by persons other than Interconnection Customer or

Transmission Owner, Transmission Owner shall at Interconnection Customer's expense use efforts, similar in nature and extent to those that it typically undertakes on its own behalf or on behalf of its Affiliates, including use of its eminent domain authority to the extent permitted and consistent with Applicable Laws and Regulations and, to the extent consistent with such Applicable Laws and Regulations, to procure from such persons any rights of use, licenses, rights of way and easements that are necessary to construct, operate, maintain, test, inspect, replace or remove the Transmission Owner's Interconnection Facilities, Network Upgrades and/or Distribution Upgrades upon such property.

5.14 Permits. Transmission Provider or Transmission Owner and Interconnection Customer shall cooperate with each other in good faith in obtaining all permits, licenses and authorizations that are necessary to accomplish the interconnection in compliance with Applicable Laws and Regulations. With respect to this paragraph, Transmission Owner shall provide permitting assistance to Interconnection Customer comparable to that provided to the Transmission Owner's own, or an Affiliate's, generation to the extent that Transmission Owner or its Affiliate owns generation.

5.15 Early Construction of Base Case Facilities. (Includes facilities required for all queued projects with interconnection agreements).Interconnection Customer may request Transmission Owner to construct, and Transmission Owner shall construct, using Reasonable Efforts to accommodate Interconnection Customer's In-Service Date, all or any portion of any Network Upgrades, Transmission Owner's System Protection Facilities or Distribution Upgrades required for Interconnection Customer to be interconnected to the Transmission or Distribution System, as applicable, which are included in the Base Case of the Interconnection Facilities Study for Interconnection Customer, and which also are required to be constructed for another Interconnection Customer with a prior GIA, but where such construction is not scheduled to be completed in time to achieve Interconnection Customer's In-Service Date. Any such Network Upgrades, System Protection Facilities or Distribution Upgrades are included in the facilities to be constructed and as set forth in Appendix A to this GIA to the extent they are reasonably known.

5.16 Suspension.

5.16.1 Interconnection Customer's Right to Suspend for Force Majeure Event; Obligations. Provided that such suspension is permissible under the authorizations, permits or approvals granted for the construction of such Interconnection Facilities, Network Upgrades or Stand Alone Network Upgrades, Interconnection Customer will not suspend unless a Force Majeure event occurs.

Interconnection Customer must provide written notice of its request for suspension to Transmission Provider and Transmission Owner, and provide a description of the Force Majeure event that is acceptable to Transmission Provider. Suspension will only apply to Interconnection Customer milestones and Interconnection Facilities described in the Appendices of this GIA. Prior to

suspension, Interconnection Customer must also provide security acceptable to Transmission Owner, equivalent to the higher of $5 million or the total cost of all Network Upgrades, Transmission Owner's System Protection Facilities, and Distribution Upgrades listed in Appendix A of this GIA. Network Upgrades and Transmission Owner's Interconnection Facilities will be constructed on the schedule described in the Appendices of this GIA unless: (1) construction is prevented by the order of a Governmental Authority; (2) the Network Upgrades are not needed by any other project; or (3) Transmission Owner or Transmission Provider determines that a Force Majeure event prevents construction. In the event of (1), (2), or (3) security shall be released upon the determination that the Network Upgrades will no longer be constructed.

If suspension occurs, the Transmission or Distribution System, as applicable, shall be left in a safe and reliable condition in accordance with Good Utility Practice and the Transmission Provider's and Transmission Owner's safety and reliability criteria. In such event, Interconnection Customer shall be responsible for all reasonable and necessary costs which Transmission Provider and Transmission Owner (i) have incurred pursuant to this GIA prior to the suspension and (ii) incur in suspending such work, including any costs incurred to perform such work as may be necessary to ensure the safety of persons and property and the integrity of the Transmission or Distribution System, as applicable, during such suspension and, if applicable, any costs incurred in connection with the cancellation or suspension of material, equipment and labor contracts which Transmission Provider and Transmission Owner cannot reasonably avoid; provided, however, that prior to canceling or suspending any such material, equipment or labor contract, Transmission Provider and Transmission Owner shall obtain Interconnection Customer's authorization to do so.

Transmission Provider and Transmission Owner shall each invoice Interconnection Customer for such costs pursuant to Article 12 and shall use Reasonable Efforts to minimize its costs. In the event Interconnection Customer suspends work by Transmission Owner required under this GIA pursuant to this Article 5.16, and has not requested Transmission Owner to recommence the work required under this GIA on or before the expiration of three (3) years following commencement of such suspension, this GIA shall be deemed terminated. The three-year period shall begin on the date the suspension is requested, or the date of the written notice to Transmission Provider, if no effective date is specified.

5.16.2 Effect of Missed Interconnection Customer Milestones. If Interconnection Customer fails to provide notice of suspension pursuant to Article 5.16, and Interconnection Customer fails to fulfill or complete any Interconnection Customer Milestone provided in Appendix B ("Milestone"), this constitutes a Breach under this GIA. Depending upon the consequences of the Breach and effectiveness of the cure pursuant to Article 17, the Transmission Owner's Milestones may be revised, following consultation with Interconnection Customer, consistent with Reasonable Efforts, and in consideration of all relevant

circumstances. Parties shall employ Reasonable Efforts to maintain their remaining respective Milestones.

5.16.3 Effect of Suspension; Parties Obligations. In the event that Interconnection Customer suspends work pursuant to this Article 5.16, no construction duration, timelines and schedules set forth in Appendix B shall be suspended during the period of suspension unless ordered by a Governmental Authority, with such order being the Force Majeure event causing the suspension. Should Interconnection Customer request that work be recommenced, Transmission Owner shall be obligated to proceed with Reasonable Efforts and in consideration of all relevant circumstances including regional outage schedules, construction availability and material procurement in performing the work as described in Appendix A and Appendix B. Transmission Owner will provide Interconnection Customer with a revised schedule for the design, procurement, construction, installation and testing of the Transmission Owner's Interconnection Facilities and Network Upgrades. Upon any suspension by Interconnection Customer pursuant to Article 5.16, Interconnection Customer shall be responsible for only those costs specified in this Article 5.16.

5.17 Taxes.

5.17.1 Interconnection Customer Payments Not Taxable. The Parties intend that all payments or property transfers made by Interconnection Customer to Transmission Owner for the installation of the Transmission Owner's Interconnection Facilities, Network Upgrades, Transmission Owner's System Protection Facilities, Distribution Upgrades and Generator Upgrades shall be non-taxable, either as contributions to capital, or as an advance, in accordance with the Internal Revenue Code and any applicable state income tax laws and shall not be taxable as contributions in aid of construction or otherwise under the Internal Revenue Code and any applicable state income tax laws. To the extent that Transmission Owner is a limited liability company and not a corporation, and has elected to be taxed as a partnership, then the following shall apply: Transmission Owner represents, and the Parties acknowledge, that Transmission Owner is a limited liability company and is treated as a partnership for federal income tax purposes. Any payment made by Interconnection Customer to Transmission Owner for Network Upgrades is to be treated as an upfront payment in accordance with Rev Proc 2005-35. It is anticipated by the parties that any amounts paid by Interconnection Customer to Transmission Owner for Network Upgrades will be reimbursed to Interconnection Customer in accordance with the terms of this GIA, provided Interconnection Customer fulfills its obligations under this GIA.

5.17.2 Representations and Covenants. In accordance with IRS Notice 2016-36, Interconnection Customer represents and covenants that (i) ownership of the electricity generated at the Generating Facility will pass to another party prior to the transmission of the electricity on the Transmission System, (ii) for

income tax purposes, the amount of any payments and the cost of any property transferred to Transmission Owner for the Transmission Owner's Interconnection Facilities will be capitalized by Interconnection Customer as an intangible asset and recovered using the straight-line method over a useful life of twenty (20) years, and (iii) any portion of the Transmission Owner's Interconnection Facilities that is a "dual-use intertie," within the meaning of IRS Notice 2016-36, is reasonably expected to carry only a de minimis amount of electricity in the direction of the Generating Facility. For this purpose, "de minimis amount" means no more than 5 percent of the total power flows in both directions, calculated in accordance with the "5 percent test" set forth in IRS Notice 2016-36. This is not intended to be an exclusive list of the relevant conditions that must be met to conform to IRS requirements for non-taxable treatment.

At Transmission Owner's request, Interconnection Customer shall provide Transmission Owner with a report from an independent engineer confirming its representation in clause (iii), above, with a copy to Transmission Provider. Transmission Owner represents and covenants that the cost of the Transmission Owner's Interconnection Facilities paid for by Interconnection Customer will have no net effect on the base upon which rates are determined.

5.17.3 Indemnification for the Cost Consequences of Current Tax Liability Upon Transmission Owner. Notwithstanding Article 5.17.1 and to the extent permitted by law, Interconnection Customer shall protect, indemnify and hold harmless Transmission Owner from the cost consequences of any tax liability imposed against Transmission Owner as the result of payments or property transfers made by Interconnection Customer to Transmission Owner under this GIA for Interconnection Facilities, as well as any interest and penalties, other than interest and penalties attributable to any delay caused by Transmission Owner.

Transmission Owner shall not include a gross-up for the cost consequences of any current tax liability in the amounts it charges Interconnection Customer under this GIA unless (i) Transmission Owner has determined, in good faith, that the payments or property transfers made by Interconnection Customer to Transmission Owner should be reported as income subject to taxation or (ii) any Governmental Authority directs Transmission Owner to report payments or property as income subject to taxation; provided, however, that Transmission Owner may require Interconnection Customer to provide security for Interconnection Facilities, in a form reasonably acceptable to Transmission Owner (such as a parental guarantee or a letter of credit), in an amount equal to the cost consequences or any current tax liability under this Article 5.17. Interconnection Customer shall reimburse Transmission Owner for such costs on a fully grossed-up basis, in accordance with Article 5.17.4, within thirty (30) Calendar Days of receiving written notification from Transmission Owner of the amount due, including detail about how the amount was calculated.

The indemnification obligation shall terminate at the earlier of (1) the expiration of the ten-year testing period and the applicable statute of limitation, as it may be extended by Transmission Owner upon request of the IRS, to keep these years open for audit or adjustment, or (2) the occurrence of a subsequent taxable event and the payment of any related indemnification obligations as contemplated by this Article 5.17.

5.17.4 Tax Gross-Up Amount. Interconnection Customer's liability for the cost consequences of any current tax liability under this Article 5.17 shall be calculated on a fully grossed-up basis. Except as may otherwise be agreed to by the parties, this means that Interconnection Customer will pay Transmission Owner, in addition to the amount paid for the Interconnection Facilities, Network Upgrades, Transmission Owner's System Protection Facilities, and/or Distribution Upgrades, an amount equal to (1) the current taxes imposed on Transmission Owner ("Current Taxes") on the excess of (a) the gross income realized by Transmission Owner as a result of payments or property transfers made by Interconnection Customer to Transmission Owner under this GIA (without regard to any payments under this Article 5.17) (the "Gross Income Amount") over (b) the present value of future tax deductions for depreciation that will be available as a result of such payments or property transfers (the "Present Value Depreciation Amount"), plus (2) an additional amount sufficient to permit Transmission Owner to receive and retain, after the payment of all Current Taxes, an amount equal to the net amount described in clause (1).

For this purpose, (i) Current Taxes shall be computed based on Transmission Owner's composite federal and state tax rates at the time the payments or property transfers are received and Transmission Owner will be treated as being subject to tax at the highest marginal rates in effect at that time (the "Current Tax Rate"), and (ii) the Present Value Depreciation Amount shall be computed by discounting Transmission Owner's anticipated tax depreciation deductions as a result of such payments or property transfers by Transmission Owner's current weighted average cost of capital. Thus, the formula for calculating Interconnection Customer's liability to Transmission Owner pursuant to this Article 5.17.4 can be expressed as follows: (Current Tax Rate x (Gross Income Amount – Present Value of Tax Depreciation))/(1-Current Tax Rate). Interconnection Customer's estimated tax liability in the event taxes are imposed shall be stated in Appendix A, Interconnection Facilities, Network Upgrades and Distribution Upgrades.

5.17.5 Private Letter Ruling or Change or Clarification of Law. At Interconnection Customer's request and expense, Transmission Owner shall file with the IRS a request for a private letter ruling as to whether any property transferred or sums paid, or to be paid, by Interconnection Customer to Transmission Owner under this GIA are subject to federal income taxation. Interconnection Customer will prepare the initial draft of the request for a private letter ruling, and will certify

under penalties of perjury that all facts represented in such request are true and accurate to the best of Interconnection Customer's knowledge. Transmission Owner and Interconnection Customer shall cooperate in good faith with respect to the submission of such request.

Transmission Owner shall keep Interconnection Customer fully informed of the status of such request for a private letter ruling and shall execute either a privacy act waiver or a limited power of attorney, in a form acceptable to the IRS, that authorizes Interconnection Customer to participate in all discussions with the IRS regarding such request for a private letter ruling. Transmission Owner shall allow Interconnection Customer to attend all meetings with IRS officials about the request and shall permit Interconnection Customer to prepare the initial drafts of any follow-up letters in connection with the request.

5.17.6 Subsequent Taxable Events. If, within 10 years from the date on which the relevant Transmission Owner's Interconnection Facilities are placed in service, (i) Interconnection Customer breaches the covenant contained in Article 5.17.2, (ii) a "disqualification event" occurs within the meaning of IRS Notice 88-129, or (iii) this GIA terminates and Transmission Owner retains ownership of the Interconnection Facilities, Network Upgrades, Transmission Owner's System Protection Facilities, and/or Distribution Upgrades, Interconnection Customer shall pay a tax gross-up for the cost consequences of any current tax liability imposed on Transmission Owner, calculated using the methodology described in Article 5.17.4 and in accordance with IRS Notice 90-60.

5.17.7 Contests. In the event any Governmental Authority determines that Transmission Owner's receipt of payments or property constitutes income that is subject to taxation, Transmission Owner shall notify Interconnection Customer, in writing, within thirty (30) Calendar Days of receiving notification of such determination by a Governmental Authority. Upon the timely written request by Interconnection Customer and at Interconnection Customer's sole expense, Transmission Owner may appeal, protest, seek abatement of, or otherwise oppose such determination. Upon Interconnection Customer's written request and sole expense, Transmission Owner shall file a claim for refund with respect to any taxes paid under this Article 5.17, whether or not it has received such a determination. Transmission Owner reserves the right to make all decisions with regard to the prosecution of such appeal, protest, abatement or other contest, including the selection of counsel and compromise or settlement of the claim, but Transmission Owner shall keep Interconnection Customer informed, shall consider in good faith suggestions from Interconnection Customer about the conduct of the contest, and shall reasonably permit Interconnection Customer or an Interconnection Customer representative to attend contest proceedings.

Interconnection Customer shall pay to Transmission Owner on a periodic basis, as invoiced by Transmission Owner, Transmission Owner's documented

reasonable costs of prosecuting such appeal, protest, abatement or other contest. At any time during the contest, Transmission Owner may agree to a settlement either with Interconnection Customer's consent or after obtaining written advice from nationally-recognized tax counsel, selected by Transmission Owner, but reasonably acceptable to Interconnection Customer, that the proposed settlement represents a reasonable settlement given the hazards of litigation. Interconnection Customer's obligation shall be based on the amount of the settlement agreed to by Interconnection Customer, or if a higher amount, so much of the settlement that is supported by the written advice from nationally-recognized tax counsel selected under the terms of the preceding sentence. The settlement amount shall be calculated on a fully grossed-up basis to cover any related cost consequences of the current tax liability. Any settlement without Interconnection Customer's consent or such written advice will relieve Interconnection Customer from any obligation to indemnify Transmission Owner for the tax at issue in the contest.

5.17.8 Refund. In the event that (a) a private letter ruling is issued to Transmission Owner which holds that any amount paid or the value of any property transferred by Interconnection Customer to Transmission Owner under the terms of this GIA is not subject to federal income taxation, (b) any legislative change or administrative announcement, notice, ruling or other determination makes it reasonably clear to Transmission Owner in good faith that any amount paid or the value of any property transferred by Interconnection Customer to Transmission Owner under the terms of this GIA is not taxable to Transmission Owner, (c) any abatement, appeal, protest, or other contest results in a determination that any payments or transfers made by Interconnection Customer to Transmission Owner are not subject to federal income tax, or (d) if Transmission Owner receives a refund from any taxing authority for any overpayment of tax attributable to any payment or property transfer made by Interconnection Customer to Transmission Owner pursuant to this GIA, Transmission Owner shall promptly refund to Interconnection Customer the following:

any payment made by Interconnection Customer under this Article 5.17 for taxes that is attributable to the amount determined to be non-taxable, together with interest thereon,

(ii) interest on any amounts paid by Interconnection Customer to Transmission Owner for such taxes which Transmission Owner did not submit to the taxing authority, calculated in accordance with the methodology set forth in 18 C.F.R. Section 35.19a(a)(2)(iii) from the date payment was made by Interconnection Customer to the date Transmission Owner refunds such payment to Interconnection Customer, and

(iii) with respect to any such taxes paid by Transmission Owner, any refund or credit Transmission Owner receives or to which it may be

entitled from any Governmental Authority, interest (or that portion thereof attributable to the payment described in clause (i), above) owed to Transmission Owner for such overpayment of taxes (including any reduction in interest otherwise payable by Transmission Owner to any Governmental Authority resulting from an offset or credit); provided, however, that Transmission Owner will remit such amount promptly to Interconnection Customer only after and to the extent that Transmission Owner has received a tax refund, credit or offset from any Governmental Authority for any applicable overpayment of income tax related to the Transmission Owner's Interconnection Facilities.

The intent of this provision is to leave both parties, to the extent practicable, in the event that no taxes are due with respect to any payment for Interconnection Facilities and Network Upgrades hereunder, in the same position they would have been in had no such tax payments been made.

5.17.9 Taxes Other Than Income Taxes. Upon the timely request by Interconnection Customer, and at Interconnection Customer's sole expense, Transmission Owner shall appeal, protest, seek abatement of, or otherwise contest any tax (other than federal or state income tax) asserted or assessed against Transmission Owner for which Interconnection Customer may be required to reimburse Transmission Owner under the terms of this GIA. Interconnection Customer shall pay to Transmission Owner on a periodic basis, as invoiced by Transmission Owner, Transmission Owner's documented reasonable costs of prosecuting such appeal, protest, abatement, or other contest. Interconnection Customer and Transmission Owner shall cooperate in good faith with respect to any such contest. Unless the payment of such taxes is a prerequisite to an appeal or abatement or cannot be deferred, no amount shall be payable by Interconnection Customer to Transmission Owner for such taxes until they are assessed by a final, non-appealable order by any court or agency of competent jurisdiction. In the event that a tax payment is withheld and ultimately due and payable after appeal, Interconnection Customer will be responsible for all taxes, interest and penalties, other than penalties attributable to any delay caused by Transmission Owner.

5.18 Tax Status. Each Party shall cooperate with the other Parties to maintain each Party's tax status. Nothing in this GIA is intended to adversely affect any Party's tax-exempt status with respect to the issuance of bonds including, but not limited to, Local Furnishing Bonds.

5.19 Modification.

5.19.1 General. Either Party may undertake modifications to its facilities. If a Party plans to undertake a modification that reasonably may be expected to affect another Party's facilities, that Party shall provide to the other Parties sufficient

information regarding such modification so that the other Parties may evaluate the potential impact of such modification prior to commencement of the work. Such information shall be deemed to be Confidential Information hereunder and shall include information concerning the timing of such modifications and whether such modifications are expected to interrupt the flow of electricity from the Generating Facility. The Party desiring to perform such work shall provide the relevant drawings, plans, and specifications to the other Parties at least ninety (90) Calendar Days in advance of the commencement of the work or such shorter period upon which the Parties may agree, which agreement shall not unreasonably be withheld, conditioned or delayed.

In the case of Generating Facility modifications that do not require Interconnection Customer to submit an Interconnection Request, Transmission Provider shall provide, within thirty (30) Calendar Days (or such other time as the Parties may agree), an estimate of any additional modifications to the Transmission or Distribution System as applicable, Transmission Owner's Interconnection Facilities, Network Upgrades, Transmission Owner's System Protection Facilities, and/or Distribution Upgrades necessitated by such Interconnection Customer modification and a good faith estimate of the costs thereof which shall be the responsibility of Interconnection Customer.

5.19.2 Standards. Any additions, modifications, or replacements made to a Party's facilities shall be designed, constructed and operated in accordance with this GIA and Good Utility Practice.

5.19.3 Modification Costs. Interconnection Customer shall not be directly assigned the costs of any additions, modifications, or replacements that Transmission Owner makes to the Transmission Owner's Interconnection Facilities, Network Upgrades, Transmission Owner's System Protection Facilities, Distribution Upgrades, or the Transmission or Distribution System, as applicable, to facilitate the interconnection of a third party to the Transmission Owner's Interconnection Facilities or the Transmission or Distribution System, as applicable, or to provide transmission service to a third party under the Tariff. Interconnection Customer shall be responsible for the costs of any additions, modifications, or replacements to the Interconnection Customer's Interconnection Facilities that may be necessary to maintain or upgrade such Interconnection Customer's Interconnection Facilities consistent with Applicable Laws and Regulations, Applicable Reliability Standards or Good Utility Practice.

ARTICLE 6. TESTING AND INSPECTION

6.1 Pre-Commercial Operation Date Testing and Modifications. Prior to the Commercial Operation Date, Transmission Owner shall test the Transmission Owner's Interconnection Facilities, Network Upgrades, Transmission Owner's System Protection Facilities and Distribution Upgrades, and Interconnection Customer shall test each

electric production device at the Generating Facility, Interconnection Customer's System Protection Facilities, including control equipment to limit injection at the POI to the level of Interconnection Service set forth in Appendix A and the Interconnection Customer's Interconnection Facilities to ensure their safe and reliable operation. Similar testing may be required after initial operation. Transmission Owner and Interconnection Customer shall make any modifications to their respective facilities that are found to be necessary as a result of such testing. Interconnection Customer shall bear the cost of all such testing and modifications. Interconnection Customer shall generate test energy at the Generating Facility only if it has arranged for the delivery of such test energy.

6.2 Post-Commercial Operation Date Testing and Modifications. Each Party shall at its own expense perform routine inspection and testing of its facilities and equipment in accordance with Good Utility Practice as may be necessary to ensure the continued interconnection of the Generating Facility with the Transmission or Distribution System, as applicable, in a safe and reliable manner. Each Party shall have the right, upon advance written notice, to require reasonable additional testing of the Interconnection Facilities, at the requesting Party's expense, as may be in accordance with Good Utility Practice.

6.3 Right to Observe Testing. Each Party shall notify the other Parties in advance of its performance of tests of its Interconnection Facilities. The other Parties shall each have the right, at its own expense, to observe such testing.

6.4 Right to Inspect. Each Party shall have the right, but shall have no obligation to: (i) observe Transmission Owner's and Interconnection Customer's tests and/or inspection of any of their respective System Protection Facilities and other protective equipment, including power system stabilizers and control equipment; (ii) review the settings of the System Protection Facilities and other protective equipment; and (iii) review the maintenance records relative to the Interconnection Facilities, the System Protection Facilities and other protective equipment. A Party may exercise these rights from time to time as it deems necessary upon reasonable notice to the other Parties. The exercise or non-exercise by a Party of any such rights shall not be construed as an endorsement or confirmation of any element or condition of the Interconnection Facilities or the System Protection Facilities or other protective equipment or the operation thereof, or as a warranty as to the fitness, safety, desirability, or reliability of same. Any information that a Party obtains through the exercise of any of its rights under this Article 6.4 shall be deemed to be Confidential Information and treated pursuant to Article 22 of this GIA.

ARTICLE 7. METERING

7.1 General. Each Party shall comply with the Electric Reliability Organization requirements. Unless the Interconnection Customer is utilizing shared Interconnection Customer Interconnection Facilities, or unless otherwise agreed by the Parties, Transmission Owner, at its election, or otherwise Interconnection Customer, shall install Metering Equipment (the "Metering Party") at the Point of Interconnection prior to any operation of the Generating Facility. Transmission Owner, at its election, or otherwise

Interconnection Customer shall own, operate, test and maintain such Metering Equipment. Power flows to and from the Generating Facility shall be measured at or, at the Metering Party's option, compensated to, the Point of Interconnection. If Interconnection Customer will share Interconnection Facilities with any other projects, Interconnection Customer shall install Metering Equipment either on its own Generating Facility or its own non-shared facilities sufficient to measure the output of such Interconnection Customer's Generating Facility separately from any other Generating Facilities with which it will share Interconnection Facilities. The Metering Party shall provide metering quantities, in analog and/or digital form, to the other Parties upon request. Interconnection Customer shall bear all reasonable documented costs associated with the purchase, installation, operation, testing and maintenance of the Metering Equipment.

7.2 Check Meters. Interconnection Customer, at its option and expense, may install and operate, on its premises and on its side of the Point of Interconnection, one or more check meters to check the Metering Equipment owned by the Metering Party. Such check meters shall be for check purposes only and shall not be used for the measurement of power flows for purposes of this GIA, except as provided in Article 7.4 below. The check meters shall be subject at all reasonable times to inspection and examination by Transmission Provider, Transmission Owner or their designees. The installation, operation and maintenance thereof shall be performed entirely by Interconnection Customer in accordance with Good Utility Practice.

7.3 Standards. The Metering Party shall install, calibrate, and test revenue quality Metering Equipment in accordance with applicable ANSI standards.

7.4 Testing of Metering Equipment. The Metering Party shall inspect and test Metering Equipment upon installation and at least once every two (2) years thereafter. If requested to do so by a Party, the Metering Party shall, at the requesting Party's expense, inspect or test Metering Equipment more frequently than every two (2) years. The Metering Party shall give reasonable notice to the other Parties of the time when any inspection or test shall take place, and the other Parties may have representatives present at the test or inspection. If at any time Metering Equipment is found to be inaccurate or defective, it shall be adjusted, repaired or replaced at Interconnection Customer's expense, in order to provide accurate metering, unless the inaccuracy or defect is due to the Metering Party's failure to maintain, then the Metering Party shall pay. If Metering Equipment fails to register, or if the measurement made by Metering Equipment during a test varies by more than two percent (2%) from the measurement made by the standard meter used in the test, the Metering Party shall adjust the measurements by correcting all measurements for the period during which Metering Equipment was in error by using Interconnection Customer's check meters, if installed. If no such check meters are installed or if the period cannot be reasonably ascertained, the adjustment shall be for the period immediately preceding the test of the Metering Equipment equal to one-half the time from the date of the previous test of the Metering Equipment.

7.5 Metering Data. At Interconnection Customer's expense, the metered data shall be

telemetered to one or more locations designated by Transmission Provider and Transmission Owner and one or more locations designated by Interconnection Customer. Such telemetered data shall be used, under normal operating conditions, as the official measurement of the amount of energy delivered from the Generating Facility to the Point of Interconnection.

ARTICLE 8. COMMUNICATIONS

8.1 Interconnection Customer Obligations. Interconnection Customer shall maintain satisfactory operating communications with Transmission Provider's Transmission System dispatcher or representative designated by Transmission Provider. Interconnection Customer shall provide standard voice line, dedicated voice line and facsimile communications at its Generating Facility control room or central dispatch facility through use of either the public telephone system, or a voice communications system that does not rely on the public telephone system. Interconnection Customer shall also provide the dedicated data circuit(s) necessary to provide Interconnection Customer data to Transmission Provider as set forth in Appendix D, Security Arrangements Details. The data circuit(s) shall extend from the Generating Facility to the location(s) specified by Transmission Provider. Any required maintenance of such communications equipment shall be performed by and at the cost of Interconnection Customer. Operational communications shall be activated and maintained under, but not be limited to, the following events: system paralleling or separation, scheduled and unscheduled shutdowns, equipment clearances, and hourly and daily load data.

Unless the Generating Facility is an Intermittent Resource not relying on wind or solar as a fuel source, Interconnection Customer shall install communication and control equipment such that the Generating Facility can receive and respond to the appropriate dispatch signals while operating under the Tariff. Where applicable, the requirements of the communication and control equipment will be enumerated in Appendix C to this GIA.

8.2 Remote Terminal Unit (RTU). Prior to the Initial Synchronization Date of the Generating Facility, a remote terminal unit, or equivalent data collection and transfer equipment acceptable to both Parties, shall be installed by Interconnection Customer, or by Transmission Owner at Interconnection Customer's expense, to gather accumulated and instantaneous data to be telemetered to the location(s) designated by Transmission Owner and Transmission Provider through use of a dedicated point-to-point data circuit(s) as indicated in Article 8.1. The communication protocol for the data circuit(s) shall be specified by Transmission Owner and Transmission Provider. Instantaneous bi-directional analog real power and reactive power flow information must be telemetered directly to the location(s) specified by Transmission Provider and Transmission Owner.

Each Party will promptly advise the other Parties if it detects or otherwise learns of any metering, telemetry or communications equipment errors or malfunctions that require the attention and/or correction. The Party owning such equipment shall correct such error or malfunction as soon as reasonably feasible.

8.3 No Annexation. Any and all equipment placed on the premises of a Party shall be and remain the property of the Party providing such equipment regardless of the mode and manner of annexation or attachment to real property, unless otherwise mutually agreed by the Parties.

8.4 Provision of Data from a Variable Energy Resource. Interconnection Customer whose Generating Facility contains at least one Variable Energy Resource shall provide meteorological and forced outage data to the Transmission Provider to the extent necessary for the Transmission Provider's development and deployment of power production forecasts for that class of Variable Energy Resources. Interconnection Customer with a Variable Energy Resource having wind as the energy source will, upon request by the Transmission Provider, be required to provide Transmission Provider with site-specific meteorological data including: temperature, wind speed, wind direction, and atmospheric pressure. Interconnection Customer with a Variable Energy Resource having solar as the energy source will, upon request by the Transmission Provider, be required to provide the Transmission Provider with site-specific meteorological data including: temperature, atmospheric pressure, and irradiance. Transmission Provider and Interconnection Customer whose Generating Facility contains a Variable Energy Resource shall mutually agree to any additional meteorological data that are required for the development and deployment of a power production forecast. Interconnection Customer whose Generating Facility contains a Variable Energy Resource also shall submit data to Transmission Provider regarding all forced outages to the extent necessary for Transmission Provider's development and deployment of power production forecasts for that class of Variable Energy Resources. The exact specifications of the meteorological and forced outage data to be provided by Interconnection Customer to Transmission Provider, including the frequency and timing of data submittals, shall be made taking into account the size and configuration of the Variable Energy Resource, its characteristics, location, and its importance in maintaining generation resource adequacy and transmission system reliability in its area. All requirements for meteorological and forced outage data must be commensurate with the power production forecasting employed by Transmission Provider. Data requirements for meteorological and forced outage data will be negotiated by Transmission Provider and Interconnection Customer, and will be set forth in Appendix C, Interconnection Details, of this GIA.

ARTICLE 9. OPERATIONS

9.1 General. Each Party shall comply with the Electric Reliability Organization requirements. Each Party shall provide to any Party all information that may reasonably be required by that Party to comply with Applicable Laws and Regulations and Applicable Reliability Standards.

9.2 Local Balancing Authority Notification. At least three (3) months before Initial Synchronization Date, Interconnection Customer shall notify Transmission Provider and Transmission Owner in writing of the Local Balancing Authority in which the Generating Facility will be located. If Interconnection Customer elects to locate the Generating Facility through dynamic metering/scheduling in a Local Balancing Authority other than

the Local Balancing Authority in which the Generating Facility is physically located, and if permitted to do so by the relevant transmission tariffs, all necessary arrangements, including but not limited to those set forth in Article 7 and Article 8 of this GIA, and remote Local Balancing Authority generator interchange agreements, if applicable, and the appropriate measures under such agreements, shall be executed and implemented prior to the placement of the Generating Facility in the other Local Balancing Authority.

9.3 Transmission Provider and Transmission Owner Obligations. Transmission Provider shall cause the Transmission System and the Transmission Owner's Interconnection Facilities to be operated, maintained and controlled in a safe and reliable manner in accordance with this GIA. Transmission Provider, or its designee, may provide operating instructions to Interconnection Customer consistent with this GIA and the Tariff and, if applicable, Transmission Owner's operating protocols and procedures as they may change from time to time. Transmission Provider will consider changes to its operating protocols and procedures proposed by Interconnection Customer.

9.4 Interconnection Customer Obligations. Interconnection Customer shall at its own expense operate, maintain and control the Generating Facility and the Interconnection Customer's Interconnection Facilities in a safe and reliable manner and in accordance with this GIA. The Generating Facility must be operated in accordance with the operating limits, if any, in the Interconnection Facilities Study and specified in Appendix C of this GIA. Interconnection Customer shall operate the Generating Facility and the Interconnection Customer's Interconnection Facilities in accordance with all applicable requirements of Transmission Provider or its designated Local Balancing Authority Operator of which the Generating Facility is part, as such requirements are set forth in Appendix C, Interconnection Details, of this GIA. Appendix C, Interconnection Details, will be modified to reflect changes to the requirements as they may change from time to time. Any Party may request that a Party provide copies of the requirements set forth in Appendix C, Interconnection Details, of this GIA.

9.5 Start-Up and Synchronization. Consistent with the Parties' mutually acceptable procedures, Interconnection Customer is responsible for the proper synchronization of the Generating Facility to the Transmission or Distribution System, as applicable.

9.6 Reactive Power and Primary Frequency Response.

9.6.1 Power Factor Design Criteria.

9.6.1.1 Synchronous Generation. Interconnection Customer shall design the Generating Facility to be capable of maintaining a composite power delivery at continuous rated power output at the Point of Interconnection at all power factors over 0.95 leading to 0.95 lagging, unless the Transmission Provider has established different requirements that apply to all synchronous generators in the Local Balancing Authority on a comparable basis. The applicable Local Balancing Authority power factor requirements are listed on the Transmission Provider's website at

https://cdn.misoenergy.org/Reactive_Generator_Requirements108137.pdf

and may be referenced in the Appendices to this GIA. The Generating Facility shall be capable of continuous dynamic operation throughout the power factor design range as measured at the Point of Interconnection. Such operation shall account for the net effect of all energy production devices on the Interconnection Customer's side of the Point of Interconnection.

9.6.1.2 Inverter-Based Resource Plants. Interconnection Customer shall design the Generating Facility to be capable of maintaining a composite power delivery at continuous rated power output at the high-side of the generator substation at all power factors over 0.95 leading to 0.95 lagging, unless the Transmission Provider has established different requirements that apply to all inverter-based resource plants in the Local Balancing Authority on a comparable basis. The applicable Local Balancing Authority power factor requirements are listed on the Transmission Provider's website at

https://cdn.misoenergy.org/Reactive_Generator_Requirements108137.pdf

and may be referenced in the Appendices to this GIA. This power factor range standard shall be dynamic and can be met using, for example, power electronics designed to supply this level of reactive capability (taking into account any limitations due to voltage level, real power output, etc.) or fixed and switched capacitors, or a combination of the two. This requirement shall only apply to newly interconnecting inverter-based resource plants that have not yet completed a System Impact Study as of the effective date of the Final Rule establishing this requirement (Order No. 827). These requirements apply to existing inverter-based resource plants making upgrades that require a new Generator Interconnection Agreement only where the Transmission Provider's System Impact Study shows the need for reactive power as a result of an upgrade. If applicable, these requirements will be memorialized in Appendix C to this GIA.

Additional reactive power requirements for inverter-based resource plants are provided in Appendix G of this GIA.

9.6.2 Voltage Schedules. Once Interconnection Customer has synchronized the Generating Facility with the Transmission System, Transmission Provider shall require Interconnection Customer to operate the Generating Facility to produce or absorb reactive power within the design limitations of the Generating Facility set forth in Article 9.6.1 (Power Factor Design Criteria), to maintain the output voltage or power factor at the Point of Interconnection as specified by Transmission Provider. Transmission Provider's voltage schedules shall treat all sources of reactive power in the Local Balancing Authority in an equitable and not unduly discriminatory manner. Transmission Provider shall exercise

Reasonable Efforts to provide Interconnection Customer with such schedules at least one (1) Calendar Day in advance, and may make changes to such schedules as necessary to maintain the reliability of the Transmission or Distribution System as applicable. Interconnection Customer shall operate the Generating Facility to maintain the specified output voltage or power factor at the Point of Interconnection within the design limitations of the Generating Facility set forth in Article 9.6.1 (Power Factor Design Criteria). If Interconnection Customer is unable to maintain the specified voltage or power factor, it shall promptly notify Transmission Provider's system operator, or its designated representative.

9.6.2.1 Voltage Regulators. Whenever the Generating Facility is operated in parallel with the Transmission or Distribution System as applicable and voltage regulators are capable of operation, Interconnection Customer shall operate the Generating Facility with its speed governors and voltage regulators in automatic operation. If the Generating Facility's voltage regulators are not capable of such automatic operation, Interconnection Customer shall immediately notify Transmission Provider's system operator, or its designated representative, and ensure that such Generating Facility's reactive power production or absorption (measured in MVARs) are within the design capability of the Generating Facility's generating unit(s) and steady state stability limits. Interconnection Customer shall not cause its Generating Facility to disconnect automatically or instantaneously from the Transmission or Distribution System, as applicable, or trip any generating unit comprising the Generating Facility for an under or over frequency condition unless the abnormal frequency condition persists for a time period beyond the limits set forth in ANSI/IEEE Standard C37.106, or such other standard as applied to other generators in the Local Balancing Authority on a comparable basis.

9.6.3 Payment for Reactive Power. Payments for reactive power shall be pursuant to any tariff or rate schedule filed by Transmission Provider and approved by the FERC.

9.6.4 Primary Frequency Response. This Section 9.6.4 shall only apply in the event that the Interconnection Request for the Generating Facility completed Definitive Planning Phase Interconnection Customer Decision Point 2 after May 15, 2018.

Interconnection Customer shall ensure the primary frequency response capability of its Generating Facility by installing, maintaining, and operating a functioning governor or equivalent controls. The term "functioning governor or equivalent controls" as used herein shall mean the required hardware and/or software that provides frequency responsive real power control with the ability to sense changes in system frequency and autonomously adjust the Generating Facility's real power output in accordance with the droop and deadband parameters and in the direction needed to correct frequency deviations. Interconnection Customer is

required to install a governor or equivalent controls with the capability of operating: (1) with a maximum 5 percent droop and ±0.036 Hz deadband; or (2) in accordance with the relevant droop, deadband, and timely and sustained response settings from an approved Reliability Organization reliability standard providing for equivalent or more stringent parameters. The droop characteristic shall be: (1) based on the nameplate capacity of the Generating Facility, and shall be linear in the range of frequencies between 59 to 61 Hz that are outside of the deadband parameter; or (2) based on an approved Electric Reliability Organization reliability standard providing for an equivalent or more stringent parameter. The deadband parameter shall be: the range of frequencies above and below nominal (60 Hz) in which the governor or equivalent controls is not expected to adjust the Generating Facility's real power output in response to frequency deviations. The deadband shall be implemented: (1) without a step to the droop curve, that is, once the frequency deviation exceeds the deadband parameter, the expected change in the Generating Facility's real power output in response to frequency deviations shall start from zero and then increase (for under-frequency deviations) or decrease (for over-frequency deviations) linearly in proportion to the magnitude of the frequency deviation; or (2) in accordance with an approved Electric Reliability Organization Reliability Standard providing for an equivalent or more stringent parameter. Interconnection Customer shall notify Transmission Provider that the primary frequency response capability of the Generating Facility has been tested and confirmed during commissioning. Once Interconnection Customer has synchronized the Generating Facility with the Transmission System, Interconnection Customer shall operate the Generating Facility consistent with the provisions specified in Articles 9.6.4.1 and 9.6.4.2 of this GIA. The primary frequency response requirements contained herein shall apply to both synchronous and inverter-based resource plant Generating Facilities.

9.6.4.1 Governor or Equivalent Controls. Whenever the Generating Facility is operated in parallel with the Transmission System, Interconnection Customer shall operate the Generating Facility with its governor or equivalent controls in service and responsive to frequency. Interconnection Customer shall: (1) in coordination with Transmission Provider and/or the relevant balancing authority, set the deadband parameter to: (a) a maximum of ±0.036 Hz and set the droop parameter to a maximum of 5 percent; or (b) implement the relevant droop and deadband settings from an approved Regional Reliability Organization reliability standard that provides for equivalent or more stringent parameters. Interconnection Customer shall be required to provide the status and settings of the governor or equivalent controls to Transmission Provider and/or the relevant balancing authority upon request. If Interconnection Customer needs to operate the Generating Facility with its governor or equivalent controls not in service, Interconnection Customer shall immediately notify Transmission Provider and the relevant balancing authority, and provide both with the following information: (1) the operating status of the governor or

equivalent controls (i.e., whether it is currently out of service or when it will be taken out of service); (2) the reasons for removing the governor or equivalent controls from service; and (3) a reasonable estimate of when the governor or equivalent controls will be returned to service. Interconnection Customer shall make Reasonable Efforts to return its governor or equivalent controls into service as soon as practicable. Interconnection Customer shall make Reasonable Efforts to keep outages of the Generating Facility's governor or equivalent controls to a minimum whenever the Generating Facility is operated in parallel with the Transmission System.

9.6.4.2 Timely and Sustained Response. Interconnection Customer shall ensure that the Generating Facility's real power response to sustained frequency deviations outside of the deadband setting is automatically provided and shall begin immediately after frequency deviates outside of the deadband, and to the extent the Generating Facility has operating capability in the direction needed to correct the frequency deviation. Interconnection Customer shall not block or otherwise inhibit the ability of the governor or equivalent controls to respond and shall ensure that the response is not inhibited, except under certain operational constraints including, but not limited to, ambient temperature limitations, physical energy limitations, outages of mechanical equipment, or regulatory requirements. The Generating Facility shall sustain the real power response at least until system frequency returns to a value within the deadband setting of the governor or equivalent controls. A Commission-approved reliability standard with equivalent or more stringent requirements shall supersede the above requirements.

9.6.4.3 Exemptions. Generating Facilities that are regulated by the United States Nuclear Regulatory Commission shall be exempt from Articles 9.6.4, 9.6.4.1, and 9.6.4.2 of this GIA. Generating Facilities that are behind the meter generation that is sized-to-load (i.e., the thermal load and the generation are near-balanced in real-time operation and the generation is primarily controlled to maintain the unique thermal, chemical, or mechanical output necessary for the operating requirements of its host facility) shall be required to install primary frequency response capability in accordance with the droop and deadband capability requirements specified in Article 9.6.4, but shall be otherwise exempt from the operating requirements in Articles 9.6.4, 9.6.4.1, 9.6.4.2, and 9.6.4.4 of this GIA.

9.6.4.4 Electric Storage Resources. Interconnection Customer interconnecting an electric storage resource shall establish an operating range in Appendix C that specifies a minimum state of charge and a maximum state of charge between which the electric storage resource will be required to provide primary frequency response consistent with the

conditions set forth in Articles 9.6.4, 9.6.4.1, 9.6.4.2 and 9.6.4.3 of this GIA. Appendix C shall specify whether the operating range is static or dynamic, and shall consider (1) the expected magnitude of frequency deviations in the interconnection; (2) the expected duration that system frequency will remain outside of the deadband parameter in the interconnection; (3) the expected incidence of frequency deviations outside of the deadband parameter in the interconnection; (4) the physical capabilities of the electric storage resource; (5) operational limitations of the electric storage resource due to manufacturer specifications; and (6) any other relevant factors agreed to by Transmission Provider and Interconnection Customer, and in consultation with the relevant transmission owner or balancing authority as appropriate. If the operating range is dynamic, then Appendix C must establish how frequently the operating range will be reevaluated and the factors that may be considered during its reevaluation.

Interconnection Customer's electric storage resource is required to provide timely and sustained primary frequency response consistent with Article 9.6.4.2 of this GIA when it is online and dispatched to inject electricity to the Transmission System and/or receive electricity from the Transmission System. This excludes circumstances when the electric storage resource is not dispatched to inject electricity to the Transmission System and/or dispatched to receive electricity from the Transmission System.

9.6.4.5 Inverter-Based Resource Plants. Additional primary frequency response requirements for inverter-based resource plants, including electric storage resources, are provided in Appendix G of this GIA.

9.7 Outages and Interruptions.

9.7.1 Outages.

9.7.1.1 Outage Authority and Coordination. Interconnection Customer and Transmission Owner may each in accordance with Good Utility Practice in coordination with the other Party and Transmission Provider remove from service any of its respective Interconnection Facilities, System Protection Facilities, Network Upgrades, System Protection Facilities or Distribution Upgrades that may impact the other Party's facilities as necessary to perform maintenance or testing or to install or replace equipment. Absent an Emergency Condition, the Party scheduling a removal of such facility(ies) from service will use Reasonable Efforts to notify one another and schedule such removal on a date and time mutually acceptable to the Parties. In all circumstances, any Party planning to remove such facility(ies) from service shall use Reasonable Efforts to minimize the effect on the other Parties of such removal.

9.7.1.2 Outage Schedules. Transmission Provider shall post scheduled outages of transmission facilities on the OASIS. Interconnection Customer shall submit its planned maintenance schedules for the Generating Facility to Transmission Provider and Transmission Owner for a minimum of a rolling twenty-four (24) month period in accordance with the Transmission Provider's procedures. Interconnection Customer shall update its planned maintenance schedules as necessary. Transmission Provider may request Interconnection Customer to reschedule its maintenance as necessary to maintain the reliability of the Transmission System; provided, however, adequacy of generation supply shall not be a criterion in determining Transmission System reliability.

Transmission Provider shall compensate, pursuant to applicable Transmission Provider tariff or rate schedule, Interconnection Customer for any additional direct costs that Interconnection Customer incurs as a result of having to reschedule maintenance, including any additional overtime, breaking of maintenance contracts or other costs above and beyond the cost Interconnection Customer would have incurred absent the Transmission Provider's request to reschedule maintenance. Interconnection Customer will not be eligible to receive compensation, if during the twelve (12) months prior to the date of the scheduled maintenance, Interconnection Customer had modified its schedule of maintenance activities.

Costs shall be determined by negotiation between Transmission Provider and Interconnection Customer prior to implementation of the voluntary change in outage schedules, or if such request is made by or on behalf of a Transmission Customer requesting firm service, costs and recovery of costs shall be determined through a bilateral agreement between the Transmission Customer and Interconnection Customer. Voluntary changes to outage schedules under this Article 9.7.1.2 are separate from actions and compensation required under Article 13 and for which costs are recovered in accordance with Transmission Provider's applicable tariff or rate schedule.

9.7.1.3 Outage Restoration. If an outage on either the Interconnection Customer's or Transmission Owner's Interconnection Facilities, Network Upgrades, System Protection Facilities or Distribution Upgrades adversely affects a Party's operations or facilities, the Party that owns or controls the facility that is out of service shall use Reasonable Efforts to promptly restore such facility(ies) to a normal operating condition consistent with the nature of the outage. The Party that owns or controls the facility that is out of service shall provide the other Parties, to the extent such information is known, information on the nature of the Emergency Condition, an estimated time of restoration,

and any corrective actions required. Initial verbal notice shall be followed up as soon as practicable with written notice to the other Parties explaining the nature of the outage.

9.7.2 Interruption of Service. If required by Good Utility Practice to do so, Transmission Provider may require Interconnection Customer to interrupt or reduce deliveries of electricity if such delivery of electricity could adversely affect Transmission Provider's ability to perform such activities as are necessary to safely and reliably operate and maintain the Transmission System. The following provisions shall apply to any interruption or reduction permitted under this Article 9.7.2:

9.7.2.1 The interruption or reduction shall continue only for so long as reasonably necessary under Good Utility Practice;

9.7.2.2 Any such interruption or reduction shall be made on an equitable, non-discriminatory basis with respect to all generating facilities directly connected to the Transmission or Distribution System, as applicable;

9.7.2.3 When the interruption or reduction must be made under circumstances which do not allow for advance notice, Transmission Provider shall notify Interconnection Customer by telephone as soon as practicable of the reasons for the curtailment, interruption, or reduction, and, if known, its expected duration. Telephone notification shall be followed by written notification as soon as practicable;

9.7.2.4 Except during the existence of an Emergency Condition, when the interruption or reduction can be scheduled without advance notice, Transmission Provider shall notify Interconnection Customer in advance regarding the timing of such scheduling and further notify Interconnection Customer of the expected duration. Transmission Provider shall coordinate with Interconnection Customer using Good Utility Practice to schedule the interruption or reduction during periods of least impact to Interconnection Customer, Transmission Owner and Transmission Provider;

9.7.2.5 The Parties shall cooperate and coordinate with each other to the extent necessary in order to restore the Generating Facility, Interconnection Facilities, and the Transmission or Distribution System, as applicable to their normal operating state, consistent with system conditions and Good Utility Practice.

9.7.3 Ride Through Capability and Performance. The Transmission System is designed to automatically activate a load-shed program as required by the Electric Reliability Organization in the event of an underfrequency system disturbance. Interconnection Customer shall implement under-frequency and over-frequency

relay set points for the Generating Facility as required by the Electric Reliability Organization to ensure frequency "ride through" capability of the Transmission System. Generating Facility response to frequency deviations of pre-determined magnitudes, both under-frequency and over-frequency deviations, shall be studied and coordinated with Transmission Provider in accordance with Good Utility Practice. Interconnection Customer shall also implement under-voltage and over-voltage relay set points, or equivalent electronic controls, as required by the Electric Reliability Organization to ensure voltage "ride through" capability of the Transmission System. The term "ride through" as used herein shall mean the ability of a Generating Facility to stay connected to and synchronized with the Transmission System during system disturbances within a range of under-frequency, over-frequency, under-voltage, and over-voltage conditions, in accordance with Good Utility Practice and consistent with any standards and guidelines that are applied to other Generating Facilities in the Balancing Authority Area on a comparable basis. For abnormal frequency conditions and voltage conditions within the "no trip zone" defined by Reliability Standard PRC-024-3 or successor mandatory ride through reliability standards, the non-synchronous Generating Facility must ensure that, within any physical limitations of the Generating Facility, its control and protection settings are configured or set to (1) continue active power production during disturbance and post disturbance periods at pre-disturbance levels, unless providing primary frequency response or fast frequency response; (2) minimize reductions in active power and remain within dynamic voltage and current limits, if reactive power priority mode is enabled, unless providing primary frequency response or fast frequency response; (3) not artificially limit dynamic reactive power capability during disturbances; and (4) return to pre-disturbance active power levels without artificial ramp rate limits if active power is reduced, unless providing primary frequency response or fast frequency response.

9.7.4 System Protection and Other Control Requirements.

9.7.4.1 System Protection Facilities. Interconnection Customer shall, at its expense, install, operate and maintain its System Protection Facilities as a part of the Generating Facility or the Interconnection Customer's Interconnection Facilities. Transmission Owner shall install at Interconnection Customer's expense any Transmission Owner's System Protection Facilities that may be required on the Transmission Owner's Interconnection Facilities or the Transmission Owner's transmission or distribution facilities as a result of the interconnection of the Generating Facility and the Interconnection Customer's Interconnection Facilities.

9.7.4.2 Interconnection Customer's and Transmission Owner's System Protection Facilities shall be designed and coordinated with Affected Systems in accordance with Good Utility Practice.

9.7.4.3 Each Party shall be responsible for protection of its facilities consistent

with Good Utility Practice.

9.7.4.4 Each Party's protective relay design shall incorporate the necessary test switches to perform the tests required in Article 6. The required test switches will be placed such that they allow operation of lockout relays while preventing breaker failure schemes from operating and causing unnecessary breaker operations and/or the tripping of the Generating Facility.

9.7.4.5 Each Party will test, operate and maintain their respective System Protection Facilities in accordance with Good Utility Practice.

9.7.4.6 Prior to the In-Service Date, and again prior to the Commercial Operation Date, Interconnection Customer or Transmission Owner, or their respective agents, shall perform a complete calibration test and functional trip test of the System Protection Facilities. At intervals suggested by Good Utility Practice and following any apparent malfunction of the System Protection Facilities, Interconnection Customer or Transmission Owner shall each perform both calibration and functional trip tests of their respective System Protection Facilities. These tests do not require the tripping of any in-service generating unit. These tests do, however, require that all protective relays and lockout contacts be activated.

9.7.5 Requirements for Protection. In compliance with Good Utility Practice, Interconnection Customer shall provide, install, own, and maintain relays, circuit breakers and all other devices necessary to remove any fault contribution of the Generating Facility to any short circuit occurring on the Transmission or Distribution System, as applicable, not otherwise isolated by Transmission Owner's equipment, such that the removal of the fault contribution shall be coordinated with the protective requirements of the Transmission or Distribution System, as applicable. Such protective equipment shall include, without limitation, a disconnecting device or switch with load-interrupting capability located between the Generating Facility and the Transmission or Distribution System, as applicable, at a site selected upon mutual agreement (not to be unreasonably withheld, conditioned or delayed) of the Parties. Interconnection Customer shall be responsible for protection of the Generating Facility and Interconnection Customer's other equipment from such conditions as negative sequence currents, over- or under-frequency, sudden load rejection, over- or under-voltage, and generator loss-of-field. Interconnection Customer shall be solely responsible to disconnect the Generating Facility and Interconnection Customer's other equipment if conditions on the Transmission or Distribution System, as applicable, could adversely affect the Generating Facility.

9.7.6 Power Quality. Neither Party's facilities shall cause excessive voltage flicker nor introduce excessive distortion to the sinusoidal voltage or current waves as

defined by ANSI Standard C84.1, in accordance with IEEE Standard 519, or any applicable superseding electric industry standard. In the event of a conflict between ANSI Standard C84.1, and any applicable superseding electric industry standard, the applicable superseding electric industry standard shall control.

9.8 Switching and Tagging Rules. Prior to the Initial Synchronization Date, each Party shall provide the other Parties a copy of its switching and tagging rules that are applicable to the other Parties' activities. Such switching and tagging rules shall be developed on a non-discriminatory basis. The Parties shall comply with applicable switching and tagging rules, as amended from time to time, in obtaining clearances for work or for switching operations on equipment.

9.9 Use of Interconnection Facilities by Other Parties.

9.9.1 Purpose of Interconnection Facilities. Except as may be required by Applicable Laws and Regulations, or as otherwise agreed to among the Parties, the Interconnection Facilities shall be constructed for the sole purpose of interconnecting the Generating Facility to the Transmission or Distribution System, as applicable, and shall be used for no other purpose.

9.9.2 Other Users. If required by Applicable Laws and Regulations or if the Parties mutually agree, such agreement not to be unreasonably withheld or delayed, to allow one or more Parties to use the Transmission Owner's Interconnection Facilities, or any part thereof, Interconnection Customer will be entitled to compensation for the capital expenses it incurred in connection with the Interconnection Facilities based upon the pro rata use of the Interconnection Facilities by Transmission Owner, all non-Party users, and Interconnection Customer, in accordance with Applicable Laws and Regulations or upon some other mutually-agreed upon methodology. In addition, cost responsibility for ongoing costs, including operation and maintenance costs associated with the Interconnection Facilities, will be allocated between Interconnection Customer and any non-Party users based upon the pro rata use of the Interconnection Facilities by Transmission Owner, all non-Party users, and Interconnection Customer, in accordance with Applicable Laws and Regulations or upon some other mutually agreed upon methodology. If the issue of such compensation or allocation cannot be resolved through such negotiations, it shall be submitted to Dispute Resolution pursuant to Section 12 of the Tariff.

9.10 Disturbance Analysis Data Exchange. The Parties will cooperate with one another in the analysis of disturbances to either the Generating Facility or the Transmission System by gathering and providing access to any information relating to any disturbance, including information from oscillography, protective relay targets, breaker operations and sequence of events records, and any disturbance information required by Good Utility Practice.

ARTICLE 10. MAINTENANCE

10.1 Transmission Owner Obligations. Transmission Owner shall maintain the Transmission Owner's Interconnection Facilities in a safe and reliable manner and in accordance with this GIA and all Applicable Laws and Regulations.

10.2 Interconnection Customer Obligations. Interconnection Customer shall maintain the Generating Facility and the Interconnection Customer's Interconnection Facilities in a safe and reliable manner and in accordance with this GIA and all Applicable Laws and Regulations.

10.3 Coordination. The Parties shall confer regularly to coordinate the planning, scheduling and performance of preventive and corrective maintenance on the Generating Facility and the Interconnection Facilities.

10.4 Secondary Systems. Each Party shall cooperate with the other in the inspection, maintenance, and testing of control or power circuits that operate below 600 volts, AC or DC, including, but not limited to, any hardware, control or protective devices, cables, conductors, electric raceways, secondary equipment panels, transducers, batteries, chargers, and voltage and current transformers that directly affect the operation of a Party's facilities and equipment which may reasonably be expected to impact another Party. Each Party shall provide advance notice to the other Parties before undertaking any work on such circuits, especially on electrical circuits involving circuit breaker trip and close contacts, current transformers, or potential transformers.

10.5 Operating and Maintenance Expenses. Subject to the provisions herein addressing the use of facilities by others, and except for operations and maintenance expenses associated with modifications made for providing Interconnection Service or Transmission Service to a non-Party and such non-Party pays for such expenses, Interconnection Customer shall be responsible for all reasonable expenses including overheads, associated with: (1) owning, operating, maintaining, repairing, and replacing Interconnection Customer's Interconnection Facilities; and (2) operation, maintenance, repair and replacement of Transmission Owner's Interconnection Facilities to the extent required by Transmission Owner on a comparable basis.

ARTICLE 11. PERFORMANCE OBLIGATION

11.1 Interconnection Customer's Interconnection Facilities. Interconnection Customer shall design, procure, construct, install, own and/or control the Interconnection Customer's Interconnection Facilities described in Appendix A at its sole expense.

11.2 Transmission Owner's Interconnection Facilities. Transmission Owner shall design, procure, construct, install, own and/or control the Transmission Owner's Interconnection Facilities described in Appendix A at the sole expense of Interconnection Customer.

11.3 Network Upgrades, System Protection Facilities and Distribution Upgrades. Transmission Owner shall design, procure, construct, install, and own the Network Upgrades, Transmission Owner's System Protection Facilities and Distribution Upgrades described in Appendix A. Interconnection Customer shall be responsible for all costs related to Distribution Upgrades and/or Generator Upgrades. As required by Section 7.3.2.1 and 7.3.3.1 of Attachment X, Transmission Owner shall have provided Transmission Provider with written notice if Transmission Owner elects to fund the capital for the Network Upgrades and Transmission Owner's System Protection Facilities; otherwise, such facilities, if any, shall be solely funded by Interconnection Customer. In the event that the Transmission Owner elects to fund the capital costs of the Network Upgrades and/or Transmission Owner's System Protection Facilities, then the Parties shall enter into a Facilities Service Agreement. The Facilities Service Agreement shall take the form of the *pro forma* Facilities Service Agreement that is included as Appendix 14 of Attachment X to the MISO Tariff .

11.3.1 Contingencies Affecting Network Upgrades, System Protection Facilities and Distribution Upgrades. Network Upgrades, System Protection Facilities and Distribution Upgrades that are required to accommodate the Generating Facility may be modified because (1) a higher queued Interconnection Request withdrew or was deemed to have withdrawn, (2) the interconnection agreement associated with a higher queued Interconnection Request was terminated prior to the project's In-Service Date, (3) the Commercial Operation Date for a higher queued Interconnection Request is delayed, or the project itself is delayed (including due to suspension) such that facilities required to accommodate lower queued projects or the project itself may be altered, (4) the queue position is reinstated for a higher-queued Interconnection Request whose queue position was subject to dispute resolution, (5) changes occur in Transmission Provider or Transmission Owner equipment design standards or reliability criteria giving rise to the need for restudy, (6) the facilities required to accommodate a higher queued Interconnection Request were modified constituting a Material Modification pursuant to Section 4.4 of the GIP, (7) a GIA with an effective date prior to this GIA is terminated, (8) when ordered to restudy by FERC, or (9) the Network Upgrade Facilities Study for a Network Upgrade, which is to be included in this GIA, is completed after execution of this GIA. The higher queued Interconnection Requests that could impact the Network Upgrades, System Protection Facilities and Distribution Upgrades required to accommodate the Generating Facility, and possible Modifications that may result from the above listed events affecting the higher queued Interconnection Requests, to the extent such modifications are reasonably known and can be determined, and estimates of the costs associated with such required Network Upgrades, System Protection Facilities and Distribution Upgrades, are provided in Appendix A.

11.3.2 Agreement to Restudy and Cost Reallocation. In the event that one of the contingencies listed in Article 11.3.1 occurs, at any time before the Network Upgrades, Common Use Upgrades, Shared Network Upgrades, System Protection Facilities and/or Distribution Upgrades associated with higher queued

Interconnection Requests with GIA in effect prior to this GIA are completed, Transmission Provider may determine, in its discretion, that a restudy is required. If a restudy is required, Transmission Provider will provide notice to Interconnection Customer and Interconnection Customer agrees to enter into an Interconnection Study Agreement for such restudy. Transmission Provider will reevaluate the need for any Common Use Upgrade(s) and/or Shared Network Upgrade(s), and if still required, reallocate the cost and responsibility for any Common Use Upgrade and/or Shared Network Upgrade, without a restudy when possible, or with a restudy if the Transmission Provider deems it necessary in order to ensure reliability of the Transmission System. The Parties agree to amend Appendix A to this GIA in accordance with Article 30.10 to reflect the results of any cost reallocation required under this Article 11.3.2.

11.3.3 Agreement to Fund Shared Network Upgrades. Interconnection Customer agrees to fund Shared Network Upgrades, as determined by Transmission Provider. Where applicable, payments to fund Shared Network Upgrade(s) that are made to Transmission Provider by Interconnection Customer will be disbursed by Transmission Provider to the appropriate entities that funded the Shared Network Upgrades in accordance with Attachment X and Attachment FF of the Tariff. In the event that Interconnection Customer fails to meet its obligation to fund Shared Network Upgrades, Transmission Owner and Transmission Provider shall not be responsible for the Interconnection Customer's funding obligation.

11.4 Transmission Credits.

11.4.1 Repayment of Amounts Advanced for Network Upgrades. Interconnection Customer shall be entitled to a cash repayment by Transmission Owner(s) and the Affected System Owner(s) that own the Network Upgrades, of the amount paid respectively to Transmission Owner and Affected System Operator, if any, for the Network Upgrades, as provided under Attachment FF of this Tariff and including any tax gross-up or other tax-related payments associated with the repayable portion of the Network Upgrades, and not repaid to Interconnection Customer pursuant to Article 5.17.8 or otherwise, to be paid to Interconnection Customer on a dollar-for-dollar basis for the non-usage sensitive portion of transmission charges, as payments are made under the Tariff and Affected System's Tariff for Transmission Services with respect to the Generating Facility. Any repayment shall include interest calculated in accordance with the methodology set forth in FERC's regulations at 18 C.F.R. § 35.19 (a)(2)(iii) from the date of any payment for Network Upgrades through the date on which Interconnection Customer receives a repayment of such payment pursuant to this subparagraph. Interest shall not accrue during periods in which Interconnection Customer has suspended construction pursuant to Article 11 or the Network Upgrades have been determined not to be needed pursuant to this Article 11.4.1. Interconnection Customer may assign such repayment rights to any person.

If the Generating Facility is designated a Network Resource under the Tariff, or if there are otherwise no incremental payments for Transmission Service resulting from the use of the Generating Facility by Transmission Customer, and in the absence of another mutually agreeable payment schedule any repayments provided under Attachment FF shall be established equal to the applicable rate for Firm Point-To-Point Transmission Service for the pricing zone where the Network Load is located multiplied by the portion of the demonstrated output of the Generating Facility designated as a Network Resource by the Network Customer(s) or in the absence of such designation, equal to the monthly firm single system-wide rate defined under Schedule 7 of the Tariff multiplied by the portion of the demonstrated output of the Generating Facility under contract to Network Customer(s) and consistent with studies pursuant to Section 3.2.2.2 of the GIP.

Notwithstanding the foregoing, as applicable and consistent with the provisions of Attachment FF of this Tariff, Interconnection Customer, Transmission Provider, Transmission Owner, and Affected System Operator may adopt any alternative payment schedule that is mutually agreeable so long as Transmission Owner and Affected System Operator take one of the following actions no later than five (5) years from the Commercial Operation Date: (1) return to Interconnection Customer any amounts advanced for Network Upgrades not previously repaid, or (2) declare in writing that Transmission Owner or Affected System Operator will continue to provide payments to Interconnection Customer on a dollar-for-dollar basis for the non-usage sensitive portion of transmission charges, or develop an alternative schedule that is mutually agreeable and provides for the return of all amounts advanced for Network Upgrades not previously repaid; however, full reimbursement shall not extend beyond twenty (20) years from the Commercial Operation Date.

If the Generating Facility is installed in phases, the amount eligible for refund as each phase achieves Commercial Operation will be reduced by the proportional amount of generation capacity not yet installed. However, all facilities in Appendix A other than the Generating Facility shall be built without consideration for the phasing of the Generating Facility as though the entire Generating Facility will be placed in Commercial Operation for the full output or increased output of the Generating Facility constructed by Interconnection Customer under this GIA.

If the Generating Facility fails to achieve Commercial Operation, but it or another generating facility is later constructed and makes use of the Network Upgrades, Transmission Owner and Affected System Operator shall at that time reimburse Interconnection Customer for the remaining applicable amounts that may be refundable pursuant to Attachment FF of this Tariff that were advanced for the Network Upgrades on their respective systems as described above. Before any such reimbursement can occur, Interconnection Customer, or the entity that ultimately constructs the Generating Facility, if different, is

responsible for identifying the entity to which the reimbursement must be made.

11.4.2 Special Provisions for Transmission Provider as an Affected System to be covered under Separate Agreements. When the Transmission Owner's Transmission or Distribution System (including for this Article 11.4.2 independent distribution systems connected to the Transmission System) is an Affected System for an interconnection in another electric system, Transmission Provider will coordinate the performance of Interconnection Studies with the other system. Transmission Provider will determine if any Network Upgrades or Distribution Upgrades, which may be required on the Transmission System as a result of the interconnection, would not have been needed but for the interconnection. Unless Transmission Owner provides, under the interconnection agreement between Interconnection Customer and the other system, for the repayment of amounts advanced to Transmission Provider or an impacted Transmission Owner for Network Upgrades, Interconnection Customer, Transmission Provider, and the impacted Transmission Owner(s) shall enter into an agreement that provides for such repayment by Transmission Owner(s) as directed by Transmission Provider. The agreement shall specify the terms governing payments to be made by Interconnection Customer to the Affected System Operator as well as the payment of refunds by the Affected System Operator.

11.4.3 Notwithstanding any other provision of this GIA, nothing herein shall be construed as relinquishing or foreclosing any rights, including but not limited to firm transmission rights, capacity rights, transmission congestion rights, or transmission credits, that Interconnection Customer, shall be entitled to, now or in the future under any other agreement or tariff as a result of, or otherwise associated with, the transmission capacity, if any, created by the Network Upgrades, including the right to obtain cash reimbursement or transmission credits for transmission service that is not associated with the Generating Facility.

11.5 Initial Payment. For upgrades that the Transmission Owner has elected to self-fund, the Interconnection Customer is responsible for making the initial payment for the total cost of Network Upgrades (excluding JTIQ Upgrades) or Transmission Owner's System Protection Facilities in the form of security pursuant to Article 11.6. For upgrades where the Transmission Owner did not elect to self-fund, the Interconnection Customer shall elect (and provide its election to the Transmission Provider within five days of the commencement of negotiation of the GIA pursuant to Section 11.2 of the GIP) to make either 1) an initial payment equal to twenty (20) percent of the total cost of Network Upgrades (excluding JTIQ Upgrades), Transmission Owner Interconnection Facilities, Transmission Owner's System Protection Facilities, Distribution Upgrades and/or Generator Upgrades (if the In-Service Date is less than or equal to five (5) years of the initial payment date); or 2) an initial payment equal to ten (10) percent of the total cost of Network Upgrades (excluding JTIQ Upgrades), Transmission Owner Interconnection Facilities, Transmission Owner's System Protection Facilities, Distribution Upgrades

and/or Generator Upgrades (if the In-Service Date exceeds the initial payment date by more than five (5) years); or 3) the total cost of Network Upgrades (excluding JTIQ Upgrades), Transmission Owner Interconnection Facilities, Transmission Owner's System Protection Facilities, Distribution Upgrades and/or Generator Upgrades in the form of security pursuant to Article 11.6. The initial payment shall be provided to Transmission Owner by Interconnection Customer pursuant to this Article 11.5 within the later of a) forty-five (45) Calendar Days of the execution of the GIA by all Parties, or b) forty-five (45) Calendar Days of acceptance by FERC if the GIA is filed unexecuted and the payment is being protested by Interconnection Customer, or c) forty-five (45) Calendar Days of the filing if the GIA is filed unexecuted and the initial payment is not being protested by Interconnection Customer. If the Interconnection Customer made its milestone payments in the form of cash and the Interconnection Customer elects a cash initial payment, then the Transmission Provider shall transfer those funds to the Transmission Owner on the Interconnection Customer's behalf.

11.6 Provision of Security. Unless a milestone cash payment schedule is provided in Appendix B, Interconnection Customer shall, at least forty-five (45) Calendar Days prior to the commencement of the design, procurement, installation, or construction of a discrete portion of a facility, not otherwise funded under Article 11.5, provide additional security. Additionally, the Interconnection Customer will be required to provide security more than forty-five (45) Calendar Days in advance if requested by Transmission Owner because regulatory approvals are required for the construction of such facilities. Interconnection Customer shall provide Transmission Owner, at Interconnection Customer's selection, a guarantee, a surety bond, letter of credit or other form of security that is reasonably acceptable to Transmission Owner and is consistent with the Uniform Commercial Code of the jurisdiction identified in Article 14.2.1. Such security for payment, as specified in Appendix B of this GIA, shall be in an amount sufficient to cover the applicable costs and cost commitments, in addition to those funded under Article 11.5, required of the Party responsible for building the facilities pursuant to the construction schedule developed in Appendix B for designing, engineering, seeking regulatory approval from any Governmental Authority, constructing, procuring and installing the applicable portion of the Transmission Owner's Interconnection Facilities, Transmission Owner's System Protection Facilities, Network Upgrades, Distribution Upgrades or Stand-Alone Network Upgrades and shall be reduced on a dollar-for-dollar basis for payments made to Transmission Owner for these purposes. Transmission Owner must use the milestone payments required under the GIP before requiring Interconnection Customer to submit additional security. Transmission Owner must specify, in Appendix B of this GIA, the dates for which Interconnection Customer must provide additional security for construction of each discrete portion of Transmission Owner's Interconnection Facilities, Network Upgrades, or Distribution Upgrades and Interconnection Customer must provide such additional security.

In addition:

11.6.1 The guarantee must be made by an entity that meets the creditworthiness requirements of Transmission Owner, and contain terms and conditions that

guarantee payment of any amount that may be due from Interconnection Customer, up to an agreed-to maximum amount.

11.6.2 The letter of credit must be issued by a financial institution reasonably acceptable to Transmission Owner and must specify a reasonable expiration date.

11.6.3 The surety bond must be issued by an insurer reasonably acceptable to Transmission Owner and must specify a reasonable expiration date.

11.6.4 If the Shared Network Upgrade is not in service, Interconnection Customer will not be required to make a payment under Schedule 26-B until the Shared Network Upgrade is in service, but Interconnection Customer will provide, as applicable, an Irrevocable Letter of Credit to fund any Shared Network Upgrade pursuant to Attachment FF of the Tariff. The Irrevocable Letter of Credit shall be in an amount sufficient to cover the Interconnection Customer's share of the applicable costs and cost commitments associated with the Shared Network Upgrades. Transmission Provider may periodically adjust the Interconnection Customer's share of the applicable costs and cost commitment of Shared Network Upgrades and may require Interconnection Customer to adjust the amount of the Irrevocable Letter of Credit accordingly.

11.7 Interconnection Customer Compensation. If Transmission Provider requests or directs Interconnection Customer to provide a service pursuant to Article 13.4 of this GIA, Transmission Provider shall compensate Interconnection Customer in accordance with any tariff or rate schedule filed by Transmission Provider and approved by the FERC.

11.8 Provision of Security for JTIQ Upgrades. If the Transmission Provider determines that the Interconnection Request meets the distribution factor and impact criteria specified in Section 9.4.2(d)((ii) of Rate Schedule 6 (MISO SPP JOA) and is included in the JTIQ Participation Group, Interconnection Customer shall be required to provide security in accordance with Attachment X, Appendix 18 (MISO JTIQ Commitment Agreement) and SPP's JTIQ Service Agreement.

ARTICLE 12. INVOICE

12.1 General. Each Party shall submit to the other Party, on a monthly basis, invoices of amounts due, if any, for the preceding month. Each invoice shall state the month to which the invoice applies and fully describe the services and equipment provided. The Parties may discharge mutual debts and payment obligations due and owing to each other on the same date through netting, in which case all amounts a Party owes to the other Party under this GIA, including interest payments or credits, shall be netted so that only the net amount remaining due shall be paid by the owing Party.

12.2 Final Invoice. Within six (6) months after completion of the construction of the Transmission Owner's Interconnection Facilities, Transmission Owner's System

Protection Facilities, Distribution Upgrades and the Network Upgrades, Transmission Owner shall provide an invoice of the final cost of the construction of the Transmission Owner's Interconnection Facilities, Transmission Owner's System Protection Facilities, Distribution Upgrades and the Network Upgrades and shall set forth such costs in sufficient detail to enable Interconnection Customer to compare the actual costs with the estimates and to ascertain deviations, if any, from the cost estimates. Transmission Owner shall refund, with interest (calculated in accordance with 18 C.F.R. Section 35.19a(a)(2)(iii), to Interconnection Customer any amount by which the actual payment by Interconnection Customer for estimated costs exceeds the actual costs of construction within thirty (30) Calendar Days of the issuance of such final construction invoice.

12.3 Payment. Invoices shall be rendered to the paying Party at the address specified in Appendix F. The Party receiving the invoice shall pay the invoice within thirty (30) Calendar Days of receipt. All payments shall be made in immediately available funds payable to the other Party, or by wire transfer to a bank named and account designated by the invoicing Party. Payment of invoices by a Party will not constitute a waiver of any rights or claims that Party may have under this GIA.

12.4 Disputes. In the event of a billing dispute among the Parties, Transmission Provider shall continue to provide Interconnection Service under this GIA as long as Interconnection Customer: (i) continues to make all payments not in dispute; and (ii) pays to Transmission Provider or Transmission Owner or into an independent escrow account the portion of the invoice in dispute, pending resolution of such dispute. If Interconnection Customer fails to meet these two requirements for continuation of service, then Transmission Provider may or, at Transmission Owner's request upon Interconnection Customer's failure to pay, Transmission Owner, shall provide notice to Interconnection Customer of a Default pursuant to Article 17. Within thirty (30) Calendar Days after the resolution of the dispute, the Party that owes money to another Party shall pay the amount due with interest calculated in accord with the methodology set forth in 18 C.F.R. § 35.19a(a)(2)(iii).

ARTICLE 13. EMERGENCIES

13.1 Obligations. Each Party shall comply with the Emergency Condition procedures of Transmission Provider, the Electric Reliability Organization, and Applicable Laws and Regulations.

13.2 Notice. Transmission Provider or Transmission Owner shall notify the other Parties promptly when it becomes aware of an Emergency Condition that affects the Transmission Owner's Interconnection Facilities or the Transmission or Distribution System, as applicable, that may reasonably be expected to affect Interconnection Customer's operation of the Generating Facility or the Interconnection Customer's Interconnection Facilities.

Interconnection Customer shall notify Transmission Provider and Transmission Owner, which includes by definition if applicable, the operator of a Distribution System,

promptly when it becomes aware of an Emergency Condition that affects the Generating Facility or the Interconnection Customer's Interconnection Facilities that may reasonably be expected to affect the Transmission or Distribution System, as applicable, or the Transmission Owner's Interconnection Facilities.

To the extent information is known, the notification shall describe the Emergency Condition, the extent of the damage or deficiency, the expected effect on the operation of Interconnection Customer's or Transmission Provider's or Transmission Owner's facilities and operations, its anticipated duration and the corrective action taken and/or to be taken. The initial notice shall be followed as soon as practicable with written notice.

13.3 Immediate Action. Unless, in a Party's reasonable judgment, immediate action is required, the Party exercising such judgment shall notify and obtain the consent of the other Parties, such consent to not be unreasonably withheld, prior to performing any manual switching operations at the Generating Facility or the Interconnection Customer's Interconnection Facilities in response to an Emergency Condition either declared by Transmission Provider or otherwise regarding the Transmission or Distribution System, as applicable.

13.4 Transmission Provider and Transmission Owner Authority.

13.4.1 General. Transmission Provider or Transmission Owner may take whatever actions or inactions with regard to the Transmission System or the Transmission Owner's Interconnection Facilities it deems necessary during an Emergency Condition in order to (i) preserve public health and safety, (ii) preserve the reliability of the Transmission System or the Transmission Owner's Interconnection Facilities, (iii) limit or prevent damage, and (iv) expedite restoration of service.

Transmission Provider or Transmission Owner shall use Reasonable Efforts to minimize the effect of such actions or inactions on the Generating Facility or the Interconnection Customer's Interconnection Facilities. Transmission Provider or Transmission Owner may, on the basis of technical considerations, require the Generating Facility to mitigate an Emergency Condition by taking actions necessary and limited in scope to remedy the Emergency Condition, including, but not limited to, directing Interconnection Customer to shut-down, start-up, increase or decrease the real or reactive power output of the Generating Facility; implementing a reduction or disconnection pursuant to Article 13.4.2; directing Interconnection Customer to assist with blackstart (if available) or restoration efforts; or altering the outage schedules of the Generating Facility and the Interconnection Customer's Interconnection Facilities. Interconnection Customer shall comply with all of Transmission Provider's or Transmission Owner's operating instructions concerning Generating Facility real power and reactive power output within the manufacturer's design limitations of the Generating Facility's equipment that is in service and physically available for operation at the time, in compliance with Applicable Laws and Regulations.

13.4.2 Reduction and Disconnection. Transmission Provider or Transmission Owner may reduce Interconnection Service or disconnect the Generating Facility or the Interconnection Customer's Interconnection Facilities, when such reduction or disconnection is necessary under Good Utility Practice due to Emergency Conditions. These rights are separate and distinct from any right of curtailment of Transmission Provider pursuant to the Tariff. When Transmission Provider can schedule the reduction or disconnection in advance, Transmission Provider shall notify Interconnection Customer of the reasons, timing and expected duration of the reduction or disconnection. Transmission Provider shall coordinate with Interconnection Customer and Transmission Owner using Good Utility Practice to schedule the reduction or disconnection during periods of least impact to Interconnection Customer, Transmission Owner and Transmission Provider. Any reduction or disconnection shall continue only for so long as reasonably necessary pursuant to Good Utility Practice. The Parties shall cooperate with each other to restore the Generating Facility, the Interconnection Facilities, and the Transmission System to their normal operating state as soon as practicable consistent with Good Utility Practice.

13.5 Interconnection Customer Authority. Consistent with Good Utility Practice and this GIA and the GIP, Interconnection Customer may take whatever actions or inactions with regard to the Generating Facility or the Interconnection Customer's Interconnection Facilities during an Emergency Condition in order to (i) preserve public health and safety, (ii) preserve the reliability of the Generating Facility or the Interconnection Customer's Interconnection Facilities, (iii) limit or prevent damage, and (iv) expedite restoration of service. Interconnection Customer shall use Reasonable Efforts to minimize the effect of such actions or inactions on the Transmission System and the Transmission Owner's Interconnection Facilities. Transmission Provider and Transmission Owner shall use Reasonable Efforts to assist Interconnection Customer in such actions.

13.6 Limited Liability. Except as otherwise provided in Article 11.6 of this GIA, no Party shall be liable to any other for any action it takes in responding to an Emergency Condition so long as such action is made in good faith and is consistent with Good Utility Practice.

13.7 Audit. In accordance with Article 25.3, any Party may audit the performance of another Party when that Party declared an Emergency Condition.

ARTICLE 14. REGULATORY REQUIREMENTS AND GOVERNING LAW

14.1 Regulatory Requirements. Each Party's obligations under this GIA shall be subject to its receipt of any required approval or certificate from one or more Governmental Authorities in the form and substance satisfactory to the applying Party, or the Party making any required filings with, or providing notice to, such Governmental Authorities, and the expiration of any time period associated therewith. Each Party shall in good faith

seek, and if necessary assist the other Party and use its Reasonable Efforts to obtain such other approvals. Nothing in this GIA shall require Interconnection Customer to take any action that could result in its inability to obtain, or its loss of, status or exemption under the Federal Power Act, the Public Utility Holding Company Act of 2005, as amended, or the Public Utility Regulatory Policies Act of 1978.

14.2 Governing Law.

14.2.1 The validity, interpretation and performance of this GIA and each of its provisions shall be governed by the laws of the state where the Point of Interconnection is located, without regard to its conflicts of law principles.

14.2.2 This GIA is subject to all Applicable Laws and Regulations.

14.2.3 Each Party expressly reserves the right to seek changes in, appeal, or otherwise contest any laws, orders, rules, or regulations of a Governmental Authority.

ARTICLE 15. NOTICES

15.1 General. Unless otherwise provided in this GIA, any notice, demand or request required or permitted to be given by any Party to the other Parties and any instrument required or permitted to be tendered or delivered by a Party in writing to the other Parties shall be effective when delivered and may be so given, tendered or delivered, by recognized national courier, or by depositing the same with the United States Postal Service with postage prepaid, for delivery by certified or registered mail, addressed to the Party, or personally delivered to the Party, at the address set out in Appendix F, Addresses for Delivery of Notices and Billings.

Either Party may change the notice information in this GIA by giving five (5) Business Days written notice prior to the effective date of the change.

15.2 Billings and Payments. Billings and payments shall be sent to the addresses set out in Appendix F.

15.3 Alternative Forms of Notice. Any notice or request required or permitted to be given by any Party to the other and not required by this GIA to be given in writing may be so given by telephone, facsimile or email to the telephone numbers and email addresses set out in Appendix F.

15.4 Operations and Maintenance Notice. Each Party shall notify the other Parties in writing of the identity of the person(s) that it designates as the point(s) of contact with respect to the implementation of Articles 9 and 10.

ARTICLE 16. FORCE MAJEURE

16.1 Force Majeure.

16.1.1 Economic hardship is not considered a Force Majeure event.

16.1.2 A Party shall not be considered to be in Default with respect to any obligation hereunder, (including obligations under Article 4 and 5), other than the obligation to pay money when due, if prevented from fulfilling such obligation by Force Majeure. A Party unable to fulfill any obligation hereunder (other than an obligation to pay money when due) by reason of Force Majeure shall give notice and the full particulars of such Force Majeure to the other Parties in writing or by telephone as soon as reasonably possible after the occurrence of the cause relied upon. Telephone, facsimile or email notices given pursuant to this Article shall be confirmed in writing as soon as reasonably possible and shall specifically state full particulars of the Force Majeure, the time and date when the Force Majeure occurred and when the Force Majeure is reasonably expected to cease. The Party affected shall exercise Reasonable Efforts to remove such disability with reasonable dispatch, but shall not be required to accede or agree to any provision not satisfactory to it in order to settle and terminate a strike or other labor disturbance.

ARTICLE 17. DEFAULT

17.1 Default

17.1.1 General. No Default shall exist where such failure to discharge an obligation (other than the payment of money) is the result of Force Majeure as defined in this GIA or the result of an act or omission of another Party. Upon a Breach, the non-Breaching Party or Parties shall give written notice of such Breach to the Breaching Party with a copy to the other Party if one Party gives notice of such Breach. Except as provided in Article 17.1.2, the Breaching Party shall have thirty (30) Calendar Days from receipt of the Breach notice within which to cure such Breach; provided however, if such Breach is not capable of cure within thirty (30) Calendar Days, the Breaching Party shall commence such cure within thirty (30) Calendar Days after notice and continuously and diligently complete such cure within ninety (90) Calendar Days from receipt of the Breach notice; and, if cured within such time, the Breach specified in such notice shall cease to exist.

17.1.2 Termination. If a Breach is not cured as provided in this Article, or if a Breach is not capable of being cured within the period provided for herein, the non-Breaching Party or Parties shall terminate this GIA, subject to Article 2.3.2 of this GIA, by written notice to the Breaching Party, with a copy to the other Party if one Party gives notice of termination, and be relieved of any further obligation hereunder and, whether or not that Party(ies) terminates this GIA, to recover from the Breaching Party all amounts due hereunder, plus all other damages and remedies to which it is (they are) entitled at law or in equity. The provisions of this Article will survive termination of this GIA.

17.1.3 Cross-Default. Pursuant to Article 11.3 of this GIA, the Parties shall enter into a Facilities Service Agreement if the Transmission Owner has elected to fund the capital for the Network Upgrades and/or Transmission Owner's System Protection Facilities. Notwithstanding anything to the contrary contained in this GIA, a breach by Interconnection Customer of any provision, covenant, or other term or condition contained in the Facilities Service Agreement shall be considered a breach under this GIA. Such breach shall be subject to the terms of Article 17 of this GIA. If a default under this GIA results from the Interconnection Customer's breach of the Facilities Service Agreement and subsequent failure to cure, the Transmission Owner and Transmission Provider shall be entitled, but in no event required, to apply all rights and remedies available by reason of default under the Facilities Service Agreement and this GIA.

Pursuant to Section 11.3 of the GIP, an Interconnection Customer included in a JTIQ Participation Group shall execute or request the unexecuted filing both of the Transmission Provider's JTIQ Commitment Agreement and the JTIQ Service Agreement included in SPP's tariff. Notwithstanding anything to the contrary contained in this GIA, a breach by Interconnection Customer of any provision, covenant, or other term or condition contained in the JTIQ Commitment Agreement or SPP's JTIQ Service Agreement shall be considered a breach under this GIA. Such breach shall be subject to the terms of Article 17 of this GIA provided, however, that the manner and timing of cure of such breach shall adhere to the requirements of the applicable agreement and cure in accordance with the provisions of such agreement shall also cure the breach of this GI. If a default under this GIA results from the Interconnection Customer's breach of the JTIQ Commitment Agreement or SPP JTIQ Service Agreement and subsequent failure to cure, the Transmission Owner and Transmission Provider shall be entitled, but in no event required, to apply all rights and remedies available by reason of default under the JTIQ Commitment Agreement, SPP JTIQ Service Agreement, and this GIA.

17.2 Violation of Operating Assumptions for Generating Facilities. If Transmission Provider requires Interconnection Customer to memorialize the operating assumptions for the charging behavior of the Generating Facility that includes at least one electric storage resource in Appendix A of this GIA, Transmission Provider may consider Interconnection Customer to be in Breach of the GIA if Interconnection Customer fails to operate the Generating Facility in accordance with those operating assumptions for charging behavior. However, if Interconnection Customer operates contrary to the operating assumptions for charging behavior specified in Appendix A of this GIA at the direction of Transmission Provider, Transmission Provider shall not consider Interconnection Customer in Breach of this GIA.

ARTICLE 18. LIMITATION OF LIABILITY, INDEMNITY, CONSEQUENTIAL DAMAGES AND INSURANCE

18.1 Limitation of Liability. A Party shall not be liable to another Party or to any third party or other person for any damages arising out of actions under this GIA, including, but not limited to, any act or omission that results in an interruption, deficiency or imperfection of Interconnection Service, except as provided in this Tariff. The provisions set forth in the Tariff shall be additionally applicable to any Party acting in good faith to implement or comply with its obligations under this GIA, regardless of whether the obligation is preceded by a specific directive.

18.2 Indemnity. To the extent permitted by law, an Indemnifying Party shall at all times indemnify, defend and hold the other Parties harmless from Loss.

18.2.1 Indemnified Party. If an Indemnified Party is entitled to indemnification under this Article 18 as a result of a claim by a non-Party, and the Indemnifying Party fails, after notice and reasonable opportunity to proceed under Article 18.2, to assume the defense of such claim, such Indemnified Party may at the expense of the Indemnifying Party contest, settle or consent to the entry of any judgment with respect to, or pay in full, such claim.

18.2.2 Indemnifying Party. If an Indemnifying Party is obligated to indemnify and hold any Indemnified Party harmless under this Article 18, the amount owing to the Indemnified Party shall be the amount of such Indemnified Party's actual Loss, net of any insurance or other recovery.

18.2.3 Indemnity Procedures. Promptly after receipt by an Indemnified Party of any claim or notice of the commencement of any action or administrative or legal proceeding or investigation as to which the indemnity provided for in Article 18.2 may apply, the Indemnified Party shall notify the Indemnifying Party of such fact. Any failure of or delay in such notification shall not affect a Party's indemnification obligation unless such failure or delay is materially prejudicial to the Indemnifying Party.

The Indemnifying Party shall have the right to assume the defense thereof with counsel designated by such Indemnifying Party and reasonably satisfactory to the Indemnified Party. If the defendants in any such action include one or more Indemnified Parties and the Indemnifying Party and if the Indemnified Party reasonably concludes that there may be legal defenses available to it and/or other Indemnified Parties which are different from or additional to those available to the Indemnifying Party, the Indemnified Party shall have the right to select separate counsel to assert such legal defenses and to otherwise participate in the defense of such action on its own behalf. In such instances, the Indemnifying Party shall only be required to pay the fees and expenses of one additional attorney to represent an Indemnified Party or Indemnified Parties having such differing or additional legal defenses.

The Indemnified Party shall be entitled, at its expense, to participate in any such

action, suit or proceeding, the defense of which has been assumed by the Indemnifying Party. Notwithstanding the foregoing, the Indemnifying Party (i) shall not be entitled to assume and control the defense of any such action, suit or proceedings if and to the extent that, in the opinion of the Indemnified Party and its counsel, such action, suit or proceeding involves the potential imposition of criminal liability on the Indemnified Party, or there exists a conflict or adversity of interest between the Indemnified Party and the Indemnifying Party, in such event the Indemnifying Party shall pay the reasonable expenses of the Indemnified Party, and (ii) shall not settle or consent to the entry of any judgment in any action, suit or proceeding without the consent of the Indemnified Party, which shall not be reasonably withheld, conditioned or delayed.

18.3 Consequential Damages. Other than the Liquidated Damages heretofore described, in no event shall either Party be liable under any provision of this GIA for any losses, damages, costs or expenses for any special, indirect, incidental, consequential, or punitive damages, including but not limited to loss of profit or revenue, loss of the use of equipment, cost of capital, cost of temporary equipment or services, whether based in whole or in part in contract, in tort, including negligence, strict liability, or any other theory of liability; provided; however, that damages for which a Party may be liable to the other Party under another agreement will not be considered to be special, indirect, incidental, or consequential damages hereunder.

18.4 Insurance. Transmission Owner and Interconnection Customer shall, at their own expense, maintain in force throughout the period of this GIA pursuant to 18.4.9, and until released by the other Party, the following minimum insurance coverages, with insurers authorized to do business or an approved surplus lines carrier in the state where the Point of Interconnection is located:

18.4.1 Employers' Liability and Workers' Compensation Insurance providing statutory benefits in accordance with the laws and regulations of the state in which the Point of Interconnection is located.

18.4.2 Commercial General Liability Insurance including premises and operations, personal injury, broad form property damage, broad form blanket contractual liability coverage (including coverage for the contractual indemnification) products and completed operations coverage, coverage for explosion, collapse and underground hazards, independent contractors coverage, coverage for pollution to the extent normally available and punitive damages to the extent normally available and a cross liability endorsement, with minimum limits of One Million Dollars ($1,000,000) per occurrence/One Million Dollars ($1,000,000) aggregate combined single limit for personal injury, bodily injury, including death and property damage.

18.4.3 Comprehensive Automobile Liability Insurance, for coverage of owned and non-owned and hired vehicles, trailers or semi-trailers licensed for travel on

public roads, with a minimum combined single limit of One Million Dollars ($1,000,000) each occurrence for bodily injury, including death, and property damage.

18.4.4 Excess Public Liability Insurance over and above the Employer's Liability, Commercial General Liability and Comprehensive Automobile Liability Insurance coverage, with a minimum combined single limit of Twenty Million Dollars ($20,000,000) per occurrence/Twenty Million Dollars ($20,000,000) aggregate.

18.4.5 The Commercial General Liability Insurance, Comprehensive Automobile Insurance and Excess Public Liability Insurance policies shall name the other Parties, their parents, associated and Affiliate companies and their respective directors, officers, agents, servants and employees ("Other Party Group") as additional insured. All policies shall contain provisions whereby the insurers waive all rights of subrogation in accordance with the provisions of this GIA against the Other Party Groups and provide thirty (30) Calendar Days' advance written notice to the Other Party Groups prior to anniversary date of cancellation or any material change in coverage or condition.

18.4.6 The Commercial General Liability Insurance, Comprehensive Automobile Liability Insurance and Excess Public Liability Insurance policies shall contain provisions that specify that the policies are primary and shall apply to such extent without consideration for other policies separately carried and shall state that each insured is provided coverage as though a separate policy had been issued to each, except the insurer's liability shall not be increased beyond the amount for which the insurer would have been liable had only one insured been covered. Each Party shall be responsible for its respective deductibles or retentions.

18.4.7 The Commercial General Liability Insurance, Comprehensive Automobile Liability Insurance and Excess Public Liability Insurance policies, if written on a Claims First Made Basis, shall be maintained in full force and effect for two (2) years after termination of this GIA, which coverage may be in the form of tail coverage or extended reporting period coverage if agreed by Transmission Owner and Interconnection Customer.

18.4.8 The requirements contained herein as to the types and limits of all insurance to be maintained by Transmission Owner and Interconnection Customer are not intended to and shall not in any manner, limit or qualify the liabilities and obligations assumed by Transmission Owner and Interconnection Customer under this GIA.

18.4.9 As of the date set forth in Appendix B, Milestones, and as soon as practicable after the end of each fiscal year or at the renewal of the insurance policy and in any event within ninety (90) Calendar Days thereafter, Interconnection

Customer and Transmission Owner shall provide the other Party with certification of all insurance required in this GIA, executed by each insurer or by an authorized representative of each insurer.

18.4.10 Notwithstanding the foregoing, Transmission Owner or Interconnection Customer may self-insure to meet the minimum insurance requirements of Articles 18.4.1 through 18.4.8, to the extent it maintains a self-insurance program; provided that, Transmission Owner's or Interconnection Customer's senior secured debt is rated at investment grade, or better, by Standard & Poor's and that its self-insurance program meets minimum insurance requirements under Articles 18.4.1 through 18.4.8. For any period of time that a Transmission Owner's or Interconnection Customer's senior secured debt is unrated by Standard & Poor's or is rated at less than investment grade by Standard & Poor's, such Party shall comply with the insurance requirements applicable to it under Articles 18.4.1 through 18.4.9. In the event that Transmission Owner or Interconnection Customer is permitted to self-insure pursuant to this article, it shall notify the other Party that it meets the requirements to self-insure and that its self-insurance program meets the minimum insurance requirements in a manner consistent with that specified in Article 18.4.9.

18.4.11 Transmission Owner and Interconnection Customer agree to report to each other in writing as soon as practical all accidents or occurrences resulting in injuries to any person, including death, and any property damage arising out of this GIA.

ARTICLE 19. ASSIGNMENT

19.1 Assignment. This GIA may be assigned by any Party only with the written consent of the other Parties; provided that a Party may assign this GIA without the consent of the other Parties to any Affiliate of the assigning Party with an equal or greater credit rating and with the legal authority and operational ability to satisfy the obligations of the assigning Party under this GIA; and provided further that Interconnection Customer shall have the right to assign this GIA, without the consent of either Transmission Provider or Transmission Owner, for collateral security purposes to aid in providing financing for the Generating Facility, provided that Interconnection Customer will promptly notify Transmission Provider of any such assignment. Any financing arrangement entered into by Interconnection Customer pursuant to this Article will provide that prior to or upon the exercise of the secured party's, trustee's or mortgagee's assignment rights pursuant to said arrangement, the secured creditor, the trustee or mortgagee will notify Transmission Provider of the date and particulars of any such exercise of assignment right(s), including providing Transmission Provider and Transmission Owner with proof that it meets the requirements of Article 11.5 and 18.4. Any attempted assignment that violates this Article is void and ineffective. Any assignment under this GIA shall not relieve a Party of its obligations, nor shall a Party's obligations be enlarged, in whole or in part, by reason thereof. Where required, consent to assignment will not be unreasonably withheld, conditioned or delayed.

ARTICLE 20. SEVERABILITY

20.1 Severability. If any provision in this GIA is finally determined to be invalid, void or unenforceable by any court or other Governmental Authority having jurisdiction, such determination shall not invalidate, void or make unenforceable any other provision, agreement or covenant of this GIA; provided that if Interconnection Customer (or any non-Party, but only if such non-Party is not acting at the direction of either Transmission Provider or Transmission Owner) seeks and obtains such a final determination with respect to any provision of the Alternate Option (Article 5.1.2), or the Negotiated Option (Article 5.1.4), then none of these provisions shall thereafter have any force or effect and the Parties' rights and obligations shall be governed solely by the Standard Option (Article 5.1.1).

ARTICLE 21. COMPARABILITY

21.1 Comparability. The Parties will comply with all applicable comparability and code of conduct laws, rules and regulations including such laws, rules and regulations of Governmental Authorities establishing standards of conduct, as amended from time to time.

ARTICLE 22. CONFIDENTIALITY

22.1 Confidentiality. Confidential Information shall include, without limitation, all information relating to a Party's technology, research and development, business affairs, and pricing, and any information supplied by a Party to another Party prior to the execution of this GIA.

Information is Confidential Information only if it is clearly designated or marked in writing as confidential on the face of the document, or, if the information is conveyed orally or by inspection, if the Party providing the information orally informs the Party receiving the information that the information is confidential. The Parties shall maintain as confidential any information that is provided and identified by a Party as Critical Energy Infrastructure Information (CEII), as that term is defined in 18 C.F.R. Section 388.113(c). Such confidentiality will be maintained in accordance with this Article 22.

If requested by the receiving Party, the disclosing Party shall provide in writing, the basis for asserting that the information referred to in this Article warrants confidential treatment, and the requesting Party may disclose such writing to the appropriate Governmental Authority. Each Party shall be responsible for the costs associated with affording confidential treatment to its information.

22.1.1 Term**.** During the term of this GIA, and for a period of three (3) years after the expiration or termination of this GIA, except as otherwise provided in this Article 22 or with regard to CEII, each Party shall hold in confidence and shall

not disclose to any person Confidential Information. CEII shall be treated in accordance with Commission policy and regulations.

22.1.2 Scope. Confidential Information shall not include information that the receiving Party can demonstrate: (1) is generally available to the public other than as a result of a disclosure by the receiving Party; (2) was in the lawful possession of the receiving Party on a non-confidential basis before receiving it from the disclosing Party; (3) was supplied to the receiving Party without restriction by a non-Party, who, to the knowledge of the receiving Party after due inquiry, was under no obligation to the disclosing Party to keep such information confidential; (4) was independently developed by the receiving Party without reference to Confidential Information of the disclosing Party; (5) is, or becomes, publicly known, through no wrongful act or omission of the receiving Party or Breach of this GIA; or (6) is required, in accordance with Article 22.1.7 of this GIA, Order of Disclosure, to be disclosed by any Governmental Authority or is otherwise required to be disclosed by law or subpoena, or is necessary in any legal proceeding establishing rights and obligations under this GIA. Information designated as Confidential Information will no longer be deemed confidential if the Party that designated the information as confidential notifies the receiving Party that it no longer is confidential.

22.1.3 Release of Confidential Information. No Party shall release or disclose Confidential Information to any other person, except to its Affiliates (limited by the Standards of Conduct requirements), subcontractors, employees, agents, consultants, or to non-parties who may be or are considering providing financing to or equity participation with Interconnection Customer, or to potential purchasers or assignees of Interconnection Customer, on a need-to-know basis in connection with this GIA, unless such person has first been advised of the confidentiality provisions of this Article 22 and has agreed to comply with such provisions. Notwithstanding the foregoing, a Party providing Confidential Information to any person shall remain primarily responsible for any release of Confidential Information in contravention of this Article 22.

22.1.4 Rights. Each Party retains all rights, title, and interest in the Confidential Information that it discloses to the receiving Party. The disclosure by a Party to the receiving Party of Confidential Information shall not be deemed a waiver by the disclosing Party or any other person or entity of the right to protect the Confidential Information from public disclosure.

22.1.5 No Warranties. By providing Confidential Information, no Party makes any warranties or representations as to its accuracy or completeness. In addition, by supplying Confidential Information, no Party obligates itself to provide any particular information or Confidential Information to another Party nor to enter into any further agreements or proceed with any other relationship or joint venture.

22.1.6 Standard of Care. Each Party shall use at least the same standard of care to protect Confidential Information it receives as it uses to protect its own Confidential Information from unauthorized disclosure, publication or dissemination. Each Party may use Confidential Information solely to fulfill its obligations to another Party under this GIA or its regulatory requirements.

22.1.7 Order of Disclosure. If a court or a Governmental Authority or entity with the right, power, and apparent authority to do so requests or requires any Party, by subpoena, oral deposition, interrogatories, requests for production of documents, administrative order, or otherwise, to disclose Confidential Information, that Party shall provide the disclosing Party with prompt notice of such request(s) or requirement(s) so that the disclosing Party may seek an appropriate protective order or waive compliance with the terms of this GIA. Notwithstanding the absence of a protective order or waiver, the Party may disclose such Confidential Information which, in the opinion of its counsel, the Party is legally compelled to disclose. Each Party will use Reasonable Efforts to obtain reliable assurance that confidential treatment will be accorded any Confidential Information so furnished.

22.1.8 Termination of Agreement. Upon termination of this GIA for any reason, each Party shall, within ten (10) Calendar Days of receipt of a written request from another Party, use Reasonable Efforts to destroy, erase, or delete (with such destruction, erasure, and deletion certified in writing to the requesting Party) or return to the requesting Party, without retaining copies thereof, any and all written or electronic Confidential Information received from the requesting Party, except that each Party may keep one copy for archival purposes, provided that the obligation to treat it as Confidential Information in accordance with this Article 22 shall survive such termination.

22.1.9 Remedies**.** The Parties agree that monetary damages would be inadequate to compensate a Party for another Party's Breach of its obligations under this Article 22. Each Party accordingly agrees that the disclosing Party shall be entitled to equitable relief, by way of injunction or otherwise, if the receiving Party Breaches or threatens to Breach its obligations under this Article 22, which equitable relief shall be granted without bond or proof of damages, and the Breaching Party shall not plead in defense that there would be an adequate remedy at law. Such remedy shall not be deemed an exclusive remedy for the Breach of this Article 22, but shall be in addition to all other remedies available at law or in equity. The Parties further acknowledge and agree that the covenants contained herein are necessary for the protection of legitimate business interests and are reasonable in scope. No Party, however, shall be liable for indirect, incidental, or consequential or punitive damages of any nature or kind resulting from or arising in connection with this Article 22.

22.1.10 Disclosure to FERC, its Staff or a State**.** Notwithstanding anything in this Article 22 to the contrary, and pursuant to 18 CFR § 1b.20, if FERC or its staff,

during the course of an investigation or otherwise, requests information from a Party that is otherwise required to be maintained in confidence pursuant to this GIA, the Party shall provide the requested information to FERC or its staff, within the time provided for in the request for information. In providing the information to FERC or its staff, the Party must, consistent with 18 CFR § 388.112, request that the information be treated as confidential and non-public by FERC and its staff and that the information be withheld from public disclosure. Parties are prohibited from notifying the other Parties to this GIA prior to the release of the Confidential Information to FERC or its staff. The Party shall notify the other Parties to this GIA when it is notified by FERC or its staff that a request to release Confidential Information has been received by FERC, at which time any of the Parties may respond before such information would be made public, pursuant to 18 CFR § 388.112. Requests from a state regulatory body conducting a confidential investigation shall be treated in a similar manner if consistent with the applicable state rules and regulations.

22.1.11 Subject to the exception in Article 22.1.10, any information that a disclosing Party claims is competitively sensitive, commercial or financial information under this GIA shall not be disclosed by the receiving Party to any person not employed or retained by the receiving Party, except to the extent disclosure is (i) required by law; (ii) reasonably deemed by the receiving Party to be required to be disclosed in connection with a dispute between or among the Parties, or the defense of litigation or dispute; (iii) otherwise permitted by consent of the disclosing Party, such consent not to be unreasonably withheld; or (iv) necessary to fulfill its obligations under this GIA or as the Regional Transmission Organization or a Local Balancing Authority operator including disclosing the Confidential Information to a regional or national reliability organization. The Party asserting confidentiality shall notify the receiving Party in writing of the information that Party claims is confidential. Prior to any disclosures of that Party's Confidential Information under this subparagraph, or if any non-Party or Governmental Authority makes any request or demand for any of the information described in this subparagraph, the Party who received the Confidential Information from the disclosing Party agrees to promptly notify the disclosing Party in writing and agrees to assert confidentiality and cooperate with the disclosing Party in seeking to protect the Confidential Information from public disclosure by confidentiality agreement, protective order or other reasonable measures.

ARTICLE 23. ENVIRONMENTAL RELEASES

23.1 Each Party shall notify the other Parties, first orally and then in writing, of the release of any Hazardous Substances, any asbestos or lead abatement activities, or any type of remediation activities related to the Generating Facility or the Interconnection Facilities, each of which may reasonably be expected to affect another Party. The notifying Party shall: (i) provide the notice as soon as practicable, provided such Party makes a good faith effort to provide the notice no later than twenty-four hours after such Party becomes

aware of the occurrence; and (ii) promptly furnish to the other Parties copies of any publicly available reports filed with any Governmental Authorities addressing such events.

ARTICLE 24. INFORMATION REQUIREMENTS

24.1 Information Acquisition. Transmission Provider, Transmission Owner and Interconnection Customer shall submit specific information regarding the electrical characteristics of their respective facilities to each other as described below and in accordance with Applicable Reliability Standards.

24.2 Information Submission by Transmission Provider and Transmission Owner The initial information submission by Transmission Provider to Interconnection Customer, with copy provided to Transmission Owner, shall occur no later than one hundred eighty (180) Calendar Days prior to Trial Operation and shall include Transmission or Distribution System information, as applicable and available, necessary to allow Interconnection Customer to select equipment and meet any system protection and stability requirements, unless otherwise mutually agreed to by the Parties. On a monthly basis, Transmission Owner shall provide Interconnection Customer a status report on the construction and installation of Transmission Owner's Interconnection Facilities, Transmission Owner's System Protection Facilities, Distribution Upgrades and Network Upgrades, including, but not limited to, the following information: (1) progress to date; (2) a description of the activities since the last report (3) a description of the action items for the next period; and (4) the delivery status of equipment ordered.

24.3 Updated Information Submission by Interconnection Customer. The updated information submission by Interconnection Customer to Transmission Provider, with copy to Transmission Owner, including manufacturer information, shall occur no later than one hundred eighty (180) Calendar Days prior to the Trial Operation. Interconnection Customer shall submit to Transmission Provider and Transmission Owner a completed copy of the Generating Facility data requirements contained in Appendix 1 to the GIP. It shall also include any additional information provided to Transmission Provider for the Interconnection Facilities Study. Information in this submission shall be the most current Generating Facility design or expected performance data. Information submitted for stability models shall be compatible with Transmission Provider standard models. If there is no compatible model, Interconnection Customer will work with a consultant mutually agreed to by Transmission Provider and Interconnection Customer to develop and supply a standard model and associated information.

If the Interconnection Customer's data is materially different from what was originally provided to Transmission Provider pursuant to the Interconnection Study Agreement between Transmission Provider and Interconnection Customer, then Transmission Provider will conduct appropriate studies to determine the impact on the Transmission System based on the actual data submitted pursuant to this Article 24.3. Interconnection Customer shall not begin Trial Operation until such studies are completed.

24.4 Information Supplementation. Prior to the Commercial Operation Date, the Parties shall supplement their information submissions described above in this Article 24 with any and all "as-built" Generating Facility information or "as-tested" performance information that differs from the initial submissions or, alternatively, written confirmation that no such differences exist. Interconnection Customer shall conduct tests on the Generating Facility as required by Good Utility Practice, such as an open circuit "step voltage" test on the Generating Facility to verify proper operation of the Generating Facility's automatic voltage regulator.

Unless otherwise agreed, the test conditions shall include: (1) Generating Facility at synchronous speed; (2) automatic voltage regulator on and in voltage control mode; and (3) a five percent (5 %) change in Generating Facility terminal voltage initiated by a change in the voltage regulators reference voltage. Interconnection Customer shall provide validated test recordings showing the responses in Generating Facility terminal and field voltages. In the event that direct recordings of these voltages is impractical, recordings of other voltages or currents that mirror the response of the Generating Facility's terminal or field voltage are acceptable if information necessary to translate these alternate quantities to actual Generating Facility terminal or field voltages is provided. Generating Facility testing shall be conducted and results provided to Transmission Provider and Transmission Owner for each individual generating unit in a station.

Subsequent to the Commercial Operation Date, Interconnection Customer shall provide Transmission Provider and Transmission Owner any information changes due to equipment replacement, repair, or adjustment. Transmission Owner shall provide Interconnection Customer, with copy to Transmission Provider, any information changes due to equipment replacement, repair or adjustment in the directly connected substation or any adjacent Transmission Owner substation that may affect the Interconnection Customer's Interconnection Facilities equipment ratings, protection or operating requirements. The Parties shall provide such information no later than thirty (30) Calendar Days after the date of the equipment replacement, repair or adjustment.

ARTICLE 25. INFORMATION ACCESS AND AUDIT RIGHTS

25.1 Information Access. Each Party (the "disclosing Party") shall make available to the other Parties information that is in the possession of the disclosing Party and is necessary in order for the other Parties to: (i) verify the costs incurred by the disclosing Party for which another Party is responsible under this GIA; and (ii) carry out its obligations and responsibilities under this GIA. The Parties shall not use such information for purposes other than those set forth in this Article 25.1 and to enforce their rights under this GIA.

25.2 Reporting of Non-Force Majeure Events. A Party (the "notifying Party") shall notify the other Parties when the notifying Party becomes aware of its inability to comply with the provisions of this GIA for a reason other than a Force Majeure event. The Parties agree to cooperate with each other and provide necessary information regarding such

inability to comply, including the date, duration, reason for the inability to comply, and corrective actions taken or planned to be taken with respect to such inability to comply. Notwithstanding the foregoing, notification, cooperation or information provided under this Article shall not entitle any Party receiving such notification to allege a cause for anticipatory breach of this GIA.

25.3 Audit Rights. Subject to the requirements of confidentiality under Article 22 of this GIA, each Party shall have the right, during normal business hours, and upon prior reasonable notice to the other Parties, to audit at its own expense the other Parties' accounts and records pertaining to the Parties' performance or the Parties' satisfaction of obligations under this GIA. Such audit rights shall include audits of the other Parties' costs, calculation of invoiced amounts, the Transmission Provider's efforts to allocate responsibility for the provision of reactive support to the Transmission or Distribution System, as applicable, the Transmission Provider's efforts to allocate responsibility for interruption or reduction of generation, and each Party's actions in an Emergency Condition. Any audit authorized by this Article shall be performed at the offices where such accounts and records are maintained and shall be limited to those portions of such accounts and records that relate to each Party's performance and satisfaction of obligations under this GIA. Each Party shall keep such accounts and records for a period equivalent to the audit rights periods described in Article 25.4.

25.4 Audit Rights Periods.

25.4.1 Audit Rights Period for Construction-Related Accounts and Records. Accounts and records related to the design, engineering, procurement, and construction of the Transmission Owner's Interconnection Facilities, Transmission Owner's System Protection Facilities, Distribution Upgrades and Network Upgrades shall be subject to audit for a period of twenty-four months following Transmission Owner's issuance of a final invoice in accordance with Article 12.2.

25.4.2 Audit Rights Period for All Other Accounts and Records. Accounts and records related to a Party's performance or satisfaction of all obligations under this GIA other than those described in Article 25.4.1 shall be subject to audit as follows: (i) for an audit relating to cost obligations, the applicable audit rights period shall be twenty-four (24) months after the auditing Party's receipt of an invoice giving rise to such cost obligations; and (ii) for an audit relating to all other obligations, the applicable audit rights period shall be twenty-four (24) months after the event for which the audit is sought.

25.5 Audit Results. If an audit by a Party determines that an overpayment or an underpayment has occurred, a notice of such overpayment or underpayment shall be given to the Party or from whom the overpayment or underpayment is owed together with those records from the audit which support such determination.

ARTICLE 26. SUBCONTRACTORS

26.1 General. Nothing in this GIA shall prevent a Party from utilizing the services of any subcontractor as it deems appropriate to perform its obligations under this GIA; provided, however, that each Party shall require its subcontractors to comply with all applicable terms and conditions of this GIA in providing such services and each Party shall remain primarily liable to the other Parties for the performance of such subcontractor.

26.2 Responsibility of Principal. The creation of any subcontract relationship shall not relieve the hiring Party of any of its obligations under this GIA. The hiring Party shall be fully responsible to the other Parties for the acts or omissions of any subcontractor the hiring Party hires as if no subcontract had been made; provided, however, that in no event shall Transmission Provider or Transmission Owner be liable for the actions or inactions of Interconnection Customer or its subcontractors with respect to obligations of Interconnection Customer under Article 5 of this GIA. Any applicable obligation imposed by this GIA upon the hiring Party shall be equally binding upon, and shall be construed as having application to, any subcontractor of such Party.

26.3 No Limitation by Insurance. The obligations under this Article 26 will not be limited in any way by any limitation of subcontractor's insurance.

ARTICLE 27. DISPUTES

27.1 Submission. In the event any Party has a dispute, or asserts a claim, that arises out of or in connection with this GIA or its performance, such Party (the "disputing Party") shall provide the other Parties with written notice of the dispute or claim ("Notice of Dispute"). Such dispute or claim shall be referred to a designated senior representative of each Party for resolution on an informal basis as promptly as practicable after receipt of the Notice of Dispute by the non-disputing Parties. In the event the designated representatives are unable to resolve the claim or dispute through unassisted or assisted negotiations within thirty (30) Calendar Days of the non-disputing Parties' receipt of the Notice of Dispute, such claim or dispute shall be submitted for resolution in accordance with the dispute resolution procedures of the Tariff.

ARTICLE 28. REPRESENTATIONS, WARRANTIES AND COVENANTS

28.1 General. Each Party makes the following representations, warranties and covenants:

28.1.1 Good Standing. Such Party is duly organized, validly existing and in good standing under the laws of the state in which it is organized, formed, or incorporated, as applicable; that it is qualified to do business in the state or states in which the Generating Facility, Interconnection Facilities and Network Upgrades owned by such Party, as applicable, are located; and that it has the corporate power and authority to own its properties, to carry on its business as now being conducted and to enter into this GIA and carry out the transactions

contemplated hereby and perform and carry out all covenants and obligations on its part to be performed under and pursuant to this GIA.

28.1.2 Authority**.** Such Party has the right, power and authority to enter into this GIA, to become a Party hereto and to perform its obligations hereunder. This GIA is a legal, valid and binding obligation of such Party, enforceable against such Party in accordance with its terms, except as the enforceability thereof may be limited by applicable bankruptcy, insolvency, reorganization or other similar laws affecting creditors' rights generally and by general equitable principles (regardless of whether enforceability is sought in a proceeding in equity or at law).

28.1.3 No Conflict. The execution, delivery and performance of this GIA does not violate or conflict with the organizational or formation documents, or bylaws or operating agreement, of such Party, or any judgment, license, permit, order, material agreement or instrument applicable to or binding upon such Party or any of its assets.

28.1.4 Consent and Approval. Such Party has sought or obtained, or, in accordance with this GIA will seek or obtain, each consent, approval, authorization, order, or acceptance by any Governmental Authority in connection with the execution, delivery and performance of this GIA, and it will provide to any Governmental Authority notice of any actions under this GIA that are required by Applicable Laws and Regulations.

ARTICLE 29. {RESERVED}

ARTICLE 30. MISCELLANEOUS

30.1 Binding Effect. This GIA and the rights and obligations hereof, shall be binding upon and shall inure to the benefit of the successors and assigns of the Parties hereto.

30.1.1 Reversion. If offered pursuant to an Agency Agreement under which this GIA is executed by Transmission Provider as agent for the relevant Transmission Owner, in the event that the relevant Agency Agreement terminates, any HVDC Service offered by Transmission Provider under this GIA shall revert to the relevant Transmission Owner and Transmission Provider shall be released from all obligations and responsibilities under this GIA.

30.2 Conflicts. In the event of a conflict between the body of this GIA and any attachment, appendices or exhibits hereto, the terms and provisions of the body of this GIA shall prevail and be deemed the final intent of the Parties.

30.3 Rules of Interpretation. This GIA, unless a clear contrary intention appears, shall be construed and interpreted as follows: (1) the singular number includes the plural number and vice versa; (2) reference to any person includes such person's successors and assigns

but, in the case of a Party, only if such successors and assigns are permitted by this GIA, and reference to a person in a particular capacity excludes such person in any other capacity or individually; (3) reference to any agreement (including this GIA), document, instrument or tariff means such agreement, document, instrument, or tariff as amended or modified and in effect from time to time in accordance with the terms thereof and, if applicable, the terms hereof; (4) reference to any Applicable Laws and Regulations means such Applicable Laws and Regulations as amended, modified, codified, or reenacted, in whole or in part, and in effect from time to time, including, if applicable, rules and regulations promulgated thereunder; (5) unless expressly stated otherwise, reference to any Article, Section or Appendix means such Article of this GIA or such Appendix to this GIA, or such Section to the GIP or such Appendix to the GIP, as the case may be; (6) "hereunder", "hereof", "herein", "hereto" and words of similar import shall be deemed references to this GIA as a whole and not to any particular Article or other provision hereof or thereof; (7) "including" (and with correlative meaning "include") means including without limiting the generality of any description preceding such term; and (8) relative to the determination of any period of time, "from" means "from and including", "to" means "to but excluding" and "through" means "through and including."

30.4 Entire Agreement. This GIA, including all Appendices and attachments hereto, constitutes the entire agreement between the Parties with reference to the subject matter hereof, and supersedes all prior and contemporaneous understandings or agreements, oral or written, between the Parties with respect to the subject matter of this GIA. There are no other agreements, representations, warranties, or covenants, which constitute any part of the consideration for, or any condition to, any Party's compliance with its obligations under this GIA.

30.5 No Third Party Beneficiaries. This GIA is not intended to and does not create rights, remedies, or benefits of any character whatsoever in favor of any persons, corporations, associations, or entities other than the Parties, and the obligations herein assumed are solely for the use and benefit of the Parties, their successors in interest and, where permitted, their assigns.

30.6 Waiver. The failure of a Party to this GIA to insist, on any occasion, upon strict performance of any provision of this GIA will not be considered a waiver of any obligation, right, or duty of, or imposed upon, such Party.

Any waiver at any time by any Party of its rights with respect to this GIA shall not be deemed a continuing waiver or a waiver with respect to any other failure to comply with any other obligation, right, duty of this GIA. Termination or Default of this GIA for any reason by Interconnection Customer shall not constitute a waiver of the Interconnection Customer's legal rights to obtain Interconnection Service from Transmission Provider. Any waiver of this GIA shall, if requested, be provided in writing.

30.7 Headings. The descriptive headings of the various Articles of this GIA have been inserted for convenience of reference only and are of no significance in the interpretation

or construction of this GIA.

30.8 Multiple Counterparts. This GIA may be executed in two or more counterparts, each of which is deemed an original but all constitute one and the same instrument.

30.9 Amendment. The Parties may by mutual agreement amend this GIA by a written instrument duly executed by all of the Parties.

30.10 Modification by the Parties. The Parties may by mutual agreement amend the Appendices to this GIA by a written instrument duly executed by all of the Parties. Such amendment shall become effective and a part of this GIA upon satisfaction of all Applicable Laws and Regulations.

30.11 Reservation of Rights. Transmission Provider shall have the right to make a unilateral filing with FERC to modify this GIA with respect to any rates, terms and conditions, charges, classifications of service, rule or regulation under Section 205 or any other applicable provision of the Federal Power Act and FERC's rules and regulations thereunder, and Transmission Owner and Interconnection Customer shall have the right to make a unilateral filing with FERC to modify this GIA pursuant to Section 206 or any other applicable provision of the Federal Power Act and FERC's rules and regulations thereunder; provided that each Party shall have the right to protest any such filing and to participate fully in any proceeding before FERC in which such modifications may be considered. Nothing in this GIA shall limit the rights of the Parties or of FERC under Sections 205 or 206 of the Federal Power Act and FERC's rules and regulations thereunder, except to the extent that the Parties otherwise mutually agree as provided herein.

30.12 No Partnership. This GIA shall not be interpreted or construed to create an association, joint venture, agency relationship, or partnership among or between the Parties or to impose any partnership obligation or partnership liability upon any Party. No Party shall have any right, power or authority to enter into any agreement or undertaking for, or act on behalf of, or to act as or be an agent or representative of, or to otherwise bind, the other Parties.

IN WITNESS WHEREOF, the Parties have executed this GIA in multiple originals; each of which shall constitute and be an original GIA among the Parties.

Transmission Provider
Midcontinent Independent System Operator, Inc.

By: _____
Name: _____
Title: _____

Transmission Owner
~~**[Insert name of Transmission Owner]**~~
Entergy Louisiana, LLC

By: _____
Name: _____
Title: _____

Interconnection Customer
~~**[Insert name of Interconnection Customer]**~~
Entergy Louisiana, LLC

By: _____
Name: _____
Title: _____

APPENDICES TO GIA

Appendix A	Interconnection Facilities, System Protection Facilities, Distribution Upgrades, Generator Upgrades and Network Upgrades
Appendix B	Milestones
Appendix B-1	Pre-Certification Generation Test Notification Form
Appendix C	Interconnection Details
Appendix D	Security Arrangements Details
Appendix E	Commercial Operation Date
Appendix F	Addresses for Delivery of Notices and Billings
Appendix G	Interconnection Requirements for Inverter-Based Resource Plants
Appendix H	Interconnection Requirements for Provisional GIA
Appendix I	Requirements Applicable to Surplus Interconnection Service

Appendix A to GIA

Interconnection Facilities, System Protection Facilities, Distribution Upgrades, Generator Upgrades and Network Upgrades

1. Description of Generating Facility

Interconnection Customer shall install a ~~[_____]~~1,928 MVA facility, rated at ~~[_____]~~1,640 MW gross and ~~[_____]~~1,536 MW net, with all studies performed at or below these outputs. The Generating Facility is composed of ~~[___]~~two (2) Mitsubishi gas turbine generation units rated at 562 MVA / 478 MW each and two (2) Mitsubishi heat recovery steam generators rated at 402 MVA / 342 MW in a ~~[*insert description* ~~combined cycle~~*, single coal-fired, wind farm, etc.*~~] rated at [_____] each. Describe the interconnection service~~ plant. Interconnection Service provided under this agreement ~~[*insert description* ~~is 1,536 MW of conditional ERIS and/or NRIS that will become 1,536 MW of NRIS upon completion of all~~ Network ~~*Resource or Energy Resource]* and level of service [ ] MW. [Insert operating~~Upgrades, Common Use Upgrades, and Affected System Upgrades under this GIA and transmission assumptions ~~that reflect the charging behavior of the Generating Facility that includes at least one electric storage resource]~~listed in Table A10-1 of Exhibit A10.

Interconnection Customer shall install a switchyard with the appropriate protection equipment coordinated per Appendix C to this GIA. The Switchyard shall contain ~~[_____]~~two (2) generator step-up ~~transformer(s), [_____]~~transformers 230/23.5 kV 360/600 MVA, two (2) generator step-up transformers 230/21 kV 252/420 MVA, four (4) 4000 A 80kA circuit breakers connected as illustrated in ~~[_____] fashion [*describe or point to a single-line diagram*].~~Exhibit A1-1.

The Generating Facility shall provide reactive compensation as necessary to meet the FERC Order 827.

2. Interconnection Facilities

(a) Point of Interconnection.

i. The Point of Interconnection (POI) shall be at the point where _____. ~~See Exhibit A1 Drawing No. _____ dated _____, which drawing is attached hereto and made a part hereof. If not located at the~~ the E0014 lead line connects to the Transmission Owner's Smalling 230kV yard substation bus.

ii. The Point of Change of Ownership (PCO) shall be at the Interconnection~~, the metering point(s) shall be located at~~ Customer's dead-end structure within the generation step-up yard.

iii. The Metering Equipment will be located on the Transmission Owner Interconnection Facilities and compensated to the Point of Interconnection. Refer to Exhibit A2 one-line diagram for the demarcation points of these facilities.

(b) Interconnection Facilities (including metering equipment) to be constructed by Interconnection Customer. Interconnection Customer shall construct ~~_____~~and ~~are detailed in Exhibit A1____~~. own the Customer Interconnection Facilities. These facilities ~~are estimated to cost $_____ and are detailed in Exhibit A1____~~.shall include:

- Two (2) approximately 0.28 mile of 230 kV generator lead lines using 954 ACSS Cardinal conductors.
- A servitude agreement will need to be executed between Interconnection Customer and Entergy for the transmission line connecting the PCO to POI, and access road(s). Actual size and final location will be determined after detail design is complete. Below is a list of the servitudes and their preliminary dimensions:
  - One PCO to POI servitude will be approximately 125 feet wide x 1800 feet long, approximately 5.15 acres and a second PCO to POI servitude will be approximately 125 feet wide x 1650 feet long, approximately 4.72 acres.
- The first underground servitude for E0014 ADSS fiber will be approximately 0.25 miles long between PCO and POI. The second underground servitude for E0014 ADSS fiber will be approximately 0.21 miles long between the PCO and POI. Total size and location will be determined after detail design is complete.
- The Interconnection Customer will provide to Transmission Owner a copy of wetland delineation for the new switching station site, access road and transmission line ROW, ESA Phase I report, and cultural resources constraint analysis/archeological survey, if required
- Interconnection Customer is responsible for coordinating and obtaining station service supply for the Interconnection Customer Interconnection Facilities and the Generating Facility. The Interconnection Customer will coordinate station supply with the local service territory provider to address normal and emergency back-up station power needs for Interconnection Customer Interconnection Facilities and for Generating Facility during construction and operation of those facilities. Net metering of Station Service power may be obtained per the requirements of Transmission Provider's Schedule 20

(c) Transmission Owner Interconnection Facilities (including metering equipment) to be constructed by Transmission Owner. ~~Transmission Owner shall construct _____and are detailed in Exhibit A1___. These facilities are estimated to cost $_____ and are detailed in Exhibit A1___~~.Transmission Owner Interconnection Facilities shall consist of the following equipment:

i. Smalling 500/230 kV Substation

General

a) Customer will transmit generator breaker status, telemetering data including MW, MVAR, MWhr and MVARhrs to Entergy's Smalling 500/230kV Substation Remote Terminal Unit (RTU) utilizing underground fiber optic cable.

b) Customer will design line protection compatible with the line relaying installed at Entergy's Smalling 500/230kV Substation.

Site

a) Installation of 5/8'' x 10' ground rods shall be installed near major equipment such as surge arresters.

Foundations

a) Drilled pier and pad foundations will be used for all equipment support structure.

b) The foundation scope of work includes design and construction of the following:

- Install twenty-nine (29) 36-inch diameter 17-foot-long drilled pier foundations for 230kV single phase, low bus support insulators.
- Install six (6) 42 inch diameter 22-foot-long drilled pier foundations for 230kV single phase, high bus support insulators.
- Install six (6) 36-inch diameter 20-foot-long drilled pier foundations for 230kV surge arrester structures.
- Install six (6) 36-inch diameter 20-foot-long drilled pier foundations for 230kV CCVT structures.
- Install two (2) set of four (4) 72-inch diameter 30-foot-long drilled pier foundations for 230kV deadend structure.

Electrical

a) Steel Structures

- Six (6) single-phase 230kV high bus support structure.
- Twenty-nine (29) single-phase 230kV low bus support structure.
- Six (6) 230kV surge arrester structures.
- Six (6) 230kV CCVT structures.
- Two (2) three-phase 230kV deadend structure.

b) 230 kV Station Post Insulators

- Forty-one (41) polymer insulators rated for nominal system voltage of 230 kV.
- Installation includes fitting accessories.

c) 230 kV Suspension Insulators

- Six (6) 230 kV polymer suspension insulators installed on the H-frame.
- Installation includes fitting accessories.

d) 230 kV Surge Arresters

- Six (6) station class surge arrester rated for nominal system voltage.

e) Conductors

- The horizontal bus will be 4" aluminum schedule 40 rigid tubular bus.
- The equipment jumpers from the horizontal bus to the string bus shall be bundled 1780 ACSR "Chukar," two conductors per phase.
- The equipment jumpers for switches to breakers shall be 1780 ACSR "Chukar," two conductors per phase.
- The equipment jumpers from the horizontal bus to the coupling capacitor voltage transformers and surge arresters shall be 1780 ACSR "Chukar," one conductor per phase.
- Include all necessary fittings.

f) Raceway & Conduit

- 2" PVC conduit with couplings, bends, adapters, liquid-tight fittings, and related hardware for CCVTs.
- All conduit at road crossings and running outside station fence will be encased in concrete.

g) Existing Control Building

- Includes installing connection of control cable wiring checkout and commissioning of the associated systems.

Relay

a) The relay protection scheme is subject to change during detailed design considering the long procurement duration.

b) Two (2) new relay panels are required for the protective relays associated with the Gen-Tie lines coming from Franklin Farms powerplant at the Smalling 500/230kV substation.

- One (1) protection panel shall include two (2) SEL-411L relays using a line current differential scheme for the new 230kV single gen-tie line from Unit#1 (CTG1-STG1) of the Franklin Farms powerplant. Entergy Standard for breaker control PM1803 OPT C5.
- One (1) protection panel shall include two (2) SEL-411L relays using a line current differential scheme for the new 230kV single gen-tie line from Unit#2 (CTG2-STG2) of the Franklin Farms powerplant. Entergy Standard for breaker control PM1803 OPT C5.
- Relay communication between terminals shall be established via fiber optic cables. Refer to the project telecommunications plan for circuit routing and connection details.
- Includes installing the panels inside the control building, de-terminating existing control cable wiring, reconnecting existing shielded control cable wiring, installing and connecting any additional control cable wiring as required, checkout and commissioning of the associated systems.

Relay Settings

a) Refer to Network Upgrade section.

Communications and SCADA

a) Refer to Network Upgrade section.

Metering

a) No metering upgrades required.

ii. Transmission Owner's 230kV Transmission Line

General

a) The transmission line scope consists of two spans of conductor located between the Franklin Farms Generation and Smalling Substation on the new single-circuit 230kV Interconnection Customer transmission line.
b) New double-bundle 954kcmil Cardinal ACSS and DNO-12776 & Alumoweld 7#7 shield wires will be installed on the interconnection span.

Structures and Foundations

a) Install (6) self-supported steel monopole dead-end structures
b) Install (2) direct embed steel monopole 0-1.5º suspension braced post structure
c) Foundation analysis to be performed during Detailed Design.

Conductor and Insulators

a) Install approximately 23,000' of 954 kcmil ACSS Cardinal (double-bundle) for main conductor
b) Install strain insulators for (6) new structures and (6) new substation terminals
c) Install braced post insulators for (2) new structures.

Shield Wire

a) Install approximately 3,000' of DNO-12776 OPGW
b) Install approximately 3,200' of Alumoweld 7#7

The estimated costs for these facilities are in year 2025 dollars, with an intended accuracy of +/- 20%, and are detailed in Exhibit A6.

3. Network Upgrades

(a) Stand-Alone Network Upgrades to be installed by _____. Transmission Owner ~~shall install _____, detailed in Exhibit A2___. These facilities are estimated to cost $_____ and are detailed in Exhibit A2___.~~ None.

(b) Network Upgrades to be installed by Transmission Owner. The Network Upgrades were developed for installing two new 562 MVA CTG and 402 MVA STG generating facility lines connected at the Transmission Owners' Smalling 500/230kV substation. Upgrades will include yard equipment upgrades, installation of relay panels and telecom upgrades at Smalling 500/230kV substation.

i. Smalling 500/230kV Substation

General

a) Customer will transmit generator breaker status, telemetering data including MW, MVAR, MWhr and MVARhrs to Transmission Owner's Smalling 500/230kV Substation Remote Terminal Unit (RTU) utilizing underground fiber optic cable.

b) Customer will design line protection compatible with the line relaying installed at the Transmission Owner's Smalling 500/230kV Substation.

Site

a) Installation of 5/8'' x 10' ground rods shall be installed near major equipment such as surge arresters.

Foundations

a) Drilled pier and pad foundations will be used for all equipment support structure.

b) The foundation scope of work includes design and construction of the following:

- Install thirty-four (34) 42 inch diameter 22-foot-long drilled pier foundations for 230kV single phase, low bus support insulators and structure.
- Install twelve (12) set of two (2) 42 inch diameter 22-foot long drilled pier foundations for 230kV low switch structures.
- Install four (4) 10'L X 10'W X 2'H slab foundations for 230kV breakers.
- Install four (4) 8'L X 6'W X 2'H slab foundations for 230kV breaker access pad.

Electrical

a) Steel Structures

- Thirty-four (34) single-phase 230kV low bus support structure.
- Eight (8) 230kV low switch structures.
- Four (4) 230kV low switch bypass structures.

b) 230 kV Station Post Insulators

- Fifty-six (56) polymer insulators rated for nominal system voltage of 230 kV.
- Installation includes fitting accessories.

c) Gas Circuit Breakers

- Four (4) 245 kV, SF6 gas circuit breakers rated 3000 A, 63 kA interrupting capability, three (3) sets of bushing CTs, designed as per Transmission Owner ~~shall install _____, detailed in Exhibit A2___. These facilities are estimated to cost $_____ and are detailed in Exhibit A2___.~~specification SD0202.

~~**(c) Shared Network Upgrade(s) to be funded by Interconnection Customer.** Alternatively, where Transmission Provider determines that Interconnection Customer benefits from one or more prior Network Upgrades or Common Use Upgrades, those Network Upgrades and/or Common Use Upgrades will be~~

~~classified by Transmission Provider as Shared Network Upgrades under this GIA, and Interconnection Customer is responsible for costs as detailed below. Interconnection Customer may later be eligible for refund and/or contribution if subsequent Interconnection Customers are identified as also benefitting from the Shared Network Upgrade(s). Interconnection Customer shall fund those Shared Network Upgrade(s) detailed in Exhibit A5. Interconnection Customer's cost share of the Share Network Upgrade(s) is estimated at $_____, as detailed in Exhibit A5. Interconnection Customer's cost share of the Shared Network Upgrade(s) may be reduced if later interconnection projects are determined to also benefit from the Shared Network Upgrade(s). Interconnection Customer's cost share of the Shared Network Upgrade(s) may also increase from this estimate where other projects are determined to adversely impact Interconnection Customer's cost share of the Shared Network Upgrade(s).i) If a Shared Network Upgrade is not yet in service as of the date of execution of this GIA, if applicable, Interconnection Customer shall post an Irrevocable Letter of Credit in the amount of its estimated proportionate share of the estimated cost of that Shared Network Upgrade in accordance with Article 11.6.4 as of the date set forth in Appendix B to this GIA.~~

- Includes installing control conduit to the circuit breakers, jumpers to the associated disconnect switches, and control cable to the control building.

d) 230 kV Disconnect Switches
- Six (6) three-phase vertical break disconnect switch is required to allow isolation of the circuit breaker that comprise the 230 kV main bus.
- Two (2) three-phase vertical break disconnect switch, with mechanical interlocked ground switch attachment, is required to allow isolation of the circuit breaker that comprise the 230 kV line terminals to the breaker for remote line isolation.
- All switches to be rated 230 kV, 3000 A continuous, 63 kA short term withstand capacity, 900 kV BIL.

e) Conductors
- The horizontal bus will be 4" aluminum schedule 40 rigid tubular bus.
- The equipment jumpers from the horizontal bus to the string bus shall be bundled 1780 ACSR "Chukar," two conductors per phase.
- The equipment jumpers for switches to breakers shall be 1780 ACSR "Chukar," two conductors per phase.
- The equipment jumpers from the horizontal bus to the coupling capacitor voltage transformers and surge arresters shall be 1780 ACSR "Chukar," one conductor per phase.
- Include all necessary fittings.

f) Raceway & Conduit
- Four (4) new, two-inch (2") conduits for the Transmission Owner-Interconnection fiber optic cable, routed from the new control house to the Interconnect Customer PCO Pole Location/POI.

i. Handhole / pull box installed at the PCO structure, according to Transmission Owner design specs.

ii. ADSS fiber between Smalling control house and the handhole / pull box installed at the PCO structure, including all associated fiber splicing.

iii. Excess slack of ADSS fiber left in the handhole / pull box located at the PCO structure such that the Interconnect Customer may pull to the generation control house.

- 2" PVC conduit with couplings, bends, adapters, liquid-tight fittings, and related hardware for breakers and switches.
- All conduit at road crossings and running outside station fence will be encased in concrete.

h) Existing Control Building

- Includes installing the panels in the control building, connection of control cable wiring checkout and commissioning of the associated systems.

Relay

a) Instrument Transformer

- Six (6) coupling capacitor voltage transformers (CCVTs), each with two (2) secondary windings, shall be installed. Scope includes installation of conduits to the CCVTs, jumpers to the associated bus, and control cables to the control building.

b) Miscellaneous equipment shall include:

- Two (2) three-phase CCVT/PT outdoor junction boxes capable of accommodating two (2) secondary windings.

c) Four (4) new relay panels are required for the new breakers in the Bay 5 & 8 at the Smalling 500/230kV substation.

- Four (4) breaker control panels for breakers RX311, RX312, RX316, and RX317 shall be provided with one (1) SEL-451 relay configured for breaker control, monitoring, and backup protection functions.
- Includes installing the panels inside the control building, de-terminating existing control cable wiring, reconnecting existing shielded control cable wiring, installing and connecting any additional control cable wiring as required, checkout and commissioning of the associated systems.

Relay Settings

a) Study and apply NERC/SERC Regulatory compliance requirements (FAC-008-3, PRC-027, PRC-023, PRC-025). Perform analysis based on Transmission Owner Standard compliance procedure for setting revisions and updates.

b) Develop new relay settings for two (2) new line protection panels associated with the 230kV interconnection gen-tie line coming from Unit#1 & Unit#2, incorporating two (2) SEL-411L relays utilizing a line current differential protection scheme.

c) Develop new relay settings for four (4) new breaker control panels associated with the 230kV breakers RX311, RX312, RX316, and RX317 incorporating one (1) SEL-451 relay for control and backup protection.
d) Develop revised relay settings for eight (8) bus protection panels associated with the 230kV Bus#1-4, each incorporating two (2) SEL-487B relays.
e) Prepare and support test plans for all newly developed and revised relay settings, ensuring complete functional and protection validation.
f) Provide both off-site and on-site support during the construction and commissioning phases, addressing relay setting database issues, relay software compatibility, and firmware version alignment.
g) Upgrade existing relays to the latest approved firmware in accordance with Transmission Owner standards and verify compatibility with relay settings and communication protocols.
h) Perform relay settings logistics and documentation tasks, including maintenance of relay database files (.rdbs), generation of viewable relay setting documents (.xls), organization of project folders for web posting (IPS), and relay model development in CAPE®.
i) All relay settings work shall be completed in strict accordance with Transmission Owner protection standards, project-specific design drawings, and applicable system studies.

Communications and SCADA

a) Provision underground (UG) fiber connections between Smalling 500/230kV Substation and the Franklin Farms Plant. Fiber shall be routed via dedicated conduits and splice points as coordinated with Transmission Owner IT Telecom.
b) Install one (1) 96-strand single mode fiber cable from Smalling Substation to the Plant Process Data Centers (PDCs), including link or fiber tie through the Admin Building to the Plant Control Building.
c) Provide a 144-strand fiber cable through the Admin Building for redundancy and future expansion.
d) Install Optical Ground Wire (OPGW) on the Gen-Tie line to provide a redundant telecommunications path between Smalling Substation and the Franklin Farms Plant, ensuring diverse and reliable routing.
e) Provide fiber panels and fiber connectors in the Smalling 500/230-kV Substation Electrical Building and Plant Electrical Building to maintain continuity of the fiber ring design.
f) Establish fully redundant singlemode direct fiber relay paths from Smalling 230kV Substation to both Plant relaying, ensuring physically diverse redundant routes for reliability.
g) Coordinate with Transmission Owner Telecom and Relay Design to define patching, port assignments, and multiplexed channel usage consistent with Transmission Owner standards.
h) Transmission Owner will complete fiber installation and splicing at the Smalling 230kV substation.

i) Complete fiber installation and splicing at the Smalling 230-kV Substation in coordination with Transmission Owner Telecom standards.

j) Transmission Owner Telecom's responsibility is to provide Direct Fiber assignments for Relay-Channels, Relay and Power Generation counterparts (on Power Gen side of Transmission) install relay communications via these channels. Transmission Owner Telecom (internal) will splice/OTDR test fibers and provide results to Relay/Power Gen. Relay and Power Gen resources responsible for testing Relays themselves. Update RTU configuration files as required to support new relay communication paths.

k) Perform SCADA integration and testing for all new fiber channels, including relay communications, telemetry, and alarm/status points.

Metering

a) No metering upgrades required.

ii. Underground ADSS Fiber

General

a) New underground fiber to be installed on this T-line section between the Franklin Farms CCCT and Smalling 500/230 kV substation.

UG Fiber

a) Approximately a total of 0.3 miles shall be installed between the Franklin Farms CCCT and Smalling 500/230 kV substation to provide communications to both stations.

(c) Shared Network Upgrade(s) to be funded by Interconnection Customer.

None.

(d) Substation Network Upgrades to be installed by ~~_____~~.

~~Transmission Owner shall install _____, detailed in Exhibit A2 ___. These facilities are estimated to cost $_____ and are detailed in Exhibit A2 ___.~~**Transmission Owner**.

None.

4. System Protection Facilities

(a) System Protection Facilities not listed in Section 2 or 3 to be constructed by Interconnection Customer. ~~Interconnection Customer shall construct _____ detailed in Exhibit A3___. These facilities are estimated to cost $_____ and are detailed in Exhibit A3___.~~None.

(b) System Protection Facilities not listed in 2 or 3 to be constructed by Transmission Owner. ~~Transmission Owner shall construct _____ and detailed in Exhibit A3___. These facilities are estimated to cost $_____ and are detailed in Exhibit A3___.~~

Smalling 500 kV Substation

a) Develop new relay settings for one (1) line protection panel associated with the 500 kV Smalling–Baxter Wilson Line, incorporating two (2) SEL-411L relays utilizing a line current differential protection scheme.
b) Develop new relay settings for three (3) line protection panels associated with the 500 kV Smalling–Car Gas Rd Lines #1, #2, and #3, each incorporating two (2) SEL-411L relays utilizing a line current differential protection scheme.

Car Gas Rd 500 kV Substation

a) Develop new relay settings for three (3) line protection panels associated with the 500 kV Car Gas Rd–Smalling Lines #1, #2, and #3, each incorporating two (2) SEL-411L relays.
b) Develop new relay settings for three (3) line protection panels associated with the 500 kV Car Gas Rd–Perryville Lines #1, #2, and #3, each incorporating two (2) SEL-411L relays.
c) Develop new relay settings for two (2) line protection panels associated with the 500 kV Car Gas Rd–Sterlington Lines #1 and #2, each incorporating two (2) SEL-411L relays.
d) Develop new relay settings for one (1) line protection panel associated with the 500 kV Car Gas Rd–Mt Olive Line, incorporating two (2) SEL-411L relays.

Perryville 500 kV Substation

a) Develop new relay settings for three (3) line protection panels associated with the 500 kV Perryville–Car Gas Rd Lines #1, #2, and #3, each incorporating two (2) SEL-411L relays.
b) Develop new relay settings for one (1) backup protection panel associated with Perryville Unit #1, incorporating one (1) SEL-311C relay.
c) Develop new relay settings for one (1) backup protection panel associated with Perryville Unit #2, incorporating one (1) SEL-311C relay.

Sterlington 500 kV Substation

a) Develop new relay settings for two (2) line protection panels associated with the 500 kV Sterlington–Car Gas Rd Lines #1 and #2, each incorporating two (2) SEL-411L relays.
b) Develop new relay settings for one (1) line protection panel associated with the 500 kV Sterlington–Ouachita Line, incorporating two (2) SEL-411L relays.
c) Develop new relay settings for one (1) line protection panel associated with the 500 kV Sterlington–Ouachita Line, incorporating one (1) SEL-321 relay with POTT/DTT scheme.
d) Develop new relay settings for one (1) line protection panel associated with the 500 kV Sterlington–El Dorado Line, incorporating one (1) SEL-411L relay (OPT Modified C5).
e) Develop new relay settings for one (1) line protection panel associated with the 500 kV Sterlington–El Dorado Line, incorporating SEL-421 and SEL-311C relays.

Ouachita 500 kV Substation

a) Develop new relay settings for two (2) line protection panels associated with the 500 kV Ouachita–Sterlington Line (three-terminal configuration), each incorporating two (2) SEL-411L relays.

b) Develop new relay settings for one (1) line protection panel associated with the 500 kV Ouachita–Sterlington Line (three-terminal configuration), incorporating one (1) SEL-321 relay.

El Dorado 500 kV Substation

a) Develop new relay settings for one (1) line protection panel associated with the 500 kV El Dorado–Sterlington Line, incorporating one (1) SEL-411L relay (OPT Modified C5).

b) Develop new relay settings for one (1) line protection panel associated with the 500 kV El Dorado–Sterlington Line, incorporating SEL-421 and SEL-321 relays.

Baxter Wilson 500 kV Substation

a) Develop new relay settings for one (1) line protection panel associated with the 500 kV Baxter Wilson–Smalling Line, incorporating two (2) SEL-411L relays.

Catahoula 230 kV Substation

a) Develop new relay settings for two (2) line protection panels associated with the 230 kV Catahoula–Smalling Lines #1 and #2, each incorporating two (2) SEL-411L relays.

Eagle 230 kV Substation

a) Develop new relay settings for one (1) line protection panel associated with the 230 kV Eagle–Smalling Line, incorporating two (2) SEL-411L relays.

b) Develop new relay settings for one (1) line protection panel associated with the 230 kV Eagle–Chotard Line, incorporating two (2) SEL-411L relays.

Chotard 230 kV Substation

a) Develop new relay settings for one (1) line protection panel associated with the 230 kV Chotard–Smalling Line, incorporating two (2) SEL-411L relays.

b) Develop new relay settings for one (1) line protection panel associated with the 230 kV Chotard–Eagle Line, incorporating two (2) SEL-411L relays.

Yucatan 230 kV Substation

a) Develop new relay settings for one (1) line protection panel associated with the 230 kV Yucatan–Smalling Line #1, incorporating two (2) SEL-411L relays.

b) Develop new relay settings for one (1) line protection panel associated with the 230 kV Yucatan–Smalling Line #2, incorporating two (2) SEL-411L relays.

Concordia 230 kV Substation

a) Develop new relay settings for one (1) line protection panel associated with the 230 kV Concordia–Smalling Line, incorporating two (2) SEL-411L relays.

b) Develop new relay settings for one (1) line protection panel associated with the 230 kV Concordia–Marengo Line, incorporating two (2) SEL-411L relays.

Marengo 230 kV Substation

a) Develop new relay settings for one (1) line protection panel associated with the 230 kV Marengo–Smalling Line, incorporating two (2) SEL-411L relays.

b) Develop new relay settings for one (1) line protection panel associated with the 230 kV Marengo–Concordia Line, incorporating two (2) SEL-411L relays.

5. Distribution Upgrades.

~~**5. Distribution Upgrades**~~

(a) Distribution Upgrades to be constructed by ~~(Transmission/Distribution) Owner (select one for final version).~~ ~~(Transmission/Distribution) Owner shall construct _____ detailed in Exhibit A4___. These facilities are estimated to cost $_____ and are detailed in Exhibit A4___.~~**Transmission Owner.** None.

~~**6.** Contingency List [include higher queued Interconnection Requests with GIAs prior to this GIA and contingency Network Upgrades, System Protection Facilities or Distribution Upgrades of higher queued Interconnection Request with GIAs prior to this GIA pursuant to Article 11.3.1 that are subject to restudy in accordance with Article 11.3.2]~~

~~**(a)** Contingency List of MTEP Appendix B projects and contingent actions should Appendix B projects not proceed by listed date to Appendix A.~~

6. Contingency List. See Exhibit A10.

7. Affected System Upgrades List ~~(include higher queued Interconnection Requests with GIAs prior to this GIA).~~

~~**8.** JTIQ Upgrades~~

~~[To be included in GIA if~~Affected Systems Studies have not concluded as of the date of this EGIA. Interconnection Customer is responsible for ~~a portion~~executing and fulfilling the obligations of ~~a portfolio~~any agreements for the study, construction, or funding of Affected System network upgrades identified by the Affected System after execution of this GIA.

8. JTIQ Upgrades~~]~~.
None.

9. Common Use Upgrades. Interconnection Customer is ~~subject to the JTIQ Generator Charge in accordance with Attachment JJJ of the MISO Tariff and Appendix I~~responsible for entering into Facilities Construction Agreements and/or Multi-Party Facilities Construction Agreement with transmission owner for Interconnection Customer's share of ~~this GIA.~~the following upgrades:

~~JTIQ Security amount:~~

~~Constructing MISO~~

10. Exhibits – The following exhibits are included:

A1. Interconnection Customer One-Line & Site Map
A1-1: Interconnection Customer One-Line Diagram (1 of 2)
A1-2: Interconnection Customer One-Line Diagram (2 of 2)
A1-3: Interconnection Project Site Map
A2. Transmission Owner One-Lines
A2-1: Transmission Owner One-Line
~~A.~~ A3. Transmission Owner Substation General Arrangement

~~1. _____~~
~~1. _____~~
~~1. _____~~
~~1. _____~~

~~A. SPP:~~
A3-1: General Arrangement Drawing
A4. Transmission Line Plan and Profile
A4-1: Tangent Structure Type
A4-2: Dead End Structure Types
A4-3: 3-D Interconnection Layout
A5. Facilities to be Constructed by Transmission Owner
A6. Detailed Cost of Facilities to be Constructed by Transmission Owner
A7. Facilities to be Constructed by Interconnection Customer
A8. Detailed Cost of Facilities to be Constructed by Interconnection Customer
A9. Facilities Subject to Transmission Owner Reimbursement
A10. Contingent Facilities
A11. Interconnection Customer Milestones
A12. Construction & Coordination Schedules
A13. Permits, Licenses, Regulatory Approvals and Authorization
A14. Interconnection and Operating Guidelines

Exhibit A1. Interconnection Customer One-Line & Site Map

A1-1: Interconnection Customer One-Line Diagram (1 of 2)

CUI//CEII MATERIAL – DO NOT RELEASE

A1-2: Interconnection Customer One-Line Diagram (2 of 2)

CUI//CEII MATERIAL – DO NOT RELEASE

A1-3: Interconnection Project Site Map




Exhibit A2. Transmission Owner One-Lines

A2-1: Transmission Owner One-Line




Exhibit A3. Transmission Owner Substation General Arrangement

A3-1: General Arrangement Drawing






Exhibit A4. Transmission Line Plan and Profile
A4-1: Tangent Structure Type



A4-2: Dead End Structure Types

0°–5°, SELF SUPPORTING, DE, JUMPER, VERTICAL,
SINGLE CIRCUIT, DE POLYMER, STEEL 230kV

ASSEMBLY LIST		
ITEM	QTY.	ASSEMBLY/DRAWING
1	3	BLT–P–S
2	6	DEP/TRB–230–XX
3	3	JLP–230–XX
4	2	OHG–DE–XX
REFERENCE DRAWINGS		
7	1	SGN–S
8	–	GND–S–XX
9	–	POLE INDEX
10	1	FOOTING
11	–	PVO, SHT 1, VW PV–19
12	–	ANODE–XX (IF REQ.)



NOTES:

1) All dimensions are to Centerline of top attachment or BLT–XX.
2) See Pole Fabricator's drawings for attachment details.
3) See Staking Sheet and CU Drawings for line angles, pole, footing, grounding, and sign requirements.
4) Refer to Assembly drawings for part details.
5) Conductor attachment vangs shall be placed within 5 degrees of Ahead and Back locations.
6) This structure shall not be used for single insulator bundled conductor applications unless the combined phase tension is less than 19.4 kips. For two insulator attachment bundled conductor applications, use the appropriate bundled framing.

Set:Phase

NO.	DATE:	REVISION	BY:	APPR:

SDJA–V–DEP–S 230

ENTERGY STANDARD DWG.

DESIGN APPROVAL	STANDARDS APPROVAL
SIGNED / DATE	SIGNED / DATE

DEADEND STEEL 230kV
0°–5° SINGLE CIRCUIT

APPROVED BY:	DATE: 8–15–03
CHECKED BY:	SCALE: NONE
DRAWN BY: LINESOFT	ESI NO. TDS559A0


Entergy

No.

PLOT 1=130 SH. 1 OF 1

70'–120', SELF SUPPORTING, DE, VERTICAL,
SINGLE CIRCUIT, DE POLMER, STEEL 230kV

ASSEMBLY LIST		
ITEM	QTY.	ASSEMBLY/DRAWING
1	6	DEP/TRB–230–XX
2	2	OHG–DE–XX
REFERENCE DRAWINGS		
7	1	SGN–S
8	–	GND–S–XX
9	–	POLE INDEX
10	1	FOOTING
11	–	PVO, SHT 2, VW PV–15
12	–	ANODE–XX (IF REQ.)



NOTES:

1) All dimensions are to Centerline of top attachment.
2) See Pole Fabricator's drawings for attachment details.
3) See Staking Sheet and CU Drawings for line angles, pole, footing, grounding, and sign requirements.
4) Refer to Assembly drawings for part details.
5) Conductor attachment vangs shall be placed within 5 degrees of Ahead and Back locations.
6) This structure shall not be used for single insulator bundled conductor applications unless the combined phase tension is less than 19.4 kips. For two insulator attachment bundled conductor applications, use the appropriate bundled framing.

Set:Phase

NO.	DATE:	REVISION	BY:	APPR:
2	8–18–04	REVISED DIMENSION FOR SIGN	ITRON	
1	4–28–03	REV., DIM., GND., NOTE 1, ADD ITEM 12, NOTE 6	ITRON	

SD–V–DEP–S 230
ENTERGY STANDARD DWG.

DESIGN APPROVAL	STANDARDS APPROVAL
SIGNED / DATE	SIGNED / DATE

DEADEND STEEL 230kV
70'–120' SINGLE CIRCUIT

APPROVED BY:	DATE: 10–18–96
CHECKED BY:	SCALE: NONE
DRAWN BY:	ESI NO. TDS419A2

Entergy

No.

PLOT 1=130 SH. 1 OF 1

A4-3: 3-D Interconnection Layout




Exhibit A5. Facilities to be Constructed by Transmission Owner

Description of Upgrade	Upgrade Classification	Estimated Cost*
J3841 500/230 kV Substation: Transmission Owner Interconnection Facilities shall consist of a high bus dead-end structure, a section of tubular bus tapping off the breaker and a half bay, a disconnect switch with a ground switch attachment, (3) 230 kV surge arresters, and (6) coupling capacitor voltage transformers, and (1) Line Protection Panel with associated wiring . The facilities shall include associated support structures and associated foundations, as shown on Exhibit A4 which is a preliminary electrical profile view of the TOIFs.	TOIF	$875,000
J3842 500/230 kV Substation: Transmission Owner Interconnection Facilities shall consist of a high bus dead-end structure, a section of tubular bus tapping off the breaker and a half bay, a disconnect switch with a ground switch attachment, (3) 230 kV surge arresters, (6) coupling capacitor voltage transformer, and (1) Line Protection Panel with associated wiring. The facilities shall include associated support structures and associated foundations, as shown on Exhibit A4 which is a preliminary electrical profile view of the TOIFs.	TOIF	$865,000
J3841 Transmission Line: Entergy's Interconnection Facilities shall consist on installing new 954 ACSS "Cardinal", DNO-12776 OPGW 96, and 7#7 Alumowled shield wires, along with all attachment hardware. Self supported steel monopole tangent (1) and dead-end (3) structures, along with all attachment hardware.	TOIF	$1,765,000
J3842 Transmission Line: Entergy's Interconnection Facilities shall consist on installing new 954 ACSS "Cardinal", DNO-12776 OPGW 96, and 7#7 Alumowled shield wires, along with all attachment hardware. Self supported steel monopole tangent (1) and dead-end (3) structures, along with all attachment hardware.	TOIF	$1,735,000
J3841 500/230 kV Substation Equipment Upgrade(s): Network upgrade shall include (2) 245 kV, 63kA Circuit, Breakers, (4) 230kV, 3000A Switches, (17) 230 kV Bus Supports, (2) Breaker	NU	$4,263,300

Control Panels and associated wiring.		
J3842 500/230 kV Substation Equipment Upgrade(s): Network upgrade shall include (2) 245 kV, 63kA Circuit, Breakers, (4) 230kV, 3000A Switches, (17) 230 kV Bus Supports, (2) Breaker Control Panels and associated wiring.	NU	$4,263,300
J3841/J3842 Telecom: Installation of new UG fiber to establish redundant communication paths, including all materials, engineering, technician labor, fiber termination panels, and transition splicing at Smalling Substation and Franklin Farms Plant.	NU	$213,400
	Total Cost:	**$13,980,000**

***Estimated Costs are in 2025 dollars**

Exhibit A6. Detailed Cost of Facilities to be Constructed by Transmission Owner

Table A6-1: Detailed Cost Estimate*

Item Description	Estimated Total	TOIF	SANU	NU
Contract Construction	$7,290,000	$2,990,000	$0	$4,300,000
Contract Project Management	$570,000	$0	$0	$570,000
ROW, Permitting Support & Environmental	$0	$0	$0	$0
Materials	$3,510,000	$1,530,000	$0	$1,980,000
Contract Engineering	$590,000	$210,000	$0	$380,000
Telecom	$200,000	$0	$0	$200,000
Payroll	$500,000	$0	$0	$500,000
Distribution	$0	$0	$0	$0
Expense	$40,000	$20,000	$0	$20,000
Total Direct Cost:	**$12,700,000**	**$4,750,000**	**$0**	**$7,950,000**
Capital Suspense:	$850,000	$320,000	$0	$530,000
AFUDC:	$390,000	$150,000	$0	$250,000
Other Overheads:	$40,000	$20,000	$0	$10,000
Total In-direct Cost:	**$1,280,000**	**$490,000**	**$0**	**$790,000**
Total Cost:	**$13,980,000**	**$5,240,000**	**$0**	**$8,740,000**

***Estimated Costs are in 2025 dollars**

Exhibit A7. Facilities to be Constructed by Interconnection Customer

Interconnection Customer facilities are not included in this Facilities Study report. To be provided by the Interconnection Customer.

Exhibit A8. Detailed Cost of Facilities to be Constructed by Interconnection Customer

Interconnection Customer facilities are not included in this Facilities Study report. To be provided by the Interconnection Customer.

Exhibit A9. Facilities Subject to Transmission Owner Reimbursement

There is no transmission owner reimbursable scope associated with this project.

A10 Contingent Facilities

Table A10-1 describes transmission assumptions modeled in the studies that were deemed necessary to allow for the Interconnection Service as described in Appendix A of this GIA and is not related to Article 11.3.1, i.e., does not describe projects associated with a higher queued and/or similarly queued ERAS Interconnection Request. Nevertheless, if the transmission assumptions are not completed or significantly modified, the Interconnection Service granted under this GIA may be restricted until such time as the Interconnection Customer funds a study to determine the applicable ERIS and NRIS level that results due to the changes in Table A10-1.

A list of higher-queued and/or similarly queued ERAS study projects are in Tables A10-2 and A10-3. A project inclusion in this GIA does not necessarily mean that these facilities would be contingencies for the Interconnection Customer's Generating Facility. If any of the higher queued and/or same cycle ERAS generators were to drop out, then the Interconnection Customer may be subject to restudy pursuant to Article 11.3.2.

Table A10-1: Transmission Assumptions

MTEP ID	Facility ID	Facility	Description	Expected Completion Date	Status
25242	28277	WEBRE- COMMODORE 500kV Circuit 1	Amite South Reliability Project Phase 1 - alternative	8/1/2028	M2 - Appendix A Approved
15654	23667	DELHI-TALLULAH 115 kV Circuit 1	Delhi to Tallulah Rebuild	12/1/2026	M2 - Appendix A Approved
15654	23668	DELHI-DEHIL RX 115 kV Circuit 1	Delhi to Tallulah Rebuild	12/1/2026	M2 - Appendix A Approved
50093	50139	CHALKBLUFFPV – GALET 500kV Circuit 1	Galet 500/230kV New Substation	2/26/2027	M2 - Appendix A Approved

50093	50139	W.MEMPHIS – GALET 500 kV Circuit 1	Galet 500/230kV New Substation	2/26/2027	M2 - Appendix A Approved
17974	24744	STILLEYS – WEST FRANK FORT EAST 345kV Circuit 1	Crab Orchard: Install 345-138 kV transformer. Tap the Shawnee-West Frankfort east-4564 line and install 345kV ring bus to make the connection.	12/1/2026	M2 - Appendix A Approved
17974	24744	STILLEYS – SHAWNEE 345 kV Circuit 1	Crab Orchard: Install 345-138 kV transformer. Tap the Shawnee-West Frankfort east-4564 line and install 345kV ring bus to make the connection.	12/1/2026	M2 - Appendix A Approved
50556	50936	S HILLS - EAST ADAIR 345 kV Circuit T2	LRTP 23 – Lakefield Junction – East Adair	6/1/2034	M2 - Appendix A Approved
50556	50931	ORIENT - EAST ADAIR 345 kV Circuit T2	LRTP 23 – Lakefield Junction – East Adair	6/1/2034	M2 - Appendix A Approved
AFS	AFS	SPP	Build New Beckham to Potter 345 kV Line	TBD	TBD

Table A10-2: Prior Queued Projects

MISO Higher Queued Project #	Service Type	TO	County, State	Point Of Interconnection	Pmax (MW)	Fuel Type
None						

Table A10-3: Similarly Queued Projects

MISO Queue Project #	Service Type	TO	County, State	Point Of Interconnection	ERIS MW	Fuel Type
None						

Exhibit A11. Interconnection Customer Milestones

This exhibit is provided for reference only. Binding dates are in Appendix B.

The customer milestones include, but are not limited to those shown in the table below:

Table A11-1: Milestone Schedule

IC Milestone Schedule	
Task Name	**Proposed Finish**
GIA Execution:	TBD
GIA Payment:	TBD
Landowner Access Approval (soil borings):	N/A
Site Acquisition (servitude agreements):	N/A
Receipt of Environmental Permitting:	Complete

Exhibit A12. Construction & Coordination Schedules

This exhibit is provided for reference only. Binding dates are in Appendix B.

The proposed schedule is dependent on obtaining a suitable substation site, on timely receipt of all approvals associated with constructing the Transmission Owner interconnection substation and lines, outage availability, equipment lead-time, and resource availability. This schedule does not include upgrades that may be required because of the system impact studies. An Engineering and Procurement Agreement between the parties could potentially be utilized to begin work before the generation interconnection agreement is executed.
A detailed schedule will be prepared subsequent to customer approval to proceed with the project. Based on the Task duration schedules listed below, the overall project in-service date is projected to be Feb 2028.

Table A12-1: Milestone Schedule

Task Name	Proposed Start	Proposed Finish
GIA Execution:	TBD	
Customer Approval & Funding:	TBD	
Complete Project Execution Plan:	Complete	
Update/ Baseline Schedule:	Complete	
Detail Design:	Complete	Complete
Order Material:	Complete	Complete
Receive Material:	Complete	Complete
Issue for Construction Design Packages:	Complete	Complete
Environmental Permits:	Complete	
Construction:	Oct 2025	Oct 2026
In-Service:	Feb 2028	

Milestone Schedule Notes:

1. This schedule does not account for adverse weather conditions or major weather events.
2. All construction work requiring outages will be performed during acceptable periods of system load, which most often is the off-peak load season. Line outages will be discussed with the SOC and TCC and the assumption is made that line outages will be executed as planned. However, last minute denial of outages by the SOC/TCC along with resulting schedule delay is possible.
3. Substation construction will be coordinated with the transmission line outages when possible.
4. The above milestone schedule assumes construction resources will be available when required.

Exhibit A13. Permits, Licenses, Regulatory Approvals and Authorization

Permits, licenses, and approvals required to construct the Transmission Owner facilities may include, but are not limited to:

1. MISO questionnaire to be submitted to MISO, TCC, and TOP for review and approval
2. Revised station one line to be submitted to MISO, TCC, and TOP for review and approval
3. Wetland delineation of servitudes and proposed construction access points
4. US Corps of Engineers permitting/approval for wetlands
5. US Corps of Engineers permitting/approval for river/levee permits
6. Environmental sampling and disposal of displaced soils
7. Develop and implement a Storm Water Pollution Prevention Plan (SWPPP)
8. Temporary landowner easements
9. Pipeline Letters of No Objection
10. Access Road Permits for Public Roads

Exhibit A14. Interconnection and Operating Guidelines / Requirement

A14.1 Interconnection

The Interconnection Customer will comply with the Interconnection Guidelines for Transmission Interconnection Producer-Owned Generation Greater Than 20 MW dated March 2007, as amended from time to time and available at: https://www.entergy.com/transmission/requirements ("ENTERGY FACILITY CONNECTION REQUIREMENTS").

A14.2 Power Factor

In accordance with FERC Order No. 827, all newly-interconnected generators (synchronous or non-synchronous) are required to provide dynamic reactive power support within the range of +/- 0.95 power factor at the transmission voltage side of the generator step-up transformer at all dispatch levels. Static reactive power devices can only be used to make up for reactive losses that occur between the inverters and the transmission voltage side of the generator step-up transformer. Any additional reactive power must be supplied by a dynamic reactive power device.

The +/-0.95 power factor requirement corresponds to a triangle-shaped reactive power capability with proportional reduction in reactive power capability at lower active power (i.e. real power) output, as shown in Figure 14.1. However, reactive power capability outside the triangular-shaped requirement yet within the reactive power capability of the plant should be utilized to the greatest extent possible. Inverters shall not have artificial settings imposed to limit reactive power output to the triangular boundary.




Figure A14-1: Inverter-based Resource Plant Reactive Power Capability

A14.3 Primary Frequency Response

In accordance with FERC Order No. 842, the Interconnection Customer shall ensure the primary frequency response capability of its Generating Facility by installing, maintaining, and operating a functioning governor or equivalent controls. The hardware and/or software that provides frequency responsive active power control shall be able to sense changes in system frequency and autonomously adjust the Generating Facility's power output in accordance with the droop and deadband parameters provided by Entergy Transmission and to the extent the Generating

Facility has operating capability in the direction needed to correct the frequency deviation. The Interconnection Customer is required to install a governor or equivalent controls with the capability of operating with a maximum 5% droop and a maximum ± 0.036 Hz deadband. This response must be timely and sustained rather than injected for a short period and then withdrawn. The primary frequency response requirements shall apply to all inverter-based generating resources including energy storage during both charging and discharging states.

The Generator Owner shall provide the status and settings of the governor or equivalent controls to Entergy Transmission upon request. If the Generator Owner needs to operate the Generating Facility with its governor or equivalent controls not in service, the Generator Owner shall immediately notify Entergy Transmission and make reasonable efforts to return its governor or equivalent controls to service as soon as practical.

A14.3.1 Dynamic Frequency Response Requirements for Inverter-Based Resources

For a step change in frequency at the Point of Interconnection (POI), inverter-based resources (IBR) shall have the capability to meet the dynamic characteristics shown in Table A14.1. The active power-frequency response shall be sustained by the resource until such time that the control signals (e.g., Balancing Authority automatic generation control (AGC)) return the generator to a new set point value.

Table A14.1: Dynamic Active Power-Frequency Performance

Parameter	Description	Performance Requirement
Reaction Time	Time between the step change in frequency and the time when the IBR's active power output begins responding to the change.	< 500 ms
Rise Time	Time in which the IBR has reached 90% of the new steady-state (target) active power output command.	< 4 s
Settling Time	Time in which the IBR has entered into, and remains within, the settling band of the new steady-state active power output command.	< 10 s
Overshoot	Percentage of rated active power output that the IBR can exceed while reaching the settling band.	< 5%
Settling Band	Percentage of rated active power output that the resource should settle to within the settling time.	< 2.5%

A14.4 Frequency and Voltage Ride Through

The frequency and voltage ride-through curves described in NERC Reliability Standard PRC-024 and PRC-029 apply to the POI and not the inverter terminals themselves. The Interconnection Customer, in coordination with their inverter manufacturer, shall reflect the ride-through requirements at the POI to the inverter terminals to ensure that the inverters can ride through and continue current injection during disturbances.

The PRC-024 and PRC-029 voltage and frequency ride-through curves specify a "No Trip Zone". Operations outside of the "No Trip Zone" shall not be interpreted as a "Must Trip Zone" but rather a "May Trip Zone".

A14.4.1 Frequency Measurements and Protection

Frequency shall be calculated over a period of time (no less than 6 cycles) and filtered to take control action on the fundamental frequency component of the calculated signal. Calculated frequency shall not be susceptible to spikes caused by phase jumps on the Bulk Electric System (BES).

Inverter-based resources shall also inhibit frequency tripping during and immediately after low voltage conditions. Inverter-based resources shall ensure that the frequency measurement and protection settings are set such that these resources are able to ride through and not trip for phase jumps or other grid disturbances where calculated frequency is affected but grid frequency is within the ride-through curves of PRC-024 and PRC-029.

A14.4.2 Momentary Cessation

Inverter-based resources interconnected to the transmission system are expected to continue current injection inside the "No Trip" zone of the PRC-024 and PRC-029 frequency and voltage ride through curves. Newly interconnecting inverter-based resources should eliminate the use of momentary cessation unless necessary in areas of the BES with low short circuit strength (SCR < 3).

A14.5 Voltage Control

BES-connected resources are required to operate in automatic voltage control mode as per NERC Reliability Standard VAR-002. All resources, including inverter-based resources, shall operate in a closed-loop, automatic voltage control mode to maintain voltage at the POI to within the specified voltage schedule tolerance band provided by the Transmission Operator as per NERC Reliability Standard VAR-002.

A14.5.1 Small Disturbance Reactive Power-Voltage Control Performance

Individual inverters shall always operate in automatic voltage control to support BES voltage schedules, post-contingency voltage recovery, and voltage stability. Each inverter shall continually respond to all changes in terminal voltage in a closed loop fashion to maintain the set point voltage level.

Inverter-based resources shall have the capability to meet the performance characteristics shown in Table A14.2. These characteristics are specified for the response of reactive power of the overall closed-loop response of the inverter-based resource plant.

Table A14.2: Dynamic Reactive Power-Voltage Performance for Small Disturbance

Parameter	Description	Performance Requirement
Reaction Time	Time between the step change in voltage and when the IBR's reactive power output begins responding to the change. Shall not include any intentional time delay.	< 500 ms
Rise Time	Time between a step change in control signal input (reference voltage) and when the reactive power output changes by 90%	< 2-30 s

	of its final value.	
Overshoot	Percentage of rated reactive power output that the IBR can exceed while reaching the settling band.	< 5%

A14.5.2 Large Disturbance Reactive Power-Voltage Performance

The reactive power-voltage control shall be stable over all expected operating and grid conditions and be tuned to provide this stable response. The dynamic response of inverter-based resources shall be programmable by the Interconnection Customer (in coordination with the inverter manufacturer) to enable changes based on changing grid conditions once installed in the field.

Inverter response to fault events on the BES shall abide by the following principles:

- **Fault Inception**: During the inception of a fault, priority shall be given to delivering as much current to the system as quickly as possible to support protective relay systems to detect and clear the fault.
- **On-Fault Current Injection**: For the remaining on-fault period after the first couple cycles up to fault clearing, priority shall be given to accurately detecting and controlling the type of current needed based on terminal conditions and providing a combination of active and reactive current as necessary.
- **Post Fault Current Injection**: Priority shall be given to ensuring sufficient local voltage support before attempting to maintain or return to pre-disturbance active current injection.
- **Post-Fault Voltage Overshoot Mitigation**: Inverter reactive current response shall not exacerbate transient overvoltage conditions on the BES.

Inverters shall be designed to have the capability to meet the performance specifications shown in Table A14.3.

Table A14.3: Dynamic Reactive Power-Voltage Performance for Large Disturbance

Parameter	Description	Performance Requirement
Reaction Time	Time between the step change in voltage and when the IBR's reactive power output begins responding to the change.	< 200 ms
Rise Time	Time between a step change in control signal input (reference voltage) and when the reactive power output changes by 90% of its final value.	< 30 s

A14.6 Transmission System Studies

NERC Reliability Standard FAC-002 requires each Transmission Planner to assess the reliability impact of interconnecting new generation as well as any material modifications to existing interconnections of generation. Steady-state, dynamic, and short circuit studies are performed as part of the MISO Definitive Planning Phase (DPP) process. However, there are other considerations that may need to be assessed based on the interconnection location, IBR control functionality, and nearby resources (SVCs, series capacitors, synchronous generation, IBR generation, etc.).

A14.6.1 Controls Interactions and Controls Instability

Inter-plant coordination is increasingly important as the penetration of inverter-based resources continues to grow. When multiple resources attempt to control the same location on the BES (e.g., controlling voltage at the same POI or close proximity), their control systems need to be coordinated with one another to avoid reactive power output imbalance, circular reactive power flows, controls overshoot, voltage control hunting, and unstable oscillations. Coordination issues shall be evaluated prior to the resource connecting to the BES. Prior to performing this analysis, the consultant selected by the Interconnection Customer shall be approved by Entergy Transmission. This analysis shall be performed during the plant design phase prior to plant backfeed. The results of the analysis shall be provided to Entergy Transmission with the cost of the study borne by the Interconnection Customer.

A14.6.2 Weak Grid Analysis (SCR < 3)

The changing nature of the electric grid and the growing complexity of IBR control systems can impact the performance of inverter-based resources and shall be assessed to ensure reliable operation of the BES. One of these changes is the continued reduction of short circuit levels in areas of high penetration of inverter-based resources. For interconnections with a short circuit ratio < 3, an EMTP study is required to assess potential SSR/SSCI and the proposed control design. Prior to performing this analysis, the consultant selected by the Interconnection Customer shall be approved by Entergy Transmission. This analysis shall be performed during the plant design phase prior to plant backfeed. The results of the analysis shall be provided to Entergy Transmission with the cost of the study borne by the Interconnection Customer.

A14.6.3 Power Quality

A14.6.3.1 Harmonic Distortion

Due to converter characteristics associated with IBR generation, there is an increased possibility of generating harmonic currents; therefore, Entergy shall install power quality monitoring devices at the POI. Entergy will install CCVTs with PQ sensors or Harmonic Measuring Devices (HMDs) to enhance accuracy of the Power Quality measurements. The harmonic current distortion at the POI shall be monitored for compliance with the IEEE 2800-2022 standard with the proposed generation. The harmonic distortion voltages at the POI shall also be monitored for compliance with the IEEE 519 standard with the proposed generation. Entergy will use IEEE 519, Table 1 to evaluate compliance with the voltage distortion limits. The table below is excerpted from the IEEE 519 standard for the transmission supply voltage levels. Entergy's evaluation of compliance with harmonic voltage distortion limits at the POI considers both the proposed generation and background harmonics present at the POI.

Table A14.4: Weekly 95th percentile (10 mins) Voltage Distortion Limits

Bus Voltage, V, at the POI	Individual harmonic (%) h ≤ 50	Total harmonic distortion THD (%)
1 kV < V ≤ 69 kV	3.0	5.0

69 kV < V ≤ 161 kV	1.5	2.5
161 kV < V	1.0	1.5[a]
[a] High-voltage systems are allowed to have up to 2.0% THD where the cause is an HVDC terminal whose effects are found to be attenuated at points in the network where future users may be connected.		

If the PQ meter at the POI records harmonic voltage distortions that exceed the limits of the IEEE 519-2022, and if such conditions result in customer complaints or Entergy equipment performance issues attributable to the interconnection customer generator, Entergy may impose operating restrictions on the IBR until the issue is resolved. In the event that further studies are required, the costs to conduct such studies will be the responsibility of the Interconnection Customer.

A14.6.3.2 Flicker

Entergy has adopted subclause 8.1.3 (Flicker), including Table 16, of the IEEE Standard 2800-2022, without modification. The IBR plant contribution to the flicker at the POI shall not exceed EPst and EPlt of 0.35 and 0.25 respectively based on the 95th percentile value for a one-week measurements period. Assessment and measurement methods for flicker are defined in IEEE Std 1453 (subclause 6.3) and IEC 61000-3-7 (subclause 6.3). Entergy will monitor the flicker at the POI and work with the customer to take corrective action when this limit is exceeded.

A14.6.3.3 Rapid Voltage Changes (RVC)

The IBR plant shall not cause the rapid voltage changes at the POI to exceed 2.5% of nominal voltage.

This RVC limit shall apply to sudden changes due to frequent energization of transformers, frequent switching of capacitors, or from abrupt output variations caused by IBR plant misoperation. These RVC limits shall not apply to infrequent events such as switching, unplanned tripping, or transformer energization related to commissioning, fault restoration, or maintenance.

A14.7 Modeling

The steady-state and dynamic models used to represent inverter-based resources shall accurately capture the small and large disturbance aspects of the resource. The following modeling information shall be provided to Entergy Transmission within 60 calendar days prior to plant backfeed.

- Steady state model including collector system equivalent as recommended by NREL, collector station transformer, padmount transformer, and transmission gen-tie line.
- Dynamic models using the 2nd Generation Renewable Energy Models [PSS/E Models REPC, REGC, and REEC].
- Frequency and voltage ride through characteristics and corresponding dynamic models [PSS/E VTGTPA, FRQTPA]. The low-voltage ride-through capability of the PV plant shall be demonstrated either through detailed modeling of the PV controls or by field/

factory tests.
- Inverter PQ curve.
- CAPE short circuit model using a Voltage Controlled Current Source Model or short circuit modeling documentation from the inverter manufacturer.
- PSCAD model of the IBR plant.

Model verification shall be performed in compliance with NERC Reliability Standards MOD-026 and MOD-027 and transmitted to the Transmission Planner within 365 calendar days after the commissioning date.

A14.8 Inverter Negative Sequence Requirements

For unbalanced faults, in addition to increased positive sequence reactive current, the IBR unit shall inject negative sequence:

- Dependent on the IBR unit terminal (POI) negative sequence voltage, and
- Leads the IBR unit terminal (POI) negative sequence voltage by an allowable range as specified below. The allowable range is provided in lieu of tolerance band specified in the definition of a settling time.
  - 90-100 degrees, for full converter-based IBR Units
  - 90-150 degrees, for type III WTGs

A14.9 Disturbance Monitoring

The IBR owner is required to comply with the disturbance monitoring and reporting requirements in PRC-028-1.

A14.10 Communication Paths

The Interconnection Customer shall coordinate with the Transmission Owner to ensure that Transmission Owner's microwave paths are not obstructed by wind turbines, as applicable, associated with the Generating Facility. Obstruction shall be defined as any encroachment on the 3D cylindrical ellipse, as determined by the Worst-Case Fresnel Zone calculation, that would interfere with communication signals propagating between the transmitter and receiver. At a minimum, this coordination shall consist of one of the following:

The Interconnection Customer shall provide the Transmission Owner with geographical coordinates, along with tower heights and blade diameters, of each proposed wind turbine associated with the Generating Facility for review against the Transmission Owner's Licensed Microwave Paths. The Transmission Owner may elect to hire an RF Consultant to determine whether the proposed turbine locations will obstruct its Licensed Microwave Paths Costs, such a study shall be allocated to the Interconnection Customer and shall not be subject to reimbursement.

The Interconnection Customer shall provide the Transmission Owner with a microwave path study, including evaluation of the Transmission Owner's Licensed Microwave Paths. The Transmission Owner will review and approve or deny the completed study within 10 business days after the study is submitted, where the approval of the Transmission Owner is not to be unreasonably withheld or denied. The Interconnection Customer shall gain approval of the submitted study prior to constructing the Generating

Facility.

A14.11 Generic Requirements for Fiber Optic Construction in Support of MISO Generation Projects

- All fiber shall be single mode, and its performance shall meet or exceed ITU-TG.657A1 specifications for Single-mode Optical Fiber, Dispersion Unshifted, with Low Water Peak.
- Minimum per-cable fiber count shall be forty-eight (48) strands.
  - To facilitate inter-company splicing, this count shall be incorporated into the fiber optic cable in four (4) bundles/tubes of twelve (12) fibers each, for a total of 48 fibers.
  - Higher count cables may be coordinated with Entergy.
- Fiber cable design shall be appropriate for the intended purpose (OPGW versus ADSS versus all-dielectric duct).
- All fiber optic joinery shall be accomplished via fusion splicing. Minimum standards for finished fusion splice performance are found in Table 1, below.
  - Mechanical fiber splicing is not permitted.
  - All fibers in the cable shall be spliced through at all intermediate splice points.
- Fiber termination connector type shall be SC ultra-polished physical contact or LC ultra-polished physical contact.
  - Mechanical fiber terminations are not permitted.
  - Connector Pigtails shall be attached to entrance cable via fusion splicing.
  - All fibers in the cable shall be terminated.
- At the designated meet point(s), Entergy will provide an all-dielectric fiber optic cable stub of sufficient length, to which the customer shall splice their fiber optic cable in a customer-provided splice enclosure appropriate to the cable and construction type.
  - This interface will be the point of demarcation for ownership and operational responsibility of the new fiber optic cable construction.
  - All fibers in the cable shall be spliced through at the point of demarcation.
- Entergy reserves the right to inspect customer-owned fiber optic facilities for compliance with these minimum requirements to ensure reliable operation of inter-company relay and communication systems.

- **Table A14.5: Summarized Fiber Optic Splice Performance Grid**

Summarized Fiber Optic Splice Performance Grid (all measurements to be recorded at 1550 nm)		
Parameter	**Measured Value**	**Action Required**
Splice Loss as estimated by Fusion Splicer:	loss ≤0.05 dB*loss ≤0.05 dB*	TARGET
	0.05 dB<loss<0.10 dB*0.05 dB<loss<0.10 dB*	acceptable
	loss ≥0.10 dB*loss ≥0.10 dB*	Break and re-splice up to three times; if no improvement, note the splice location and the fiber number for communication to Entergy.

Splice Loss as measured by OTDR:	loss ≤0.05 dB*loss ≤0.05 dB*	TARGET
	0.05 dB<loss<0.10 dB*0.05 dB<loss<0.10 dB*	acceptable
	loss ≥0.10 dB*loss ≥0.10 dB*	Note the splice location and fiber number for communication to Entergy.

Appendix B to GIA
Milestones

1. Selected Option pursuant to Article 5.1: Interconnection Customer selects the [~~_____~~]Standard Option as described in Article 5.1[~~ ~~].1. Articles 5.1[~~ ~~].2, 5.1.3, and 5.1[~~ ~~].4 shall not apply to this GIA.

2. Milestones: The description and date entries listed in the following tables are provided solely for the convenience of the Parties in establishing their applicable Milestones consistent with the provisions of this GIA and the GIP.

A. Interconnection Customer Milestones

No.	Description	Date
1a.	Provide initial payment to Transmission Owner (GIA 11.5) in form of security for $ 13,980,000 (100% of total cost of Transmission Owner Interconnection Facilities and Network Upgrades). Coordinate Initial Payment confirmation with Transmission Owner and notify Transmission Provider via email notice to gifinance@misoenergy.org.	Because Interconnection Customer and Transmission Owner are the same Party, no security is being transferred . -Completed.
1b.	Provide security, *i.e.*, a guarantee, surety bond, letter of credit or other reasonably acceptable form of security to Transmission Owner (GIA 11.6).	Not Applicable.
1c.	Enter into a Facilities Service Agreement ("FSA") as may be applicable, with Transmission Owner for the Network Upgrades associated with this GIA.	Not Applicable.

~~No.~~	~~Description~~	~~Date~~
~~1a.~~	~~Provide initial payment to Transmission Owner (GIA 11.5)~~	~~Within the later of a) 45 Calendar Days of the execution of the GIA by all Parties, or b) 45 Calendar Days of acceptance by FERC if the GIA is filed unexecuted and the payment is being protested by Interconnection Customer, or c) 45 Calendar Days of the filing if the GIA is filed unexecuted and the initial payment is~~

		~~not being protested by Interconnection Customer.~~
~~1b.~~	~~Provide security, *i.e.*, a guarantee, surety bond, letter of credit or other reasonably acceptable form of security to Transmission Owner (GIA 11.6).~~	~~45 Calendar Days prior to design, procurement and construction.~~
~~1c.~~	~~Enter into a Facilities Service Agreement ("FSA") as may be applicable, with Transmission Owner for the Network Upgrades associated with this GIA.~~	~~Within 90 Calendar Days of the Effective Date of the GIA and prior to in-service date of Network Upgrades associated with this GIA.~~
1d.	Enter into amendment of this GIA, if required, for Interconnection Requests that did not elect optional negotiation period adjustment for Interconnection Facilities Study pursuant to GIA Section 11.3.1.	Within 90 days of the posting of the final Interconnection Facilities report.
1e.	Enter into SPP JTIQ Service Agreement (if included in JTIQ Participation Group) pursuant to GIP Section 11.1.	~~Within 15 Calendar Days after tender.~~Not Applicable.
1f.	Enter into any agreement required by an Affected System for the study, construction, or funding of a network upgrade to mitigate impacts (for Interconnection Requests processed through ERAS) pursuant to GIP Section 3.5.2.	Within 15 Calendar Days after tender.
1g.	Demonstrate 100% Site Control (if not provided earlier due to qualifying regulatory limitations) or the GIA may be terminated per Article 2 of this GIA and the Interconnection Customer may be subject to Withdrawal Penalties per Section 7.6.2.1.1 of the GIP (Calculation of the Automatic Withdrawal Penalty).	Within 180 Calendar Days of the Effective Date.
2.	Provide Certificate of Insurance (GIA 18.4.9).	The earlier of the construction work commencement date or the milestone date; thereafter, within 90 Calendar Days of end of fiscal year or insurance renewal date.
3.	Provide evidence of one or more of the following milestones being achieved: (1) execution of contract for (a) fuel supply or transport;	Within 180

	(b) cooling water supply; (c) engineering procurement of major equipment or construction; (d) execution of a contract for the sale of electric energy or capacity from the Generating Facility, or a statement signed by an officer or authorized agent of Interconnection Customer attesting that the Generating Facility is included in an applicable state resource adequacy plan; or other information that Transmission Provider deems to be reasonable evidence that the Generating Facility will qualify as a designated network resource; or (2) documentation of application for state or local air, water, land, or federal nuclear or hydroelectric permits and that the application is proceeding per regulations (GIP 11.3).	Calendar Days of Effective Date.
4.	~~Provide~~ Cash Payment and security ~~in the amount of $_____~~obligations are subject to quarterly review and update by Transmission Owner; who will take into account actual costs, updated cost projections and schedule revisions and make changes to ~~commence design, equipment procurement and construction for~~ the Interconnection ~~Facilities (GIA 5.5 and 5.6).~~Customer's Cash Payments and security obligations as required.	~~As may be agreed to by the Parties.~~Because Interconnection Customer and Transmission Owner are the same Party, no security or cash is being provided.
5.	Invoice Transmission Owner for the estimated amount to be expended by the Interconnection Customer to construct any Stand Alone Network Upgrades for which the Interconnection Customer has exercised its Option to Build if the Transmission Owner has elected to Self Fund (GIA 5.2.13).	~~As may be agreed to by the Parties, but in no event later than 45 Calendar Days prior to the date the Interconnection Customer must make any construction payment.~~Not Applicable.
6.	Pre-construction meeting.	As may be agreed to by the Parties.
7.	Provide initial design and specifications for Interconnection Customer's Interconnection Facilities to Transmission Owner and Transmission Provider for comment (GIA 5.10.1).	180 Calendar Days prior to initial synchronization date.
8.	Provide final design and specifications for Interconnection Customer's Interconnection Facilities to Transmission Owner and Transmission Provider for comment (GIA 5.10.1).	90 Calendar Days prior to initial

		synchronization date.
9.	Deliver to Transmission Owner and Transmission Provider "as-built" drawings, information and documents regarding Interconnection Customer's Interconnection Facilities (GIA 5.10.3).	Within 120 Calendar Days of Commercial Operation Date.
10.	Provide Transmission Owner final cost invoices to construct Stand Alone Network Upgrades for which the Interconnection Customer has exercised its Option to Build if the Transmission Owner has elected to Self Fund (GIA 5.2.13).	~~Within six (6) months of completion.~~Not Applicable.
~~10a.~~	~~Transfer ownership of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades to Transmission Owner if Interconnection Customer has exercised the Option to Build (GIA 5.2.9).~~	~~As agreed to by the Parties but in no event later than the earlier of energization or three days prior to the Initial Synchronization Date.~~
~~10b.~~	~~Refund overpayment, if any, of estimated costs to construct any Stand Alone Network Upgrades for which the Interconnection Customer has exercised its Option to Build if the Transmission Owner has elected to Self Fund (GIA 5.2.13).~~	~~Within 30 Calendar Days after submitting invoice for final costs under Milestone 10.~~
11.	Notify Transmission Provider and Transmission Owner in writing of Local Balancing Authority where Generating Facility is located (GIA 9.2).	~~Three~~Nine months prior to Initial Synchronization Date.
12.	Pre-energization meeting.	As may be agreed to by the Parties.
13.	Initial Synchronization Date.	~~As agreed to by the Parties.~~08/05/2028
14.	Commercial Operation Date.	~~As agreed to by the Parties.~~08/06/2028
15.	Interconnection Customer shall provide the Parties with notice on the status of the Generating Facility, including COD, under Article 15 of this GIA and shall also send such notice by email to ~~ResourceIntegration@misoenergy.org.~~ResourceIntegration@misoener	6 months prior to Initial Synchronization Date.

	gy.org. Notification shall include Interconnection Customer's name, and as applicable Market Participant(s) name(s), and project number.	
16.	Interconnection Customer shall provide notice to the Parties of a test plan in advance of conducting tests for the Generating Facility. The notice shall be in the form below and should be provided under Article 15 of this GIA, and a copy of such notice should be emailed to ~~ResourceIntegration@misoenergy.org.~~ResourceIntegration@misoenergy.org.	5 Business Days prior to testing.
17.	In the event the Interconnection Customer makes any modifications to the design of the site layouts or interconnection facility routes after execution of this GIA, Interconnection Customer shall notify the Parties of such changes immediately upon identifying the need for such changes. After providing such notification, the Interconnection Customer shall provide to Transmission Provider evidence of continued Site Control for land sufficient to accommodate the changes in site layouts and/or interconnection facility routes (GIP 7.2.2).	90 Calendar Days after Interconnection Customer provides notice to Parties.

~~**B. Transmission Owner Milestones**~~

18.	Provide TO a PSCAD Model and a PSCAD Model Parameter Verification Report. This report shall provide evidence that tunable parameters match what is implemented in the field. Evidence can take the form of screenshots, nameplate photographs, signed manufacturer commissioning reports, parameter dump file, etc. All of these must be cross referenced with the settings in the PSCAD model. Field tunable parameters should be identified by the manufacturer but should include at a minimum, protection settings, ride through settings and any tunable control gains. Evidence must also be provided that proves the PSCAD PPC model has all communication delays, any sample and hold type outputs and all gains that are in the field. This must be confirmed with voltage step tests in the field and in PSCAD. The PPC must be tuned to work over a range of expected SCRs.	30 days prior to Commercial Operation Date.

B. Transmission Owner Milestones

No.	Description	Date
0.	Transmission Owner to enter Network Upgrade information into Transmission Provider's MTEP database and model on demand.	10 Business Days after Effective Date.
1.	Provide Certificate of Insurance (GIA 18.4.9).	The earlier of the construction work commencement date or the milestone date; within 90 Calendar Days of end of fiscal year or insurance renewal date.
2.	• Commence design of Interconnection Facilities (GIA 5.5 et seq.). • Commence equipment procurement.	As agreed to by the Parties (after completion of Interconnection Facilities Study, receipt of written authorization from Interconnection Customer and Interconnection Customer's deposit of security.
3.	Commence construction of Interconnection Facilities (GIA 5.6 et seq.).	As agreed to by the Parties (after receiving approval of Governmental Authority, receipt of written authorization and security from Interconnection Customer).
4.	Comment on Interconnection Customer's final design and specifications.	Within 30 Calendar Days of Interconnection Customer's submission of final design and specifications.
5.	Deliver to Interconnection Customer and Transmission Provider "as-built" drawings, information and documents regarding Transmission Owner's Interconnection Facilities (GIA 5.11).	Within 120 Calendar Days of Commercial Operation Date.
6.	Provide payment for invoiced estimated costs to construct for which the Interconnection Customer has exercised its Option to Build if the Transmission Owner has elected to Self Fund (GIA 5.2.13).	~~Within 30 Calendar Days of receipt of Interconnection Customer's invoice for estimated costs.~~Not Applicable.
~~6a.~~	~~Provide payment for invoiced final cost to construct Stand Alone Network Upgrades for which the Interconnection Customer has exercised its Option to Build if the Transmission Owner has elected to Self Fund (GIA 5.2.13).~~	~~Within 30 Calendar Days of receipt of Interconnection Customer's invoice for final costs.~~

7.	Provide Interconnection Customer final cost invoices (GIA 12.2 *et seq.*).	Within (6) six months of completion.
8.	Refund overpayment of estimated costs (GIA 12.2).	~~90 Calendar Days prior to initial synchronization date.~~ Refunds within 30 Calendar Days after final invoice.
9.	In-Service Date/Backfeed Date.	~~As agreed to by the Parties.~~08/04/2028

C. Affected System Owner Milestones

~~Task~~**No.**	**Description**	**Date** ~~Due~~
1	Affected Systems Studies have not concluded as of the date of this EGIA. Interconnection Customer is responsible for executing and fulfilling the obligations of any agreements for the study, construction, or funding of Affected System network upgrades identified by the Affected System after execution of this GIA.	Execute agreements tendered by the affected system within fifteen (15) Calendar Days of tender.

Appendix B-1 to GIA
Pre-Certification Generation Test Notification Form

The following form would need to be submitted to MISO Real Time Operations at least five (5) Business Days prior to the first date of testing.

Project Number:

Project Name:

Point of Interconnection:

Dispatcher Contact Information:

Date	Start Time (in EST)	End Time (in EST)	Expected MW Output	Expected MVAR Output (Only needed if beyond normal power factor)

Appendix C to GIA
Interconnection Details

This Appendix C is a part of this GIA among Interconnection Customer, Transmission Owner and Transmission Provider.

~~1. Transmission Owner shall provide the following "as-built" drawings, information and documents regarding the Transmission Owner's Interconnection Facilities pursuant to Article 5.11 of this GIA.~~

~~2~~1. The unique requirements of each generation interconnection will dictate the establishment of mutually agreeable Interconnection and/or Operating Guidelines that further define the requirements of this GIA. The Interconnection and/or Operating Guidelines applicable to this GIA consist of the following information. Additional detail may be provided through attachment to this Appendix C or through electronic means via the web address specified.

(a) System Protection Facilities;
(b) Communication requirements;
(c) Metering requirements;
(d) Grounding requirements;
(e) Transmission Line and Substation Connection configurations;
(f) Unit Stability requirements;
(g) Equipment ratings;
(h) Short Circuit requirements;
(i) Synchronizing requirements;
(j) Generation and Operation Control requirements;
(k) Data provisions;
(l) Energization inspection and testing requirements; and
(m) Control equipment, if any.

~~3~~

Entergy Facility Connection Requirements website:
http://www.entergy.com/energydelivery/facility_requirements.aspx

Reference material regarding the Entergy Facility Connection Requirements can be found on the two (2) links below located on the above mentioned web address.

(1) Entergy Facilities Connection Requirements Document, March 2007; and
(2) Entergy Facilities Connection Spreadsheet, October 2008.

In the event that the Interconnection and/or Operating Guidelines conflict with this GIA, this GIA will govern.

2. Information required pursuant to Section 8.4 for Variable Energy Resource Generating Facilities:

~~_____.~~ _____.

Not Applicable

Appendix D to GIA
Security Arrangements Details

Infrastructure security of Transmission or Distribution System equipment and operations, as applicable, and control hardware and software is essential to ensure day-to-day Transmission and Distribution System reliability and operational security. The Commission will expect all Transmission Providers, market participants, and Interconnection Customers interconnected to the Transmission or Distribution System, as applicable, to comply with the recommendations provided by Governmental Authorities regarding Critical Energy Infrastructure Information ("CEII") as that term is defined in 18 C.F.R. Section 388.113(c) and best practice recommendations from the electric reliability authority. All public utilities will be expected to meet basic standards for system infrastructure and operational security, including physical, operational, and cyber-security practices.

Appendix E to GIA
Commercial Operation Date

This Appendix E is a part of this GIA between Transmission Provider, Transmission Owner and Interconnection Customer.

[Date]

Midcontinent Independent System Operator, Inc.
Attn: Director, Transmission Access Planning
720 City Center Drive
Carmel, IN 46032

Re: _____ Generating Facility

Dear _____:

On **[Date] [Interconnection Customer]** has completed Trial Operation of Unit No. ___. This letter confirms that **[Interconnection Customer]** commenced commercial operation of Unit No. ___ at the Generating Facility, effective as of **[Date plus one Calendar Day]**.

Thank you.

[Signature]

[Interconnection Customer Representative]

cc: Transmission Owner

Appendix F to GIA
Addresses for Delivery of Notices and Billings

Notices:

Transmission Provider:

MISO
Attn: Director, Transmission Access Planning
720 City Center Drive
Carmel, IN 46032

Transmission Owner:

~~[To be supplied.]~~

Entergy Services, LLC
Attn: Sr Manager, Interconnection Planning and Customer~~:~~ Service

~~[To be supplied.]~~
9585 Pecue Blvd
Baton Rouge, LA 70818

Interconnection Customer:

Entergy Services, LLC
Attn: Power Development/Jonathan Alvis
2107 Research Forest Drive
The Woodlands, TX 77380

Billings and Payments:

Transmission Provider:

MISO
Attn: Director, Transmission Access Planning
720 City Center Drive
Carmel, IN 46032

Transmission Owner:

~~[To be supplied.]~~

Entergy Louisiana, LLC
P.O. Box 679505

Dallas, TX 75267-9505

Interconnection Customer:

~~[To be supplied.]~~
Entergy Louisiana, LLC
Attn: Miscellaneous Accounts Receivable
P.O. Box 679505
Dallas, TX 75267-9505

Alternative Forms of Delivery of Notices (telephone, facsimile or email):

Transmission Provider:

Phone: (317) 249-5700
Email: misotap@misoenergy.org or
MISOTransmissionAccessPlanning@misoenergy.org

Transmission Owner:

~~[To be supplied.]~~
Entergy Services, LLC
Voice telephone: (504)-576-7940
Email address: GIA@entergy.com

Interconnection Customer:

~~[To be supplied.]~~
Entergy Louisiana, LLC
Voice telephone: (281) 719-7109
Email: jalvis@entergy.com

Entergy Louisiana, LLC
Attn: Sr Manager, Resource Planning
4809 Jefferson Highway
Jefferson LA 70121

Appendix G to GIA
Interconnection Requirements for Inverter-Based Resource Plants

Appendix G sets forth requirements and provisions specific to inverter-based resource (IBR) plants. Transmission Owner Local Planning Criteria for IBR performance may differ from Appendix G requirements. In such cases, Transmission Owner Local Planning Criteria shall supersede the Appendix G requirements and be documented in Appendix C of this GIA[1]. All other requirements of this GIA also apply to IBR plant interconnections. *IBR plants* shall meet both Applicable Reliability Standards and Appendix G requirements. Battery energy storage systems required to furnish grid-forming controls shall be exempt from specific IEEE 2800 requirements as outlined in the BPM for Generator Interconnection. Italicized terms indicate IEEE 2800-2022 defined terms[2]. IEEE 2800-2022's definitions will govern these italicized terms unless otherwise defined herein.

A. General

The *IBR plant* shall adhere to IEEE 2800-2022 Clause 4 requirements, except for subclauses 4.1 (introduction), 4.5 (operational measurement and communication capability), 4.6 (control capability requirements), 4.8 (isolation devices), 4.9 (inadvertent energization of TS), 4.11 (interconnection integrity), and 4.12 (integration with TS grounding).

Within the adopted IEEE 2800-2022 Subclauses, the following requirements shall be incorporated as Transmission Provider and Transmission Owner[3] specification options noted in IEEE 2800-2022.

- Subclause 4.2.1: The *reference point of applicability* (RPA) shall be at the *point of measurement* (POM) bus with the exception of requirements specified in Clauses 7.2.2.3.4 and 7.2.2.3.5 of the standard to have the RPA at the *point of connection* (POC).

- Subclause 4.3: The Transmission Owner shall specify the nominal voltage and frequency at the RPA in Appendix C of this GIA.

- Subclause 4.10.2: The *enter service* criteria shall use the default values for *applicable voltages* and *applicable frequency* specified in the table below unless otherwise specified in Appendix C of this GIA[4].

---

[1] IEEE 2800-2022 points to "weak grid" issues requiring exceptions to default values and ranges of available settings for various types of performance. IEEE 2800-2022 Annex C.2 contains discussion on characterizing weak grid areas.

[2] "IEEE Standard for Interconnection and Interoperability of Inverter-Based Resources (IBRs) Interconnecting with Associated Transmission Electric Power Systems," in IEEE Std 2800-2022 , vol., no., pp.1-180, 22 April 2022, doi: 10.1109/IEEESTD.2022.9762253.

[3] For the purpose of this GIA, the IEEE 2800 term of *TS operator* is synonymous with Transmission Owner and the IEEE 2800 term of *TS owner* is synonymous with Transmission Planner or Transmission Owner, as applicable.

[4] MISO default values may be modified within the IEEE 2800 range of allowable settings by Transmission Owner Local Planning Criteria.

Enter service criteria	Default setting
Applicable voltage, minimum value	0.9 p.u.
Applicable voltage, maximum value	1.05 p.u.
Applicable frequency, minimum value	58.8 Hz
Applicable frequency, maximum value	60.12 Hz.

- Subclause 4.10.3: The performance during *enter service* shall use the default values specified below unless otherwise specified in Appendix C of this GIA.

  - The minimum intentional delay performance, as defined in Subclause 4.10.3, b), shall be 0 seconds.

  - The duration of the *enter service* period, as defined in Subclause 4.10.3, c), shall be 300 seconds.

B. Response to Abnormal Conditions

The *IBR plant* shall adhere to IEEE 2800-2022 Clause 7 requirements, except for subclauses 7.2.1 (voltage protection) and 7.3.1 (mandatory frequency tripping). Where Applicable Reliability Standards require more stringent ride-through requirements compared to IEEE 2800-2022 Clause 7 requirements, those standards shall take precedence[5].

Within the adopted IEEE 2800-2022 Subclauses, the following requirements shall be incorporated as the Transmission Provider and Transmission Owner decision points[6] noted in IEEE 2800-2022.

- Subclause 7.2.2.1: The Transmission Owner shall specify the nominal voltage for use by this clause. Nominal voltages may include nominal transmission system voltages that are different from standard ANSI C84.1-2016 voltages.

- Subclause 7.2.2.2: If the *IBR plant* cannot deliver both active and reactive power due to its current limit (or apparent power limit), when the *applicable voltage* is below 95%, then preference shall be given to reactive power while minimizing any reductions in active power.

- Subclause 7.2.2.3: The *IBR plant* shall give preference to reactive power unless otherwise specified in Appendix C of this GIA. In addition, the *IBR plant* shall minimize reductions in active power while carrying out the reactive current priority mode response.

[5] More stringent ride-through requirements include, but are not limited to, expanded voltage and frequency conditions or extended cumulative times under which *IBR plants* must ride-through.

[6] Decision points refer to language in the IEEE 2800-2022 standard that leaves default values, application of requirements, and other details open for the *TS Owner* or *TS Operator* to define.

- Subclause 7.2.2.3.4: The Interconnection Customer shall submit the *IBR plant* controls default relationship between the magnitude of incremental positive and negative sequence reactive currents. The Transmission Provider and Transmission Owner, through this agreement, may specify a required *IBR plant* response relationship between the incremental positive and negative sequence reactive currents.

C. Reactive Power

The *IBR plant* shall adhere to IEEE 2800-2022 Clause 5 requirements.

Within the adopted IEEE 2800-2022 Subclauses, the following requirements shall be incorporated as the Transmission Provider and Transmission Owner decision points noted in IEEE 2800-2022.

- Subclause 5.1: The *IBR plant* shall have the reactive power capabilities outlined in this clause. Consistent with section 9.6.1 of this GIA, an *IBR plant* shall maintain a power factor within the range of 0.95 leading to 0.95 lagging, unless Transmission Provider has established different requirements that apply to all Generating Facilities in the Local Balancing Authority on a comparable basis, measured at the high side of the generator substation.

- Subclause 5.2.2: The voltage control dynamic performance requirements in Table 5 shall apply when the system short-circuit strength at the RPA is equal to or above the minimum short-circuit strength identified by the Transmission Provider or Transmission Owner.

- Subclause 5.2.2: The *reaction time*, as defined in Subclause 5.2.2 Table 5, shall be 250 milliseconds or less.

- Subclause 5.2.2: The maximum *step response time*, as defined in Subclause 5.2.2 Table 5, shall be 30 seconds.

- Subclause 5.2.3: The power factor control mode shall appropriately operate at all active power levels from the Inverter Based Resource Continuous Rating ("ICR") down to, but not including, zero.

D. Primary Frequency Response

The *IBR plant* shall adhere to IEEE 2800-2022 Clause 6 requirements, except for Subclause 6.2 (fast frequency response).

Within the adopted IEEE 2800-2022 Subclauses, the following requirements shall be incorporated as the Transmission Provider and Transmission Owner decision points noted in IEEE 2800-2022.

- Subclause 6.1.1: The use of primary frequency response capabilities shall be required for all *IBR plants.*
- Subclause 6.1.1: Frequency droop shall be based on the difference between nameplate capacity and zero output such that the slopes of the droop curves are always constant.
- Subclause 6.1.2: The *settling band* default value in Table 8 shall be based on the maximum of 2.5% of change or 0.5% of nameplate capacity.

The exceptions to primary frequency response requirements provided to electric storage resources in Article 9.6.4.4 of this GIA shall still apply.

TABLE 2. SUMMARY OF ADOPTION TREATMENT OF IEEE 2800-2022 SUBCLAUSES

IEEE 2800-2022 Subclause	Required by Appendix G for DPP-2022 and later	Required by Appendix G for DPP-2023 and later	Exception
4.1 Introduction			**X**
4.2 Reference Point of Applicability	**X**		
4.3 Applicable Voltages and Frequencies	**X**		
4.4 Measurement Accuracy	**X**		
4.5 Operational Measurement and Communication Capability			**X**
4.6 Control Capability			**X**
4.7 Prioritization of IBR Responses	**X**		
4.8 Isolation Devices			**X**
4.9 Inadvertent Energization of TS			**X**
4.10 Enter Service	**X**		
4.11 Interconnection Integrity			**X**
4.12 Integration with TS grounding			**X**
5.1 Reactive Power Capability		**X**	
5.2 Voltage and Reactive Power Modes		**X**	
6.1 Primary Frequency Response		**X**	
6.2 Fast Frequency Response			**X**
7.1 Introduction	**X**		
7.2.1 Voltage protection			**X**
7.2.2.1 Voltage disturbance ride-through: General	**X**		
7.2.2.2 Voltage disturbances within continuous operation	**X**		

7.2.2.3 Low- and high-voltage ride-through	**X**		
7.2.2.4 Consecutive voltage deviations ride-through		**X**	
7.2.2.5 Dynamic voltage support	**X**		
7.2.2.6 Restore output after voltage ride-through	**X**		
7.2.3 Transient overvoltage	**X**		
7.3.1 Mandatory frequency tripping			**X**
7.3.2 Frequency disturbance ride-through	**X**		
7.4 Return to service	**X**		

E. Supervisory Control and Data Acquisition (SCADA) Capability

The *IBR plant* shall provide SCADA capability to transmit data and receive instructions from Transmission Provider to protect system reliability. Transmission Provider and Interconnection Customer shall determine what SCADA information is essential for the proposed *IBR plant*, taking into account the size of the plant and its characteristics, location, and importance in maintaining generation resource adequacy and transmission system reliability in its area.

F. Disturbance Monitoring and Reporting Requirements

IBR plants with generating capacities of more than 20 MW must monitor and record data for all frequency ride-through events, transient low-voltage disturbances that initiated reactive current injection, reactive current injection or momentary cessation for transient high-voltage disturbances, and inverter trips. Dynamic Disturbance Recording ("DDR") data must be recorded continuously. The data may be recorded and stored in a central plant control system. The following data must be recorded:

Plant Level

(1) Plant three-phase voltage, current and power factor

(2) Status of ancillary reactive devices

(3) Status of all plant circuit breakers

(4) Status of plant controller

(5) Plant control set points

(6) Status of main plant transformer no load taps

(7) Status of main plant transformer tap changer (if applicable)

(8) Protective relay trips (relay target data)

Inverter Level Data

(1) Frequency, current, and voltage during frequency ride-through events

(2) Voltage and current during momentary cessation for transient high-voltage events (when used)

(3) Voltage and current during reactive current injection for transient low or high-voltage events

(4) Inverter alarm and fault codes

(5) DC current

(6) DC voltage

DDR Data – Plant Level

(1) One phase-to-neutral or positive sequence voltage on high-side of the main power transformer(s)

(2) Positive sequence current or phase current for the same phase as (1)

(3) Real and reactive power flows expressed on a three-phase basis corresponding to each main power transformer(s) where current measurements are required

(4) Frequency of any one of the voltages in (1)

The data must be time synchronized to a one millisecond level of resolution. All data except DDR data must be sampled at least every 10 milliseconds. DDR data must have an input sampling rate of at least 960 samples per second and an output recording rate of electrical quantities of at least 60 times per second.

The *IBR plant* shall store this data for a minimum of 60 calendar days. The *IBR plant*, upon request from MISO or the transmission owner, shall make this data available within 10 calendar days of the request.

Phasor measurement unit ("PMU") capabilities shall be used to facilitate the DDR data.

G. Applicability

IBR plants that are, or have been, interconnected to the network at the effective date of the Appendix G abnormal voltage ride-through standard are exempt from meeting the Appendix G abnormal voltage ride-through standard for the remaining life of the existing generation

equipment. Except for *IBR plants* actively undergoing a Generating Facility Replacement at the effective date of this GIA that have equipment on order where the OEM has documented performance that differs from what is required in this GIA, all individual IBR units that are replaced are required to meet the Appendix G performance requirements.

The IEEE 2800-2022 requirements cited in Section A (IEEE 2800-2022 Clause 4) and Section B (IEEE 2800-2022 Clause 7, except Subclause 7.2.2.4) of Appendix G shall apply to *IBR plants* in the DPP-2022-Cycle and beyond. For the DPP-2022-Cycle, Interconnection Customers may request exceptions confined to these sections only if specific limitations or uncertainties of equipment or plant capabilities prevent implementation of these requirements. GIAs signed or amended with inverter changes on or after January 1, 2025, are not eligible for requirement exceptions. Further, the process for establishing exceptions for these requirements shall not apply beyond the DPP-2022-Cycle.

The IEEE 2800-2022 requirements cited in Section B (IEEE 2800-2022 Subclause 7.2.2.4), Section C (IEEE 2800-2022 Clause 5), and Section D (IEEE 2800.2022 Clause 6) of Appendix G shall apply to *IBR plants* in the DPP-2023-Cycle and beyond. For the DPP-2023-Cycle, Generating Facilities Replacements, and Surplus Interconnections, Interconnection Customers may request exceptions confined to these sections only if specific limitations or uncertainties of equipment or plant capabilities prevent implementation of these requirements. GIAs signed or amended with inverter changes on or after January 1, 2026, are not eligible for requirement exceptions. Further, the process for establishing exceptions for these requirements shall not apply beyond the DPP-2023-Cycle.

Interconnection Customers requesting exceptions shall submit documentation to the Transmission Provider outlining the specific IEEE 2800-2022 subclauses pertinent to the request along with information from the manufacturer regarding the nature of the issue conforming to or assessing conformance with requirements herein. The Transmission Provider will, in good faith, accept Original Equipment Manufacturer (OEM)-documented requirement exceptions and document these exceptions in Appendix C of this GIA.

If the performance or capability exception can be mitigated through equipment firmware upgrades still under development, the Interconnection Customer shall use commercially reasonable efforts to implement the firmware upgrade within sixty (60) calendar days of commercial availability of such firmware.

The DDR and PMU requirements in the Section F, Disturbance Monitoring and Reporting Requirements of Appendix G shall apply to *IBR plants* in the DPP-2023-Cycle and beyond.

Appendix H to GIA – Not Applicable
Interconnection Requirements for Provisional GIA

Provisional Agreement

This GIA is being provided in accordance with Section 11.5 of the Transmission Provider's GIP, which provides among other things, that an Interconnection Customer may request that Transmission Provider provide Interconnection Customer with a Provisional Generator Interconnection Agreement that limits the transfer of energy by Interconnection Customer commensurate with that allowed for Energy Resource Interconnection Service. Interconnection Customer requested Transmission Provider to provide a Provisional Generator Interconnection Agreement for limited operation at the discretion of Transmission Provider based upon the results of available studies (by Interconnection Customer and by Transmission Provider).

A Provisional Interconnection Study, the results of which are posted on the confidential portion of the Transmission Provider's internet website, was performed by Transmission Provider in order to confirm the facilities that are required for provisional Interconnection Service and to require them to be in place prior to commencement of service under the GIA.

Interconnection Customer represents that the Interconnection Customer facilities (including Network Upgrades, Interconnection Facilities, Distribution Upgrades, System Protection Upgrades and/or Generator Upgrades) that are necessary to commence provisional Interconnection Service and meet the requirements of the Electric Reliability Organization, or any applicable regional entity for the interconnection of a new generator are in place prior to the commencement of generation from the Generating Facility and will remain in place during the term of the service. The requisite Interconnection Studies were performed for the Generating Facility. Interconnection Customer shall meet any additional requirements (including reactive power requirements) pursuant to the results of applicable future Interconnection System Impact Studies. Until such time as the applicable Interconnection Studies and any identified facilities are completed, the output of the Generating Facility will operate within the output limit prescribed in a future, if applicable, operating guide.

The maximum permissible output of the Generating Facility under Appendix A will be updated by Transmission Provider on a quarterly basis, determined in accordance with Section 11.5 of the GIP, by finding the transfer limit of energy commensurate with the analysis for Energy Resource Interconnection Service ("ERIS"). This study shall be performed assuming the system topology represented by the base cases used to calculate Available Flowgate Capability, as described in Attachment C of the Tariff, with dispatch and optimization algorithms posted on the MISO internet site and operation above those limits will be deemed as unauthorized use of the Transmission System and subject to provisions in the Tariff surrounding that use.

Use of interim operating guide

Implementation of interim operating guide, if applicable, will constitute an interim solution that will permit Interconnection Customer to operate the Generating Facility under conditional Interconnection Service until planned Network Upgrades are constructed. Any interim operating

guide will be subject to the approval of Transmission Owner and Transmission Provider. Minimum requirements for an interim operating guide are as indicated below.

* Transmission Operator will have control of breaker(s) dedicated to the Generating Facility and will be able to trip the Interconnection Customer's Generating Facility
* Protection schemes must be tested and operative
* Interconnection Customer will provide continuous communication capability with the Generator Operator
* Interconnection Customer and the owner of the Existing Generating Facility will enter into an operating agreement or similar agreement which designates, among other things, the responsibilities and authorities of each of the parties and shall be subject to the acceptance of Transmission Provider and Transmission Owner.
* A termination date consistent with completion of construction of Network Upgrades will be included as part of all operating guides accepted by Transmission Owner and Transmission Provider.

Interconnection Customer assumes all risks and liabilities with respect to changes, which may impact the Generator Interconnection Agreement including, but not limited to, change in output limits and responsibilities for future Network Upgrade and cost responsibilities that have not yet been identified on the direct connect Transmission System as well as all affected Transmission, Distribution or Generation System(s) including non-Transmission Provider Systems. Such upgrades will be determined pursuant to the Tariff and Policies in effect at the time of the Interconnection Studies.

Appendix I to GIA – Not Applicable
Requirements Applicable to Surplus Interconnection Service

Where this GIA provides for Surplus Interconnection Service, Interconnection Customer acknowledges, agrees to, and will be required to operate under the following conditions:

1) The combined Real-Time Offers, including Energy and Operating Reserves, of the Generating Facility and the Existing Generating Facility with which Interconnection Customer has an executed Energy Displacement Agreement must be less than or equal to Interconnection Service limit (MW, MVAR, MVA output) provided in Exhibit I-1 (Monitoring and Consent Agreement) (hereinafter, "Interconnection Service limit"). In the event that the sum of the simultaneous energy output of the Surplus Interconnection Service Generating Facility and the Existing Generating Facility exceeds such Interconnection Service limit, MISO reserves the right to curtail and/or disconnect the Generating Facility immediately.

   In the event that the sum of the emergency and/or economic maximum offer limits of the Generating Facility and the Existing Generating Facility exceeds the Interconnection Service limit, MISO reserves the right to curtail and/or disconnect the Generating Facility immediately.
2) The total MW, MVAR, MVA output at the Point of Interconnection resulting from the combined output of the Generating Facility with Surplus Interconnection Service and the Existing Generating Facility with which Interconnection Customer has an executed Energy Displacement Agreement shall not at any time exceed the Interconnection Service limit.

3) The Existing Generating Facility with which Interconnection Customer has an executed Energy Displacement Agreement is not relieved of any applicable requirements under the RAR of the Tariff.

4) The Interconnection Customer shall submit to the Transmission Provider a report by the seventh Calendar Day of each month showing the prior month's output, by 15 minute increment, the combined real-time offers and cleared energy injection. The Existing Generating Facility and the Interconnection Customer shall cooperate consistent with other provisions in the Tariff to the extent necessary to ensure accuracy of the report. Transmission Provider shall provide a template for this report.

Exhibit I-1 (Completed Monitoring and Consent Agreement - Appendix 11 of the GIP)

Exhibit I-2 (Completed Energy Displacement Agreement - Appendix 12 of the GIP)

TAB C

UNITED STATES OF AMERICA
BEFORE THE
FEDERAL ENERGY REGULATORY COMMISSION

Case Name **) Docket No.**

PROTECTIVE AGREEMENT

1. This Protective Agreement shall govern the access to, and use of all Privileged Materials and Critical Energy Infrastructure Information ("CEII") produced by, or on behalf of, any Participant.

2. Notwithstanding any order terminating this proceeding, this Protective Agreement shall become effective as of the date the attached Non-Disclosure Certificate is executed and shall remain in effect until specifically modified or terminated by the Federal Energy Regulatory Commission ("Commission").

3. Definitions – For purposes of this Protective Agreement:

(a) The meaning of the term "Participant" shall be as defined at 18 C.F.R. § 385.102(b).

(b) The term "Privileged Materials" includes those materials, and information contained therein, which customarily are treated as sensitive or proprietary, which are not available to the public, and which, if disclosed publicly, would subject the Participant or its customers to risk of competitive disadvantage or other business injury. Privileged Materials may include: (A) materials designated by a Participant as "Privileged Materials"; (B) any information contained in or obtained from such designated materials in (A); (C) any other materials which are made subject to this Protective Agreement by the Presiding Judge or the Chief Judge, by the Commission, by any court or other body having appropriate authority, or by agreement of the Participants; (D) notes of Privileged Materials (notes means memorandum, summaries, or other documents produced by a Participant or Reviewing Representative as a part of their review of the Privileged Materials) ("Notes of Privileged Materials"); and (E) copies of Privileged Materials. The Participant producing the Privileged Materials shall physically mark them on each page as "PRIVILEGED MATERIALS" or with words of similar import as long as the term "Privileged" is included in that designation to indicate that they are Privileged Materials.

(c) The meaning of the term "CEII" shall be as defined at 18 C.F.R. § 388.113(c). In producing a document that contains CEII, a Participant shall label the document in conformance with the requirements of this Protective Agreement, including but not limited to the requirements of Paragraphs 12 and 20 hereof. For the purposes of this Protective Agreement, documents that are labeled in conformance with the requirements of Paragraphs 12 and 20 are defined as "Designated CEII."

(d) The term "Non-Disclosure Certificate" shall mean the certificate annexed hereto by which Reviewing Representatives who have been granted access to Designated CEII or Privileged Materials shall certify their understanding that such access is provided pursuant to the terms and restrictions of this Protective Agreement, and that such Reviewing Representatives have read the Protective Agreement and agree to be bound by it. All executed Non-Disclosure Certificates shall be served on all Participants on the official service list maintained by the Secretary of the Commission in this proceeding.

(e) The term "Reviewing Representative" shall mean a person who has signed a Non-Disclosure Certificate and who is:

(1) a member of the Commission Trial Staff;

(2) an attorney who has made an appearance in this proceeding for a Participant;

(3) attorneys, paralegals, and other employees associated for purposes of this proceeding with an attorney who has made an appearance in this proceeding for a Participant;

(4) an expert or an employee of an expert retained by a Participant for the purpose of advising, preparing for, submitting evidence, or testifying in this proceeding;

(5) a person designated as a Reviewing Representative by order of the Presiding Judge or the Chief Judge or the Commission; or

(6) employees or other representatives of Participants with significant responsibility for this docket.

4. All Privileged Materials and Designated CEII shall be made available under the terms of this Protective Agreement only to Participants and only through their Reviewing Representatives as provided in Paragraphs 6–10.

5. All Privileged Materials and Designated CEII shall remain available to Participants until an order terminating this proceeding becomes no longer subject to judicial review, or

another date specifically designated by the Commission or the Presiding Judge. If requested to do so in writing after that date, the Participants shall, within fifteen (15) days of such request, return the Privileged Materials and the Designated CEII to the Participant that produced them, or shall destroy the materials, except that copies of filings, official transcripts and exhibits in this proceeding that contain Privileged Materials or Designated CEII, and Notes of Privileged Material may be retained, if they are maintained in accordance with Paragraph 6 below. Within such time period each Participant, if requested to do so, shall also submit to the producing Participant an affidavit stating that, to the best of its knowledge, all Privileged Materials, Designated CEII and all Notes of Privileged Materials have been returned or have been destroyed or will be maintained in accordance with Paragraphs 6-7. To the extent Privileged Materials and Designated CEII are not returned or destroyed, they shall remain subject to the Protective Agreement or any superseding protective agreement or protective order.

6. All Privileged Materials and Designated CEII shall be maintained by the receiving Participant or Reviewing Representatives in a secure place. Access to those materials shall be limited to those Reviewing Representatives specifically authorized pursuant to Paragraphs 8–9. The Secretary shall place any Privileged Materials and Designated CEII filed with the Commission in a non-public file. By placing such documents in a non-public file, the Commission is not making a determination of any claim of privilege or whether the materials actually meet the definition of CEII. The Commission retains the right to make determinations regarding any claim of privilege and the discretion to release information necessary to carry out its jurisdictional responsibilities. For documents submitted to Commission Trial Staff ("Staff"), Staff shall follow the notification procedures of 18 C.F.R. § 388.112 before making public any Privileged Materials or Designated CEII.

7. All Privileged Materials and Designated CEII shall be treated as confidential by each Participant and by the Reviewing Representative in accordance with the Non-Disclosure Certificate executed pursuant to Paragraph 9 and shall be afforded the same protections that the Participant or Reviewing Representative affords to its own similarly situated confidential information. A Participant or Reviewing Representative shall promptly notify the other Participants if it has cause to believe that the Privileged Materials or Designated CEII have been disclosed, including if that disclosure was inadvertent or the result of a breach. All Privileged Materials and Designated CEII shall not be used except as necessary for the conduct of this proceeding, nor shall they be disclosed in any manner to any person except a Reviewing Representative who is engaged in the conduct of this proceeding and who needs to know the information in order to carry out that person's responsibilities in this proceeding.

8. (a) If a Reviewing Representative's scope of employment includes the marketing of energy, the direct supervision of any employee(s) whose duties include the marketing of energy, or the provision of consulting services to any person whose duties include the marketing of energy, such Reviewing Representative may not use information contained in any Privileged Materials or Designated CEII to give any Participant or any

competitor of any Participant a commercial advantage.

(b) In the event that a Participant wishes to designate as a Reviewing Representative a person not described in Paragraph 3(e) above, the Participant shall seek agreement from the Participant providing the Privileged Materials or Designated CEII. If an agreement is reached, that person shall be a Reviewing Representative pursuant to Paragraph 3(e) above with respect to those materials. If no agreement is reached, the Participant shall submit the disputed designation to the Presiding Judge for resolution.

9. (a) A Reviewing Representative shall not be permitted to inspect, participate in discussions regarding, or otherwise be permitted access to Privileged Materials or Designated CEII pursuant to this Protective Agreement unless that person has first executed a Non-Disclosure Certificate; provided, that if an attorney is a Reviewing Representative, the paralegals, secretarial and clerical personnel under the attorney's instruction, supervision or control need not execute a Non-Disclosure Certificate. A copy of each Non-Disclosure Certificate shall be provided to counsel for the Participant 3 days prior to disclosure of any Privileged Material or Designated CEII to that Reviewing Representative, thus providing an opportunity to object to the disclosure.

(b) Attorneys qualified as Reviewing Representatives shall be responsible for ensuring that persons under their supervision or control comply with this Protective Agreement.

10. Any Reviewing Representative may disclose Privileged Materials or Designated CEII to any other such person as long as the disclosing person and the receiving person both have executed a Non-Disclosure Certificate. In the event that any Reviewing Representative to whom the Privileged Materials or Designated CEII is disclosed ceases to be engaged in this matter or is employed or retained for a position whose occupant is not qualified to be a Reviewing Representative under Paragraph 3(e), access to Privileged Materials or Designated CEII by that person shall be terminated. Even if no longer engaged in this proceeding, every person who has executed a Non-Disclosure Certificate shall continue to be bound by the provisions of this Protective Agreement and the certification.

11. Subject to Paragraphs 17-19, the Presiding Judge or the Chief Judge or the Commission shall resolve any disputes arising under this Protective Agreement. Prior to presenting any dispute under this Protective Agreement to the Presiding Judge or the Chief Judge or the Commission, the parties to the dispute shall use their best efforts to resolve it. Any Participant that contests the designation of materials as Privileged shall notify the Participant that provided the Privileged Materials by specifying in writing the basis for its objection. This Protective Agreement shall automatically cease to apply to such materials five (5) business days after the notification is made unless the designator, within said 5-day period, files a motion with the Presiding Judge or the Chief Judge or the Commission, with supporting affidavits, demonstrating that the materials should continue to be privileged. In any challenge to the designation of materials as Privileged, the burden of proof shall be on the Participant seeking protection. If the Presiding Judge or the Chief

Judge or the Commission finds that the materials at issue are not entitled to privilege, the procedures of Paragraphs 17-19 shall apply. The procedures described in this Paragraph shall not apply to materials designated by a Participant as CEII. Materials so designated shall remain privileged and subject to the provisions of this Protective Agreement, unless a Participant requests and obtains a determination from the Commission's Critical Energy Infrastructure Information Coordinator that such materials need not remain as Designated CEII.

12. All copies of all documents reflecting Privileged Materials, including the portion of the hearing testimony, exhibits, transcripts, briefs and other documents, which refer to Privileged Materials, shall be filed and served in sealed envelopes or other appropriate containers endorsed to the effect that they are sealed pursuant to this Protective Agreement. Such documents shall be marked "PRIVILEGED MATERIALS" and shall be filed under seal and served under seal upon the Presiding Judge and all Reviewing Representatives who are on the service list. Such documents containing CEII shall be additionally marked "CONTAINS CUI//CEII MATERIAL – DO NOT RELEASE." For anything filed under seal, redacted versions or, where an entire document is privileged or confidential, a letter indicating such, will also be filed with the Commission and served on all Participants on the service list and the Presiding Judge. Counsel for the producing Participant shall provide to all Participants who request the same, a list of Reviewing Representatives who are entitled to receive such materials. Counsel shall take all reasonable precautions necessary to assure that Privileged Materials and Designated CEII are not distributed to unauthorized persons.

13. If any Participant desires to include, utilize or refer to any Privileged Materials or Designated CEII or information derived therefrom in testimony or exhibits during the hearing in these proceedings in such a manner that might require disclosure of such material to persons other than Reviewing Representatives, such Participant shall first notify both counsel for the disclosing Participant and the Presiding Judge of such desire, identifying with particularity each of the Privileged Materials or Designated CEII. Thereafter, use of such Privileged Material or Designated CEII will be governed by procedures determined by the Presiding Judge.

14. Nothing in this Protective Agreement shall be construed as precluding any Participant from objecting to the use of Privileged Materials or Designated CEII on any legal grounds.

15. Nothing in this Protective Agreement shall preclude any Participant from requesting the Presiding Judge, the Chief Judge, the Commission, or any other body having appropriate authority, to find that this Protective Agreement should not apply to all or any materials previously designated as Privileged Materials or CEII pursuant to this Protective Agreement.

16. This Protective Agreement may be modified only by mutual agreement among Participants that have signed Non-Disclosure Certificates. This Protective Agreement may be replaced and superseded by a protective order issued by the Presiding Judge, the Chief

Judge, or the Commission.

17. Nothing in this Protective Agreement shall be deemed to preclude any Participant from independently seeking, through discovery in any other administrative or judicial proceeding, Privileged Materials or Designated CEII produced by any Participant under this Protective Agreement.

18. None of the Participants waives the right to pursue any other legal or equitable remedies that may be available in the event of actual or anticipated disclosure of Privileged Materials or Designated CEII.

19. The contents of Privileged Materials or Designated CEII or any other form of information that copies or discloses Privileged Materials or Designated CEII shall not be disclosed to anyone other than in accordance with this Protective Agreement and shall be used only in connection with the Participants' review of these proceedings. Any violation of this Protective Agreement and of any Non-Disclosure Certificate executed hereunder shall constitute a violation of an order of the Commission.

20. All Privileged Material or Designated CEII provided by Participants that is filed with the Commission, submitted to a Presiding Judge, or submitted to any Commission personnel or any other judicial or administrative body, must comply with the Commission's *Notice of Document Labelling Guidance for Documents Submitted to or Filed with the Commission or Commission Staff*, as issued on April 14, 2017 (82 Fed. Reg. 18632 (April 20, 2017)).

21. The provisions of 18 C.F.R. § 388.112 and 18 C.F.R. § 388.113 shall apply to any requests under the Freedom of Information Act (5 U.S.C. § 552) for Privileged Materials or Designated CEII in the files of the Commission.

IN WITNESS WHEREOF, Midcontinent Independent System Operator, Inc. has caused its authorized representative to execute this Protective Agreement.

Midcontinent Independent System Operator, Inc.

By: _____
Printed Name: _____
Title: _____
Date: _____

UNITED STATES OF AMERICA
BEFORE THE
FEDERAL ENERGY REGULATORY COMMISSION

Case Name **) Docket No. _____**

NON-DISCLOSURE CERTIFICATE

I hereby certify my understanding that access to Privileged Materials or Designated CEII is provided to me pursuant to the terms and restrictions of the Protective Agreement in this proceeding, that I have been given a copy of and have read the Protective Agreement, and that I agree to be bound by it. I understand that the contents of the Privileged Materials or Designated CEII, any notes or other memoranda, or any other form of information that copies or discloses Privileged Materials or Designated CEII shall not be disclosed to anyone other than in accordance with that Protective Agreement. I acknowledge that a violation of this certificate constitutes a violation of an order of the Federal Energy Regulatory Commission.

By: _____
Printed Name: _____
Title: _____
Representing: _____
Date: _____

FERC rendition of the electronically filed tariff records in Docket No. ER26-00590-000

Filing Data:

CID	Filing Title	Company Filing Identifier	Type of Filing Code	Associated Filing Identifier
C001344	2025-11-24_SA 4596 Entergy Louisiana-Entergy Louisiana GIA (E0014)	16323	10	
	Tariff Title	**Tariff ID**	**Payment Confirmation**	**Suspension Motion**
	Midwest ISO Agreements	13		

Tariff Record Data:

Record Content Description	**SA 4596**
Tariff Record Title	**Entergy Louisiana-Entergy Louisiana GIA (E0014)**
Record Version Number	**31.0.0**
Option Code	**A**
Record Narrative Name	
Tariff Record ID	**11981**
Tariff Record Collation Value	**277633024**
Tariff Record Parent Identifier	**4505**
Proposed Date	**2025-11-19**
Priority Order	**1000000000**
Record Change Type	**NEW**
Record Content Type	**2**
Associated Filing Identifier	

Midcontinent Independent System Operator, Inc.

FERC FPA Electric Tariff

Tariff Title: Midwest ISO Agreements

Effective: 11/19/2025

Tariff Record Title: SA 4596, Entergy Louisiana-Entergy Louisiana GIA (E0014)

Option Code: A

Document Accession #: 20251124-5333 Filed Date: 11/24/2025

SA 4596 ENTERGY LOUISIANA-ENTERGY LOUISIANA GIA VERSION 31.0.0

EFFECTIVE 11/19/2025

ORIGINAL SERVICE AGREEMENT NO. 4596

PUBLIC VERSION

Project E0014

GENERATOR INTERCONNECTION AGREEMENT

entered into by the

Midcontinent Independent System Operator, Inc.,

Entergy Louisiana, LLC

And

Entergy Louisiana, LLC

GENERATOR INTERCONNECTION AGREEMENT (GIA)

THIS GENERATOR INTERCONNECTION AGREEMENT ("GIA") is made and entered into this 19th day of November, 2025, by and between **Entergy Louisiana, LLC**, a limited liability company organized and existing under the laws of the State of Texas ("Interconnection Customer" with a Generating Facility), and **Entergy Louisiana, LLC**, a limited liability company organized and existing under the laws of the State of Texas ("Transmission Owner"), and the **Midcontinent Independent System Operator, Inc**., a non-profit, non-stock corporation organized and existing under the laws of the State of Delaware ("Transmission Provider"). Interconnection Customer, Transmission Owner and Transmission Provider each may be referred to as a "Party," or collectively as the "Parties."

RECITALS

WHEREAS, Transmission Provider has functional control of the operations of the Transmission System, as defined herein, and is responsible for providing Transmission Service and Interconnection Service on the transmission facilities under its control; and

WHEREAS, Interconnection Customer intends to own, lease and/or control and operate the Generating Facility identified as a Generating Facility in Appendix A to this GIA; and

WHEREAS, Transmission Owner owns or operates the Transmission System, whose operations are subject to the functional control of Transmission Provider, to which Interconnection Customer desires to connect the Generating Facility, and may therefore be required to construct certain Interconnection Facilities and Network Upgrades, as set forth in this GIA; and

WHEREAS, Interconnection Customer, Transmission Owner and Transmission Provider have agreed to enter into this GIA, and where applicable subject to Appendix H for a Provisional Generator Interconnection Agreement, for the purpose of interconnecting the Generating Facility with the Transmission System;

NOW, THEREFORE, in consideration of and subject to the mutual covenants contained herein, it is agreed:

ARTICLE 1. DEFINITIONS

When used in this GIA, terms with initial capitalization that are not defined in Article 1 shall have the meanings specified in the Article in which they are used. Those capitalized terms used in this GIA that are not otherwise defined in this GIA have the meaning set forth in the Tariff.

10 kW Inverter Process shall mean the procedure for evaluating an Interconnection Request for a certified inverter-based Small Generating Facility no larger than 10 kW that uses the screen set forth in Section 14.

Adverse System Impact shall mean the negative effects due to technical or operational limits on conductors or equipment being exceeded that may compromise the safety and reliability of the electric system.

Affected System(s) shall mean an electric transmission system or the electric system associated with an Existing Generating Facility or of a higher queued Generating Facility, which is an electric system other than the Transmission Provider's Transmission System that is affected by the Interconnection Request. An Affected System may or may not be subject to FERC jurisdiction.

Affected System Facilities Construction Agreement shall mean the agreement that is made between Transmission Provider and Interconnection Customer(s) to facilitate the construction of and to set forth cost responsibility for necessary Affected System Network Upgrades. This may or may not be a multi-party agreement, as determined by the Transmission Provider.

Affected System Interconnection Customer shall mean any entity that submits an interconnection request for a Generating Facility to a transmission system other than Transmission Provider's Transmission System that may cause the need for Affected System Network Upgrades on the Transmission Provider's Transmission System.

Affected System Network Upgrades shall mean the additions, modifications, and upgrades to Transmission Provider's Transmission System required to accommodate Affected System Interconnection Customer's proposed interconnection to a transmission System other than Transmission Provider's Transmission System.

Affected System Network Upgrade Facilities Study shall mean the facilities study performed by the Affected System Operator or Affected System Operator transmission owner to determine a list of facilities (including Affected System Interconnection Customer's interconnection facilities, transmission owner's interconnection facilities, system protection facilities, and if such upgrades have been determined, network upgrades, distribution upgrades, generator upgrades, common use upgrades, the cost of those facilities, and the time required to interconnect the generating facility(ies) with the Affected System Operator's transmission system.

Affected System Network Upgrade Facilities Study Report shall mean the report issued by the Affected System Operator following the completion of the Affected System Network Upgrade Facilities Study pursuant to Section 7.3.3 of the GIP.

Affected System Operator shall mean the entity that operates an Affected System.

Affected System Queue Position shall mean the queue position of an Affected System Interconnection Customer in Transmission Provider's interconnection queue relative to Transmission Provider's Interconnection Customers' Queue Position.

Affected System Study shall mean the evaluation of Affected System Interconnection Customers' proposed interconnection(s) to a transmission system other than the Transmission Provider's Transmission System that have an impact on Transmission Provider's Transmission System, as described in Section 8 of this GIP.

Affected System Study Agreement shall mean the agreement contained in Appendix 16 to the GIP that is made between Transmission Provider and host transmission provider, in absence of a JOA, JPA, or other agreement filed with the Commission, as noted in Section 8.

Affected System Study Report shall mean the report issued following completion of an Affected System Study.

Affiliate shall mean, with respect to a corporation, partnership or other entity, each such other corporation, partnership or other entity that directly or indirectly, through one or more intermediaries, controls, is controlled by, or is under common control with, such corporation, partnership or other entity.

Ancillary Services shall mean those services that are necessary to support the transmission of capacity and energy from resources to loads while maintaining reliable operation of the Transmission System in accordance with Good Utility Practice.

Applicable Laws and Regulations shall mean all duly promulgated applicable federal, state and local laws, regulations, rules, ordinances, codes, decrees, judgments, directives, or judicial or administrative orders, permits and other duly authorized actions of any Governmental Authority having jurisdiction over the Parties, their respective facilities and/or the respective services they provide.

Applicable Reliability Standards shall mean the requirements and guidelines of the Electric Reliability Organization and the Balancing Authority Area of the Transmission System to which the Generating Facility is directly interconnected.

Balancing Authority shall mean an entity that integrates resource plans ahead of time, maintains demand and resource balance within a Balancing Authority Area, and supports interconnection frequency in real time.

Balancing Authority Area shall mean the collection of generation, transmission, and

loads within the metered boundaries of the Balancing Authority. The Balancing Authority maintains load-resource balance within this area.

Base Case shall mean the base case power flow, short circuit, and stability databases used for the Interconnection Studies by Transmission Provider or Interconnection Customer.

Base Case Data shall mean base case power flow, short circuit and stability databases, including all underlying assumptions, and contingency lists. Such databases and lists, hereinafter referred to as Base Cases, shall include all (1) generation projects and (2) transmission projects, including merchant transmission projects that are proposed for the Transmission System for which a transmission expansion plan has been submitted and approved by the MISO Board.

Breach shall mean the failure of a Party to perform or observe any material term or condition of this GIA.

Breaching Party shall mean a Party that is in Breach of this GIA.

Business Day shall mean Monday through Friday, excluding Federal Holidays.

Calendar Day shall mean any day including Saturday, Sunday or a Federal Holiday. In the event that a period specified in this GIA is calculated in Calendar Days ends on a non-business day, such period shall be deemed to conclude on the following business day.

Cluster shall mean a group of one or more Interconnection Requests that are studied together for the purpose of conducting a Group Study.

Commercial Operation shall mean the status of a Generating Facility that has commenced generating electricity for sale, excluding electricity generated during Trial Operation.

Commercial Operation Date (COD) of a unit shall mean the date on which the Generating Facility commences Commercial Operation as agreed to by the Parties pursuant to Appendix E to this GIA.

Commitment Projection shall mean a projection of the number of MW expected to commit to the JTIQ Portfolio from ERAS and all DPP study clusters that already have passed DP1 as described in Section 9.4.2.e.ii of Rate Schedule 6 (MISO SPP-JOA).

Common Use Upgrade (CUU) shall mean an Interconnection Facility, Network Upgrade, System Protection Facility, or any other classified addition, alteration, or improvement on the Transmission System or the transmission system of an Affected System, not classified under Attachment FF as a Baseline Reliability Project, Market Efficiency Project, or Multi-Value Project, that is needed for the interconnection of multiple Interconnection Customers' Generating Facilities and which is the shared responsibility of such Interconnection Customers.

Confidential Information shall mean any proprietary or commercially or competitively

sensitive information, trade secret or information regarding a plan, specification, pattern, procedure, design, device, list, concept, policy or compilation relating to the present or planned business of a Party, or any other information as specified in Article 22, which is designated as confidential by the Party supplying the information, whether conveyed orally, electronically, in writing, through inspection, or otherwise, that is received by another Party.

Connection Facilities shall mean the Transmission Owner's Connection Facilities and the MHVDC Connection Customer's Connection Facilities, as defined in the MHCP.

Contingent Facilities shall mean those unbuilt Interconnection Facilities and Network Upgrades upon which the Interconnection Request's costs, timing and study findings are dependent, and if delayed or not built, could cause a need for restudies of the Interconnection Request or a reassessment of the Interconnection Facilities and/or Network Upgrades and/or costs and timing. Contingent Facilities may include facilities identified in MTEP that if delayed or not built could impact the timing of the Interconnection Request.

Customer Engagement Window shall mean the time period prior to the start of Definitive Planning Phase I set forth in Section 3.3.4 of the GIP.

Default shall mean the failure of a Breaching Party to cure its Breach in accordance with Article 17 of this GIA.

Definitive Planning Phase shall mean the Generator Interconnection Procedures process which leads to a Generator Interconnection Agreement. An Interconnection Customer enters the Definitive Planning Phase pursuant to GIP Section 7.2. The Definitive Planning Phase includes three distinct phases (Definitive Planning Phases I, II, and III) pursuant to Section 7 of the Generator Interconnection Procedures.

Definitive Planning Phase Queue Position shall mean the order of a valid Interconnection Request, relative to all other pending valid Interconnection Requests, in the Definitive Planning Phase. The Definitive Planning Phase Queue Position is established based upon the date Interconnection Customer satisfies all of the requirements of GIP Section 7.2 to enter the Definitive Planning Phase. All Interconnection Requests within the same Definitive Planning Phase cycle shall have equal priority (i.e. similarly queued).

Demonstrated Capability shall mean the continuous net real power output that the Generating Facility is required to demonstrate in compliance with Applicable Reliability Standards.

Dispute Resolution shall mean the procedure for resolution of a dispute between or among the Parties in which they will first attempt to resolve the dispute on an informal basis.

Distribution System shall mean the Transmission Owner's facilities and equipment, or the Distribution System of another party that is interconnected with the Transmission Owner's Transmission System, if any, connected to the Transmission System, over which facilities Transmission Service or Wholesale Distribution Service under the Tariff is available at the time

Interconnection Customer has requested interconnection of a Generating Facility for the purpose of either transmitting electric energy in interstate commerce or selling electric energy at wholesale in interstate commerce and which are used to transmit electricity to ultimate usage points such as homes and industries directly from nearby generators or from interchanges with higher voltage transmission networks which transport bulk power over longer distances. The voltage levels at which distribution systems operate differ among Local Balancing Authorities and other entities owning distribution facilities interconnected to the Transmission System.

Distribution Upgrades shall mean the additions, modifications, and upgrades to the Distribution System at or beyond the Point of Interconnection to facilitate interconnection of the Generating Facility and render the delivery service necessary to affect Interconnection Customer's wholesale sale of electricity in interstate commerce. Distribution Upgrades do not include Interconnection Facilities.

Effective Date shall mean the date on which this GIA becomes effective upon execution by the Parties subject to acceptance by the Commission, or if filed unexecuted, upon the date specified by the Commission.

Electric Reliability Organization shall mean the North American Electric Reliability Corporation or its successor organization.

Emergency Condition shall mean a condition or situation: (1) that in the reasonable judgment of the Party making the claim is imminently likely to endanger, or is contributing to the endangerment of, life, property, or public health and safety; or (2) that, in the case of either Transmission Provider or Transmission Owner, is imminently likely (as determined in a non-discriminatory manner) to cause a material adverse effect on the security of, or damage to the Transmission System, Transmission Owner's Interconnection Facilities or the electric systems of others to which the Transmission System is directly connected; or (3) that, in the case of Interconnection Customer, is imminently likely (as determined in a non-discriminatory manner) to cause a material adverse effect on the security of, or damage to, the Generating Facility or Interconnection Customer's Interconnection Facilities. System restoration and blackstart shall be considered Emergency Conditions; provided that Interconnection Customer is not obligated by this GIA to possess blackstart capability. Any condition or situation that results from lack of sufficient generating capacity to meet load requirements or that results solely from economic conditions shall not constitute an Emergency Condition, unless one of the enumerated conditions or situations identified in this definition also exists.

Energy Displacement Agreement shall mean an agreement between an Interconnection Customer with an Existing Generating Facility on the Transmission Provider's Transmission System and an Interconnection Customer with a proposed Generating Facility seeking to interconnect with Surplus Interconnection Service. The Energy Displacement Agreement specifies the term of operation, the Generating Facility Interconnection Service limit, and the mode of operation for energy production (common or singular operation).

Energy Resource Interconnection Service (ER Interconnection Service) shall mean an Interconnection Service that allows Interconnection Customer to connect its Generating

Facility to the Transmission System or Distribution System, as applicable, to be eligible to deliver the Generating Facility's electric output using the existing firm or non-firm capacity of the Transmission System on an as available basis. Energy Resource Interconnection Service does not convey transmission service.

Engineering & Procurement (E&P) Agreement shall mean an agreement that authorizes Transmission Owner to begin engineering and procurement of long lead-time items necessary for the establishment of the interconnection in order to advance the implementation of the Interconnection Request.

Environmental Law shall mean Applicable Laws or Regulations relating to pollution or protection of the environment or natural resources.

Existing Generating Facility shall mean a Generating Facility that is either under construction or is in service, and has an unsuspended interconnection agreement with its host transmission provider.

Expanded Scope Analysis shall mean the analysis described in Section 9.4.2.d.iv.a of Rate Schedule 6 (MISO-SPP JOA).

Expedited Resource Addition Study (ERAS) shall mean the temporary procedure for expediting interconnection projects identified for claimed resource adequacy and/or reliability needs.

Expedited Generator Interconnection Agreement (EGIA) shall mean the interconnection agreement for the Expedited Resource Addition Study established between the Transmission Provider and/or the Transmission Owner and the Interconnection Customer as set forth in Section 3.9 of this Attachment X. This agreement shall take the form of the Transmission Provider's *pro forma* Generator Interconnection Agreement modified for the Expedited Resource Addition Study. Unless otherwise provided in the GIP, all requirements applicable to the *pro forma* Generator Interconnection Agreement shall apply to the Expedited Generator Interconnection Agreement.

Facilities Construction Agreement (FCA) shall mean the form of facilities construction agreement, set forth in Appendix 8 to these Generator Interconnection Procedures. The FCA shall be used when an Interconnection Customer or an Affected System Interconnection Customer causes the need for the construction of Network Upgrades or System Protection Facilities on the transmission system of the Transmission Provider.

Fast Track Process shall mean the procedure for evaluating an Interconnection Request for a certified Small Generating Facility no larger than five MW that includes the screen set forth in Section 14, customer options meeting, and optional supplemental review.

Federal Holiday shall mean a Federal Reserve Bank holiday for a Party that has its principal place of business in the United States and a Canadian Federal or Provincial banking holiday for a Party that has its principal place of business located in Canada.

Federal Power Act shall mean the Federal Power Act, as amended, 16 U.S.C. §§ 791a *et seq*.

FERC shall mean the Federal Energy Regulatory Commission, also known as Commission, or its successor.

Final System Impact Study shall mean the Interconnection System Impact Study performed during Definitive Planning Phase III.

Force Majeure shall mean any act of God, labor disturbance, act of the public enemy, war, insurrection, riot, fire, storm or flood, explosion, breakage or accident to machinery or equipment, any order, regulation or restriction imposed by governmental, military or lawfully established civilian authorities, or any other cause beyond a Party's control. A Force Majeure event does not include an act of negligence or intentional wrongdoing by the Party claiming Force Majeure.

Generating Facility shall mean Interconnection Customer's device(s) for the production and/or storage for later injection of electricity identified in the Interconnection Request, but shall not include the Interconnection Customer's Interconnection Facilities. A Generating Facility consists of one or more generating unit(s) and/or storage device(s) which usually can operate independently and be brought online or taken offline individually.

Generating Facility Capacity shall mean the net capacity of the Generating Facility and the aggregate net capacity of the Generating Facility where it includes more than one device for the production and/or storage for later injection of electricity.

Generating Facility Modification shall mean modification to an Existing Generating Facility, including comparable replacement of only a portion of its equipment at the Existing Generating Facility.

Generating Facility Replacement shall mean replacement of one or more generating units and/or storage devices at the Existing Generating Facility with one or more new generating units or storage devices at the same electrical Point of Interconnection as the generating units and/or storage devices that is/are being decommissioned and electrically disconnected.

Generator Interconnection Agreement (GIA) shall mean the form of interconnection agreement, set forth herein.

Generator Interconnection Procedures (GIP) shall mean the interconnection procedures set forth in Attachment X of the Tariff.

Generator Upgrades shall mean the additions, modifications, and upgrades to the electric system of an Existing Generating Facility or of a higher queued Generating Facility at or beyond the Point of Interconnection to facilitate interconnection of the Generating Facility and render the Transmission Service necessary to affect Interconnection Customer's wholesale sale

of electricity in interstate commerce.

Good Utility Practice shall mean any of the practices, methods and acts engaged in or approved by a significant portion of the electric industry during the relevant time period, or any of the practices, methods and acts which, in the exercise of reasonable judgment in light of the facts known at the time the decision was made, could have been expected to accomplish the desired result at a reasonable cost consistent with good business practices, reliability, safety and expedition. Good Utility Practice is not intended to be limited to the optimum practice, method, or act to the exclusion of all others, but rather to be acceptable practices, methods, or acts generally accepted in the region.

Governmental Authority shall mean any federal, state, local or other governmental regulatory or administrative agency, court, commission, department, board, or other governmental subdivision, legislature, rulemaking board, tribunal, or other governmental authority having jurisdiction over the Parties, their respective facilities, or the respective services they provide, and exercising or entitled to exercise any administrative, executive, police, or taxing authority or power; provided, however, that such term does not include Interconnection Customer, Transmission Provider, Transmission Owner, or any Affiliate thereof.

Group Restudy shall mean a restudy of a Group Study conducted pursuant to Section 7.5 of the GIP

Group Study(ies) shall mean the evaluation of one or more Interconnection Requests within a Cluster as described in Section 7 of the GIP. Group Studies are divided into phases as described in section 7.3 of the GIP.

Hazardous Substances shall mean any chemicals, materials or substances defined as or included in the definition of "hazardous substances," "hazardous wastes," "hazardous materials," "hazardous constituents," "restricted hazardous materials," "extremely hazardous substances," "toxic substances," "radioactive substances," "contaminants," "pollutants," "toxic pollutants" or words of similar meaning and regulatory effect under any applicable Environmental Law, or any other chemical, material or substance, exposure to which is prohibited, limited or regulated by any applicable Environmental Law.

HVDC Facilities shall mean the high voltage direct current transmission facilities, including associated alternating current facilities, if any, that are subject to Section 27A of the Tariff and that are specifically identified in (i) any Agency Agreement pertaining to such facilities between Transmission Provider and Transmission Owner that owns or operates such facilities, or (ii) in any other arrangement that permits or will permit Transmission Provider to provide HVDC Service over such facilities as set forth in Section 27A of the Tariff.

HVDC Service shall mean Firm and Non-Firm Point-To-Point Transmission Service provided by Transmission Provider on HVDC Facilities pursuant to Section 27A of the Tariff.

Initial Synchronization Date shall mean the date upon which the Generating Facility is initially synchronized and upon which Trial Operation begins.

Injection Rights shall mean the Transmission Provider's pre-certification of the Transmission System's capability to receive capacity and energy from the MHVDC Transmission Line at the requested Point of Connection, and in the specified MW quantity, without degrading the reliability of the Transmission System, as described in Section 16 of the GIP and Section 3.2.3 of the MHCP.

In-Service Date (ISD) shall mean the date upon which Interconnection Customer reasonably expects it will be ready to begin use of the Transmission Owner's Interconnection Facilities to obtain backfeed power.

Interconnection Customer shall mean any entity, including Transmission Provider, Transmission Owner or any of the Affiliates or subsidiaries of either, that proposes to interconnect its Generating Facility with the Transmission System.

Interconnection Customer Decision Point I shall mean the time period beginning when the Interconnection Customer is provided the Preliminary System Impact Study results including cost estimates for upgrades and concludes after fifteen (15) Business Days.

Interconnection Customer Decision Point II shall mean the time period beginning when the Interconnection Customer is provided the Revised System Impact Study results including cost estimates for upgrades and concludes after fifteen (15) Business Days.

Interconnection Customer's Interconnection Facilities (ICIF) shall mean all facilities and equipment, as identified in Appendix A of this GIA, that are located between the Generating Facility and the Point of Change of Ownership, including any modification, addition, or upgrades to such facilities and equipment necessary to physically and electrically interconnect the Generating Facility to the Transmission System or Distribution System, as applicable. Interconnection Customer's Interconnection Facilities are sole use facilities.

Interconnection Facilities shall mean the Transmission Owner's Interconnection Facilities and the Interconnection Customer's Interconnection Facilities. Collectively, Interconnection Facilities include all facilities and equipment between the Generating Facility and the Point of Interconnection, including any modification, additions or upgrades that are necessary to physically and electrically interconnect the Generating Facility to the Transmission System. Interconnection Facilities shall not include Distribution Upgrades, Generator Upgrades, Stand Alone Network Upgrades or Network Upgrades.

Interconnection Facilities Study(ies) shall mean a study conducted by Transmission Owner, or its agent, for Interconnection Customer(s) to determine a list of facilities (including Interconnection Customer's Interconnection Facilities or Affected System Interconnection Customer's interconnection facilities, Transmission Owner's Interconnection Facilities, System Protection Facilities, and if such upgrades have been determined, Network Upgrades, Distribution Upgrades, Generator Upgrades, Common Use Upgrades, and Affected System Network Upgrades, as identified in the Interconnection System Impact Study), the cost of those facilities, and the time required to interconnect the Generating Facility(ies) with the

Transmission System.

Interconnection Facilities Study Agreement shall mean the form of agreement contained in Appendix 4 of the Generator Interconnection Procedures for conducting the Interconnection Facilities Study.

Interconnection Request shall mean (1) an Interconnection Customer's request, in the form of Appendix 1 to the Generator Interconnection Procedures, to interconnect a new Generating Facility, or a request for the Expedited Resource Addition Study for new generation capacity, or to increase the capacity of, or make a Material Modification to the operating characteristics of, an Existing Generating Facility that is interconnected with the Transmission System, or to interconnect an Existing Generating Facility that is external to the Transmission System, or to change Energy Resource Interconnection Service to Network Resource Interconnection Service for an Existing Generating Facility; or (2) an MHVDC Connection Customer's request, in the form of Appendix 1 to the Generator Interconnection Procedures, to obtain Injection Rights..

Interconnection Service shall mean the service provided by Transmission Provider associated with interconnecting the Generating Facility to the Transmission System, or external host transmission provider if applicable, and enabling it to receive electric energy and capacity from the Generating Facility at the Point of Interconnection pursuant to the terms of this Generator Interconnection Agreement or Point of Delivery as set forth in the Service Agreement for Network Resource Interconnection Service for an External Generating Facility and, if applicable, the Tariff.

Interconnection Study (or Study) shall mean any of the studies described in the Generator Interconnection Procedures.

Interconnection Study Agreement shall mean the form of agreement contained in Attachment B to Appendix 1 of the Generator Interconnection procedures for conducting all studies required by the Generator Interconnection Procedures.

Interconnection System Impact Study shall mean an engineering study that evaluates the impact of the proposed interconnection on the safety and reliability of Transmission System and, if applicable, an Affected System. The study shall identify and detail the system impacts that would result if the Generating Facility were interconnected without project modifications or system modifications, or to study potential impacts, including but not limited to those identified in the Scoping Meeting as described in the Generator Interconnection Procedures.

Interconnection Study Agreement shall mean the forms of agreement contained in Attachment B to Appendix 1 of the Generator Interconnection Procedures for conducting all studies required by the Generator Interconnection Procedures.

IRS shall mean the Internal Revenue Service.

Joint Operating Agreement ("JOA") shall mean an agreement between adjacent

balancing authorities or transmission providers for the coordination of operations.

Joint Operating Agreement between the Midcontinent Independent System Operator, Inc. and Southwest Power Pool, Inc. (MISO-SPP JOA) shall mean Rate Schedule 6 to the MISO Tariff.

Joint Planning Agreement ("JPA") shall mean an agreement between adjacent balancing authorities or transmission providers for the coordination of planning.

Joint Targeted Interconnection Queue (JTIQ) shall refer to the study and processes described in Section 9.4.2 of Rate Schedule 6 (MISO-SPP JOA).

Joint Targeted Interconnection Queue Study ("JTIQ Study") shall mean a transmission planning study conducted jointly by SPP and MISO to facilitate the interconnection of new generator capacity in both Parties' regions.

JTIQ Commitment Group Member shall mean any JTIQ Commitment Group Member included in a Commitment Group consistent with Section 9.4 of Rate Schedule 6 (MISO-SPP JOA).

JTIQ Commitment Group or Commitment Group shall mean a group of JTIQ Commitment Group Members that have executed a JTIQ Generator Interconnection Agreement within the twelve (12) month period ending April 30th of each year. The Commitment Group shall also include JTIQ Commitment Group Members for which a JTIQ Generator Interconnection Agreement has been filed unexecuted by SPP or the Transmission Provider and the Commission has accepted the agreement within the twelve (12) month period ending April 30th of each year.

JTIQ Generator Charge shall mean the charge to JTIQ Commitment Group Members to recover the JTIQ Commitment Group Member's share of the JTIQ Monthly Revenue Requirement for each of the JTIQ Upgrades in the JTIQ Portfolio in the Transmission Provider's Region.

JTIQ Participation Group shall mean the group of Interconnection Requests that shall consist of all interconnection customers included in the JTIQ Screening Groups whose interconnection request meets the distribution factor and impact criteria specified in Section 9.4.2(d)((ii) of Rate Schedule 6 (MISO-SPP JOA).

JTIQ Portfolio shall mean a group of JTIQ Upgrades identified pursuant to Section 9.4 of Rate Schedule 6 (MISO-SPP JOA).

JTIQ Screening Group shall mean a group of MISO Interconnection Customers and SPP interconnection customers whose Interconnection Requests will be screened for inclusion in a JTIQ Participation Group. The JTIQ Screening Group shall consist of all interconnection customers who have submitted interconnection requests into a MISO ERAS, SPP ERAS, DPP study cluster, or SPP DISIS study cluster that: (1) has a study commencement or kick off date

that is after the date that the Parties' respective Boards of Directors have approved a JTIQ Portfolio; and (2) has not commenced DPP Phase I, a MISO ERAS, the SPP ERAS or DISIS Phase One studies pursuant to each party's OATT as of the date that the Parties have declared the JTIQ Portfolio fully subscribed.

JTIQ Service Agreements shall mean the JTIQ Commitment Agreement attached to the MISO GIA as Appendix 17 and the SPP's *pro forma* agreement(s) that obligate interconnection customers to provide security for and pay the JTIQ Generator Charge for JTIQ Network Upgrades included in the applicable JTIQ Portfolio.

JTIQ Upgrade shall mean a Network Upgrade included in a JTIQ portfolio pursuant to Section 9.4 of Rate Schedule 6 (MISO-SPP JOA)**.**

Local Balancing Authority shall mean an operational entity or a Joint Registration Organization which is (i) responsible for compliance with the subset of Electric Reliability Organization Balancing Authority Reliability Standards defined in the Balancing Authority Agreement for their local area within the MISO Balancing Authority Area, (ii) a Party to Balancing Authority Agreement, excluding MISO, and (iii) provided in the Balancing Authority Agreement.

Local Resource Zone (LRZ) shall mean a geographic area within the Transmission Provider Region that is prescribed by the Transmission Provider, based upon the criteria in Section 68A.3, to address congestion that limits Planning Resource deliverability.

Loss shall mean any and all damages, losses, claims, including claims and actions relating to injury to or death of any person or damage to property, demand, suits, recoveries, costs and expenses, court costs, attorney fees, and all other obligations by or to third parties, arising out of or resulting from the other Party's performance, or non-performance of its obligations under this GIA on behalf of the indemnifying Party, except in cases of gross negligence or intentional wrongdoing, by the indemnified party.

Material Modification shall mean: (1) modification to an Interconnection Request in the queue, that has a material adverse impact on the cost or timing of any other Interconnection Request with an equal or later queue priority date; or Qualified Change.

Metering Equipment shall mean all metering equipment installed or to be installed at the Generating Facility, Interconnection Customer's Interconnection Facilities, and/or Transmission Owner's Interconnection Facilities pursuant to this GIA at the metering points, including but not limited to instrument transformers, MWh-meters, data acquisition equipment, transducers, remote terminal unit, communications equipment, phone lines, and fiber optics.

Monitoring and Consent Agreement shall mean an agreement that defines the terms and conditions applicable to a Generating Facility acquiring Surplus Interconnection Service. The Monitoring and Consent Agreement will list the roles and responsibilities of an Interconnection Customer seeking to interconnect with Surplus Interconnection Service and Transmission Owner to maintain the total output of the Generating Facility inside the parameters

delineated in the GIA.

Multi-Party Facilities Construction Agreement (MPFCA) shall mean the form of facilities construction agreement, set forth in Appendix 9 to these Generator Interconnection Procedures. The MPFCA shall be used when multiple Interconnection Requests or interconnection requests from Affected System Interconnection Customers cause the need for the construction of Common Use Upgrades on the Transmission System and share cost responsibility for such Common Use Upgrades.

Network Customer shall have that meaning as provided in the Tariff.

Network Resource shall mean any designated generating resource owned, purchased, or leased by a Network Customer under the Tariff. Network Resources do not include any resource, or any portion thereof, that is committed for sale to third parties or otherwise cannot be called upon to meet the Network Customer's Network Load on a non-interruptible basis.

Network Resource Interconnection Service (NR Interconnection Service) shall mean an Interconnection Service that allows Interconnection Customer to integrate its Generating Facility with the Transmission System in the same manner as for any Generating Facility being designated as a Network Resource. Network Resource Interconnection Service does not convey transmission service. Network Resource Interconnection Service shall include any network resource interconnection service established under an agreement with, or the tariff of, a Transmission Owner prior to integration into MISO, that is determined to be deliverable through the integration deliverability study process.

Network Upgrades shall mean the additions, modifications, and upgrades to the Transmission System required at or beyond the point at which the Interconnection Facilities connect to the Transmission System or Distribution System, as applicable, to accommodate the interconnection of the Generating Facility(ies) to the Transmission System. Network Upgrades shall not include any HVDC Facility Upgrades.

Notice of Dispute shall mean a written notice of a dispute or claim that arises out of or in connection with this GIA or its performance.

Optional Interconnection Study shall mean a sensitivity analysis based on assumptions specified by Interconnection Customer in the Optional Interconnection Study Agreement.

Optional Interconnection Study Agreement shall mean the form of agreement contained in Appendix 5 of the Generator Interconnection Procedures for conducting the Optional Interconnection Study.

Outage Transfer Distribution Factor (OTDF) Outage Transfer Distribution Factor, as defined by the Electric Reliability Organization.

Party or Parties shall mean Transmission Provider, Transmission Owner, Interconnection Customer, or any combination of the above.

Permissible Technological Advancement shall mean advancements to turbines, inverters, plant supervisory controls, excitation systems, or other technological advancements submitted to the Transmission Provider prior to the issuance of this draft Generator Interconnection Agreement for such project provided that such advancements does not: (1) degrade the electrical characteristics of the generating equipment; (2) does not cause any material adverse impact on the Transmission System with regard to short circuit capability limits, steady-state thermal and voltage limits, or dynamic system stability and response; (3) does not increase the installed capacity of the Generating Facility; or (4) change the fuel source of the proposed Generating Facility.

Point of Change of Ownership (PCO) shall mean the point, as set forth in Appendix A to the Generator Interconnection Agreement, where the Interconnection Customer's Interconnection Facilities connect to the Transmission Owner's Interconnection Facilities.

Point of Interconnection (POI) shall mean the point, as set forth in Appendix A of the GIA, where the Interconnection Facilities connect to the Transmission System.

Potential MW Total shall mean a projection of the number of MW that may commit to the JTIQ Portfolio from all ERAS and study clusters to date, including the current study cluster(s).

Preliminary System Impact Study shall mean the Interconnection System Impact Study performed during Definitive Planning Phase I.

Pre-Queue Phase shall mean Interconnection Customer outreach and education effort undertaken prior to the submission of the Interconnection Request.

Proportional Impact Method shall mean a technical analysis conducted by Transmission Provider to determine the degree to which each Generating Facility in the Group Study contributes to the need for a specific Network Upgrade.

Provisional Generator Interconnection Agreement shall mean the interconnection agreement for Provisional Interconnection Service established between the Transmission Provider and/or the Transmission Owner and the Interconnection Customer as set forth in Section 7.9 of this Attachment X. This agreement shall take the form of the Generator Interconnection Agreement modified for provisional purposes. Unless otherwise provided in the GIP, all requirements applicable to the Generator Interconnection Agreement shall apply to the Provisional Generator Interconnection Agreement.

Provisional Interconnection Service shall mean Interconnection Service provided by the Transmission Provider associated with interconnecting the Interconnection Customer's Generating Facility to the Transmission Provider's Transmission System and enabling that Transmission System to receive electric energy and capacity from the Generating Facility at the Point of Interconnection, pursuant to the terms of the Provisional Generator Interconnection Agreement and the Tariff.

Provisional Interconnection Study shall mean an engineering study, performed at Interconnection Customer's request, as a condition to entering into a Provisional Generator Interconnection Agreement, that evaluates the impact of the proposed interconnection on the safety and reliability of the Transmission System and, if applicable, any Affected System. The study shall identify and detail the impacts on the Transmission System and, if applicable, an Affected System, from stability, short circuit, and voltage issues that would result if the Generating Facility were interconnected without project modifications or system modifications.

Qualified Change shall mean a planned modification to an Existing Generating Facility that is undergoing evaluation for a Generating Facility Modification or Generating Facility Replacement, and has a material adverse impact on the Transmission System with respect to: i) steady-state thermal or voltage limits, ii) dynamic system stability and response, or iii) short-circuit capability limit; compared to the impacts of the Existing Generating Facility prior to the modification or replacement.

Queue Position shall mean the order of a valid Interconnection Request, relative to all other pending valid Interconnection Requests pursuant to Section 4.1 of the GIP.

Reasonable Efforts shall mean, with respect to an action required to be attempted or taken by a Party under this Generator Interconnection Agreement, efforts that are timely and consistent with Good Utility Practice and are otherwise substantially equivalent to those a Party would use to protect its own interests.

Relevant Electric Retail Regulatory Authority (RERRA) shall mean an entity that has jurisdiction over and establishes prices and/or policies for providers of retail electric service to end-customers, such as the city council for a municipal utility, the governing board of a cooperative utility, the state public utility commission or any such entity.

Reliability Assessment Study shall mean an engineering study that evaluates the impact of a proposed Generating Facility Replacement on the reliability of Transmission System during the time period between the date that the Existing Generating Facility ceases commercial operations and the Commercial Operation Date of the Replacement Generating Facility.

Replacement Generating Facility shall mean a Generating Facility that replaces an Existing Generating Facility, or a portion thereof, at the same electrical Point of Interconnection pursuant to Section 3.7 of this Attachment X.

Replacement Impact Study shall mean an engineering study that evaluates the impact of a proposed Generating Facility Replacement on the reliability of the Transmission System.

Revised System Impact Study shall mean the Interconnection System Impact Study performed during Definitive Planning Phase II.

Scoping Meeting shall mean the meeting between representatives of Interconnection Customer, Transmission Owner, Affected System Operator(s) and Transmission Provider

conducted for the purpose of discussing the proposed Interconnection Request and any alternative interconnection options, exchanging information including any transmission data and earlier study evaluations that would be reasonably expected to impact such interconnection options, refining information and models provided by Interconnection Customer(s), discussing the Group Study materials posted to OASIS pursuant to Section 3.4 of the GIP, and analyzing such information.

Shared Interconnection Request shall mean (1) multiple Interconnection Customer's request, in the form of Appendix 1 to the Generator Interconnection Procedures, to interconnect new Generating Facilities, or to increase the capacity of, or make a Material Modification to the operating characteristics of, Existing Generating Facilities that are interconnected with the Transmission System, or to interconnect Existing Generating Facilities that are external to the Transmission System, or to change Energy Resource Interconnection Service to Network Resource Interconnection Service for Existing Generating Facilities; or (2) multiple MHVDC Connection Customer's request, in the form of Appendix 1 to the Generator Interconnection Procedures, to obtain Injection Rights.

Shared Network Upgrade shall mean a Network Upgrade or Common Use Upgrade that is funded by an Interconnection Customer(s), including when the Transmission Owner elects to fund the capital cost of such a Network Upgrade or Common Use Upgrade under Section 11.3 of the GIA, and also benefits other Interconnection Customer(s) that are later identified as beneficiaries.

Site Control shall mean a documented right for one or more parcels of land for the purpose of constructing a Generating Facility, Interconnection Customer's Interconnection Facilities, and, if applicable (*i.e.*, when the Interconnection Customer is providing the site for such facilities), the Transmission Owner's Interconnection Facilities and Network Upgrades at the POI that the Interconnection Customer will develop. Such documented right shall be one of the following: (1) ownership of a site; (2) a leasehold interest in a site; or (3) an option to purchase or acquire a leasehold interest in a site; or (4) any other contractual or legal right to possess or occupy a site. Transmission Provider will maintain acreage requirements for each Generating Facility type on its OASIS or public website.

Small Generating Facility shall mean a Generating Facility that has an aggregate net Generating Facility Capacity of no more than five MW and meets the requirements of Section 14 and Appendix 3 of the GIP.

Southwest Power Pool (SPP) shall refer to the Southwest Power Pool, Inc. the Regional Transmission Organization that is the counterparty to Rate Schedule 6 (MISO-SPP JOA).

Special Protection System (SPS) shall mean an automatic protection system or remedial action scheme designed to detect abnormal or predetermined system conditions, and take corrective actions other than and/or in addition to the isolation of faulted components, to maintain system reliability. Such action may include changes in demand (MW and MVar), energy (MWh and MVarh), or system configuration to maintain system stability, acceptable voltage, or power flows. An SPS does not include (a) underfrequency or undervoltage load

shedding, (b) fault conditions that must be isolated, (c) out-of-step relaying not designed as an integral part of an SPS, or (d) Transmission Control Devices.

Stand Alone Network Upgrades shall mean Network Upgrades, that are not part of an Affected System or a JTIQ Upgrade, that Interconnection Customer may construct without affecting day-to-day operations of the Transmission System during their construction. Transmission Provider, Transmission Owner and Interconnection Customer must agree as to what constitutes Stand Alone Network Upgrades and identify them in Appendix A to this GIA. If the Transmission Provider or Transmission Owner and Interconnection Customer disagree about whether a particular Network Upgrade is a Stand Alone Network Upgrade, the Transmission Provider or Transmission Owner that disagrees with the Interconnection Customer must provide the Interconnection Customer a written technical explanation outlining why the Transmission Provider or Transmission Owner does not consider the Network Upgrade to be a Stand Alone Network Upgrade within fifteen (15) Business Days of its determination.

Substation Network Upgrades shall mean Network Upgrades that are required at or near the Point of Interconnection and are identified in the first portion of the Interconnection Facilities Study as described in GIP Section 7.3.2.5.

Supplemental Affected System Analysis shall mean **t**he affected systems analysis described in Section 7.3.2.3.1 of this GIP and Section 9.4.2.e.iii.a.i of the Rate Schedule 6 (MISO-SPP JOA) to determine if Supplemental Affected System Upgrades are required for one or more JTIQ Participation Group member(s).

Supplemental Affected System Upgrade shall mean a Network Upgrade in addition to those required to address the impact of interconnection requests in the current study cluster as described in Section 9.4.2.e.iii.a.i of Rate Schedule 6 (MISO-SPP-JOA).

Surplus Interconnection Service shall mean any Interconnection Service that is derived from the unneeded portion of Interconnection Service established in a GIA or in agreement with, or under the tariff of, a Transmission Owner prior to integration into MISO, such that if Surplus Interconnection Service is utilized the total amount of Interconnection Service at the Point of Interconnection would remain the same.

System Planning and Analysis Phase shall mean the phase of the Generator Interconnection Procedure process, prior to January 4, 2017, which consisted of an Interconnection System Impact Study for those Interconnection Requests that were studied in this phase.

System Protection Facilities shall mean the equipment, including necessary protection signal communications equipment, required to protect (1) the Transmission System or other delivery systems or other generating systems from faults or other electrical disturbances occurring at the Generating Facility and (2) the Generating Facility from faults or other electrical system disturbances occurring on the Transmission System or on other delivery systems or other generating systems to which the Transmission System is directly connected.

Target MW Value shall mean the projected new generation interconnection MW enabled by the JTIQ Portfolio. The Target MW Value for each JTIQ Portfolio shall be identified in Section 9.4 and related subsections of Rate Schedule 6.

Tariff shall mean the Transmission Provider's Tariff through which open access transmission service and Interconnection Service are offered, as filed with the Commission, and as amended or supplemented from time to time, or any successor tariff.

Threshold Charge shall mean the charge calculated using an estimate of plant in service value for the JTIQ Portfolio, excluding amounts funded under the GRIP Program, as described in Section 9.4.2 of Rate Schedule 6 (MISO-SPP JOA).

Transmission Control Devices shall mean a generally accepted transmission device that is planned and designed to provide dynamic control of electric system quantities, and are usually employed as solutions to specific system performance issues. Examples of such devices include fast valving, high response exciters, high voltage DC links, active or real power flow control and reactive compensation devices using power electronics (*e.g.*, unified power flow controllers), static var compensators, thyristor controlled series capacitors, braking resistors, and in some cases mechanically-switched capacitors and reactors. In general, such systems are not considered to be Special Protection Systems.

Transmission Owner shall mean that Transmission Owner as defined in the Tariff, which includes an entity that owns, leases or otherwise possesses an interest in the portion of the Transmission System at which Interconnection Customer proposes to interconnect or otherwise integrate the operation of the Generating Facility. Transmission Owner should be read to include any Independent Transmission Company that manages the transmission facilities of Transmission Owner and shall include, as applicable, the owner and/or operator of distribution facilities interconnected to the Transmission System, over which facilities transmission service or Wholesale Distribution Service under the Tariff is available at the time Interconnection Customer requests Interconnection Service and to which Interconnection Customer has requested interconnection of a Generating Facility for the purpose of either transmitting electric energy in interstate commerce or selling electric energy at wholesale in interstate commerce.

Transmission Provider shall mean the Midcontinent Independent System Operator, Inc. ("MISO"), the Regional Transmission Organization that controls or operates the transmission facilities of its transmission-owning members used for the transmission of electricity in interstate commerce and provides transmission service under the Tariff.

Transmission Owner's Interconnection Facilities (TOIF) shall mean all facilities and equipment owned by Transmission Owner from the Point of Change of Ownership to the Point of Interconnection as identified in Appendix A to this GIA, including any modifications, additions or upgrades to such facilities and equipment. Transmission Owner's Interconnection Facilities are sole use facilities and shall not include Distribution Upgrades, Generator Upgrades, Stand Alone Network Upgrades or Network Upgrades.

Transmission System shall mean the facilities owned by Transmission Owner and

controlled or operated by Transmission Provider or Transmission Owner that are used to provide Transmission Service (including HVDC Service) or Wholesale Distribution Service under the Tariff.

Trial Operation shall mean the period during which Interconnection Customer is engaged in on-site test operations and commissioning of the Generating Facility prior to Commercial Operation.

User-Defined Model shall mean any set of programming code created by equipment manufacturers or developers that captures the latest features of controllers that are mainly software-based and represent the entities' control strategy but does not necessarily correspond to any particular generic library model, as contained in Attachment A to Appendix 1 of the GIP.

Variable Energy Resource shall mean a device for the production of electricity that is characterized by an energy source that: (1) is renewable; (2) cannot be stored by the facility owner or operator; and (3) has variability that is beyond the control of the facility owner or operator.

Wholesale Distribution Service shall have that meaning as provided in the Tariff. Wherever the term "transmission delivery service" is used, Wholesale Distribution Service shall also be implied.

ARTICLE 2. EFFECTIVE DATE, TERM AND TERMINATION

2.1 Effective Date. This GIA shall become effective upon execution by the Parties subject to acceptance by FERC (if applicable), or if filed unexecuted, upon the date specified by FERC. Transmission Provider shall promptly file this GIA with FERC upon execution in accordance with Article 3.1, if required.

2.2 Term of Agreement. Subject to the provisions of Article 2.3, this GIA shall remain in effect for a period of thirty (30) years from the Effective Date and shall be automatically renewed for each successive one-year period thereafter on the anniversary of the Effective Date.

2.3 Termination Procedures. This GIA may be terminated as follows:

2.3.1 Written Notice. This GIA may be terminated by Interconnection Customer after giving Transmission Provider and Transmission Owner ninety (90) Calendar Days advance written notice. This GIA shall be terminated by Transmission Provider if the Generating Facility or a portion of the Generating Facility fails to achieve Commercial Operation by the Commercial Operation Date established in accordance with Section 4.4.4 of Attachment X, including any extension provided thereunder, or has ceased Commercial Operation for three (3) consecutive years, beginning with the last date of Commercial Operation for the Generating Facility, after giving Interconnection Customer ninety (90) Calendar Days advance written notice. Where only a portion of the Generating Facility fails to achieve Commercial Operation by the Commercial Operation Date established in accordance with Section 4.4.4 of Attachment X, including any extension provided thereunder, Transmission Provider shall only terminate that portion of the GIA. Notwithstanding the foregoing, in the limited circumstance that the Interconnection Request is served by a contingent Network Upgrade with an in-service date that is farther out than the Commercial Operation Date permitted under Section 4.4.4 of Attachment X, Transmission Provider shall only terminate this GIA for failure to achieve Commercial Operation by that later in-service date of the contingent Network Upgrade. The Generating Facility will not be deemed to have ceased Commercial Operation for purposes of this Article 2.3.1 if Interconnection Customer can document that it has taken other significant steps to maintain or restore operational readiness of the Generating Facility for the purpose of returning the Generating Facility to Commercial Operation as soon as possible.

2.3.1.1 Surplus Interconnection Service. Where this GIA provides for Surplus Interconnection Service and the Energy Displacement Agreement or the Monitoring and Consent Agreement required for Surplus Interconnection Service are no longer in effect, Interconnection Customer shall immediately cease Commercial Operation of the Generating Facility and this GIA shall be deemed terminated. In the event that the Existing Generating Facility retires and/or permanently ceases commercial

operation, the Surplus Interconnection Service provided under this GIA shall terminate except as provided in Section 3.3.1.3 of the GIP.

2.3.2 Default. Any Party may terminate this GIA in accordance with Article 17.

2.3.3 Notwithstanding Articles 2.3.1 and 2.3.2, no termination shall become effective until the Parties have complied with all Applicable Laws and Regulations applicable to such termination, including the filing with FERC of a notice of termination of this GIA, if required, which notice has been accepted for filing by FERC.

For EGIAs, no termination shall become effective until Interconnection Customer has provided all security as required by Section 2.4.

2.4 Termination Costs. If a Party elects to terminate this GIA pursuant to Article 2.3 above, each Party shall pay all costs incurred for which that Party is responsible (including any cancellation costs relating to orders or contracts for Interconnection Facilities, applicable upgrades, and related equipment) or charges assessed by the other Parties, as of the date of the other Parties' receipt of such notice of termination, under this GIA. In the event that this GIA is terminated by Interconnection Customer, Interconnection Customer is responsible for all financial impact that is caused as a result of this termination or the termination of Interconnection Customer's FCA(s) or MPFCA(s), such financial impact being determined through the financial impact analysis performed in accordance with Section 7.8 of Attachment X. In the event of termination by a Party, the Parties shall use commercially Reasonable Efforts to mitigate the costs, damages and charges arising as a consequence of termination. Upon termination of this GIA, unless otherwise ordered or approved by FERC:

In the event that this EGIA is terminated by Interconnection Customer that had an Interconnection Request studied in ERAS, Interconnection Customer is responsible for the full cost of all Network Upgrades identified in this EGIA as well as any Network Upgrades identified during the ERAS process that are to be memorialized in an agreement other that this EGIA, including any applicable FCA, MPFCA, or JTIQ Service Agreements. If the Network Upgrade costs for Network Upgrades subject to an FCA, MPFCA, or JTIQ Service Agreement have not been finalized or the Interconnection Customer has not made the payment under such agreement as of the date that termination of this EGIA is sought, Interconnection Customer shall provide the payment or security for such Network Upgrades in the amount required by the applicable agreement. If such agreement has not been executed and final costs are not available as of a date that termination is sought, Interconnection Customer shall provide such payment or security in an amount corresponding to the most recent estimate provided by the Transmission Provider during the ERAS process. Interconnection Customer shall pay or Transmission Provider shall refund, as applicable, to Interconnection Customer the difference between the amount of any estimated payment or security made pursuant to this Article and the final cost of such NU within ninety (90) Calendar Days after such final costs are invoiced to the Interconnection Customer.

2.4.1 With respect to any portion of the Transmission Owner's Interconnection Facilities, Network Upgrades, System Protection Facilities, Distribution Upgrades, Generator Upgrades, and if so determined and made a part of this GIA, upgrades on Affected Systems, that have not yet been constructed or installed, Transmission Owner shall to the extent possible and to the extent of Interconnection Customer's written notice under Article 2.3.1, cancel any pending orders of, or return, any materials or equipment for, or contracts for construction of, such facilities; provided that in the event Interconnection Customer elects not to authorize such cancellation, Interconnection Customer shall assume all payment obligations with respect to such materials, equipment, and contracts, and Transmission Owner shall deliver such material and equipment, and, if necessary, assign such contracts, to Interconnection Customer as soon as practicable, at Interconnection Customer's expense. To the extent that Interconnection Customer has already paid Transmission Owner for any or all such costs of materials or equipment not taken by Interconnection Customer or upgrades not yet constructed, Transmission Owner shall promptly transfer such amounts to Transmission Provider, less any costs, including penalties incurred by Transmission Owner to cancel any pending orders of or return such materials, equipment, or contracts. Transmission Provider will perform a financial impact analysis in accordance with Section 7.8 of Attachment X to determine the amount that should be refunded to Interconnection Customer. Transmission Provider shall refund such remaining amounts to Interconnection Customer, less the amount of Automatic Withdrawal Penalty funds received by the Interconnection Customer in accordance with Section 7.8.1 of the Attachment X and less any financial impact caused by the termination of this GIA or Interconnection Customer's FCA(s) or MPFCA(s), as determined through the analysis performed in accordance with Section 7.8 of Attachment X. If Interconnection Customer made its payment(s) through a letter of credit, surety bond, or parental guarantee, Transmission Owner will draw against that letter of credit, surety bond, or parental guarantee in an amount determined through the analysis performed in accordance with Section 7.8 of Attachment X plus the amount of any Automatic Withdrawal Penalty funds received by the Interconnection Customer in accordance with Section 7.8.1 of the Attachment X, and transfer that amount to Transmission Provider, unless Interconnection Customer funds the financial impact through another means.

If an Interconnection Customer terminates this GIA, it shall be responsible for all costs incurred in association with that Interconnection Customer's interconnection, including any cancellation costs relating to orders or contracts for Interconnection Facilities and equipment, and other expenses including any upgrades or related equipment for which Transmission Owner has incurred expenses and has not been reimbursed by Interconnection Customer.

2.4.2 Transmission Owner may, at its option, retain any portion of such materials, equipment, or facilities that Interconnection Customer chooses not to accept delivery of, in which case Transmission Owner shall be responsible for all costs

associated with procuring such materials, equipment, or facilities. If Transmission Owner does not so elect, then Interconnection Customer shall be responsible for such costs.

2.4.3 With respect to any portion of the Interconnection Facilities, and any other facilities already installed or constructed pursuant to the terms of this GIA, Interconnection Customer shall be responsible for all costs associated with the removal, relocation, reconfiguration or other disposition or retirement of such materials, equipment, or facilities, and such other expenses actually incurred by Transmission Owner necessary to return the Transmission, Distribution or Generator System, as applicable, to safe and reliable operation.

2.5 **Disconnection**. Upon termination of this GIA, the Parties will take all appropriate steps to disconnect the Generating Facility from the Transmission or Distribution System, as applicable. All costs required to effectuate such disconnection shall be borne by the terminating Party, unless such termination resulted from the non-terminating Party's Default of this GIA or such non-terminating Party otherwise is responsible for these costs under this GIA.

2.6 **Survival.** This GIA shall continue in effect after termination to the extent necessary to provide for final billings and payments and for costs incurred hereunder, including billings and payments pursuant to this GIA; to permit the determination and enforcement of liability and indemnification obligations arising from acts or events that occurred while this GIA was in effect; and to permit each Party to have access to the lands of the other Party pursuant to this GIA or other applicable agreements, to disconnect, remove or salvage its own facilities and equipment.

ARTICLE 3. REGULATORY FILINGS

3.1 **Filing.** Transmission Provider shall file this GIA (and any amendment hereto) with the appropriate Governmental Authority, if required. A Party may request that any information so provided be subject to the confidentiality provisions of Article 22. If that Party has executed this GIA, or any amendment thereto, the Party shall reasonably cooperate with Transmission Provider with respect to such filing and to provide any information reasonably requested by Transmission Provider needed to comply with applicable regulatory requirements.

ARTICLE 4. SCOPE OF SERVICE

4.1 **Interconnection Product Options**. Interconnection Customer has selected the following (checked) type of Interconnection Service:

Check: _____ SI or ____ ER and/or __X__ NR (See Appendix A for details)

4.1.1 Energy Resource Interconnection Service (ER Interconnection Service).

4.1.1.1 The Product. ER Interconnection Service allows Interconnection Customer to connect the Generating Facility to the Transmission or Distribution System, as applicable, and be eligible to deliver the Generating Facility's output using the existing firm or non-firm capacity of the Transmission System on an "as available" basis. To the extent Interconnection Customer wants to receive ER Interconnection Service, Transmission Owner shall construct facilities consistent with the studies identified in Appendix A.

An Interconnection Customer seeking ER Interconnection Service for new or added capacity at a Generating Facility may be granted conditional ER Interconnection Service status to the extent there is such capacity available on the Transmission System to accommodate the Interconnection Customer's Generating Facility. At the request of Interconnection Customer, conditional ER Interconnection Service status may be granted subject to the system being able to accommodate the interconnection without upgrades, until such time as a higher queued project(s) with a later service date affecting the same common elements is placed into service. The conditional ER Interconnection Service shall be terminated in the event Interconnection Customer fails to fund the necessary studies and the Network Upgrades necessary to grant the Interconnection Customer's ER Interconnection Service upon the completion of higher queued projects involving the same common elements.

4.1.1.2 Transmission Delivery Service Implications. Under ER Interconnection Service, Interconnection Customer will be eligible to inject power from the Generating Facility into and deliver power across the Transmission System on an "as available" basis up to the amount of MW identified in the applicable stability and steady state studies to the extent the upgrades initially required to qualify for ER Interconnection Service have been constructed. After that date FERC makes effective MISO's Energy Market Tariff filed in Docket No. ER04-691-000, Interconnection Customer may place a bid to sell into the market up to the maximum identified Generating Facility output, subject to any conditions specified in the Interconnection Service approval, and the Generating Facility will be dispatched to the extent the Interconnection Customer's bid clears. In all other instances, no transmission or other delivery service from the Generating Facility is assured, but Interconnection Customer may obtain Point-To-Point Transmission Service, Network Integration Transmission Service or be used for secondary network transmission service, pursuant to the Tariff, up to the maximum output identified in the stability and steady state studies. In those instances, in order for Interconnection Customer to obtain the right to deliver or inject energy beyond the Point of Interconnection or to improve its ability to do so, transmission delivery service must be

obtained pursuant to the provisions of the Tariff. The Interconnection Customer's ability to inject its Generating Facility output beyond the Point of Interconnection, therefore, will depend on the existing capacity of the Transmission or Distribution System as applicable, at such time as a Transmission Service request is made that would accommodate such delivery. The provision of Firm Point-To-Point Transmission Service or Network Integration Transmission Service may require the construction of additional Network or Distribution Upgrades.

4.1.2 Network Resource Interconnection Service (NR Interconnection Service).

4.1.2.1 The Product. Transmission Provider must conduct the necessary studies and Transmission Owner shall construct the facilities identified in Appendix A of this GIA, subject to the approval of Governmental Authorities, needed to integrate the Generating Facility in the same manner as for any Generating Facility being designated as a Network Resource.

4.1.2.2 Transmission Delivery Service Implications. NR Interconnection Service allows the Generating Facility to be designated by any Network Customer under the Tariff on the Transmission System as a Network Resource, up to the Generating Facility's full output, on the same basis as existing Network Resources that are interconnected to the Transmission or Distribution System, as applicable, and to be studied as a Network Resource on the assumption that such a designation will occur. Although NR Interconnection Service does not convey a reservation of Transmission Service, any Network Customer can utilize Network Integration Transmission Service under the Tariff to obtain delivery of energy from the Generating Facility in the same manner as it accesses Network Resources. A Generating Facility receiving NR Interconnection Service may also be used to provide Ancillary Services after technical studies and/or periodic analyses are performed with respect to the Generating Facility's ability to provide any applicable Ancillary Services, provided that such studies and analyses have been or would be required in connection with the provision of such Ancillary Services by any existing Network Resource. However, if the Generating Facility has not been designated as a Network Resource by any Network Customer, it cannot be required to provide Ancillary Services except to the extent such requirements extend to all generating facilities that are similarly situated. The provision of Network Integration Transmission Service or Firm Point-To-Point Transmission Service may require additional studies and the construction of additional upgrades. Because such studies and upgrades would be associated with a request for delivery service under the Tariff, cost responsibility for the studies and upgrades would be in accordance with FERC's policy for pricing transmission delivery services.

NR Interconnection Service does not necessarily provide Interconnection Customer with the capability to physically deliver the output of its Generating Facility to any particular load on the Transmission System without incurring congestion costs. In the event of transmission or distribution constraints on the Transmission or Distribution System, as applicable, the Generating Facility shall be subject to the applicable congestion management procedures in the Transmission System in the same manner as Network Resources.

There is no requirement either at the time of study or interconnection, or at any point in the future, that the Generating Facility be designated as a Network Resource by a Network Customer or that Interconnection Customer identify a specific buyer (or sink). To the extent a Network Customer does designate the Generating Facility as a Network Resource, it must do so pursuant to the Tariff.

Once an Interconnection Customer satisfies the requirements for obtaining NR Interconnection Service, any future Transmission Service request for delivery from the Generating Facility within the Transmission System of any amount of capacity and/or energy, up to the amount initially studied, will not require that any additional studies be performed or that any further upgrades associated with such Generating Facility be undertaken, regardless of whether such Generating Facility is ever designated by a Network Customer as a Network Resource and regardless of changes in ownership of the Generating Facility. To the extent Interconnection Customer enters into an arrangement for long term Transmission Service for deliveries from the Generating Facility to customers other than the studied Network Customers, or for any Point-To-Point Transmission Service, such request may require additional studies and upgrades in order for Transmission Provider to grant such request. However, the reduction or elimination of congestion or redispatch costs may require additional studies and the construction of additional upgrades.

To the extent Interconnection Customer enters into an arrangement for long term Transmission Service for deliveries from the Generating Facility outside the Transmission System, such request may require additional studies and upgrades in order for Transmission Provider to grant such request.

4.1.2.3 Conditional NR Interconnection Service. An Interconnection Customer seeking NR Interconnection Service for new or added capacity at a Generating Facility may be granted conditional NR Interconnection Service status to the extent there is such capacity available on the Transmission System to accommodate the Interconnection Customer's

Generating Facility. At the request of Interconnection Customer, conditional NR Interconnection Service status may be granted subject to the system being able to accommodate the interconnection without upgrades, until such time as higher queued project(s) with a later service date affecting the same common elements is placed into service. The conditional NR Interconnection Service status may be converted to ER Interconnection Service if either of the following occurs:

1) Interconnection Customer fails to fund necessary studies and Network Upgrades required to allow the Interconnection Customer's Generating Facility to receive NR Interconnection Service upon the completion of higher queued projects involving the same common elements; or

2) The higher queued project(s) or planned and required Network Upgrades are placed in service and the Network Upgrades required to provide NR Interconnection Service status to the Interconnection Customer's Generating Facility are not in service.

In the event Interconnection Customer fails to fund the necessary studies and Network Upgrades for NR Interconnection Service, the Interconnection Customer's conditional NR Interconnection Service status shall be converted to ER Interconnection Service status unless Interconnection Customer makes a new Interconnection Request. Such new Interconnection Request shall be evaluated in accordance with the GIP and its new queue position.

Some or all of the conditional NR Interconnection Service status may be temporarily revoked if the Network Upgrades are not in service when the higher queued project(s) are placed in service. The availability of conditional NR Interconnection Service status will be determined by Transmission Provider's studies. Upon funding and completion of the Network Upgrades required to establish the Generating Facility's NR Interconnection Service status, the Generating Facility will be granted NR Interconnection Service status.

The Parties agree that the portion of the Generating Facility classified as NR Interconnection Service is the first portion of the output of the combined output of all the units at the Generating Facility except in circumstances where Interconnection Customer otherwise elects this GIA, as amended, to allocate that portion to the output of specific unit(s) at the Generating Facility, the total of which will not exceed the output eligible for NR Interconnection Service as shown by the additional studies. To the extent Interconnection Customer desires to obtain NR Interconnection Service for any portion of the Generating Facility in addition to that supported by such additional studies, Interconnection Customer will be

required to request such additional NR Interconnection Service through a separate Interconnection Request in accordance with the GIP.

4.1.3 Surplus Interconnection Service (SI).

4.1.3.1 The Product. Surplus Interconnection Service is restricted Interconnection Service that allows an Interconnection Customer to increase the gross generating capability at the same Point of Interconnection of an Existing Generating Facility without increasing the total amount of Interconnection Service at the Point of Interconnection.

4.1.3.2 Transmission Delivery Service Implications. Surplus Interconnection Service does not convey any right to deliver electricity to any specific customer or Point of Delivery.

4.2 Provision of Service. Transmission Provider shall provide Interconnection Service for the Generating Facility at the Point of Interconnection.

4.3 Performance Standards. Each Party shall perform all of its obligations under this GIA in accordance with Applicable Laws and Regulations, Applicable Reliability Standards, and Good Utility Practice. To the extent a Party is required or prevented or limited in taking any action by such regulations and standards, or if the obligations of any Party may become limited by a change in Applicable Laws and Regulations, Applicable Reliability Standards, and Good Utility Practice after the execution of this GIA, that Party shall not be deemed to be in Breach of this GIA for its compliance therewith. The Party so limited shall notify the other Parties whereupon Transmission Provider shall amend this GIA in concurrence with the other Parties and submit the amendment to the Commission for approval.

4.4 No Transmission Delivery Service. The execution of this GIA does not constitute a request for, or the provision of, any transmission delivery service under the Tariff, and does not convey any right to deliver electricity to any specific customer or Point of Delivery.

4.5 Interconnection Customer Provided Services. The services provided by Interconnection Customer under this GIA are set forth in Article 9.6 and Article 13.4.1. Interconnection Customer shall be paid for such services in accordance with Article 11.7.

ARTICLE 5. INTERCONNECTION FACILITIES ENGINEERING, PROCUREMENT, AND CONSTRUCTION

5.1 Options. Unless otherwise mutually agreed to between the Parties, Interconnection Customer shall select: 1) the In-Service Date, Initial Synchronization Date, and Commercial Operation Date based on a reasonable construction schedule that will allow sufficient time for design, construction, equipment procurement, and permit acquisition of Transmission System equipment or right-of-way; and 2) either the Standard Option or

Alternate Option set forth below and such dates and selected option shall be set forth in Appendix B. If the dates designated by Interconnection Customer are not acceptable to Transmission Owner, Transmission Owner shall so notify Interconnection Customer within thirty (30) Calendar Days. Upon receipt of the notification that Interconnection Customer's designated dates are not acceptable to Transmission Owner, the Interconnection Customer shall notify Transmission Owner within thirty (30) Calendar Days whether it elects to exercise the Option to Build if it has not already elected to exercise the Option to Build.

5.1.1 Standard Option. Transmission Owner shall design, procure, and construct the Transmission Owner's Interconnection Facilities, Network Upgrades, System Protection Facilities, Distribution Upgrades, and Generator Upgrades using Reasonable Efforts to complete the Transmission Owner's Interconnection Facilities, Network Upgrades, System Protection Facilities, Distribution Upgrades and Generator Upgrades by the dates set forth in Appendix B, Milestones, subject to the receipt of all approvals required from Governmental Authorities and the receipt of all land rights necessary to commence construction of such facilities, and such other permits or authorizations as may be required. Transmission Provider or Transmission Owner shall not be required to undertake any action which is inconsistent with its standard safety practices, its material and equipment specifications, its design criteria and construction procedures, its labor agreements, Applicable Laws and Regulations and Good Utility Practice. In the event Transmission Owner reasonably expects that it will not be able to complete the Transmission Owner's Interconnection Facilities, Network Upgrades, System Protection Facilities, Distribution Upgrades and Generator Upgrades by the specified dates, Transmission Owner shall promptly provide written notice to Interconnection Customer and Transmission Provider and shall undertake Reasonable Efforts to meet the earliest dates thereafter.

5.1.2 Alternate Option. If the dates designated by Interconnection Customer are acceptable to Transmission Provider and Transmission Owner, Transmission Provider shall so notify Interconnection Customer within thirty (30) Calendar Days, and Transmission Owner shall assume responsibility for the design, procurement and construction of the Transmission Owner's Interconnection Facilities by the designated dates.

If Transmission Owner subsequently fails to complete the Transmission Owner's Interconnection Facilities by the In-Service Date, to the extent necessary to provide back feed power; or fails to complete Network Upgrades by the Initial Synchronization Date to the extent necessary to allow for Trial Operation at full power output, unless other arrangements are made by the Parties for such Trial Operation; or fails to complete the Network Upgrades by the Commercial Operation Date, as such dates are reflected in Appendix B, Milestones; Transmission Owner shall pay Interconnection Customer liquidated damages in accordance with Article 5.3, Liquidated Damages, provided, however, the dates designated by Interconnection Customer shall be extended day for day for each

Calendar Day that Transmission Provider refuses to grant clearances to install equipment.

Transmission Owner and Interconnection Customer may adopt an incentive payment schedule that is mutually agreeable to encourage Transmission Owner to meet specified accelerated dates. Such payment by Interconnection Customer is not subject to refund.

5.1.3 Option to Build. Pursuant to Section 7.3.2.5 & 7.3.3.5 of the GIP, Individual or Multiple Interconnection Customers shall have the option to assume responsibility for the design, procurement and construction of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades by the dates originally designated by Interconnection Customer under Article 5.1.2, if the requirements of this Article 5.1.3 are met. When multiple Interconnection Customers exercise this option, multiple Interconnection Customers may agree to exercise this option provided (1) all Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades constructed under this option are only required for Interconnection Customers in a single Cluster and (2) all impacted Interconnection Customers execute and provide to Transmission Provider an agreement regarding responsibilities, and payment for, the construction of Transmission Provider's Interconnection Facilities and Stand Alone Network Upgrades planned to be built under this option. The Parties must agree as to what constitutes Stand Alone Network Upgrades and identify such Stand Alone Network Upgrades in Appendix A. Except for Stand Alone Network Upgrades, Interconnection Customer shall have no right to construct Network Upgrades under this option.

5.1.4 Negotiated Option. If the dates designated by Interconnection Customer pursuant to Article 5.1 are not acceptable to Transmission Owner, the Parties shall in good faith attempt to negotiate terms and conditions (including revision of the specified dates and liquidated damages, the provision of incentives, or the procurement and construction of all facilities other than Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades if the Interconnection Customer elects to exercise the Option to Build under Article 5.1.3). If the Parties are unable to reach agreement on such terms and conditions, then, pursuant to Article 5.1.1 (Standard Option), Transmission Owner shall assume responsibility for the design, procurement and construction of all facilities other than Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades if Interconnection Customer has elected to exercise the Option to Build.

Transmission Owner and Interconnection Customer may adopt an incentive payment schedule that is mutually agreeable to encourage Transmission Owner to meet specified accelerated dates. Such payment by Interconnection Customer is not subject to refund.

5.2 General Conditions Applicable to Option to Build. If Interconnection Customer assumes responsibility for the design, procurement and construction of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades after receipt of all required approvals from Governmental Authorities necessary to commence construction,

(1) Interconnection Customer shall engineer, procure equipment, and construct the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades (or portions thereof) using Good Utility Practice and using standards and specifications provided in advance by Transmission Owner, or as required by any Governmental Authority;

(2) Interconnection Customer's engineering, procurement and construction of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades shall comply with all requirements of law or Governmental Authority to which Transmission Owner would be subject in the engineering, procurement or construction of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades;

(3) Transmission Provider, at Transmission Provider's option, and Transmission Owner shall be entitled to review and approve the engineering design, equipment acceptance tests(including witnessing of acceptance tests), and the construction (including monitoring of construction) of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades, and shall have the right to reject any design, procurement, construction or acceptance test of any equipment that does not meet the standards and specifications of Transmission Provider, Transmission Owner and any Governmental Authority;

(4) prior to commencement of construction, Interconnection Customer shall provide to Transmission Provider and Transmission Owner a schedule for construction of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades, and shall promptly respond to requests for information from Transmission Provider and Transmission Owner;

(5) at any time during construction, Transmission Provider and Transmission Owner shall have unrestricted access to the construction site for the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades and to conduct inspections of the same;

(6) at any time during construction, should any phase of the engineering, equipment procurement, or construction of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades not meet the standards and specifications provided by Transmission Owner, Interconnection Customer shall be obligated to remedy deficiencies in that portion of the Transmission Owner's Interconnection Facilities and Stand Alone Network

Upgrades to meet the standards and specifications provided by Transmission Provider and Transmission Owner;

(7) Interconnection Customer shall indemnify Transmission Provider and Transmission Owner for claims arising from the Interconnection Customer's construction of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades under the terms and procedures applicable to Article 18.1, Indemnity;

(8) Interconnection Customer shall transfer control of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades to Transmission Owner;

(9) Unless Parties otherwise agree, Interconnection Customer shall transfer ownership of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades to Transmission Owner in accordance with Appendix B;

(10) Transmission Provider, at Transmission Provider's option, and Transmission Owner shall approve and accept for operation and maintenance the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades to the extent engineered, procured, and constructed in accordance with this Article 5.2 only if the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades meet the standards and specifications of Transmission Provider, Transmission Owner and any Governmental Authority.

(11) Interconnection Customer shall deliver to Transmission Owner "as-built" drawings, information, and any other documents that are reasonably required by Transmission Owner to assure that the Interconnection Facilities and Stand-Alone Network Upgrades are built to the standards and specifications required by Transmission Owner.

(12) If Interconnection Customer exercises the Option to Build pursuant to Article 5.1.3, Interconnection Customer shall pay Transmission Owner the agreed upon amount of [$ PLACEHOLDER] for Transmission Owner to execute the responsibilities enumerated to Transmission Owner under Article 5.2. Transmission Owner shall invoice Interconnection Customer for this total amount to be divided on a monthly basis pursuant to Article 12.

(13) If Interconnection Customer exercises the Option to Build pursuant to Article 5.1.3, and the Transmission Owner has elected to fund the costs of Network Upgrades pursuant to Article 11.3, then prior to Interconnection Customer incurring any construction costs relating to the Option to Build and by the date specified in Appendix B, Interconnection Customer shall invoice the Transmission Owner for the estimated amount to be expended by the Interconnection Customer to construct any Stand Alone Network Upgrades for

which the Interconnection Customer has exercised its Option to Build in accordance with Appendix B. The Transmission Owner shall be required to reimburse Interconnection Customer for the full amount of such invoiced costs by the date specified in Appendix B, which shall be prior to the date by which Interconnection Customer must make any construction payment for such Stand Alone Network Upgrades. After completion of the construction of Stand Alone Network Upgrades by the Interconnection Customer and by the date specified in Appendix B for the Interconnection Customer to transfer such Stand Alone Network Upgrades to the Transmission Owner, Interconnection Customer shall provide an invoice of the final cost of the construction of Stand Alone Upgrades and shall set forth such costs in sufficient detail to enable the Transmission Owner to compare the actual costs with the estimates and to ascertain deviations, if any, from the cost estimates. In the event that the actual costs exceed the estimated costs previously invoiced by Interconnection Customer and paid by Transmission Owner, Transmission Owner shall pay to Interconnection Customer the difference between the amount previously paid and the actual costs within thirty (30) Calendar Days after receipt of a final construction invoice from Interconnection Customer. In the event that the actual costs are less than the estimated costs previously invoiced by Interconnection Customer and paid by Transmission Owner, Interconnection Customer shall refund, with interest (calculated in accordance with 18 C.F.R. Section 35.19a(a)(2)(iii), to Transmission Owner any amount by which the actual payment by Transmission Owner for estimated costs exceeds the actual costs of construction within thirty (30) Calendar Days of the issuance of such final construction invoice. Following the transfer of the Stand Alone Network Upgrades from the Interconnection Customer to the Transmission Owner, the Interconnection Customer shall make payments for such facilities to the Transmission Owner pursuant to an agreement between and among the Parties.

5.3 Liquidated Damages. The actual damages to Interconnection Customer, in the event the Transmission Owner's Interconnection Facilities or Network Upgrades are not completed by the dates designated by Interconnection Customer and accepted by Transmission Provider and Transmission Owner pursuant to subparagraphs 5.1.2 or 5.1.4, above, may include Interconnection Customer's fixed operation and maintenance costs and lost opportunity costs. Such actual damages are uncertain and impossible to determine at this time. Because of such uncertainty, any liquidated damages paid by Transmission Owner to Interconnection Customer in the event that Transmission Owner does not complete any portion of the Transmission Owner's Interconnection Facilities or Network Upgrades by the applicable dates, shall be an amount equal to ½ of 1 percent per day of the actual cost of the Transmission Owner's Interconnection Facilities and Network Upgrades, in the aggregate, for which Transmission Owner has assumed responsibility to design, procure and construct.

However, in no event shall the total liquidated damages exceed 20 percent of the actual cost of the Transmission Owner's Interconnection Facilities and Network Upgrades for which Transmission Owner has assumed responsibility to design, procure, and construct.

The foregoing payments will be made by Transmission Owner to Interconnection Customer as just compensation for the damages caused to Interconnection Customer, which actual damages are uncertain and impossible to determine at this time, and as reasonable liquidated damages, but not as a penalty or a method to secure performance of this GIA. Liquidated damages, when the Parties agree to them, are the exclusive remedy for the Transmission Owner's failure to meet its schedule.

No liquidated damages shall be paid to Interconnection Customer if: (1) Interconnection Customer is not ready to commence use of the Transmission Owner's Interconnection Facilities or Network Upgrades to take the delivery of power for the Generating Facility's Trial Operation or to export power from the Generating Facility on the specified dates, unless Interconnection Customer would have been able to commence use of the Transmission Owner's Interconnection Facilities or Network Upgrades to take the delivery of power for Generating Facility's Trial Operation or to export power from the Generating Facility, but for Transmission Owner's delay; (2) the Transmission Owner's failure to meet the specified dates is the result of the action or inaction of Transmission Provider, Interconnection Customer or any other earlier queued Interconnection Customer who has entered into an earlier GIA with Transmission Provider and/or a Transmission Owner or with an Affected System Operator, or any cause beyond Transmission Owner's reasonable control or reasonable ability to cure; (3) Interconnection Customer has assumed responsibility for the design, procurement and construction of the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades; (4) the delay is due to the inability of Transmission Owner to obtain all required approvals from Governmental Authorities in a timely manner for the construction of any element of the Interconnection Facilities, Network Upgrades or Stand Alone Network Upgrades, or any other permit or authorization required, or any land rights or other private authorizations that may be required, and Transmission Owner has exercised Reasonable Efforts in procuring such approvals, permits, rights or authorizations; or (5) the Parties have otherwise agreed.

5.4 Power System Stabilizers. Interconnection Customer shall procure, install, maintain and operate power system stabilizers in accordance with the guidelines and procedures established by the Electric Reliability Organization. Transmission Provider and Transmission Owner reserve the right to reasonably establish minimum acceptable settings for any installed power system stabilizers, subject to the design and operating limitations of the Generating Facility. If the Generating Facility's power system stabilizers are removed from service or are not capable of automatic operation, Interconnection Customer shall immediately notify the Transmission Provider's system operator, or its designated representative. The requirements of this paragraph shall not apply to induction generators.

5.5 Equipment Procurement. If responsibility for construction of the Transmission Owner's Interconnection Facilities, Network Upgrades and/or Distribution Upgrades is to be borne by Transmission Owner, then Transmission Owner shall commence design of the Transmission Owner's Interconnection Facilities, Network Upgrades and/or Distribution Upgrades, and procure necessary equipment as soon as practicable after all

of the following conditions are satisfied, unless the Parties otherwise agree in writing:

5.5.1 Transmission Provider has completed the Interconnection Facilities Study pursuant to the Interconnection Facilities Study Agreement; and

5.5.2 Where applicable, Interconnection Customer has provided security to Transmission Owner in accordance with Article 11.6 by the dates specified in Appendix B, Milestones.

5.6 Construction Commencement. Transmission Owner shall commence construction of the Transmission Owner's Interconnection Facilities, Network Upgrades, Transmission Owner's System Protection Facilities, Distribution Upgrades, and Generator Upgrades for which it is responsible as soon as practicable after the following additional conditions are satisfied:

5.6.1 Approval of the appropriate Governmental Authority has been obtained for any facilities requiring regulatory approval; and

5.6.2 Where applicable, Interconnection Customer has provided security to Transmission Owner in accordance with Article 11.6 by the dates specified in Appendix B, Milestones.

5.7 Work Progress. Transmission Owner and Interconnection Customer will keep each other and Transmission Provider advised periodically as to the progress of their respective design, procurement and construction efforts. Either Transmission Owner or Interconnection Customer may, at any time, request a progress report from the other, with a copy to be provided to the other Parties. If, at any time, Interconnection Customer determines that the completion of the Transmission Owner's Interconnection Facilities, Network Upgrades, or Transmission Owner's System Protection Facilities will not be required until after the specified In-Service Date, Interconnection Customer will provide written notice to Transmission Provider and Transmission Owner of such later date upon which the completion of the Transmission Owner's Interconnection Facilities, Network Upgrades or Transmission Owner's System Protection Facilities will be required. Transmission Owner may delay the In-Service Date of its facilities accordingly.

5.8 Information Exchange. As soon as reasonably practicable after the Effective Date, the Parties shall exchange information regarding the design and compatibility of the Interconnection Facilities and compatibility of the Interconnection Facilities with the Transmission System or Distribution System, as applicable, and shall work diligently and in good faith to make any necessary design changes.

5.9 Other Interconnection Options.

5.9.1 Limited Operation. If any of the Transmission Owner's Interconnection Facilities, Network Upgrades, or Transmission Owner's System Protection Facilities, Distribution Upgrades or Generator Upgrades are not reasonably

expected to be completed prior to the Commercial Operation Date of the Generating Facility, Transmission Provider shall, upon the request and at the expense of Interconnection Customer, perform operating studies on a timely basis to determine the extent to which the Generating Facility and the Interconnection Customer's Interconnection Facilities may operate prior to the completion of the Transmission Owner's Interconnection Facilities, Network Upgrades, Transmission Owner's System Protection Facilities, Distribution Upgrades or Generator Upgrades consistent with Applicable Laws and Regulations, Applicable Reliability Standards, Good Utility Practice, and this GIA. Transmission Provider and Transmission Owner shall permit Interconnection Customer to operate the Generating Facility and the Interconnection Customer's Interconnection Facilities in accordance with the results of such studies; provided, however, such studies reveal that such operation may occur without detriment to the Transmission System as then configured and in accordance with the safety requirements of Transmission Owner and any Governmental Authority.

The maximum permissible output of the Generating Facility will be updated on a quarterly basis if the Network Upgrades necessary for the interconnection of the Generating Facility pursuant to this GIA are not in service within six (6) months following the Commercial Operation Date of the Generating Facility as specified in Appendix B of this GIA. These quarterly studies will be performed using the same methodology set forth in Section 11.5 of the GIP. These quarterly updates will end when all Network Upgrades necessary for the interconnection of the Generating Facility pursuant to this GIA are in service.

5.9.2 Provisional Interconnection Service.

Upon the request of Interconnection Customer, and prior to completion of requisite Interconnection Facilities, Network Upgrades, Distribution Upgrades, or System Protection Facilities Transmission Provider may execute a Provisional Generator Interconnection Agreement or Interconnection Customer may request the filing of an unexecuted Provisional Generator Interconnection Agreement with the Interconnection Customer for limited interconnection service at the discretion of Transmission Provider based upon an evaluation that will consider the results of available studies. Transmission Provider shall determine, through available studies or additional studies as necessary, whether stability, short circuit, thermal, and/or voltage issues would arise if Interconnection Customer interconnects without modifications to the Generating Facility or Transmission Provider's system. Transmission Provider shall determine whether any Interconnection Facilities, Network Upgrades, Distribution Upgrades, or System Protection Facilities that are necessary to meet the requirements of the Electric Reliability Organization, or any applicable Regional Entity for the interconnection of a new, modified and/or expanded Generating Facility are in place prior to the commencement of interconnection service from the Generating Facility. Where available studies indicate that such Interconnection Facilities, Network Upgrades, Distribution Upgrades, and/or System Protection Facilities that are required for the interconnection of a new, modified and/or expanded Generating Facility are

not currently in place, Transmission Provider will perform a study, at the Interconnection Customer's expense, to confirm the facilities that are required for Provisional Interconnection Service. The maximum permissible output of the Generating Facility in the Provisional Generator Interconnection Agreement shall be studied and updated on a quarterly basis. Interconnection Customer assumes all risk and liabilities with respect to changes between the Provisional Generator Interconnection Agreement and the Generator Interconnection Agreement, including changes in output limits and Interconnection Facilities, Network Upgrades, Distribution Upgrades, and/or System Protection Facilities cost responsibilities.

5.10 Interconnection Customer's Interconnection Facilities. Interconnection Customer shall, at its expense, design, procure, construct, own or control, and install the ICIF, as set forth in Appendix A.

5.10.1 Interconnection Customer's Interconnection Facility Specifications. Interconnection Customer shall submit initial design and specifications for the ICIF, including Interconnection Customer's System Protection Facilities, to Transmission Provider and Transmission Owner at least one hundred eighty (180) Calendar Days prior to the Initial Synchronization Date; and final design and specifications for review and comment at least ninety (90) Calendar Days prior to the Initial Synchronization Date. Transmission Provider at Transmission Provider's option, and Transmission Owner shall review such specifications to ensure that the ICIF are compatible with their respective technical specifications, operational control, and safety requirements and comment on such design and specifications within thirty (30) Calendar Days of Interconnection Customer's submission. All specifications provided hereunder shall be deemed confidential.

5.10.2 Transmission Provider's and Transmission Owner's Review. Transmission Provider's and Transmission Owner's review of Interconnection Customer's final specifications shall not be construed as confirming, endorsing, or providing a warranty as to the design, fitness, safety, durability or reliability of the Generating Facility, or the ICIF. Interconnection Customer shall make such changes to the ICIF as may reasonably be required by Transmission Provider and Transmission Owner, in accordance with Good Utility Practice, to ensure that the ICIF are compatible with the technical specifications, operational control and safety requirements of Transmission Provider and Transmission Owner.

5.10.3 ICIF Construction. The ICIF shall be designed and constructed in accordance with Good Utility Practice. Within one hundred twenty (120) Calendar Days after the Commercial Operation Date, unless the Parties agree on another mutually acceptable deadline, Interconnection Customer shall deliver to Transmission Provider and Transmission Owner "as-built" drawings, information and documents for the ICIF, such as: a one-line diagram, a site plan

showing the Generating Facility and the ICIF, plan and elevation drawings showing the layout of the ICIF, a relay functional diagram, relaying AC and DC schematic wiring diagrams and relay settings for all facilities associated with the Interconnection Customer's step-up transformers, the facilities connecting the Generating Facility to the step-up transformers and the ICIF, and the impedances (determined by factory tests) for the associated step-up transformers and the Generating Facility. Interconnection Customer shall provide Transmission Provider and Transmission Owner with Interconnection Customer's specifications for the excitation system, automatic voltage regulator, Generating Facility control and protection settings, transformer tap settings, and communications, if applicable.

5.11 Transmission Owner's Interconnection Facilities Construction. The Transmission Owner's Interconnection Facilities shall be designed and constructed in accordance with Good Utility Practice. Upon request, within one hundred twenty (120) Calendar Days after the Commercial Operation Date, unless the Parties agree on another mutually acceptable deadline, Transmission Owner shall deliver to Transmission Provider (if requested) and Interconnection Customer the "as-built" drawings, information and documents for the Transmission Owner's Interconnection Facilities specified in Appendix C to this GIA.

Such drawings, information and documents shall be deemed Confidential Information.

Upon completion, the Transmission Owner's Interconnection Facilities and Stand Alone Network Upgrades shall be under the control of Transmission Provider or its designated representative.

5.12 Access Rights. Upon reasonable notice by a Party, and subject to any required or necessary regulatory approvals, a Party ("Granting Party") shall furnish *at no cost* to the other Party ("Access Party") any rights of use, licenses, rights of way and easements with respect to lands owned or controlled by the Granting Party, its agents (if allowed under the applicable agency agreement), or any Affiliate, that are necessary to enable the Access Party to obtain ingress and egress to construct, operate, maintain, repair, test (or witness testing), inspect, replace or remove facilities and equipment to: (i) interconnect the Generating Facility with the Transmission System; (ii) operate and maintain the Generating Facility, the Interconnection Facilities and the Transmission System; and (iii) disconnect or remove the Access Party's facilities and equipment upon termination of this GIA. In exercising such licenses, rights of way and easements, the Access Party shall not unreasonably disrupt or interfere with normal operation of the Granting Party's business and shall adhere to the safety rules and procedures established in advance, as may be changed from time to time, by the Granting Party and provided to the Access Party.

5.13 Lands of Other Property Owners. If any part of the Transmission Owner's Interconnection Facilities, Network Upgrades, and/or Distribution Upgrades is to be installed on property owned by persons other than Interconnection Customer or

Transmission Owner, Transmission Owner shall at Interconnection Customer's expense use efforts, similar in nature and extent to those that it typically undertakes on its own behalf or on behalf of its Affiliates, including use of its eminent domain authority to the extent permitted and consistent with Applicable Laws and Regulations and, to the extent consistent with such Applicable Laws and Regulations, to procure from such persons any rights of use, licenses, rights of way and easements that are necessary to construct, operate, maintain, test, inspect, replace or remove the Transmission Owner's Interconnection Facilities, Network Upgrades and/or Distribution Upgrades upon such property.

5.14 Permits. Transmission Provider or Transmission Owner and Interconnection Customer shall cooperate with each other in good faith in obtaining all permits, licenses and authorizations that are necessary to accomplish the interconnection in compliance with Applicable Laws and Regulations. With respect to this paragraph, Transmission Owner shall provide permitting assistance to Interconnection Customer comparable to that provided to the Transmission Owner's own, or an Affiliate's, generation to the extent that Transmission Owner or its Affiliate owns generation.

5.15 Early Construction of Base Case Facilities. (Includes facilities required for all queued projects with interconnection agreements).Interconnection Customer may request Transmission Owner to construct, and Transmission Owner shall construct, using Reasonable Efforts to accommodate Interconnection Customer's In-Service Date, all or any portion of any Network Upgrades, Transmission Owner's System Protection Facilities or Distribution Upgrades required for Interconnection Customer to be interconnected to the Transmission or Distribution System, as applicable, which are included in the Base Case of the Interconnection Facilities Study for Interconnection Customer, and which also are required to be constructed for another Interconnection Customer with a prior GIA, but where such construction is not scheduled to be completed in time to achieve Interconnection Customer's In-Service Date. Any such Network Upgrades, System Protection Facilities or Distribution Upgrades are included in the facilities to be constructed and as set forth in Appendix A to this GIA to the extent they are reasonably known.

5.16 Suspension.

5.16.1 Interconnection Customer's Right to Suspend for Force Majeure Event; Obligations. Provided that such suspension is permissible under the authorizations, permits or approvals granted for the construction of such Interconnection Facilities, Network Upgrades or Stand Alone Network Upgrades, Interconnection Customer will not suspend unless a Force Majeure event occurs.

Interconnection Customer must provide written notice of its request for suspension to Transmission Provider and Transmission Owner, and provide a description of the Force Majeure event that is acceptable to Transmission Provider. Suspension will only apply to Interconnection Customer milestones and Interconnection Facilities described in the Appendices of this GIA. Prior to

suspension, Interconnection Customer must also provide security acceptable to Transmission Owner, equivalent to the higher of $5 million or the total cost of all Network Upgrades, Transmission Owner's System Protection Facilities, and Distribution Upgrades listed in Appendix A of this GIA. Network Upgrades and Transmission Owner's Interconnection Facilities will be constructed on the schedule described in the Appendices of this GIA unless: (1) construction is prevented by the order of a Governmental Authority; (2) the Network Upgrades are not needed by any other project; or (3) Transmission Owner or Transmission Provider determines that a Force Majeure event prevents construction. In the event of (1), (2), or (3) security shall be released upon the determination that the Network Upgrades will no longer be constructed.

If suspension occurs, the Transmission or Distribution System, as applicable, shall be left in a safe and reliable condition in accordance with Good Utility Practice and the Transmission Provider's and Transmission Owner's safety and reliability criteria. In such event, Interconnection Customer shall be responsible for all reasonable and necessary costs which Transmission Provider and Transmission Owner (i) have incurred pursuant to this GIA prior to the suspension and (ii) incur in suspending such work, including any costs incurred to perform such work as may be necessary to ensure the safety of persons and property and the integrity of the Transmission or Distribution System, as applicable, during such suspension and, if applicable, any costs incurred in connection with the cancellation or suspension of material, equipment and labor contracts which Transmission Provider and Transmission Owner cannot reasonably avoid; provided, however, that prior to canceling or suspending any such material, equipment or labor contract, Transmission Provider and Transmission Owner shall obtain Interconnection Customer's authorization to do so.

Transmission Provider and Transmission Owner shall each invoice Interconnection Customer for such costs pursuant to Article 12 and shall use Reasonable Efforts to minimize its costs. In the event Interconnection Customer suspends work by Transmission Owner required under this GIA pursuant to this Article 5.16, and has not requested Transmission Owner to recommence the work required under this GIA on or before the expiration of three (3) years following commencement of such suspension, this GIA shall be deemed terminated. The three-year period shall begin on the date the suspension is requested, or the date of the written notice to Transmission Provider, if no effective date is specified.

5.16.2 Effect of Missed Interconnection Customer Milestones. If Interconnection Customer fails to provide notice of suspension pursuant to Article 5.16, and Interconnection Customer fails to fulfill or complete any Interconnection Customer Milestone provided in Appendix B ("Milestone"), this constitutes a Breach under this GIA. Depending upon the consequences of the Breach and effectiveness of the cure pursuant to Article 17, the Transmission Owner's Milestones may be revised, following consultation with Interconnection Customer, consistent with Reasonable Efforts, and in consideration of all relevant

circumstances. Parties shall employ Reasonable Efforts to maintain their remaining respective Milestones.

5.16.3 Effect of Suspension; Parties Obligations. In the event that Interconnection Customer suspends work pursuant to this Article 5.16, no construction duration, timelines and schedules set forth in Appendix B shall be suspended during the period of suspension unless ordered by a Governmental Authority, with such order being the Force Majeure event causing the suspension. Should Interconnection Customer request that work be recommenced, Transmission Owner shall be obligated to proceed with Reasonable Efforts and in consideration of all relevant circumstances including regional outage schedules, construction availability and material procurement in performing the work as described in Appendix A and Appendix B. Transmission Owner will provide Interconnection Customer with a revised schedule for the design, procurement, construction, installation and testing of the Transmission Owner's Interconnection Facilities and Network Upgrades. Upon any suspension by Interconnection Customer pursuant to Article 5.16, Interconnection Customer shall be responsible for only those costs specified in this Article 5.16.

5.17 Taxes.

5.17.1 Interconnection Customer Payments Not Taxable. The Parties intend that all payments or property transfers made by Interconnection Customer to Transmission Owner for the installation of the Transmission Owner's Interconnection Facilities, Network Upgrades, Transmission Owner's System Protection Facilities, Distribution Upgrades and Generator Upgrades shall be non-taxable, either as contributions to capital, or as an advance, in accordance with the Internal Revenue Code and any applicable state income tax laws and shall not be taxable as contributions in aid of construction or otherwise under the Internal Revenue Code and any applicable state income tax laws. To the extent that Transmission Owner is a limited liability company and not a corporation, and has elected to be taxed as a partnership, then the following shall apply: Transmission Owner represents, and the Parties acknowledge, that Transmission Owner is a limited liability company and is treated as a partnership for federal income tax purposes. Any payment made by Interconnection Customer to Transmission Owner for Network Upgrades is to be treated as an upfront payment in accordance with Rev Proc 2005-35. It is anticipated by the parties that any amounts paid by Interconnection Customer to Transmission Owner for Network Upgrades will be reimbursed to Interconnection Customer in accordance with the terms of this GIA, provided Interconnection Customer fulfills its obligations under this GIA.

5.17.2 Representations and Covenants. In accordance with IRS Notice 2016-36, Interconnection Customer represents and covenants that (i) ownership of the electricity generated at the Generating Facility will pass to another party prior to the transmission of the electricity on the Transmission System, (ii) for

income tax purposes, the amount of any payments and the cost of any property transferred to Transmission Owner for the Transmission Owner's Interconnection Facilities will be capitalized by Interconnection Customer as an intangible asset and recovered using the straight-line method over a useful life of twenty (20) years, and (iii) any portion of the Transmission Owner's Interconnection Facilities that is a "dual-use intertie," within the meaning of IRS Notice 2016-36, is reasonably expected to carry only a de minimis amount of electricity in the direction of the Generating Facility. For this purpose, "de minimis amount" means no more than 5 percent of the total power flows in both directions, calculated in accordance with the "5 percent test" set forth in IRS Notice 2016-36. This is not intended to be an exclusive list of the relevant conditions that must be met to conform to IRS requirements for non-taxable treatment.

At Transmission Owner's request, Interconnection Customer shall provide Transmission Owner with a report from an independent engineer confirming its representation in clause (iii), above, with a copy to Transmission Provider. Transmission Owner represents and covenants that the cost of the Transmission Owner's Interconnection Facilities paid for by Interconnection Customer will have no net effect on the base upon which rates are determined.

5.17.3 Indemnification for the Cost Consequences of Current Tax Liability Upon Transmission Owner. Notwithstanding Article 5.17.1 and to the extent permitted by law, Interconnection Customer shall protect, indemnify and hold harmless Transmission Owner from the cost consequences of any tax liability imposed against Transmission Owner as the result of payments or property transfers made by Interconnection Customer to Transmission Owner under this GIA for Interconnection Facilities, as well as any interest and penalties, other than interest and penalties attributable to any delay caused by Transmission Owner.

Transmission Owner shall not include a gross-up for the cost consequences of any current tax liability in the amounts it charges Interconnection Customer under this GIA unless (i) Transmission Owner has determined, in good faith, that the payments or property transfers made by Interconnection Customer to Transmission Owner should be reported as income subject to taxation or (ii) any Governmental Authority directs Transmission Owner to report payments or property as income subject to taxation; provided, however, that Transmission Owner may require Interconnection Customer to provide security for Interconnection Facilities, in a form reasonably acceptable to Transmission Owner (such as a parental guarantee or a letter of credit), in an amount equal to the cost consequences or any current tax liability under this Article 5.17. Interconnection Customer shall reimburse Transmission Owner for such costs on a fully grossed-up basis, in accordance with Article 5.17.4, within thirty (30) Calendar Days of receiving written notification from Transmission Owner of the amount due, including detail about how the amount was calculated.

The indemnification obligation shall terminate at the earlier of (1) the expiration of the ten-year testing period and the applicable statute of limitation, as it may be extended by Transmission Owner upon request of the IRS, to keep these years open for audit or adjustment, or (2) the occurrence of a subsequent taxable event and the payment of any related indemnification obligations as contemplated by this Article 5.17.

5.17.4 Tax Gross-Up Amount. Interconnection Customer's liability for the cost consequences of any current tax liability under this Article 5.17 shall be calculated on a fully grossed-up basis. Except as may otherwise be agreed to by the parties, this means that Interconnection Customer will pay Transmission Owner, in addition to the amount paid for the Interconnection Facilities, Network Upgrades, Transmission Owner's System Protection Facilities, and/or Distribution Upgrades, an amount equal to (1) the current taxes imposed on Transmission Owner ("Current Taxes") on the excess of (a) the gross income realized by Transmission Owner as a result of payments or property transfers made by Interconnection Customer to Transmission Owner under this GIA (without regard to any payments under this Article 5.17) (the "Gross Income Amount") over (b) the present value of future tax deductions for depreciation that will be available as a result of such payments or property transfers (the "Present Value Depreciation Amount"), plus (2) an additional amount sufficient to permit Transmission Owner to receive and retain, after the payment of all Current Taxes, an amount equal to the net amount described in clause (1).

For this purpose, (i) Current Taxes shall be computed based on Transmission Owner's composite federal and state tax rates at the time the payments or property transfers are received and Transmission Owner will be treated as being subject to tax at the highest marginal rates in effect at that time (the "Current Tax Rate"), and (ii) the Present Value Depreciation Amount shall be computed by discounting Transmission Owner's anticipated tax depreciation deductions as a result of such payments or property transfers by Transmission Owner's current weighted average cost of capital. Thus, the formula for calculating Interconnection Customer's liability to Transmission Owner pursuant to this Article 5.17.4 can be expressed as follows: (Current Tax Rate x (Gross Income Amount – Present Value of Tax Depreciation))/(1-Current Tax Rate). Interconnection Customer's estimated tax liability in the event taxes are imposed shall be stated in Appendix A, Interconnection Facilities, Network Upgrades and Distribution Upgrades.

5.17.5 Private Letter Ruling or Change or Clarification of Law. At Interconnection Customer's request and expense, Transmission Owner shall file with the IRS a request for a private letter ruling as to whether any property transferred or sums paid, or to be paid, by Interconnection Customer to Transmission Owner under this GIA are subject to federal income taxation. Interconnection Customer will prepare the initial draft of the request for a private letter ruling, and will certify

under penalties of perjury that all facts represented in such request are true and accurate to the best of Interconnection Customer's knowledge. Transmission Owner and Interconnection Customer shall cooperate in good faith with respect to the submission of such request.

Transmission Owner shall keep Interconnection Customer fully informed of the status of such request for a private letter ruling and shall execute either a privacy act waiver or a limited power of attorney, in a form acceptable to the IRS, that authorizes Interconnection Customer to participate in all discussions with the IRS regarding such request for a private letter ruling. Transmission Owner shall allow Interconnection Customer to attend all meetings with IRS officials about the request and shall permit Interconnection Customer to prepare the initial drafts of any follow-up letters in connection with the request.

5.17.6 Subsequent Taxable Events. If, within 10 years from the date on which the relevant Transmission Owner's Interconnection Facilities are placed in service, (i) Interconnection Customer breaches the covenant contained in Article 5.17.2, (ii) a "disqualification event" occurs within the meaning of IRS Notice 88-129, or (iii) this GIA terminates and Transmission Owner retains ownership of the Interconnection Facilities, Network Upgrades, Transmission Owner's System Protection Facilities, and/or Distribution Upgrades, Interconnection Customer shall pay a tax gross-up for the cost consequences of any current tax liability imposed on Transmission Owner, calculated using the methodology described in Article 5.17.4 and in accordance with IRS Notice 90-60.

5.17.7 Contests. In the event any Governmental Authority determines that Transmission Owner's receipt of payments or property constitutes income that is subject to taxation, Transmission Owner shall notify Interconnection Customer, in writing, within thirty (30) Calendar Days of receiving notification of such determination by a Governmental Authority. Upon the timely written request by Interconnection Customer and at Interconnection Customer's sole expense, Transmission Owner may appeal, protest, seek abatement of, or otherwise oppose such determination. Upon Interconnection Customer's written request and sole expense, Transmission Owner shall file a claim for refund with respect to any taxes paid under this Article 5.17, whether or not it has received such a determination. Transmission Owner reserves the right to make all decisions with regard to the prosecution of such appeal, protest, abatement or other contest, including the selection of counsel and compromise or settlement of the claim, but Transmission Owner shall keep Interconnection Customer informed, shall consider in good faith suggestions from Interconnection Customer about the conduct of the contest, and shall reasonably permit Interconnection Customer or an Interconnection Customer representative to attend contest proceedings.

Interconnection Customer shall pay to Transmission Owner on a periodic basis, as invoiced by Transmission Owner, Transmission Owner's documented

reasonable costs of prosecuting such appeal, protest, abatement or other contest. At any time during the contest, Transmission Owner may agree to a settlement either with Interconnection Customer's consent or after obtaining written advice from nationally-recognized tax counsel, selected by Transmission Owner, but reasonably acceptable to Interconnection Customer, that the proposed settlement represents a reasonable settlement given the hazards of litigation. Interconnection Customer's obligation shall be based on the amount of the settlement agreed to by Interconnection Customer, or if a higher amount, so much of the settlement that is supported by the written advice from nationally-recognized tax counsel selected under the terms of the preceding sentence. The settlement amount shall be calculated on a fully grossed-up basis to cover any related cost consequences of the current tax liability. Any settlement without Interconnection Customer's consent or such written advice will relieve Interconnection Customer from any obligation to indemnify Transmission Owner for the tax at issue in the contest.

5.17.8 Refund. In the event that (a) a private letter ruling is issued to Transmission Owner which holds that any amount paid or the value of any property transferred by Interconnection Customer to Transmission Owner under the terms of this GIA is not subject to federal income taxation, (b) any legislative change or administrative announcement, notice, ruling or other determination makes it reasonably clear to Transmission Owner in good faith that any amount paid or the value of any property transferred by Interconnection Customer to Transmission Owner under the terms of this GIA is not taxable to Transmission Owner, (c) any abatement, appeal, protest, or other contest results in a determination that any payments or transfers made by Interconnection Customer to Transmission Owner are not subject to federal income tax, or (d) if Transmission Owner receives a refund from any taxing authority for any overpayment of tax attributable to any payment or property transfer made by Interconnection Customer to Transmission Owner pursuant to this GIA, Transmission Owner shall promptly refund to Interconnection Customer the following:

any payment made by Interconnection Customer under this Article 5.17 for taxes that is attributable to the amount determined to be non-taxable, together with interest thereon,

(ii) interest on any amounts paid by Interconnection Customer to Transmission Owner for such taxes which Transmission Owner did not submit to the taxing authority, calculated in accordance with the methodology set forth in 18 C.F.R. Section 35.19a(a)(2)(iii) from the date payment was made by Interconnection Customer to the date Transmission Owner refunds such payment to Interconnection Customer, and

(iii) with respect to any such taxes paid by Transmission Owner, any refund or credit Transmission Owner receives or to which it may be

entitled from any Governmental Authority, interest (or that portion thereof attributable to the payment described in clause (i), above) owed to Transmission Owner for such overpayment of taxes (including any reduction in interest otherwise payable by Transmission Owner to any Governmental Authority resulting from an offset or credit); provided, however, that Transmission Owner will remit such amount promptly to Interconnection Customer only after and to the extent that Transmission Owner has received a tax refund, credit or offset from any Governmental Authority for any applicable overpayment of income tax related to the Transmission Owner's Interconnection Facilities.

The intent of this provision is to leave both parties, to the extent practicable, in the event that no taxes are due with respect to any payment for Interconnection Facilities and Network Upgrades hereunder, in the same position they would have been in had no such tax payments been made.

5.17.9 Taxes Other Than Income Taxes. Upon the timely request by Interconnection Customer, and at Interconnection Customer's sole expense, Transmission Owner shall appeal, protest, seek abatement of, or otherwise contest any tax (other than federal or state income tax) asserted or assessed against Transmission Owner for which Interconnection Customer may be required to reimburse Transmission Owner under the terms of this GIA. Interconnection Customer shall pay to Transmission Owner on a periodic basis, as invoiced by Transmission Owner, Transmission Owner's documented reasonable costs of prosecuting such appeal, protest, abatement, or other contest. Interconnection Customer and Transmission Owner shall cooperate in good faith with respect to any such contest. Unless the payment of such taxes is a prerequisite to an appeal or abatement or cannot be deferred, no amount shall be payable by Interconnection Customer to Transmission Owner for such taxes until they are assessed by a final, non-appealable order by any court or agency of competent jurisdiction. In the event that a tax payment is withheld and ultimately due and payable after appeal, Interconnection Customer will be responsible for all taxes, interest and penalties, other than penalties attributable to any delay caused by Transmission Owner.

5.18 Tax Status. Each Party shall cooperate with the other Parties to maintain each Party's tax status. Nothing in this GIA is intended to adversely affect any Party's tax-exempt status with respect to the issuance of bonds including, but not limited to, Local Furnishing Bonds.

5.19 Modification.

5.19.1 General. Either Party may undertake modifications to its facilities. If a Party plans to undertake a modification that reasonably may be expected to affect another Party's facilities, that Party shall provide to the other Parties sufficient

information regarding such modification so that the other Parties may evaluate the potential impact of such modification prior to commencement of the work. Such information shall be deemed to be Confidential Information hereunder and shall include information concerning the timing of such modifications and whether such modifications are expected to interrupt the flow of electricity from the Generating Facility. The Party desiring to perform such work shall provide the relevant drawings, plans, and specifications to the other Parties at least ninety (90) Calendar Days in advance of the commencement of the work or such shorter period upon which the Parties may agree, which agreement shall not unreasonably be withheld, conditioned or delayed.

In the case of Generating Facility modifications that do not require Interconnection Customer to submit an Interconnection Request, Transmission Provider shall provide, within thirty (30) Calendar Days (or such other time as the Parties may agree), an estimate of any additional modifications to the Transmission or Distribution System as applicable, Transmission Owner's Interconnection Facilities, Network Upgrades, Transmission Owner's System Protection Facilities, and/or Distribution Upgrades necessitated by such Interconnection Customer modification and a good faith estimate of the costs thereof which shall be the responsibility of Interconnection Customer.

5.19.2 Standards. Any additions, modifications, or replacements made to a Party's facilities shall be designed, constructed and operated in accordance with this GIA and Good Utility Practice.

5.19.3 Modification Costs. Interconnection Customer shall not be directly assigned the costs of any additions, modifications, or replacements that Transmission Owner makes to the Transmission Owner's Interconnection Facilities, Network Upgrades, Transmission Owner's System Protection Facilities, Distribution Upgrades, or the Transmission or Distribution System, as applicable, to facilitate the interconnection of a third party to the Transmission Owner's Interconnection Facilities or the Transmission or Distribution System, as applicable, or to provide transmission service to a third party under the Tariff. Interconnection Customer shall be responsible for the costs of any additions, modifications, or replacements to the Interconnection Customer's Interconnection Facilities that may be necessary to maintain or upgrade such Interconnection Customer's Interconnection Facilities consistent with Applicable Laws and Regulations, Applicable Reliability Standards or Good Utility Practice.

ARTICLE 6. TESTING AND INSPECTION

6.1 Pre-Commercial Operation Date Testing and Modifications. Prior to the Commercial Operation Date, Transmission Owner shall test the Transmission Owner's Interconnection Facilities, Network Upgrades, Transmission Owner's System Protection Facilities and Distribution Upgrades, and Interconnection Customer shall test each

electric production device at the Generating Facility, Interconnection Customer's System Protection Facilities, including control equipment to limit injection at the POI to the level of Interconnection Service set forth in Appendix A and the Interconnection Customer's Interconnection Facilities to ensure their safe and reliable operation. Similar testing may be required after initial operation. Transmission Owner and Interconnection Customer shall make any modifications to their respective facilities that are found to be necessary as a result of such testing. Interconnection Customer shall bear the cost of all such testing and modifications. Interconnection Customer shall generate test energy at the Generating Facility only if it has arranged for the delivery of such test energy.

6.2 Post-Commercial Operation Date Testing and Modifications. Each Party shall at its own expense perform routine inspection and testing of its facilities and equipment in accordance with Good Utility Practice as may be necessary to ensure the continued interconnection of the Generating Facility with the Transmission or Distribution System, as applicable, in a safe and reliable manner. Each Party shall have the right, upon advance written notice, to require reasonable additional testing of the Interconnection Facilities, at the requesting Party's expense, as may be in accordance with Good Utility Practice.

6.3 Right to Observe Testing. Each Party shall notify the other Parties in advance of its performance of tests of its Interconnection Facilities. The other Parties shall each have the right, at its own expense, to observe such testing.

6.4 Right to Inspect. Each Party shall have the right, but shall have no obligation to: (i) observe Transmission Owner's and Interconnection Customer's tests and/or inspection of any of their respective System Protection Facilities and other protective equipment, including power system stabilizers and control equipment; (ii) review the settings of the System Protection Facilities and other protective equipment; and (iii) review the maintenance records relative to the Interconnection Facilities, the System Protection Facilities and other protective equipment. A Party may exercise these rights from time to time as it deems necessary upon reasonable notice to the other Parties. The exercise or non-exercise by a Party of any such rights shall not be construed as an endorsement or confirmation of any element or condition of the Interconnection Facilities or the System Protection Facilities or other protective equipment or the operation thereof, or as a warranty as to the fitness, safety, desirability, or reliability of same. Any information that a Party obtains through the exercise of any of its rights under this Article 6.4 shall be deemed to be Confidential Information and treated pursuant to Article 22 of this GIA.

ARTICLE 7. METERING

7.1 General. Each Party shall comply with the Electric Reliability Organization requirements. Unless the Interconnection Customer is utilizing shared Interconnection Customer Interconnection Facilities, or unless otherwise agreed by the Parties, Transmission Owner, at its election, or otherwise Interconnection Customer, shall install Metering Equipment (the "Metering Party") at the Point of Interconnection prior to any operation of the Generating Facility. Transmission Owner, at its election, or otherwise

Interconnection Customer shall own, operate, test and maintain such Metering Equipment. Power flows to and from the Generating Facility shall be measured at or, at the Metering Party's option, compensated to, the Point of Interconnection. If Interconnection Customer will share Interconnection Facilities with any other projects, Interconnection Customer shall install Metering Equipment either on its own Generating Facility or its own non-shared facilities sufficient to measure the output of such Interconnection Customer's Generating Facility separately from any other Generating Facilities with which it will share Interconnection Facilities. The Metering Party shall provide metering quantities, in analog and/or digital form, to the other Parties upon request. Interconnection Customer shall bear all reasonable documented costs associated with the purchase, installation, operation, testing and maintenance of the Metering Equipment.

7.2 Check Meters. Interconnection Customer, at its option and expense, may install and operate, on its premises and on its side of the Point of Interconnection, one or more check meters to check the Metering Equipment owned by the Metering Party. Such check meters shall be for check purposes only and shall not be used for the measurement of power flows for purposes of this GIA, except as provided in Article 7.4 below. The check meters shall be subject at all reasonable times to inspection and examination by Transmission Provider, Transmission Owner or their designees. The installation, operation and maintenance thereof shall be performed entirely by Interconnection Customer in accordance with Good Utility Practice.

7.3 Standards. The Metering Party shall install, calibrate, and test revenue quality Metering Equipment in accordance with applicable ANSI standards.

7.4 Testing of Metering Equipment. The Metering Party shall inspect and test Metering Equipment upon installation and at least once every two (2) years thereafter. If requested to do so by a Party, the Metering Party shall, at the requesting Party's expense, inspect or test Metering Equipment more frequently than every two (2) years. The Metering Party shall give reasonable notice to the other Parties of the time when any inspection or test shall take place, and the other Parties may have representatives present at the test or inspection. If at any time Metering Equipment is found to be inaccurate or defective, it shall be adjusted, repaired or replaced at Interconnection Customer's expense, in order to provide accurate metering, unless the inaccuracy or defect is due to the Metering Party's failure to maintain, then the Metering Party shall pay. If Metering Equipment fails to register, or if the measurement made by Metering Equipment during a test varies by more than two percent (2%) from the measurement made by the standard meter used in the test, the Metering Party shall adjust the measurements by correcting all measurements for the period during which Metering Equipment was in error by using Interconnection Customer's check meters, if installed. If no such check meters are installed or if the period cannot be reasonably ascertained, the adjustment shall be for the period immediately preceding the test of the Metering Equipment equal to one-half the time from the date of the previous test of the Metering Equipment.

7.5 Metering Data. At Interconnection Customer's expense, the metered data shall be

telemetered to one or more locations designated by Transmission Provider and Transmission Owner and one or more locations designated by Interconnection Customer. Such telemetered data shall be used, under normal operating conditions, as the official measurement of the amount of energy delivered from the Generating Facility to the Point of Interconnection.

ARTICLE 8. COMMUNICATIONS

8.1 Interconnection Customer Obligations. Interconnection Customer shall maintain satisfactory operating communications with Transmission Provider's Transmission System dispatcher or representative designated by Transmission Provider. Interconnection Customer shall provide standard voice line, dedicated voice line and facsimile communications at its Generating Facility control room or central dispatch facility through use of either the public telephone system, or a voice communications system that does not rely on the public telephone system. Interconnection Customer shall also provide the dedicated data circuit(s) necessary to provide Interconnection Customer data to Transmission Provider as set forth in Appendix D, Security Arrangements Details. The data circuit(s) shall extend from the Generating Facility to the location(s) specified by Transmission Provider. Any required maintenance of such communications equipment shall be performed by and at the cost of Interconnection Customer. Operational communications shall be activated and maintained under, but not be limited to, the following events: system paralleling or separation, scheduled and unscheduled shutdowns, equipment clearances, and hourly and daily load data.

Unless the Generating Facility is an Intermittent Resource not relying on wind or solar as a fuel source, Interconnection Customer shall install communication and control equipment such that the Generating Facility can receive and respond to the appropriate dispatch signals while operating under the Tariff. Where applicable, the requirements of the communication and control equipment will be enumerated in Appendix C to this GIA.

8.2 Remote Terminal Unit (RTU). Prior to the Initial Synchronization Date of the Generating Facility, a remote terminal unit, or equivalent data collection and transfer equipment acceptable to both Parties, shall be installed by Interconnection Customer, or by Transmission Owner at Interconnection Customer's expense, to gather accumulated and instantaneous data to be telemetered to the location(s) designated by Transmission Owner and Transmission Provider through use of a dedicated point-to-point data circuit(s) as indicated in Article 8.1. The communication protocol for the data circuit(s) shall be specified by Transmission Owner and Transmission Provider. Instantaneous bi-directional analog real power and reactive power flow information must be telemetered directly to the location(s) specified by Transmission Provider and Transmission Owner.

Each Party will promptly advise the other Parties if it detects or otherwise learns of any metering, telemetry or communications equipment errors or malfunctions that require the attention and/or correction. The Party owning such equipment shall correct such error or malfunction as soon as reasonably feasible.

8.3 No Annexation. Any and all equipment placed on the premises of a Party shall be and remain the property of the Party providing such equipment regardless of the mode and manner of annexation or attachment to real property, unless otherwise mutually agreed by the Parties.

8.4 Provision of Data from a Variable Energy Resource. Interconnection Customer whose Generating Facility contains at least one Variable Energy Resource shall provide meteorological and forced outage data to the Transmission Provider to the extent necessary for the Transmission Provider's development and deployment of power production forecasts for that class of Variable Energy Resources. Interconnection Customer with a Variable Energy Resource having wind as the energy source will, upon request by the Transmission Provider, be required to provide Transmission Provider with site-specific meteorological data including: temperature, wind speed, wind direction, and atmospheric pressure. Interconnection Customer with a Variable Energy Resource having solar as the energy source will, upon request by the Transmission Provider, be required to provide the Transmission Provider with site-specific meteorological data including: temperature, atmospheric pressure, and irradiance. Transmission Provider and Interconnection Customer whose Generating Facility contains a Variable Energy Resource shall mutually agree to any additional meteorological data that are required for the development and deployment of a power production forecast. Interconnection Customer whose Generating Facility contains a Variable Energy Resource also shall submit data to Transmission Provider regarding all forced outages to the extent necessary for Transmission Provider's development and deployment of power production forecasts for that class of Variable Energy Resources. The exact specifications of the meteorological and forced outage data to be provided by Interconnection Customer to Transmission Provider, including the frequency and timing of data submittals, shall be made taking into account the size and configuration of the Variable Energy Resource, its characteristics, location, and its importance in maintaining generation resource adequacy and transmission system reliability in its area. All requirements for meteorological and forced outage data must be commensurate with the power production forecasting employed by Transmission Provider. Data requirements for meteorological and forced outage data will be negotiated by Transmission Provider and Interconnection Customer, and will be set forth in Appendix C, Interconnection Details, of this GIA.

ARTICLE 9. OPERATIONS

9.1 General. Each Party shall comply with the Electric Reliability Organization requirements. Each Party shall provide to any Party all information that may reasonably be required by that Party to comply with Applicable Laws and Regulations and Applicable Reliability Standards.

9.2 Local Balancing Authority Notification. At least three (3) months before Initial Synchronization Date, Interconnection Customer shall notify Transmission Provider and Transmission Owner in writing of the Local Balancing Authority in which the Generating Facility will be located. If Interconnection Customer elects to locate the Generating Facility through dynamic metering/scheduling in a Local Balancing Authority other than

the Local Balancing Authority in which the Generating Facility is physically located, and if permitted to do so by the relevant transmission tariffs, all necessary arrangements, including but not limited to those set forth in Article 7 and Article 8 of this GIA, and remote Local Balancing Authority generator interchange agreements, if applicable, and the appropriate measures under such agreements, shall be executed and implemented prior to the placement of the Generating Facility in the other Local Balancing Authority.

9.3 Transmission Provider and Transmission Owner Obligations. Transmission Provider shall cause the Transmission System and the Transmission Owner's Interconnection Facilities to be operated, maintained and controlled in a safe and reliable manner in accordance with this GIA. Transmission Provider, or its designee, may provide operating instructions to Interconnection Customer consistent with this GIA and the Tariff and, if applicable, Transmission Owner's operating protocols and procedures as they may change from time to time. Transmission Provider will consider changes to its operating protocols and procedures proposed by Interconnection Customer.

9.4 Interconnection Customer Obligations. Interconnection Customer shall at its own expense operate, maintain and control the Generating Facility and the Interconnection Customer's Interconnection Facilities in a safe and reliable manner and in accordance with this GIA. The Generating Facility must be operated in accordance with the operating limits, if any, in the Interconnection Facilities Study and specified in Appendix C of this GIA. Interconnection Customer shall operate the Generating Facility and the Interconnection Customer's Interconnection Facilities in accordance with all applicable requirements of Transmission Provider or its designated Local Balancing Authority Operator of which the Generating Facility is part, as such requirements are set forth in Appendix C, Interconnection Details, of this GIA. Appendix C, Interconnection Details, will be modified to reflect changes to the requirements as they may change from time to time. Any Party may request that a Party provide copies of the requirements set forth in Appendix C, Interconnection Details, of this GIA.

9.5 Start-Up and Synchronization. Consistent with the Parties' mutually acceptable procedures, Interconnection Customer is responsible for the proper synchronization of the Generating Facility to the Transmission or Distribution System, as applicable.

9.6 Reactive Power and Primary Frequency Response.

9.6.1 Power Factor Design Criteria.

9.6.1.1 Synchronous Generation. Interconnection Customer shall design the Generating Facility to be capable of maintaining a composite power delivery at continuous rated power output at the Point of Interconnection at all power factors over 0.95 leading to 0.95 lagging, unless the Transmission Provider has established different requirements that apply to all synchronous generators in the Local Balancing Authority on a comparable basis. The applicable Local Balancing Authority power factor requirements are listed on the Transmission Provider's website at

https://cdn.misoenergy.org/Reactive_Generator_Requirements108137.pdf

and may be referenced in the Appendices to this GIA. The Generating Facility shall be capable of continuous dynamic operation throughout the power factor design range as measured at the Point of Interconnection. Such operation shall account for the net effect of all energy production devices on the Interconnection Customer's side of the Point of Interconnection.

9.6.1.2 Inverter-Based Resource Plants. Interconnection Customer shall design the Generating Facility to be capable of maintaining a composite power delivery at continuous rated power output at the high-side of the generator substation at all power factors over 0.95 leading to 0.95 lagging, unless the Transmission Provider has established different requirements that apply to all inverter-based resource plants in the Local Balancing Authority on a comparable basis. The applicable Local Balancing Authority power factor requirements are listed on the Transmission Provider's website at

https://cdn.misoenergy.org/Reactive_Generator_Requirements108137.pdf

and may be referenced in the Appendices to this GIA. This power factor range standard shall be dynamic and can be met using, for example, power electronics designed to supply this level of reactive capability (taking into account any limitations due to voltage level, real power output, etc.) or fixed and switched capacitors, or a combination of the two. This requirement shall only apply to newly interconnecting inverter-based resource plants that have not yet completed a System Impact Study as of the effective date of the Final Rule establishing this requirement (Order No. 827). These requirements apply to existing inverter-based resource plants making upgrades that require a new Generator Interconnection Agreement only where the Transmission Provider's System Impact Study shows the need for reactive power as a result of an upgrade. If applicable, these requirements will be memorialized in Appendix C to this GIA.

Additional reactive power requirements for inverter-based resource plants are provided in Appendix G of this GIA.

9.6.2 Voltage Schedules. Once Interconnection Customer has synchronized the Generating Facility with the Transmission System, Transmission Provider shall require Interconnection Customer to operate the Generating Facility to produce or absorb reactive power within the design limitations of the Generating Facility set forth in Article 9.6.1 (Power Factor Design Criteria), to maintain the output voltage or power factor at the Point of Interconnection as specified by Transmission Provider. Transmission Provider's voltage schedules shall treat all sources of reactive power in the Local Balancing Authority in an equitable and not unduly discriminatory manner. Transmission Provider shall exercise

Reasonable Efforts to provide Interconnection Customer with such schedules at least one (1) Calendar Day in advance, and may make changes to such schedules as necessary to maintain the reliability of the Transmission or Distribution System as applicable. Interconnection Customer shall operate the Generating Facility to maintain the specified output voltage or power factor at the Point of Interconnection within the design limitations of the Generating Facility set forth in Article 9.6.1 (Power Factor Design Criteria). If Interconnection Customer is unable to maintain the specified voltage or power factor, it shall promptly notify Transmission Provider's system operator, or its designated representative.

9.6.2.1 Voltage Regulators. Whenever the Generating Facility is operated in parallel with the Transmission or Distribution System as applicable and voltage regulators are capable of operation, Interconnection Customer shall operate the Generating Facility with its speed governors and voltage regulators in automatic operation. If the Generating Facility's voltage regulators are not capable of such automatic operation, Interconnection Customer shall immediately notify Transmission Provider's system operator, or its designated representative, and ensure that such Generating Facility's reactive power production or absorption (measured in MVARs) are within the design capability of the Generating Facility's generating unit(s) and steady state stability limits. Interconnection Customer shall not cause its Generating Facility to disconnect automatically or instantaneously from the Transmission or Distribution System, as applicable, or trip any generating unit comprising the Generating Facility for an under or over frequency condition unless the abnormal frequency condition persists for a time period beyond the limits set forth in ANSI/IEEE Standard C37.106, or such other standard as applied to other generators in the Local Balancing Authority on a comparable basis.

9.6.3 Payment for Reactive Power. Payments for reactive power shall be pursuant to any tariff or rate schedule filed by Transmission Provider and approved by the FERC.

9.6.4 Primary Frequency Response. This Section 9.6.4 shall only apply in the event that the Interconnection Request for the Generating Facility completed Definitive Planning Phase Interconnection Customer Decision Point 2 after May 15, 2018.

Interconnection Customer shall ensure the primary frequency response capability of its Generating Facility by installing, maintaining, and operating a functioning governor or equivalent controls. The term "functioning governor or equivalent controls" as used herein shall mean the required hardware and/or software that provides frequency responsive real power control with the ability to sense changes in system frequency and autonomously adjust the Generating Facility's real power output in accordance with the droop and deadband parameters and in the direction needed to correct frequency deviations. Interconnection Customer is

required to install a governor or equivalent controls with the capability of operating: (1) with a maximum 5 percent droop and ±0.036 Hz deadband; or (2) in accordance with the relevant droop, deadband, and timely and sustained response settings from an approved Reliability Organization reliability standard providing for equivalent or more stringent parameters. The droop characteristic shall be: (1) based on the nameplate capacity of the Generating Facility, and shall be linear in the range of frequencies between 59 to 61 Hz that are outside of the deadband parameter; or (2) based on an approved Electric Reliability Organization reliability standard providing for an equivalent or more stringent parameter. The deadband parameter shall be: the range of frequencies above and below nominal (60 Hz) in which the governor or equivalent controls is not expected to adjust the Generating Facility's real power output in response to frequency deviations. The deadband shall be implemented: (1) without a step to the droop curve, that is, once the frequency deviation exceeds the deadband parameter, the expected change in the Generating Facility's real power output in response to frequency deviations shall start from zero and then increase (for under-frequency deviations) or decrease (for over-frequency deviations) linearly in proportion to the magnitude of the frequency deviation; or (2) in accordance with an approved Electric Reliability Organization Reliability Standard providing for an equivalent or more stringent parameter. Interconnection Customer shall notify Transmission Provider that the primary frequency response capability of the Generating Facility has been tested and confirmed during commissioning. Once Interconnection Customer has synchronized the Generating Facility with the Transmission System, Interconnection Customer shall operate the Generating Facility consistent with the provisions specified in Articles 9.6.4.1 and 9.6.4.2 of this GIA. The primary frequency response requirements contained herein shall apply to both synchronous and inverter-based resource plant Generating Facilities.

9.6.4.1 Governor or Equivalent Controls. Whenever the Generating Facility is operated in parallel with the Transmission System, Interconnection Customer shall operate the Generating Facility with its governor or equivalent controls in service and responsive to frequency. Interconnection Customer shall: (1) in coordination with Transmission Provider and/or the relevant balancing authority, set the deadband parameter to: (a) a maximum of ±0.036 Hz and set the droop parameter to a maximum of 5 percent; or (b) implement the relevant droop and deadband settings from an approved Regional Reliability Organization reliability standard that provides for equivalent or more stringent parameters. Interconnection Customer shall be required to provide the status and settings of the governor or equivalent controls to Transmission Provider and/or the relevant balancing authority upon request. If Interconnection Customer needs to operate the Generating Facility with its governor or equivalent controls not in service, Interconnection Customer shall immediately notify Transmission Provider and the relevant balancing authority, and provide both with the following information: (1) the operating status of the governor or

equivalent controls (i.e., whether it is currently out of service or when it will be taken out of service); (2) the reasons for removing the governor or equivalent controls from service; and (3) a reasonable estimate of when the governor or equivalent controls will be returned to service. Interconnection Customer shall make Reasonable Efforts to return its governor or equivalent controls into service as soon as practicable. Interconnection Customer shall make Reasonable Efforts to keep outages of the Generating Facility's governor or equivalent controls to a minimum whenever the Generating Facility is operated in parallel with the Transmission System.

9.6.4.2 Timely and Sustained Response. Interconnection Customer shall ensure that the Generating Facility's real power response to sustained frequency deviations outside of the deadband setting is automatically provided and shall begin immediately after frequency deviates outside of the deadband, and to the extent the Generating Facility has operating capability in the direction needed to correct the frequency deviation. Interconnection Customer shall not block or otherwise inhibit the ability of the governor or equivalent controls to respond and shall ensure that the response is not inhibited, except under certain operational constraints including, but not limited to, ambient temperature limitations, physical energy limitations, outages of mechanical equipment, or regulatory requirements. The Generating Facility shall sustain the real power response at least until system frequency returns to a value within the deadband setting of the governor or equivalent controls. A Commission-approved reliability standard with equivalent or more stringent requirements shall supersede the above requirements.

9.6.4.3 Exemptions. Generating Facilities that are regulated by the United States Nuclear Regulatory Commission shall be exempt from Articles 9.6.4, 9.6.4.1, and 9.6.4.2 of this GIA. Generating Facilities that are behind the meter generation that is sized-to-load (i.e., the thermal load and the generation are near-balanced in real-time operation and the generation is primarily controlled to maintain the unique thermal, chemical, or mechanical output necessary for the operating requirements of its host facility) shall be required to install primary frequency response capability in accordance with the droop and deadband capability requirements specified in Article 9.6.4, but shall be otherwise exempt from the operating requirements in Articles 9.6.4, 9.6.4.1, 9.6.4.2, and 9.6.4.4 of this GIA.

9.6.4.4 Electric Storage Resources. Interconnection Customer interconnecting an electric storage resource shall establish an operating range in Appendix C that specifies a minimum state of charge and a maximum state of charge between which the electric storage resource will be required to provide primary frequency response consistent with the

conditions set forth in Articles 9.6.4, 9.6.4.1, 9.6.4.2 and 9.6.4.3 of this GIA. Appendix C shall specify whether the operating range is static or dynamic, and shall consider (1) the expected magnitude of frequency deviations in the interconnection; (2) the expected duration that system frequency will remain outside of the deadband parameter in the interconnection; (3) the expected incidence of frequency deviations outside of the deadband parameter in the interconnection; (4) the physical capabilities of the electric storage resource; (5) operational limitations of the electric storage resource due to manufacturer specifications; and (6) any other relevant factors agreed to by Transmission Provider and Interconnection Customer, and in consultation with the relevant transmission owner or balancing authority as appropriate. If the operating range is dynamic, then Appendix C must establish how frequently the operating range will be reevaluated and the factors that may be considered during its reevaluation.

Interconnection Customer's electric storage resource is required to provide timely and sustained primary frequency response consistent with Article 9.6.4.2 of this GIA when it is online and dispatched to inject electricity to the Transmission System and/or receive electricity from the Transmission System. This excludes circumstances when the electric storage resource is not dispatched to inject electricity to the Transmission System and/or dispatched to receive electricity from the Transmission System.

9.6.4.5 Inverter-Based Resource Plants. Additional primary frequency response requirements for inverter-based resource plants, including electric storage resources, are provided in Appendix G of this GIA.

9.7 Outages and Interruptions.

9.7.1 Outages.

9.7.1.1 Outage Authority and Coordination. Interconnection Customer and Transmission Owner may each in accordance with Good Utility Practice in coordination with the other Party and Transmission Provider remove from service any of its respective Interconnection Facilities, System Protection Facilities, Network Upgrades, System Protection Facilities or Distribution Upgrades that may impact the other Party's facilities as necessary to perform maintenance or testing or to install or replace equipment. Absent an Emergency Condition, the Party scheduling a removal of such facility(ies) from service will use Reasonable Efforts to notify one another and schedule such removal on a date and time mutually acceptable to the Parties. In all circumstances, any Party planning to remove such facility(ies) from service shall use Reasonable Efforts to minimize the effect on the other Parties of such removal.

9.7.1.2 Outage Schedules. Transmission Provider shall post scheduled outages of transmission facilities on the OASIS. Interconnection Customer shall submit its planned maintenance schedules for the Generating Facility to Transmission Provider and Transmission Owner for a minimum of a rolling twenty-four (24) month period in accordance with the Transmission Provider's procedures. Interconnection Customer shall update its planned maintenance schedules as necessary. Transmission Provider may request Interconnection Customer to reschedule its maintenance as necessary to maintain the reliability of the Transmission System; provided, however, adequacy of generation supply shall not be a criterion in determining Transmission System reliability.

Transmission Provider shall compensate, pursuant to applicable Transmission Provider tariff or rate schedule, Interconnection Customer for any additional direct costs that Interconnection Customer incurs as a result of having to reschedule maintenance, including any additional overtime, breaking of maintenance contracts or other costs above and beyond the cost Interconnection Customer would have incurred absent the Transmission Provider's request to reschedule maintenance. Interconnection Customer will not be eligible to receive compensation, if during the twelve (12) months prior to the date of the scheduled maintenance, Interconnection Customer had modified its schedule of maintenance activities.

Costs shall be determined by negotiation between Transmission Provider and Interconnection Customer prior to implementation of the voluntary change in outage schedules, or if such request is made by or on behalf of a Transmission Customer requesting firm service, costs and recovery of costs shall be determined through a bilateral agreement between the Transmission Customer and Interconnection Customer. Voluntary changes to outage schedules under this Article 9.7.1.2 are separate from actions and compensation required under Article 13 and for which costs are recovered in accordance with Transmission Provider's applicable tariff or rate schedule.

9.7.1.3 Outage Restoration. If an outage on either the Interconnection Customer's or Transmission Owner's Interconnection Facilities, Network Upgrades, System Protection Facilities or Distribution Upgrades adversely affects a Party's operations or facilities, the Party that owns or controls the facility that is out of service shall use Reasonable Efforts to promptly restore such facility(ies) to a normal operating condition consistent with the nature of the outage. The Party that owns or controls the facility that is out of service shall provide the other Parties, to the extent such information is known, information on the nature of the Emergency Condition, an estimated time of restoration,

and any corrective actions required. Initial verbal notice shall be followed up as soon as practicable with written notice to the other Parties explaining the nature of the outage.

9.7.2 Interruption of Service. If required by Good Utility Practice to do so, Transmission Provider may require Interconnection Customer to interrupt or reduce deliveries of electricity if such delivery of electricity could adversely affect Transmission Provider's ability to perform such activities as are necessary to safely and reliably operate and maintain the Transmission System. The following provisions shall apply to any interruption or reduction permitted under this Article 9.7.2:

9.7.2.1 The interruption or reduction shall continue only for so long as reasonably necessary under Good Utility Practice;

9.7.2.2 Any such interruption or reduction shall be made on an equitable, non-discriminatory basis with respect to all generating facilities directly connected to the Transmission or Distribution System, as applicable;

9.7.2.3 When the interruption or reduction must be made under circumstances which do not allow for advance notice, Transmission Provider shall notify Interconnection Customer by telephone as soon as practicable of the reasons for the curtailment, interruption, or reduction, and, if known, its expected duration. Telephone notification shall be followed by written notification as soon as practicable;

9.7.2.4 Except during the existence of an Emergency Condition, when the interruption or reduction can be scheduled without advance notice, Transmission Provider shall notify Interconnection Customer in advance regarding the timing of such scheduling and further notify Interconnection Customer of the expected duration. Transmission Provider shall coordinate with Interconnection Customer using Good Utility Practice to schedule the interruption or reduction during periods of least impact to Interconnection Customer, Transmission Owner and Transmission Provider;

9.7.2.5 The Parties shall cooperate and coordinate with each other to the extent necessary in order to restore the Generating Facility, Interconnection Facilities, and the Transmission or Distribution System, as applicable to their normal operating state, consistent with system conditions and Good Utility Practice.

9.7.3 Ride Through Capability and Performance. The Transmission System is designed to automatically activate a load-shed program as required by the Electric Reliability Organization in the event of an underfrequency system disturbance. Interconnection Customer shall implement under-frequency and over-frequency

relay set points for the Generating Facility as required by the Electric Reliability Organization to ensure frequency "ride through" capability of the Transmission System. Generating Facility response to frequency deviations of pre-determined magnitudes, both under-frequency and over-frequency deviations, shall be studied and coordinated with Transmission Provider in accordance with Good Utility Practice. Interconnection Customer shall also implement under-voltage and over-voltage relay set points, or equivalent electronic controls, as required by the Electric Reliability Organization to ensure voltage "ride through" capability of the Transmission System. The term "ride through" as used herein shall mean the ability of a Generating Facility to stay connected to and synchronized with the Transmission System during system disturbances within a range of under-frequency, over-frequency, under-voltage, and over-voltage conditions, in accordance with Good Utility Practice and consistent with any standards and guidelines that are applied to other Generating Facilities in the Balancing Authority Area on a comparable basis. For abnormal frequency conditions and voltage conditions within the "no trip zone" defined by Reliability Standard PRC-024-3 or successor mandatory ride through reliability standards, the non-synchronous Generating Facility must ensure that, within any physical limitations of the Generating Facility, its control and protection settings are configured or set to (1) continue active power production during disturbance and post disturbance periods at pre-disturbance levels, unless providing primary frequency response or fast frequency response; (2) minimize reductions in active power and remain within dynamic voltage and current limits, if reactive power priority mode is enabled, unless providing primary frequency response or fast frequency response; (3) not artificially limit dynamic reactive power capability during disturbances; and (4) return to pre-disturbance active power levels without artificial ramp rate limits if active power is reduced, unless providing primary frequency response or fast frequency response.

9.7.4 System Protection and Other Control Requirements.

9.7.4.1 System Protection Facilities. Interconnection Customer shall, at its expense, install, operate and maintain its System Protection Facilities as a part of the Generating Facility or the Interconnection Customer's Interconnection Facilities. Transmission Owner shall install at Interconnection Customer's expense any Transmission Owner's System Protection Facilities that may be required on the Transmission Owner's Interconnection Facilities or the Transmission Owner's transmission or distribution facilities as a result of the interconnection of the Generating Facility and the Interconnection Customer's Interconnection Facilities.

9.7.4.2 Interconnection Customer's and Transmission Owner's System Protection Facilities shall be designed and coordinated with Affected Systems in accordance with Good Utility Practice.

9.7.4.3 Each Party shall be responsible for protection of its facilities consistent

with Good Utility Practice.

9.7.4.4 Each Party's protective relay design shall incorporate the necessary test switches to perform the tests required in Article 6. The required test switches will be placed such that they allow operation of lockout relays while preventing breaker failure schemes from operating and causing unnecessary breaker operations and/or the tripping of the Generating Facility.

9.7.4.5 Each Party will test, operate and maintain their respective System Protection Facilities in accordance with Good Utility Practice.

9.7.4.6 Prior to the In-Service Date, and again prior to the Commercial Operation Date, Interconnection Customer or Transmission Owner, or their respective agents, shall perform a complete calibration test and functional trip test of the System Protection Facilities. At intervals suggested by Good Utility Practice and following any apparent malfunction of the System Protection Facilities, Interconnection Customer or Transmission Owner shall each perform both calibration and functional trip tests of their respective System Protection Facilities. These tests do not require the tripping of any in-service generating unit. These tests do, however, require that all protective relays and lockout contacts be activated.

9.7.5 Requirements for Protection. In compliance with Good Utility Practice, Interconnection Customer shall provide, install, own, and maintain relays, circuit breakers and all other devices necessary to remove any fault contribution of the Generating Facility to any short circuit occurring on the Transmission or Distribution System, as applicable, not otherwise isolated by Transmission Owner's equipment, such that the removal of the fault contribution shall be coordinated with the protective requirements of the Transmission or Distribution System, as applicable. Such protective equipment shall include, without limitation, a disconnecting device or switch with load-interrupting capability located between the Generating Facility and the Transmission or Distribution System, as applicable, at a site selected upon mutual agreement (not to be unreasonably withheld, conditioned or delayed) of the Parties. Interconnection Customer shall be responsible for protection of the Generating Facility and Interconnection Customer's other equipment from such conditions as negative sequence currents, over- or under-frequency, sudden load rejection, over- or under-voltage, and generator loss-of-field. Interconnection Customer shall be solely responsible to disconnect the Generating Facility and Interconnection Customer's other equipment if conditions on the Transmission or Distribution System, as applicable, could adversely affect the Generating Facility.

9.7.6 Power Quality. Neither Party's facilities shall cause excessive voltage flicker nor introduce excessive distortion to the sinusoidal voltage or current waves as

defined by ANSI Standard C84.1, in accordance with IEEE Standard 519, or any applicable superseding electric industry standard. In the event of a conflict between ANSI Standard C84.1, and any applicable superseding electric industry standard, the applicable superseding electric industry standard shall control.

9.8 Switching and Tagging Rules. Prior to the Initial Synchronization Date, each Party shall provide the other Parties a copy of its switching and tagging rules that are applicable to the other Parties' activities. Such switching and tagging rules shall be developed on a non-discriminatory basis. The Parties shall comply with applicable switching and tagging rules, as amended from time to time, in obtaining clearances for work or for switching operations on equipment.

9.9 Use of Interconnection Facilities by Other Parties.

9.9.1 Purpose of Interconnection Facilities. Except as may be required by Applicable Laws and Regulations, or as otherwise agreed to among the Parties, the Interconnection Facilities shall be constructed for the sole purpose of interconnecting the Generating Facility to the Transmission or Distribution System, as applicable, and shall be used for no other purpose.

9.9.2 Other Users. If required by Applicable Laws and Regulations or if the Parties mutually agree, such agreement not to be unreasonably withheld or delayed, to allow one or more Parties to use the Transmission Owner's Interconnection Facilities, or any part thereof, Interconnection Customer will be entitled to compensation for the capital expenses it incurred in connection with the Interconnection Facilities based upon the pro rata use of the Interconnection Facilities by Transmission Owner, all non-Party users, and Interconnection Customer, in accordance with Applicable Laws and Regulations or upon some other mutually-agreed upon methodology. In addition, cost responsibility for ongoing costs, including operation and maintenance costs associated with the Interconnection Facilities, will be allocated between Interconnection Customer and any non-Party users based upon the pro rata use of the Interconnection Facilities by Transmission Owner, all non-Party users, and Interconnection Customer, in accordance with Applicable Laws and Regulations or upon some other mutually agreed upon methodology. If the issue of such compensation or allocation cannot be resolved through such negotiations, it shall be submitted to Dispute Resolution pursuant to Section 12 of the Tariff.

9.10 Disturbance Analysis Data Exchange. The Parties will cooperate with one another in the analysis of disturbances to either the Generating Facility or the Transmission System by gathering and providing access to any information relating to any disturbance, including information from oscillography, protective relay targets, breaker operations and sequence of events records, and any disturbance information required by Good Utility Practice.

ARTICLE 10. MAINTENANCE

10.1 Transmission Owner Obligations. Transmission Owner shall maintain the Transmission Owner's Interconnection Facilities in a safe and reliable manner and in accordance with this GIA and all Applicable Laws and Regulations.

10.2 Interconnection Customer Obligations. Interconnection Customer shall maintain the Generating Facility and the Interconnection Customer's Interconnection Facilities in a safe and reliable manner and in accordance with this GIA and all Applicable Laws and Regulations.

10.3 Coordination. The Parties shall confer regularly to coordinate the planning, scheduling and performance of preventive and corrective maintenance on the Generating Facility and the Interconnection Facilities.

10.4 Secondary Systems. Each Party shall cooperate with the other in the inspection, maintenance, and testing of control or power circuits that operate below 600 volts, AC or DC, including, but not limited to, any hardware, control or protective devices, cables, conductors, electric raceways, secondary equipment panels, transducers, batteries, chargers, and voltage and current transformers that directly affect the operation of a Party's facilities and equipment which may reasonably be expected to impact another Party. Each Party shall provide advance notice to the other Parties before undertaking any work on such circuits, especially on electrical circuits involving circuit breaker trip and close contacts, current transformers, or potential transformers.

10.5 Operating and Maintenance Expenses. Subject to the provisions herein addressing the use of facilities by others, and except for operations and maintenance expenses associated with modifications made for providing Interconnection Service or Transmission Service to a non-Party and such non-Party pays for such expenses, Interconnection Customer shall be responsible for all reasonable expenses including overheads, associated with: (1) owning, operating, maintaining, repairing, and replacing Interconnection Customer's Interconnection Facilities; and (2) operation, maintenance, repair and replacement of Transmission Owner's Interconnection Facilities to the extent required by Transmission Owner on a comparable basis.

ARTICLE 11. PERFORMANCE OBLIGATION

11.1 Interconnection Customer's Interconnection Facilities. Interconnection Customer shall design, procure, construct, install, own and/or control the Interconnection Customer's Interconnection Facilities described in Appendix A at its sole expense.

11.2 Transmission Owner's Interconnection Facilities. Transmission Owner shall design, procure, construct, install, own and/or control the Transmission Owner's Interconnection Facilities described in Appendix A at the sole expense of Interconnection Customer.

11.3 Network Upgrades, System Protection Facilities and Distribution Upgrades.

Transmission Owner shall design, procure, construct, install, and own the Network Upgrades, Transmission Owner's System Protection Facilities and Distribution Upgrades described in Appendix A. Interconnection Customer shall be responsible for all costs related to Distribution Upgrades and/or Generator Upgrades. As required by Section 7.3.2.1 and 7.3.3.1 of Attachment X, Transmission Owner shall have provided Transmission Provider with written notice if Transmission Owner elects to fund the capital for the Network Upgrades and Transmission Owner's System Protection Facilities; otherwise, such facilities, if any, shall be solely funded by Interconnection Customer. In the event that the Transmission Owner elects to fund the capital costs of the Network Upgrades and/or Transmission Owner's System Protection Facilities, then the Parties shall enter into a Facilities Service Agreement. The Facilities Service Agreement shall take the form of the *pro forma* Facilities Service Agreement that is included as Appendix 14 of Attachment X to the MISO Tariff .

11.3.1 Contingencies Affecting Network Upgrades, System Protection Facilities and Distribution Upgrades. Network Upgrades, System Protection Facilities and Distribution Upgrades that are required to accommodate the Generating Facility may be modified because (1) a higher queued Interconnection Request withdrew or was deemed to have withdrawn, (2) the interconnection agreement associated with a higher queued Interconnection Request was terminated prior to the project's In-Service Date, (3) the Commercial Operation Date for a higher queued Interconnection Request is delayed, or the project itself is delayed (including due to suspension) such that facilities required to accommodate lower queued projects or the project itself may be altered, (4) the queue position is reinstated for a higher-queued Interconnection Request whose queue position was subject to dispute resolution, (5) changes occur in Transmission Provider or Transmission Owner equipment design standards or reliability criteria giving rise to the need for restudy, (6) the facilities required to accommodate a higher queued Interconnection Request were modified constituting a Material Modification pursuant to Section 4.4 of the GIP, (7) a GIA with an effective date prior to this GIA is terminated, (8) when ordered to restudy by FERC, or (9) the Network Upgrade Facilities Study for a Network Upgrade, which is to be included in this GIA, is completed after execution of this GIA. The higher queued Interconnection Requests that could impact the Network Upgrades, System Protection Facilities and Distribution Upgrades required to accommodate the Generating Facility, and possible Modifications that may result from the above listed events affecting the higher queued Interconnection Requests, to the extent such modifications are reasonably known and can be determined, and estimates of the costs associated with such required Network Upgrades, System Protection Facilities and Distribution Upgrades, are provided in Appendix A.

11.3.2 Agreement to Restudy and Cost Reallocation. In the event that one of the contingencies listed in Article 11.3.1 occurs, at any time before the Network Upgrades, Common Use Upgrades, Shared Network Upgrades, System Protection Facilities and/or Distribution Upgrades associated with higher queued Interconnection Requests with GIA in effect prior to this GIA are completed,

Transmission Provider may determine, in its discretion, that a restudy is required. If a restudy is required, Transmission Provider will provide notice to Interconnection Customer and Interconnection Customer agrees to enter into an Interconnection Study Agreement for such restudy. Transmission Provider will reevaluate the need for any Common Use Upgrade(s) and/or Shared Network Upgrade(s), and if still required, reallocate the cost and responsibility for any Common Use Upgrade and/or Shared Network Upgrade, without a restudy when possible, or with a restudy if the Transmission Provider deems it necessary in order to ensure reliability of the Transmission System. The Parties agree to amend Appendix A to this GIA in accordance with Article 30.10 to reflect the results of any cost reallocation required under this Article 11.3.2.

11.3.3 Agreement to Fund Shared Network Upgrades. Interconnection Customer agrees to fund Shared Network Upgrades, as determined by Transmission Provider. Where applicable, payments to fund Shared Network Upgrade(s) that are made to Transmission Provider by Interconnection Customer will be disbursed by Transmission Provider to the appropriate entities that funded the Shared Network Upgrades in accordance with Attachment X and Attachment FF of the Tariff. In the event that Interconnection Customer fails to meet its obligation to fund Shared Network Upgrades, Transmission Owner and Transmission Provider shall not be responsible for the Interconnection Customer's funding obligation.

11.4 Transmission Credits.

11.4.1 Repayment of Amounts Advanced for Network Upgrades. Interconnection Customer shall be entitled to a cash repayment by Transmission Owner(s) and the Affected System Owner(s) that own the Network Upgrades, of the amount paid respectively to Transmission Owner and Affected System Operator, if any, for the Network Upgrades, as provided under Attachment FF of this Tariff and including any tax gross-up or other tax-related payments associated with the repayable portion of the Network Upgrades, and not repaid to Interconnection Customer pursuant to Article 5.17.8 or otherwise, to be paid to Interconnection Customer on a dollar-for-dollar basis for the non-usage sensitive portion of transmission charges, as payments are made under the Tariff and Affected System's Tariff for Transmission Services with respect to the Generating Facility. Any repayment shall include interest calculated in accordance with the methodology set forth in FERC's regulations at 18 C.F.R. § 35.19 (a)(2)(iii) from the date of any payment for Network Upgrades through the date on which Interconnection Customer receives a repayment of such payment pursuant to this subparagraph. Interest shall not accrue during periods in which Interconnection Customer has suspended construction pursuant to Article 11 or the Network Upgrades have been determined not to be needed pursuant to this Article 11.4.1. Interconnection Customer may assign such repayment rights to any person.

If the Generating Facility is designated a Network Resource under the Tariff, or

if there are otherwise no incremental payments for Transmission Service resulting from the use of the Generating Facility by Transmission Customer, and in the absence of another mutually agreeable payment schedule any repayments provided under Attachment FF shall be established equal to the applicable rate for Firm Point-To-Point Transmission Service for the pricing zone where the Network Load is located multiplied by the portion of the demonstrated output of the Generating Facility designated as a Network Resource by the Network Customer(s) or in the absence of such designation, equal to the monthly firm single system-wide rate defined under Schedule 7 of the Tariff multiplied by the portion of the demonstrated output of the Generating Facility under contract to Network Customer(s) and consistent with studies pursuant to Section 3.2.2.2 of the GIP.

Notwithstanding the foregoing, as applicable and consistent with the provisions of Attachment FF of this Tariff, Interconnection Customer, Transmission Provider, Transmission Owner, and Affected System Operator may adopt any alternative payment schedule that is mutually agreeable so long as Transmission Owner and Affected System Operator take one of the following actions no later than five (5) years from the Commercial Operation Date: (1) return to Interconnection Customer any amounts advanced for Network Upgrades not previously repaid, or (2) declare in writing that Transmission Owner or Affected System Operator will continue to provide payments to Interconnection Customer on a dollar-for-dollar basis for the non-usage sensitive portion of transmission charges, or develop an alternative schedule that is mutually agreeable and provides for the return of all amounts advanced for Network Upgrades not previously repaid; however, full reimbursement shall not extend beyond twenty (20) years from the Commercial Operation Date.

If the Generating Facility is installed in phases, the amount eligible for refund as each phase achieves Commercial Operation will be reduced by the proportional amount of generation capacity not yet installed. However, all facilities in Appendix A other than the Generating Facility shall be built without consideration for the phasing of the Generating Facility as though the entire Generating Facility will be placed in Commercial Operation for the full output or increased output of the Generating Facility constructed by Interconnection Customer under this GIA.

If the Generating Facility fails to achieve Commercial Operation, but it or another generating facility is later constructed and makes use of the Network Upgrades, Transmission Owner and Affected System Operator shall at that time reimburse Interconnection Customer for the remaining applicable amounts that may be refundable pursuant to Attachment FF of this Tariff that were advanced for the Network Upgrades on their respective systems as described above. Before any such reimbursement can occur, Interconnection Customer, or the entity that ultimately constructs the Generating Facility, if different, is responsible for identifying the entity to which the reimbursement must be made.

11.4.2 Special Provisions for Transmission Provider as an Affected System to be covered under Separate Agreements. When the Transmission Owner's Transmission or Distribution System (including for this Article 11.4.2 independent distribution systems connected to the Transmission System) is an Affected System for an interconnection in another electric system, Transmission Provider will coordinate the performance of Interconnection Studies with the other system. Transmission Provider will determine if any Network Upgrades or Distribution Upgrades, which may be required on the Transmission System as a result of the interconnection, would not have been needed but for the interconnection. Unless Transmission Owner provides, under the interconnection agreement between Interconnection Customer and the other system, for the repayment of amounts advanced to Transmission Provider or an impacted Transmission Owner for Network Upgrades, Interconnection Customer, Transmission Provider, and the impacted Transmission Owner(s) shall enter into an agreement that provides for such repayment by Transmission Owner(s) as directed by Transmission Provider. The agreement shall specify the terms governing payments to be made by Interconnection Customer to the Affected System Operator as well as the payment of refunds by the Affected System Operator.

11.4.3 Notwithstanding any other provision of this GIA, nothing herein shall be construed as relinquishing or foreclosing any rights, including but not limited to firm transmission rights, capacity rights, transmission congestion rights, or transmission credits, that Interconnection Customer, shall be entitled to, now or in the future under any other agreement or tariff as a result of, or otherwise associated with, the transmission capacity, if any, created by the Network Upgrades, including the right to obtain cash reimbursement or transmission credits for transmission service that is not associated with the Generating Facility.

11.5 Initial Payment. For upgrades that the Transmission Owner has elected to self-fund, the Interconnection Customer is responsible for making the initial payment for the total cost of Network Upgrades (excluding JTIQ Upgrades) or Transmission Owner's System Protection Facilities in the form of security pursuant to Article 11.6. For upgrades where the Transmission Owner did not elect to self-fund, the Interconnection Customer shall elect (and provide its election to the Transmission Provider within five days of the commencement of negotiation of the GIA pursuant to Section 11.2 of the GIP) to make either 1) an initial payment equal to twenty (20) percent of the total cost of Network Upgrades (excluding JTIQ Upgrades), Transmission Owner Interconnection Facilities, Transmission Owner's System Protection Facilities, Distribution Upgrades and/or Generator Upgrades (if the In-Service Date is less than or equal to five (5) years of the initial payment date); or 2) an initial payment equal to ten (10) percent of the total cost of Network Upgrades (excluding JTIQ Upgrades), Transmission Owner Interconnection Facilities, Transmission Owner's System Protection Facilities, Distribution Upgrades and/or Generator Upgrades (if the In-Service Date exceeds the initial payment date by

more than five (5) years); or 3) the total cost of Network Upgrades (excluding JTIQ Upgrades), Transmission Owner Interconnection Facilities, Transmission Owner's System Protection Facilities, Distribution Upgrades and/or Generator Upgrades in the form of security pursuant to Article 11.6. The initial payment shall be provided to Transmission Owner by Interconnection Customer pursuant to this Article 11.5 within the later of a) forty-five (45) Calendar Days of the execution of the GIA by all Parties, or b) forty-five (45) Calendar Days of acceptance by FERC if the GIA is filed unexecuted and the payment is being protested by Interconnection Customer, or c) forty-five (45) Calendar Days of the filing if the GIA is filed unexecuted and the initial payment is not being protested by Interconnection Customer. If the Interconnection Customer made its milestone payments in the form of cash and the Interconnection Customer elects a cash initial payment, then the Transmission Provider shall transfer those funds to the Transmission Owner on the Interconnection Customer's behalf.

11.6 Provision of Security. Unless a milestone cash payment schedule is provided in Appendix B, Interconnection Customer shall, at least forty-five (45) Calendar Days prior to the commencement of the design, procurement, installation, or construction of a discrete portion of a facility, not otherwise funded under Article 11.5, provide additional security. Additionally, the Interconnection Customer will be required to provide security more than forty-five (45) Calendar Days in advance if requested by Transmission Owner because regulatory approvals are required for the construction of such facilities. Interconnection Customer shall provide Transmission Owner, at Interconnection Customer's selection, a guarantee, a surety bond, letter of credit or other form of security that is reasonably acceptable to Transmission Owner and is consistent with the Uniform Commercial Code of the jurisdiction identified in Article 14.2.1. Such security for payment, as specified in Appendix B of this GIA, shall be in an amount sufficient to cover the applicable costs and cost commitments, in addition to those funded under Article 11.5, required of the Party responsible for building the facilities pursuant to the construction schedule developed in Appendix B for designing, engineering, seeking regulatory approval from any Governmental Authority, constructing, procuring and installing the applicable portion of the Transmission Owner's Interconnection Facilities, Transmission Owner's System Protection Facilities, Network Upgrades, Distribution Upgrades or Stand-Alone Network Upgrades and shall be reduced on a dollar-for-dollar basis for payments made to Transmission Owner for these purposes. Transmission Owner must use the milestone payments required under the GIP before requiring Interconnection Customer to submit additional security. Transmission Owner must specify, in Appendix B of this GIA, the dates for which Interconnection Customer must provide additional security for construction of each discrete portion of Transmission Owner's Interconnection Facilities, Network Upgrades, or Distribution Upgrades and Interconnection Customer must provide such additional security.

In addition:

11.6.1 The guarantee must be made by an entity that meets the creditworthiness requirements of Transmission Owner, and contain terms and conditions that guarantee payment of any amount that may be due from Interconnection

Customer, up to an agreed-to maximum amount.

11.6.2 The letter of credit must be issued by a financial institution reasonably acceptable to Transmission Owner and must specify a reasonable expiration date.

11.6.3 The surety bond must be issued by an insurer reasonably acceptable to Transmission Owner and must specify a reasonable expiration date.

11.6.4 If the Shared Network Upgrade is not in service, Interconnection Customer will not be required to make a payment under Schedule 26-B until the Shared Network Upgrade is in service, but Interconnection Customer will provide, as applicable, an Irrevocable Letter of Credit to fund any Shared Network Upgrade pursuant to Attachment FF of the Tariff. The Irrevocable Letter of Credit shall be in an amount sufficient to cover the Interconnection Customer's share of the applicable costs and cost commitments associated with the Shared Network Upgrades. Transmission Provider may periodically adjust the Interconnection Customer's share of the applicable costs and cost commitment of Shared Network Upgrades and may require Interconnection Customer to adjust the amount of the Irrevocable Letter of Credit accordingly.

11.7 Interconnection Customer Compensation. If Transmission Provider requests or directs Interconnection Customer to provide a service pursuant to Article 13.4 of this GIA, Transmission Provider shall compensate Interconnection Customer in accordance with any tariff or rate schedule filed by Transmission Provider and approved by the FERC.

11.8 Provision of Security for JTIQ Upgrades. If the Transmission Provider determines that the Interconnection Request meets the distribution factor and impact criteria specified in Section 9.4.2(d)((ii) of Rate Schedule 6 (MISO SPP JOA) and is included in the JTIQ Participation Group, Interconnection Customer shall be required to provide security in accordance with Attachment X, Appendix 18 (MISO JTIQ Commitment Agreement) and SPP's JTIQ Service Agreement.

ARTICLE 12. INVOICE

12.1 General. Each Party shall submit to the other Party, on a monthly basis, invoices of amounts due, if any, for the preceding month. Each invoice shall state the month to which the invoice applies and fully describe the services and equipment provided. The Parties may discharge mutual debts and payment obligations due and owing to each other on the same date through netting, in which case all amounts a Party owes to the other Party under this GIA, including interest payments or credits, shall be netted so that only the net amount remaining due shall be paid by the owing Party.

12.2 Final Invoice. Within six (6) months after completion of the construction of the Transmission Owner's Interconnection Facilities, Transmission Owner's System Protection Facilities, Distribution Upgrades and the Network Upgrades, Transmission

Owner shall provide an invoice of the final cost of the construction of the Transmission Owner's Interconnection Facilities, Transmission Owner's System Protection Facilities, Distribution Upgrades and the Network Upgrades and shall set forth such costs in sufficient detail to enable Interconnection Customer to compare the actual costs with the estimates and to ascertain deviations, if any, from the cost estimates. Transmission Owner shall refund, with interest (calculated in accordance with 18 C.F.R. Section 35.19a(a)(2)(iii), to Interconnection Customer any amount by which the actual payment by Interconnection Customer for estimated costs exceeds the actual costs of construction within thirty (30) Calendar Days of the issuance of such final construction invoice.

12.3 Payment. Invoices shall be rendered to the paying Party at the address specified in Appendix F. The Party receiving the invoice shall pay the invoice within thirty (30) Calendar Days of receipt. All payments shall be made in immediately available funds payable to the other Party, or by wire transfer to a bank named and account designated by the invoicing Party. Payment of invoices by a Party will not constitute a waiver of any rights or claims that Party may have under this GIA.

12.4 Disputes. In the event of a billing dispute among the Parties, Transmission Provider shall continue to provide Interconnection Service under this GIA as long as Interconnection Customer: (i) continues to make all payments not in dispute; and (ii) pays to Transmission Provider or Transmission Owner or into an independent escrow account the portion of the invoice in dispute, pending resolution of such dispute. If Interconnection Customer fails to meet these two requirements for continuation of service, then Transmission Provider may or, at Transmission Owner's request upon Interconnection Customer's failure to pay, Transmission Owner, shall provide notice to Interconnection Customer of a Default pursuant to Article 17. Within thirty (30) Calendar Days after the resolution of the dispute, the Party that owes money to another Party shall pay the amount due with interest calculated in accord with the methodology set forth in 18 C.F.R. § 35.19a(a)(2)(iii).

ARTICLE 13. EMERGENCIES

13.1 Obligations. Each Party shall comply with the Emergency Condition procedures of Transmission Provider, the Electric Reliability Organization, and Applicable Laws and Regulations.

13.2 Notice. Transmission Provider or Transmission Owner shall notify the other Parties promptly when it becomes aware of an Emergency Condition that affects the Transmission Owner's Interconnection Facilities or the Transmission or Distribution System, as applicable, that may reasonably be expected to affect Interconnection Customer's operation of the Generating Facility or the Interconnection Customer's Interconnection Facilities.

Interconnection Customer shall notify Transmission Provider and Transmission Owner, which includes by definition if applicable, the operator of a Distribution System, promptly when it becomes aware of an Emergency Condition that affects the Generating

Facility or the Interconnection Customer's Interconnection Facilities that may reasonably be expected to affect the Transmission or Distribution System, as applicable, or the Transmission Owner's Interconnection Facilities.

To the extent information is known, the notification shall describe the Emergency Condition, the extent of the damage or deficiency, the expected effect on the operation of Interconnection Customer's or Transmission Provider's or Transmission Owner's facilities and operations, its anticipated duration and the corrective action taken and/or to be taken. The initial notice shall be followed as soon as practicable with written notice.

13.3 Immediate Action. Unless, in a Party's reasonable judgment, immediate action is required, the Party exercising such judgment shall notify and obtain the consent of the other Parties, such consent to not be unreasonably withheld, prior to performing any manual switching operations at the Generating Facility or the Interconnection Customer's Interconnection Facilities in response to an Emergency Condition either declared by Transmission Provider or otherwise regarding the Transmission or Distribution System, as applicable.

13.4 Transmission Provider and Transmission Owner Authority.

13.4.1 General. Transmission Provider or Transmission Owner may take whatever actions or inactions with regard to the Transmission System or the Transmission Owner's Interconnection Facilities it deems necessary during an Emergency Condition in order to (i) preserve public health and safety, (ii) preserve the reliability of the Transmission System or the Transmission Owner's Interconnection Facilities, (iii) limit or prevent damage, and (iv) expedite restoration of service.

Transmission Provider or Transmission Owner shall use Reasonable Efforts to minimize the effect of such actions or inactions on the Generating Facility or the Interconnection Customer's Interconnection Facilities. Transmission Provider or Transmission Owner may, on the basis of technical considerations, require the Generating Facility to mitigate an Emergency Condition by taking actions necessary and limited in scope to remedy the Emergency Condition, including, but not limited to, directing Interconnection Customer to shut-down, start-up, increase or decrease the real or reactive power output of the Generating Facility; implementing a reduction or disconnection pursuant to Article 13.4.2; directing Interconnection Customer to assist with blackstart (if available) or restoration efforts; or altering the outage schedules of the Generating Facility and the Interconnection Customer's Interconnection Facilities. Interconnection Customer shall comply with all of Transmission Provider's or Transmission Owner's operating instructions concerning Generating Facility real power and reactive power output within the manufacturer's design limitations of the Generating Facility's equipment that is in service and physically available for operation at the time, in compliance with Applicable Laws and Regulations.

13.4.2 Reduction and Disconnection. Transmission Provider or Transmission Owner may reduce Interconnection Service or disconnect the Generating Facility or the Interconnection Customer's Interconnection Facilities, when such reduction or disconnection is necessary under Good Utility Practice due to Emergency Conditions. These rights are separate and distinct from any right of curtailment of Transmission Provider pursuant to the Tariff. When Transmission Provider can schedule the reduction or disconnection in advance, Transmission Provider shall notify Interconnection Customer of the reasons, timing and expected duration of the reduction or disconnection. Transmission Provider shall coordinate with Interconnection Customer and Transmission Owner using Good Utility Practice to schedule the reduction or disconnection during periods of least impact to Interconnection Customer, Transmission Owner and Transmission Provider. Any reduction or disconnection shall continue only for so long as reasonably necessary pursuant to Good Utility Practice. The Parties shall cooperate with each other to restore the Generating Facility, the Interconnection Facilities, and the Transmission System to their normal operating state as soon as practicable consistent with Good Utility Practice.

13.5 Interconnection Customer Authority. Consistent with Good Utility Practice and this GIA and the GIP, Interconnection Customer may take whatever actions or inactions with regard to the Generating Facility or the Interconnection Customer's Interconnection Facilities during an Emergency Condition in order to (i) preserve public health and safety, (ii) preserve the reliability of the Generating Facility or the Interconnection Customer's Interconnection Facilities, (iii) limit or prevent damage, and (iv) expedite restoration of service. Interconnection Customer shall use Reasonable Efforts to minimize the effect of such actions or inactions on the Transmission System and the Transmission Owner's Interconnection Facilities. Transmission Provider and Transmission Owner shall use Reasonable Efforts to assist Interconnection Customer in such actions.

13.6 Limited Liability. Except as otherwise provided in Article 11.6 of this GIA, no Party shall be liable to any other for any action it takes in responding to an Emergency Condition so long as such action is made in good faith and is consistent with Good Utility Practice.

13.7 Audit. In accordance with Article 25.3, any Party may audit the performance of another Party when that Party declared an Emergency Condition.

ARTICLE 14. REGULATORY REQUIREMENTS AND GOVERNING LAW

14.1 Regulatory Requirements. Each Party's obligations under this GIA shall be subject to its receipt of any required approval or certificate from one or more Governmental Authorities in the form and substance satisfactory to the applying Party, or the Party making any required filings with, or providing notice to, such Governmental Authorities, and the expiration of any time period associated therewith. Each Party shall in good faith seek, and if necessary assist the other Party and use its Reasonable Efforts to obtain such

other approvals. Nothing in this GIA shall require Interconnection Customer to take any action that could result in its inability to obtain, or its loss of, status or exemption under the Federal Power Act, the Public Utility Holding Company Act of 2005, as amended, or the Public Utility Regulatory Policies Act of 1978.

14.2 Governing Law.

14.2.1 The validity, interpretation and performance of this GIA and each of its provisions shall be governed by the laws of the state where the Point of Interconnection is located, without regard to its conflicts of law principles.

14.2.2 This GIA is subject to all Applicable Laws and Regulations.

14.2.3 Each Party expressly reserves the right to seek changes in, appeal, or otherwise contest any laws, orders, rules, or regulations of a Governmental Authority.

ARTICLE 15. NOTICES

15.1 General. Unless otherwise provided in this GIA, any notice, demand or request required or permitted to be given by any Party to the other Parties and any instrument required or permitted to be tendered or delivered by a Party in writing to the other Parties shall be effective when delivered and may be so given, tendered or delivered, by recognized national courier, or by depositing the same with the United States Postal Service with postage prepaid, for delivery by certified or registered mail, addressed to the Party, or personally delivered to the Party, at the address set out in Appendix F, Addresses for Delivery of Notices and Billings.

Either Party may change the notice information in this GIA by giving five (5) Business Days written notice prior to the effective date of the change.

15.2 Billings and Payments. Billings and payments shall be sent to the addresses set out in Appendix F.

15.3 Alternative Forms of Notice. Any notice or request required or permitted to be given by any Party to the other and not required by this GIA to be given in writing may be so given by telephone, facsimile or email to the telephone numbers and email addresses set out in Appendix F.

15.4 Operations and Maintenance Notice. Each Party shall notify the other Parties in writing of the identity of the person(s) that it designates as the point(s) of contact with respect to the implementation of Articles 9 and 10.

ARTICLE 16. FORCE MAJEURE

16.1 Force Majeure.

16.1.1 Economic hardship is not considered a Force Majeure event.

16.1.2 A Party shall not be considered to be in Default with respect to any obligation hereunder, (including obligations under Article 4 and 5), other than the obligation to pay money when due, if prevented from fulfilling such obligation by Force Majeure. A Party unable to fulfill any obligation hereunder (other than an obligation to pay money when due) by reason of Force Majeure shall give notice and the full particulars of such Force Majeure to the other Parties in writing or by telephone as soon as reasonably possible after the occurrence of the cause relied upon. Telephone, facsimile or email notices given pursuant to this Article shall be confirmed in writing as soon as reasonably possible and shall specifically state full particulars of the Force Majeure, the time and date when the Force Majeure occurred and when the Force Majeure is reasonably expected to cease. The Party affected shall exercise Reasonable Efforts to remove such disability with reasonable dispatch, but shall not be required to accede or agree to any provision not satisfactory to it in order to settle and terminate a strike or other labor disturbance.

ARTICLE 17. DEFAULT

17.1 Default

17.1.1 General. No Default shall exist where such failure to discharge an obligation (other than the payment of money) is the result of Force Majeure as defined in this GIA or the result of an act or omission of another Party. Upon a Breach, the non-Breaching Party or Parties shall give written notice of such Breach to the Breaching Party with a copy to the other Party if one Party gives notice of such Breach. Except as provided in Article 17.1.2, the Breaching Party shall have thirty (30) Calendar Days from receipt of the Breach notice within which to cure such Breach; provided however, if such Breach is not capable of cure within thirty (30) Calendar Days, the Breaching Party shall commence such cure within thirty (30) Calendar Days after notice and continuously and diligently complete such cure within ninety (90) Calendar Days from receipt of the Breach notice; and, if cured within such time, the Breach specified in such notice shall cease to exist.

17.1.2 Termination. If a Breach is not cured as provided in this Article, or if a Breach is not capable of being cured within the period provided for herein, the non-Breaching Party or Parties shall terminate this GIA, subject to Article 2.3.2 of this GIA, by written notice to the Breaching Party, with a copy to the other Party if one Party gives notice of termination, and be relieved of any further obligation hereunder and, whether or not that Party(ies) terminates this GIA, to recover from the Breaching Party all amounts due hereunder, plus all other damages and remedies to which it is (they are) entitled at law or in equity. The provisions of this Article will survive termination of this GIA.

17.1.3 Cross-Default. Pursuant to Article 11.3 of this GIA, the Parties shall enter into a

Facilities Service Agreement if the Transmission Owner has elected to fund the capital for the Network Upgrades and/or Transmission Owner's System Protection Facilities. Notwithstanding anything to the contrary contained in this GIA, a breach by Interconnection Customer of any provision, covenant, or other term or condition contained in the Facilities Service Agreement shall be considered a breach under this GIA. Such breach shall be subject to the terms of Article 17 of this GIA. If a default under this GIA results from the Interconnection Customer's breach of the Facilities Service Agreement and subsequent failure to cure, the Transmission Owner and Transmission Provider shall be entitled, but in no event required, to apply all rights and remedies available by reason of default under the Facilities Service Agreement and this GIA.

Pursuant to Section 11.3 of the GIP, an Interconnection Customer included in a JTIQ Participation Group shall execute or request the unexecuted filing both of the Transmission Provider's JTIQ Commitment Agreement and the JTIQ Service Agreement included in SPP's tariff. Notwithstanding anything to the contrary contained in this GIA, a breach by Interconnection Customer of any provision, covenant, or other term or condition contained in the JTIQ Commitment Agreement or SPP's JTIQ Service Agreement shall be considered a breach under this GIA. Such breach shall be subject to the terms of Article 17 of this GIA provided, however, that the manner and timing of cure of such breach shall adhere to the requirements of the applicable agreement and cure in accordance with the provisions of such agreement shall also cure the breach of this GI. If a default under this GIA results from the Interconnection Customer's breach of the JTIQ Commitment Agreement or SPP JTIQ Service Agreement and subsequent failure to cure, the Transmission Owner and Transmission Provider shall be entitled, but in no event required, to apply all rights and remedies available by reason of default under the JTIQ Commitment Agreement, SPP JTIQ Service Agreement, and this GIA.

17.2 Violation of Operating Assumptions for Generating Facilities. If Transmission Provider requires Interconnection Customer to memorialize the operating assumptions for the charging behavior of the Generating Facility that includes at least one electric storage resource in Appendix A of this GIA, Transmission Provider may consider Interconnection Customer to be in Breach of the GIA if Interconnection Customer fails to operate the Generating Facility in accordance with those operating assumptions for charging behavior. However, if Interconnection Customer operates contrary to the operating assumptions for charging behavior specified in Appendix A of this GIA at the direction of Transmission Provider, Transmission Provider shall not consider Interconnection Customer in Breach of this GIA.

ARTICLE 18. LIMITATION OF LIABILITY, INDEMNITY, CONSEQUENTIAL DAMAGES AND INSURANCE

18.1 Limitation of Liability. A Party shall not be liable to another Party or to any third party or other person for any damages arising out of actions under this GIA, including, but not limited to, any act or omission that results in an interruption, deficiency or imperfection of Interconnection Service, except as provided in this Tariff. The provisions set forth in the Tariff shall be additionally applicable to any Party acting in good faith to implement or comply with its obligations under this GIA, regardless of whether the obligation is preceded by a specific directive.

18.2 Indemnity. To the extent permitted by law, an Indemnifying Party shall at all times indemnify, defend and hold the other Parties harmless from Loss.

18.2.1 Indemnified Party. If an Indemnified Party is entitled to indemnification under this Article 18 as a result of a claim by a non-Party, and the Indemnifying Party fails, after notice and reasonable opportunity to proceed under Article 18.2, to assume the defense of such claim, such Indemnified Party may at the expense of the Indemnifying Party contest, settle or consent to the entry of any judgment with respect to, or pay in full, such claim.

18.2.2 Indemnifying Party. If an Indemnifying Party is obligated to indemnify and hold any Indemnified Party harmless under this Article 18, the amount owing to the Indemnified Party shall be the amount of such Indemnified Party's actual Loss, net of any insurance or other recovery.

18.2.3 Indemnity Procedures. Promptly after receipt by an Indemnified Party of any claim or notice of the commencement of any action or administrative or legal proceeding or investigation as to which the indemnity provided for in Article 18.2 may apply, the Indemnified Party shall notify the Indemnifying Party of such fact. Any failure of or delay in such notification shall not affect a Party's indemnification obligation unless such failure or delay is materially prejudicial to the Indemnifying Party.

The Indemnifying Party shall have the right to assume the defense thereof with counsel designated by such Indemnifying Party and reasonably satisfactory to the Indemnified Party. If the defendants in any such action include one or more Indemnified Parties and the Indemnifying Party and if the Indemnified Party reasonably concludes that there may be legal defenses available to it and/or other Indemnified Parties which are different from or additional to those available to the Indemnifying Party, the Indemnified Party shall have the right to select separate counsel to assert such legal defenses and to otherwise participate in the defense of such action on its own behalf. In such instances, the Indemnifying Party shall only be required to pay the fees and expenses of one additional attorney to represent an Indemnified Party or Indemnified Parties having such differing or additional legal defenses.

The Indemnified Party shall be entitled, at its expense, to participate in any such action, suit or proceeding, the defense of which has been assumed by the

Indemnifying Party. Notwithstanding the foregoing, the Indemnifying Party (i) shall not be entitled to assume and control the defense of any such action, suit or proceedings if and to the extent that, in the opinion of the Indemnified Party and its counsel, such action, suit or proceeding involves the potential imposition of criminal liability on the Indemnified Party, or there exists a conflict or adversity of interest between the Indemnified Party and the Indemnifying Party, in such event the Indemnifying Party shall pay the reasonable expenses of the Indemnified Party, and (ii) shall not settle or consent to the entry of any judgment in any action, suit or proceeding without the consent of the Indemnified Party, which shall not be reasonably withheld, conditioned or delayed.

18.3 Consequential Damages. Other than the Liquidated Damages heretofore described, in no event shall either Party be liable under any provision of this GIA for any losses, damages, costs or expenses for any special, indirect, incidental, consequential, or punitive damages, including but not limited to loss of profit or revenue, loss of the use of equipment, cost of capital, cost of temporary equipment or services, whether based in whole or in part in contract, in tort, including negligence, strict liability, or any other theory of liability; provided; however, that damages for which a Party may be liable to the other Party under another agreement will not be considered to be special, indirect, incidental, or consequential damages hereunder.

18.4 Insurance. Transmission Owner and Interconnection Customer shall, at their own expense, maintain in force throughout the period of this GIA pursuant to 18.4.9, and until released by the other Party, the following minimum insurance coverages, with insurers authorized to do business or an approved surplus lines carrier in the state where the Point of Interconnection is located:

18.4.1 Employers' Liability and Workers' Compensation Insurance providing statutory benefits in accordance with the laws and regulations of the state in which the Point of Interconnection is located.

18.4.2 Commercial General Liability Insurance including premises and operations, personal injury, broad form property damage, broad form blanket contractual liability coverage (including coverage for the contractual indemnification) products and completed operations coverage, coverage for explosion, collapse and underground hazards, independent contractors coverage, coverage for pollution to the extent normally available and punitive damages to the extent normally available and a cross liability endorsement, with minimum limits of One Million Dollars ($1,000,000) per occurrence/One Million Dollars ($1,000,000) aggregate combined single limit for personal injury, bodily injury, including death and property damage.

18.4.3 Comprehensive Automobile Liability Insurance, for coverage of owned and non-owned and hired vehicles, trailers or semi-trailers licensed for travel on public roads, with a minimum combined single limit of One Million Dollars

($1,000,000) each occurrence for bodily injury, including death, and property damage.

18.4.4 Excess Public Liability Insurance over and above the Employer's Liability, Commercial General Liability and Comprehensive Automobile Liability Insurance coverage, with a minimum combined single limit of Twenty Million Dollars ($20,000,000) per occurrence/Twenty Million Dollars ($20,000,000) aggregate.

18.4.5 The Commercial General Liability Insurance, Comprehensive Automobile Insurance and Excess Public Liability Insurance policies shall name the other Parties, their parents, associated and Affiliate companies and their respective directors, officers, agents, servants and employees ("Other Party Group") as additional insured. All policies shall contain provisions whereby the insurers waive all rights of subrogation in accordance with the provisions of this GIA against the Other Party Groups and provide thirty (30) Calendar Days' advance written notice to the Other Party Groups prior to anniversary date of cancellation or any material change in coverage or condition.

18.4.6 The Commercial General Liability Insurance, Comprehensive Automobile Liability Insurance and Excess Public Liability Insurance policies shall contain provisions that specify that the policies are primary and shall apply to such extent without consideration for other policies separately carried and shall state that each insured is provided coverage as though a separate policy had been issued to each, except the insurer's liability shall not be increased beyond the amount for which the insurer would have been liable had only one insured been covered. Each Party shall be responsible for its respective deductibles or retentions.

18.4.7 The Commercial General Liability Insurance, Comprehensive Automobile Liability Insurance and Excess Public Liability Insurance policies, if written on a Claims First Made Basis, shall be maintained in full force and effect for two (2) years after termination of this GIA, which coverage may be in the form of tail coverage or extended reporting period coverage if agreed by Transmission Owner and Interconnection Customer.

18.4.8 The requirements contained herein as to the types and limits of all insurance to be maintained by Transmission Owner and Interconnection Customer are not intended to and shall not in any manner, limit or qualify the liabilities and obligations assumed by Transmission Owner and Interconnection Customer under this GIA.

18.4.9 As of the date set forth in Appendix B, Milestones, and as soon as practicable after the end of each fiscal year or at the renewal of the insurance policy and in any event within ninety (90) Calendar Days thereafter, Interconnection Customer and Transmission Owner shall provide the other Party with

certification of all insurance required in this GIA, executed by each insurer or by an authorized representative of each insurer.

18.4.10 Notwithstanding the foregoing, Transmission Owner or Interconnection Customer may self-insure to meet the minimum insurance requirements of Articles 18.4.1 through 18.4.8, to the extent it maintains a self-insurance program; provided that, Transmission Owner's or Interconnection Customer's senior secured debt is rated at investment grade, or better, by Standard & Poor's and that its self-insurance program meets minimum insurance requirements under Articles 18.4.1 through 18.4.8. For any period of time that a Transmission Owner's or Interconnection Customer's senior secured debt is unrated by Standard & Poor's or is rated at less than investment grade by Standard & Poor's, such Party shall comply with the insurance requirements applicable to it under Articles 18.4.1 through 18.4.9. In the event that Transmission Owner or Interconnection Customer is permitted to self-insure pursuant to this article, it shall notify the other Party that it meets the requirements to self-insure and that its self-insurance program meets the minimum insurance requirements in a manner consistent with that specified in Article 18.4.9.

18.4.11 Transmission Owner and Interconnection Customer agree to report to each other in writing as soon as practical all accidents or occurrences resulting in injuries to any person, including death, and any property damage arising out of this GIA.

ARTICLE 19. ASSIGNMENT

19.1 Assignment. This GIA may be assigned by any Party only with the written consent of the other Parties; provided that a Party may assign this GIA without the consent of the other Parties to any Affiliate of the assigning Party with an equal or greater credit rating and with the legal authority and operational ability to satisfy the obligations of the assigning Party under this GIA; and provided further that Interconnection Customer shall have the right to assign this GIA, without the consent of either Transmission Provider or Transmission Owner, for collateral security purposes to aid in providing financing for the Generating Facility, provided that Interconnection Customer will promptly notify Transmission Provider of any such assignment. Any financing arrangement entered into by Interconnection Customer pursuant to this Article will provide that prior to or upon the exercise of the secured party's, trustee's or mortgagee's assignment rights pursuant to said arrangement, the secured creditor, the trustee or mortgagee will notify Transmission Provider of the date and particulars of any such exercise of assignment right(s), including providing Transmission Provider and Transmission Owner with proof that it meets the requirements of Article 11.5 and 18.4. Any attempted assignment that violates this Article is void and ineffective. Any assignment under this GIA shall not relieve a Party of its obligations, nor shall a Party's obligations be enlarged, in whole or in part, by reason thereof. Where required, consent to assignment will not be unreasonably withheld, conditioned or delayed.

ARTICLE 20. SEVERABILITY

20.1 **Severability**. If any provision in this GIA is finally determined to be invalid, void or unenforceable by any court or other Governmental Authority having jurisdiction, such determination shall not invalidate, void or make unenforceable any other provision, agreement or covenant of this GIA; provided that if Interconnection Customer (or any non-Party, but only if such non-Party is not acting at the direction of either Transmission Provider or Transmission Owner) seeks and obtains such a final determination with respect to any provision of the Alternate Option (Article 5.1.2), or the Negotiated Option (Article 5.1.4), then none of these provisions shall thereafter have any force or effect and the Parties' rights and obligations shall be governed solely by the Standard Option (Article 5.1.1).

ARTICLE 21. COMPARABILITY

21.1 **Comparability**. The Parties will comply with all applicable comparability and code of conduct laws, rules and regulations including such laws, rules and regulations of Governmental Authorities establishing standards of conduct, as amended from time to time.

ARTICLE 22. CONFIDENTIALITY

22.1 **Confidentiality.** Confidential Information shall include, without limitation, all information relating to a Party's technology, research and development, business affairs, and pricing, and any information supplied by a Party to another Party prior to the execution of this GIA.

Information is Confidential Information only if it is clearly designated or marked in writing as confidential on the face of the document, or, if the information is conveyed orally or by inspection, if the Party providing the information orally informs the Party receiving the information that the information is confidential. The Parties shall maintain as confidential any information that is provided and identified by a Party as Critical Energy Infrastructure Information (CEII), as that term is defined in 18 C.F.R. Section 388.113(c). Such confidentiality will be maintained in accordance with this Article 22.

If requested by the receiving Party, the disclosing Party shall provide in writing, the basis for asserting that the information referred to in this Article warrants confidential treatment, and the requesting Party may disclose such writing to the appropriate Governmental Authority. Each Party shall be responsible for the costs associated with affording confidential treatment to its information.

22.1.1 Term**.** During the term of this GIA, and for a period of three (3) years after the expiration or termination of this GIA, except as otherwise provided in this Article 22 or with regard to CEII, each Party shall hold in confidence and shall not disclose to any person Confidential Information. CEII shall be treated in

accordance with Commission policy and regulations.

22.1.2 Scope. Confidential Information shall not include information that the receiving Party can demonstrate: (1) is generally available to the public other than as a result of a disclosure by the receiving Party; (2) was in the lawful possession of the receiving Party on a non-confidential basis before receiving it from the disclosing Party; (3) was supplied to the receiving Party without restriction by a non-Party, who, to the knowledge of the receiving Party after due inquiry, was under no obligation to the disclosing Party to keep such information confidential; (4) was independently developed by the receiving Party without reference to Confidential Information of the disclosing Party; (5) is, or becomes, publicly known, through no wrongful act or omission of the receiving Party or Breach of this GIA; or (6) is required, in accordance with Article 22.1.7 of this GIA, Order of Disclosure, to be disclosed by any Governmental Authority or is otherwise required to be disclosed by law or subpoena, or is necessary in any legal proceeding establishing rights and obligations under this GIA. Information designated as Confidential Information will no longer be deemed confidential if the Party that designated the information as confidential notifies the receiving Party that it no longer is confidential.

22.1.3 Release of Confidential Information. No Party shall release or disclose Confidential Information to any other person, except to its Affiliates (limited by the Standards of Conduct requirements), subcontractors, employees, agents, consultants, or to non-parties who may be or are considering providing financing to or equity participation with Interconnection Customer, or to potential purchasers or assignees of Interconnection Customer, on a need-to-know basis in connection with this GIA, unless such person has first been advised of the confidentiality provisions of this Article 22 and has agreed to comply with such provisions. Notwithstanding the foregoing, a Party providing Confidential Information to any person shall remain primarily responsible for any release of Confidential Information in contravention of this Article 22.

22.1.4 Rights. Each Party retains all rights, title, and interest in the Confidential Information that it discloses to the receiving Party. The disclosure by a Party to the receiving Party of Confidential Information shall not be deemed a waiver by the disclosing Party or any other person or entity of the right to protect the Confidential Information from public disclosure.

22.1.5 No Warranties. By providing Confidential Information, no Party makes any warranties or representations as to its accuracy or completeness. In addition, by supplying Confidential Information, no Party obligates itself to provide any particular information or Confidential Information to another Party nor to enter into any further agreements or proceed with any other relationship or joint venture.

22.1.6 Standard of Care. Each Party shall use at least the same standard of care to

protect Confidential Information it receives as it uses to protect its own Confidential Information from unauthorized disclosure, publication or dissemination. Each Party may use Confidential Information solely to fulfill its obligations to another Party under this GIA or its regulatory requirements.

22.1.7 Order of Disclosure. If a court or a Governmental Authority or entity with the right, power, and apparent authority to do so requests or requires any Party, by subpoena, oral deposition, interrogatories, requests for production of documents, administrative order, or otherwise, to disclose Confidential Information, that Party shall provide the disclosing Party with prompt notice of such request(s) or requirement(s) so that the disclosing Party may seek an appropriate protective order or waive compliance with the terms of this GIA. Notwithstanding the absence of a protective order or waiver, the Party may disclose such Confidential Information which, in the opinion of its counsel, the Party is legally compelled to disclose. Each Party will use Reasonable Efforts to obtain reliable assurance that confidential treatment will be accorded any Confidential Information so furnished.

22.1.8 Termination of Agreement. Upon termination of this GIA for any reason, each Party shall, within ten (10) Calendar Days of receipt of a written request from another Party, use Reasonable Efforts to destroy, erase, or delete (with such destruction, erasure, and deletion certified in writing to the requesting Party) or return to the requesting Party, without retaining copies thereof, any and all written or electronic Confidential Information received from the requesting Party, except that each Party may keep one copy for archival purposes, provided that the obligation to treat it as Confidential Information in accordance with this Article 22 shall survive such termination.

22.1.9 Remedies**.** The Parties agree that monetary damages would be inadequate to compensate a Party for another Party's Breach of its obligations under this Article 22. Each Party accordingly agrees that the disclosing Party shall be entitled to equitable relief, by way of injunction or otherwise, if the receiving Party Breaches or threatens to Breach its obligations under this Article 22, which equitable relief shall be granted without bond or proof of damages, and the Breaching Party shall not plead in defense that there would be an adequate remedy at law. Such remedy shall not be deemed an exclusive remedy for the Breach of this Article 22, but shall be in addition to all other remedies available at law or in equity. The Parties further acknowledge and agree that the covenants contained herein are necessary for the protection of legitimate business interests and are reasonable in scope. No Party, however, shall be liable for indirect, incidental, or consequential or punitive damages of any nature or kind resulting from or arising in connection with this Article 22.

22.1.10 Disclosure to FERC, its Staff or a State**.** Notwithstanding anything in this Article 22 to the contrary, and pursuant to 18 CFR § 1b.20, if FERC or its staff, during the course of an investigation or otherwise, requests information from a

Party that is otherwise required to be maintained in confidence pursuant to this GIA, the Party shall provide the requested information to FERC or its staff, within the time provided for in the request for information. In providing the information to FERC or its staff, the Party must, consistent with 18 CFR § 388.112, request that the information be treated as confidential and non-public by FERC and its staff and that the information be withheld from public disclosure. Parties are prohibited from notifying the other Parties to this GIA prior to the release of the Confidential Information to FERC or its staff. The Party shall notify the other Parties to this GIA when it is notified by FERC or its staff that a request to release Confidential Information has been received by FERC, at which time any of the Parties may respond before such information would be made public, pursuant to 18 CFR § 388.112. Requests from a state regulatory body conducting a confidential investigation shall be treated in a similar manner if consistent with the applicable state rules and regulations.

22.1.11 Subject to the exception in Article 22.1.10, any information that a disclosing Party claims is competitively sensitive, commercial or financial information under this GIA shall not be disclosed by the receiving Party to any person not employed or retained by the receiving Party, except to the extent disclosure is (i) required by law; (ii) reasonably deemed by the receiving Party to be required to be disclosed in connection with a dispute between or among the Parties, or the defense of litigation or dispute; (iii) otherwise permitted by consent of the disclosing Party, such consent not to be unreasonably withheld; or (iv) necessary to fulfill its obligations under this GIA or as the Regional Transmission Organization or a Local Balancing Authority operator including disclosing the Confidential Information to a regional or national reliability organization. The Party asserting confidentiality shall notify the receiving Party in writing of the information that Party claims is confidential. Prior to any disclosures of that Party's Confidential Information under this subparagraph, or if any non-Party or Governmental Authority makes any request or demand for any of the information described in this subparagraph, the Party who received the Confidential Information from the disclosing Party agrees to promptly notify the disclosing Party in writing and agrees to assert confidentiality and cooperate with the disclosing Party in seeking to protect the Confidential Information from public disclosure by confidentiality agreement, protective order or other reasonable measures.

ARTICLE 23. ENVIRONMENTAL RELEASES

23.1 Each Party shall notify the other Parties, first orally and then in writing, of the release of any Hazardous Substances, any asbestos or lead abatement activities, or any type of remediation activities related to the Generating Facility or the Interconnection Facilities, each of which may reasonably be expected to affect another Party. The notifying Party shall: (i) provide the notice as soon as practicable, provided such Party makes a good faith effort to provide the notice no later than twenty-four hours after such Party becomes aware of the occurrence; and (ii) promptly furnish to the other Parties copies of any

publicly available reports filed with any Governmental Authorities addressing such events.

ARTICLE 24. INFORMATION REQUIREMENTS

24.1 Information Acquisition. Transmission Provider, Transmission Owner and Interconnection Customer shall submit specific information regarding the electrical characteristics of their respective facilities to each other as described below and in accordance with Applicable Reliability Standards.

24.2 Information Submission by Transmission Provider and Transmission Owner The initial information submission by Transmission Provider to Interconnection Customer, with copy provided to Transmission Owner, shall occur no later than one hundred eighty (180) Calendar Days prior to Trial Operation and shall include Transmission or Distribution System information, as applicable and available, necessary to allow Interconnection Customer to select equipment and meet any system protection and stability requirements, unless otherwise mutually agreed to by the Parties. On a monthly basis, Transmission Owner shall provide Interconnection Customer a status report on the construction and installation of Transmission Owner's Interconnection Facilities, Transmission Owner's System Protection Facilities, Distribution Upgrades and Network Upgrades, including, but not limited to, the following information: (1) progress to date; (2) a description of the activities since the last report (3) a description of the action items for the next period; and (4) the delivery status of equipment ordered.

24.3 Updated Information Submission by Interconnection Customer. The updated information submission by Interconnection Customer to Transmission Provider, with copy to Transmission Owner, including manufacturer information, shall occur no later than one hundred eighty (180) Calendar Days prior to the Trial Operation. Interconnection Customer shall submit to Transmission Provider and Transmission Owner a completed copy of the Generating Facility data requirements contained in Appendix 1 to the GIP. It shall also include any additional information provided to Transmission Provider for the Interconnection Facilities Study. Information in this submission shall be the most current Generating Facility design or expected performance data. Information submitted for stability models shall be compatible with Transmission Provider standard models. If there is no compatible model, Interconnection Customer will work with a consultant mutually agreed to by Transmission Provider and Interconnection Customer to develop and supply a standard model and associated information.

If the Interconnection Customer's data is materially different from what was originally provided to Transmission Provider pursuant to the Interconnection Study Agreement between Transmission Provider and Interconnection Customer, then Transmission Provider will conduct appropriate studies to determine the impact on the Transmission System based on the actual data submitted pursuant to this Article 24.3. Interconnection Customer shall not begin Trial Operation until such studies are completed.

24.4 Information Supplementation. Prior to the Commercial Operation Date, the Parties shall supplement their information submissions described above in this Article 24 with any and all "as-built" Generating Facility information or "as-tested" performance information that differs from the initial submissions or, alternatively, written confirmation that no such differences exist. Interconnection Customer shall conduct tests on the Generating Facility as required by Good Utility Practice, such as an open circuit "step voltage" test on the Generating Facility to verify proper operation of the Generating Facility's automatic voltage regulator.

Unless otherwise agreed, the test conditions shall include: (1) Generating Facility at synchronous speed; (2) automatic voltage regulator on and in voltage control mode; and (3) a five percent (5 %) change in Generating Facility terminal voltage initiated by a change in the voltage regulators reference voltage. Interconnection Customer shall provide validated test recordings showing the responses in Generating Facility terminal and field voltages. In the event that direct recordings of these voltages is impractical, recordings of other voltages or currents that mirror the response of the Generating Facility's terminal or field voltage are acceptable if information necessary to translate these alternate quantities to actual Generating Facility terminal or field voltages is provided. Generating Facility testing shall be conducted and results provided to Transmission Provider and Transmission Owner for each individual generating unit in a station.

Subsequent to the Commercial Operation Date, Interconnection Customer shall provide Transmission Provider and Transmission Owner any information changes due to equipment replacement, repair, or adjustment. Transmission Owner shall provide Interconnection Customer, with copy to Transmission Provider, any information changes due to equipment replacement, repair or adjustment in the directly connected substation or any adjacent Transmission Owner substation that may affect the Interconnection Customer's Interconnection Facilities equipment ratings, protection or operating requirements. The Parties shall provide such information no later than thirty (30) Calendar Days after the date of the equipment replacement, repair or adjustment.

ARTICLE 25. INFORMATION ACCESS AND AUDIT RIGHTS

25.1 Information Access. Each Party (the "disclosing Party") shall make available to the other Parties information that is in the possession of the disclosing Party and is necessary in order for the other Parties to: (i) verify the costs incurred by the disclosing Party for which another Party is responsible under this GIA; and (ii) carry out its obligations and responsibilities under this GIA. The Parties shall not use such information for purposes other than those set forth in this Article 25.1 and to enforce their rights under this GIA.

25.2 Reporting of Non-Force Majeure Events. A Party (the "notifying Party") shall notify the other Parties when the notifying Party becomes aware of its inability to comply with the provisions of this GIA for a reason other than a Force Majeure event. The Parties agree to cooperate with each other and provide necessary information regarding such inability to comply, including the date, duration, reason for the inability to comply, and

corrective actions taken or planned to be taken with respect to such inability to comply. Notwithstanding the foregoing, notification, cooperation or information provided under this Article shall not entitle any Party receiving such notification to allege a cause for anticipatory breach of this GIA.

25.3 Audit Rights. Subject to the requirements of confidentiality under Article 22 of this GIA, each Party shall have the right, during normal business hours, and upon prior reasonable notice to the other Parties, to audit at its own expense the other Parties' accounts and records pertaining to the Parties' performance or the Parties' satisfaction of obligations under this GIA. Such audit rights shall include audits of the other Parties' costs, calculation of invoiced amounts, the Transmission Provider's efforts to allocate responsibility for the provision of reactive support to the Transmission or Distribution System, as applicable, the Transmission Provider's efforts to allocate responsibility for interruption or reduction of generation, and each Party's actions in an Emergency Condition. Any audit authorized by this Article shall be performed at the offices where such accounts and records are maintained and shall be limited to those portions of such accounts and records that relate to each Party's performance and satisfaction of obligations under this GIA. Each Party shall keep such accounts and records for a period equivalent to the audit rights periods described in Article 25.4.

25.4 Audit Rights Periods.

25.4.1 Audit Rights Period for Construction-Related Accounts and Records. Accounts and records related to the design, engineering, procurement, and construction of the Transmission Owner's Interconnection Facilities, Transmission Owner's System Protection Facilities, Distribution Upgrades and Network Upgrades shall be subject to audit for a period of twenty-four months following Transmission Owner's issuance of a final invoice in accordance with Article 12.2.

25.4.2 Audit Rights Period for All Other Accounts and Records. Accounts and records related to a Party's performance or satisfaction of all obligations under this GIA other than those described in Article 25.4.1 shall be subject to audit as follows: (i) for an audit relating to cost obligations, the applicable audit rights period shall be twenty-four (24) months after the auditing Party's receipt of an invoice giving rise to such cost obligations; and (ii) for an audit relating to all other obligations, the applicable audit rights period shall be twenty-four (24) months after the event for which the audit is sought.

25.5 Audit Results. If an audit by a Party determines that an overpayment or an underpayment has occurred, a notice of such overpayment or underpayment shall be given to the Party or from whom the overpayment or underpayment is owed together with those records from the audit which support such determination.

ARTICLE 26. SUBCONTRACTORS

26.1 General. Nothing in this GIA shall prevent a Party from utilizing the services of any subcontractor as it deems appropriate to perform its obligations under this GIA; provided, however, that each Party shall require its subcontractors to comply with all applicable terms and conditions of this GIA in providing such services and each Party shall remain primarily liable to the other Parties for the performance of such subcontractor.

26.2 Responsibility of Principal. The creation of any subcontract relationship shall not relieve the hiring Party of any of its obligations under this GIA. The hiring Party shall be fully responsible to the other Parties for the acts or omissions of any subcontractor the hiring Party hires as if no subcontract had been made; provided, however, that in no event shall Transmission Provider or Transmission Owner be liable for the actions or inactions of Interconnection Customer or its subcontractors with respect to obligations of Interconnection Customer under Article 5 of this GIA. Any applicable obligation imposed by this GIA upon the hiring Party shall be equally binding upon, and shall be construed as having application to, any subcontractor of such Party.

26.3 No Limitation by Insurance. The obligations under this Article 26 will not be limited in any way by any limitation of subcontractor's insurance.

ARTICLE 27. DISPUTES

27.1 Submission. In the event any Party has a dispute, or asserts a claim, that arises out of or in connection with this GIA or its performance, such Party (the "disputing Party") shall provide the other Parties with written notice of the dispute or claim ("Notice of Dispute"). Such dispute or claim shall be referred to a designated senior representative of each Party for resolution on an informal basis as promptly as practicable after receipt of the Notice of Dispute by the non-disputing Parties. In the event the designated representatives are unable to resolve the claim or dispute through unassisted or assisted negotiations within thirty (30) Calendar Days of the non-disputing Parties' receipt of the Notice of Dispute, such claim or dispute shall be submitted for resolution in accordance with the dispute resolution procedures of the Tariff.

ARTICLE 28. REPRESENTATIONS, WARRANTIES AND COVENANTS

28.1 General. Each Party makes the following representations, warranties and covenants:

28.1.1 Good Standing. Such Party is duly organized, validly existing and in good standing under the laws of the state in which it is organized, formed, or incorporated, as applicable; that it is qualified to do business in the state or states in which the Generating Facility, Interconnection Facilities and Network Upgrades owned by such Party, as applicable, are located; and that it has the corporate power and authority to own its properties, to carry on its business as now being conducted and to enter into this GIA and carry out the transactions contemplated hereby and perform and carry out all covenants and obligations on

its part to be performed under and pursuant to this GIA.

28.1.2 Authority**.** Such Party has the right, power and authority to enter into this GIA, to become a Party hereto and to perform its obligations hereunder. This GIA is a legal, valid and binding obligation of such Party, enforceable against such Party in accordance with its terms, except as the enforceability thereof may be limited by applicable bankruptcy, insolvency, reorganization or other similar laws affecting creditors' rights generally and by general equitable principles (regardless of whether enforceability is sought in a proceeding in equity or at law).

28.1.3 No Conflict. The execution, delivery and performance of this GIA does not violate or conflict with the organizational or formation documents, or bylaws or operating agreement, of such Party, or any judgment, license, permit, order, material agreement or instrument applicable to or binding upon such Party or any of its assets.

28.1.4 Consent and Approval. Such Party has sought or obtained, or, in accordance with this GIA will seek or obtain, each consent, approval, authorization, order, or acceptance by any Governmental Authority in connection with the execution, delivery and performance of this GIA, and it will provide to any Governmental Authority notice of any actions under this GIA that are required by Applicable Laws and Regulations.

ARTICLE 29. {RESERVED}

ARTICLE 30. MISCELLANEOUS

30.1 Binding Effect. This GIA and the rights and obligations hereof, shall be binding upon and shall inure to the benefit of the successors and assigns of the Parties hereto.

30.1.1 Reversion. If offered pursuant to an Agency Agreement under which this GIA is executed by Transmission Provider as agent for the relevant Transmission Owner, in the event that the relevant Agency Agreement terminates, any HVDC Service offered by Transmission Provider under this GIA shall revert to the relevant Transmission Owner and Transmission Provider shall be released from all obligations and responsibilities under this GIA.

30.2 Conflicts. In the event of a conflict between the body of this GIA and any attachment, appendices or exhibits hereto, the terms and provisions of the body of this GIA shall prevail and be deemed the final intent of the Parties.

30.3 Rules of Interpretation. This GIA, unless a clear contrary intention appears, shall be construed and interpreted as follows: (1) the singular number includes the plural number and vice versa; (2) reference to any person includes such person's successors and assigns but, in the case of a Party, only if such successors and assigns are permitted by this GIA,

and reference to a person in a particular capacity excludes such person in any other capacity or individually; (3) reference to any agreement (including this GIA), document, instrument or tariff means such agreement, document, instrument, or tariff as amended or modified and in effect from time to time in accordance with the terms thereof and, if applicable, the terms hereof; (4) reference to any Applicable Laws and Regulations means such Applicable Laws and Regulations as amended, modified, codified, or reenacted, in whole or in part, and in effect from time to time, including, if applicable, rules and regulations promulgated thereunder; (5) unless expressly stated otherwise, reference to any Article, Section or Appendix means such Article of this GIA or such Appendix to this GIA, or such Section to the GIP or such Appendix to the GIP, as the case may be; (6) "hereunder", "hereof", "herein", "hereto" and words of similar import shall be deemed references to this GIA as a whole and not to any particular Article or other provision hereof or thereof; (7) "including" (and with correlative meaning "include") means including without limiting the generality of any description preceding such term; and (8) relative to the determination of any period of time, "from" means "from and including", "to" means "to but excluding" and "through" means "through and including."

30.4 Entire Agreement. This GIA, including all Appendices and attachments hereto, constitutes the entire agreement between the Parties with reference to the subject matter hereof, and supersedes all prior and contemporaneous understandings or agreements, oral or written, between the Parties with respect to the subject matter of this GIA. There are no other agreements, representations, warranties, or covenants, which constitute any part of the consideration for, or any condition to, any Party's compliance with its obligations under this GIA.

30.5 No Third Party Beneficiaries. This GIA is not intended to and does not create rights, remedies, or benefits of any character whatsoever in favor of any persons, corporations, associations, or entities other than the Parties, and the obligations herein assumed are solely for the use and benefit of the Parties, their successors in interest and, where permitted, their assigns.

30.6 Waiver. The failure of a Party to this GIA to insist, on any occasion, upon strict performance of any provision of this GIA will not be considered a waiver of any obligation, right, or duty of, or imposed upon, such Party.

Any waiver at any time by any Party of its rights with respect to this GIA shall not be deemed a continuing waiver or a waiver with respect to any other failure to comply with any other obligation, right, duty of this GIA. Termination or Default of this GIA for any reason by Interconnection Customer shall not constitute a waiver of the Interconnection Customer's legal rights to obtain Interconnection Service from Transmission Provider. Any waiver of this GIA shall, if requested, be provided in writing.

30.7 Headings. The descriptive headings of the various Articles of this GIA have been inserted for convenience of reference only and are of no significance in the interpretation or construction of this GIA.

30.8 Multiple Counterparts. This GIA may be executed in two or more counterparts, each of which is deemed an original but all constitute one and the same instrument.

30.9 Amendment. The Parties may by mutual agreement amend this GIA by a written instrument duly executed by all of the Parties.

30.10 Modification by the Parties. The Parties may by mutual agreement amend the Appendices to this GIA by a written instrument duly executed by all of the Parties. Such amendment shall become effective and a part of this GIA upon satisfaction of all Applicable Laws and Regulations.

30.11 Reservation of Rights. Transmission Provider shall have the right to make a unilateral filing with FERC to modify this GIA with respect to any rates, terms and conditions, charges, classifications of service, rule or regulation under Section 205 or any other applicable provision of the Federal Power Act and FERC's rules and regulations thereunder, and Transmission Owner and Interconnection Customer shall have the right to make a unilateral filing with FERC to modify this GIA pursuant to Section 206 or any other applicable provision of the Federal Power Act and FERC's rules and regulations thereunder; provided that each Party shall have the right to protest any such filing and to participate fully in any proceeding before FERC in which such modifications may be considered. Nothing in this GIA shall limit the rights of the Parties or of FERC under Sections 205 or 206 of the Federal Power Act and FERC's rules and regulations thereunder, except to the extent that the Parties otherwise mutually agree as provided herein.

30.12 No Partnership. This GIA shall not be interpreted or construed to create an association, joint venture, agency relationship, or partnership among or between the Parties or to impose any partnership obligation or partnership liability upon any Party. No Party shall have any right, power or authority to enter into any agreement or undertaking for, or act on behalf of, or to act as or be an agent or representative of, or to otherwise bind, the other Parties.

IN WITNESS WHEREOF, the Parties have executed this GIA in multiple originals; each of which shall constitute and be an original GIA among the Parties.

Transmission Provider
Midcontinent Independent System Operator, Inc.

By: _____ DMK 11/17/2025
Name: Aubrey Johnson
Title: Vice President, System Planning

Transmission Owner
Entergy Louisiana, LLC

By: John T. Anderson
Name: John T. Anderson
Title: VP - Project & Portfolio Development

Interconnection Customer
Entergy Louisiana, LLC

By: _____
Name: Phillip R. May
Title: President and CEO

APPENDICES TO GIA

Appendix A	Interconnection Facilities, System Protection Facilities, Distribution Upgrades, Generator Upgrades and Network Upgrades
Appendix B	Milestones
Appendix B-1	Pre-Certification Generation Test Notification Form
Appendix C	Interconnection Details
Appendix D	Security Arrangements Details
Appendix E	Commercial Operation Date
Appendix F	Addresses for Delivery of Notices and Billings
Appendix G	Interconnection Requirements for Inverter-Based Resource Plants
Appendix H	Interconnection Requirements for Provisional GIA
Appendix I	Requirements Applicable to Surplus Interconnection Service

Appendix A to GIA
Interconnection Facilities, System Protection Facilities, Distribution Upgrades, Generator Upgrades and Network Upgrades

1. Description of Generating Facility

Interconnection Customer shall install a 1,928 MVA facility, rated at 1,640 MW gross and 1,536 MW net, with all studies performed at or below these outputs. The Generating Facility is composed of two (2) Mitsubishi gas turbine generation units rated at 562 MVA / 478 MW each and two (2) Mitsubishi heat recovery steam generators rated at 402 MVA / 342 MW in a combined cycle plant. Interconnection Service provided under this agreement is 1,536 MW of conditional ERIS and/or NRIS that will become 1,536 MW of NRIS upon completion of all Network Upgrades, Common Use Upgrades, and Affected System Upgrades under this GIA and transmission assumptions listed in Table A10-1 of Exhibit A10.

Interconnection Customer shall install a switchyard with the appropriate protection equipment coordinated per Appendix C to this GIA. The Switchyard shall contain two (2) generator step-up transformers 230/23.5 kV 360/600 MVA, two (2) generator step-up transformers 230/21 kV 252/420 MVA, four (4) 4000 A 80kA circuit breakers connected as illustrated in Exhibit A1-1.

The Generating Facility shall provide reactive compensation as necessary to meet the FERC Order 827.

2. Interconnection Facilities

(a) Point of Interconnection.

i. The Point of Interconnection (POI) shall be at the point where the E0014 lead line connects to the Transmission Owner's Smalling 230kV yard substation bus.
ii. The Point of Change of Ownership (PCO) shall be at the Interconnection Customer's dead-end structure within the generation step-up yard.
iii. The Metering Equipment will be located on the Transmission Owner Interconnection Facilities and compensated to the Point of Interconnection. Refer to Exhibit A2 one-line diagram for the demarcation points of these facilities.

(b) Interconnection Facilities (including metering equipment) to be constructed by Interconnection Customer.

Interconnection Customer shall construct and own the Customer Interconnection Facilities. These facilities shall include:

- Two (2) approximately 0.28 mile of 230 kV generator lead lines using 954 ACSS Cardinal conductors.
- A servitude agreement will need to be executed between Interconnection Customer and Entergy for the transmission line connecting the PCO to

POI, and access road(s). Actual size and final location will be determined after detail design is complete. Below is a list of the servitudes and their preliminary dimensions:

- One PCO to POI servitude will be approximately 125 feet wide x 1800 feet long, approximately 5.15 acres and a second PCO to POI servitude will be approximately 125 feet wide x 1650 feet long, approximately 4.72 acres.

- The first underground servitude for E0014 ADSS fiber will be approximately 0.25 miles long between PCO and POI. The second underground servitude for E0014 ADSS fiber will be approximately 0.21 miles long between the PCO and POI. Total size and location will be determined after detail design is complete.
- The Interconnection Customer will provide to Transmission Owner a copy of wetland delineation for the new switching station site, access road and transmission line ROW, ESA Phase I report, and cultural resources constraint analysis/archeological survey, if required
- Interconnection Customer is responsible for coordinating and obtaining station service supply for the Interconnection Customer Interconnection Facilities and the Generating Facility. The Interconnection Customer will coordinate station supply with the local service territory provider to address normal and emergency back-up station power needs for Interconnection Customer Interconnection Facilities and for Generating Facility during construction and operation of those facilities. Net metering of Station Service power may be obtained per the requirements of Transmission Provider's Schedule 20

(c) Transmission Owner Interconnection Facilities (including metering equipment) to be constructed by Transmission Owner. Transmission Owner Interconnection Facilities shall consist of the following equipment:

i. Smalling 500/230 kV Substation

General

a) Customer will transmit generator breaker status, telemetering data including MW, MVAR, MWhr and MVARhrs to Entergy's Smalling 500/230kV Substation Remote Terminal Unit (RTU) utilizing underground fiber optic cable.
b) Customer will design line protection compatible with the line relaying installed at Entergy's Smalling 500/230kV Substation.

Site

a) Installation of 5/8'' x 10' ground rods shall be installed near major equipment such as surge arresters.

Foundations

a) Drilled pier and pad foundations will be used for all equipment support structure.
b) The foundation scope of work includes design and construction of the following:

- Install twenty-nine (29) 36-inch diameter 17-foot-long drilled pier foundations for 230kV single phase, low bus support insulators.
- Install six (6) 42 inch diameter 22-foot-long drilled pier foundations for 230kV single phase, high bus support insulators.
- Install six (6) 36-inch diameter 20-foot-long drilled pier foundations for 230kV surge arrester structures.
- Install six (6) 36-inch diameter 20-foot-long drilled pier foundations for 230kV CCVT structures.
- Install two (2) set of four (4) 72-inch diameter 30-foot-long drilled pier foundations for 230kV deadend structure.

Electrical

a) Steel Structures
- Six (6) single-phase 230kV high bus support structure.
- Twenty-nine (29) single-phase 230kV low bus support structure.
- Six (6) 230kV surge arrester structures.
- Six (6) 230kV CCVT structures.
- Two (2) three-phase 230kV deadend structure.

b) 230 kV Station Post Insulators
- Forty-one (41) polymer insulators rated for nominal system voltage of 230 kV.
- Installation includes fitting accessories.

c) 230 kV Suspension Insulators
- Six (6) 230 kV polymer suspension insulators installed on the H-frame.
- Installation includes fitting accessories.

d) 230 kV Surge Arresters
- Six (6) station class surge arrester rated for nominal system voltage.

e) Conductors
- The horizontal bus will be 4” aluminum schedule 40 rigid tubular bus.
- The equipment jumpers from the horizontal bus to the string bus shall be bundled 1780 ACSR “Chukar,” two conductors per phase.
- The equipment jumpers for switches to breakers shall be 1780 ACSR “Chukar,” two conductors per phase.
- The equipment jumpers from the horizontal bus to the coupling capacitor voltage transformers and surge arresters shall be 1780 ACSR “Chukar,” one conductor per phase.
- Include all necessary fittings.

f) Raceway & Conduit
- 2” PVC conduit with couplings, bends, adapters, liquid-tight fittings, and related hardware for CCVTs.
- All conduit at road crossings and running outside station fence will be encased in concrete.

g) Existing Control Building

- Includes installing connection of control cable wiring checkout and commissioning of the associated systems.

Relay

a) The relay protection scheme is subject to change during detailed design considering the long procurement duration.
b) Two (2) new relay panels are required for the protective relays associated with the Gen-Tie lines coming from Franklin Farms powerplant at the Smalling 500/230kV substation.
   - One (1) protection panel shall include two (2) SEL-411L relays using a line current differential scheme for the new 230kV single gen-tie line from Unit#1 (CTG1-STG1) of the Franklin Farms powerplant. Entergy Standard for breaker control PM1803 OPT C5.
   - One (1) protection panel shall include two (2) SEL-411L relays using a line current differential scheme for the new 230kV single gen-tie line from Unit#2 (CTG2-STG2) of the Franklin Farms powerplant. Entergy Standard for breaker control PM1803 OPT C5.
   - Relay communication between terminals shall be established via fiber optic cables. Refer to the project telecommunications plan for circuit routing and connection details.
   - Includes installing the panels inside the control building, de-terminating existing control cable wiring, reconnecting existing shielded control cable wiring, installing and connecting any additional control cable wiring as required, checkout and commissioning of the associated systems.

Relay Settings

a) Refer to Network Upgrade section.

Communications and SCADA

a) Refer to Network Upgrade section.

Metering

a) No metering upgrades required.

ii. Transmission Owner's 230kV Transmission Line

General

a) The transmission line scope consists of two spans of conductor located between the Franklin Farms Generation and Smalling Substation on the new single-circuit 230kV Interconnection Customer transmission line.
b) New double-bundle 954kcmil Cardinal ACSS and DNO-12776 & Alumoweld 7#7 shield wires will be installed on the interconnection span.

Structures and Foundations

a) Install (6) self-supported steel monopole dead-end structures
b) Install (2) direct embed steel monopole 0-1.5º suspension braced post structure
c) Foundation analysis to be performed during Detailed Design.

Conductor and Insulators

a) Install approximately 23,000’ of 954 kcmil ACSS Cardinal (double-bundle) for main conductor
b) Install strain insulators for (6) new structures and (6) new substation terminals
c) Install braced post insulators for (2) new structures.

Shield Wire

a) Install approximately 3,000’ of DNO-12776 OPGW
b) Install approximately 3,200’ of Alumoweld 7#7

The estimated costs for these facilities are in year 2025 dollars, with an intended accuracy of +/- 20%, and are detailed in Exhibit A6.

3. Network Upgrades

(a) Stand-Alone Network Upgrades to be installed by Transmission Owner. None.

(b) Network Upgrades to be installed by Transmission Owner. The Network Upgrades were developed for installing two new 562 MVA CTG and 402 MVA STG generating facility lines connected at the Transmission Owners’ Smalling 500/230kV substation. Upgrades will include yard equipment upgrades, installation of relay panels and telecom upgrades at Smalling 500/230kV substation.

i. Smalling 500/230kV Substation

General

a) Customer will transmit generator breaker status, telemetering data including MW, MVAR, MWhr and MVARhrs to Transmission Owner’s Smalling 500/230kV Substation Remote Terminal Unit (RTU) utilizing underground fiber optic cable.
b) Customer will design line protection compatible with the line relaying installed at the Transmission Owner’s Smalling 500/230kV Substation.

Site

a) Installation of 5/8’’ x 10’ ground rods shall be installed near major equipment such as surge arresters.

Foundations

a) Drilled pier and pad foundations will be used for all equipment support structure.
b) The foundation scope of work includes design and construction of the following:
   - Install thirty-four (34) 42 inch diameter 22-foot-long drilled pier foundations for 230kV single phase, low bus support insulators and structure.
   - Install twelve (12) set of two (2) 42 inch diameter 22-foot long drilled pier foundations for 230kV low switch structures.

- Install four (4) 10'L X 10'W X 2'H slab foundations for 230kV breakers.
- Install four (4) 8'L X 6'W X 2'H slab foundations for 230kV breaker access pad.

Electrical

a) Steel Structures
- Thirty-four (34) single-phase 230kV low bus support structure.
- Eight (8) 230kV low switch structures.
- Four (4) 230kV low switch bypass structures.

b) 230 kV Station Post Insulators
- Fifty-six (56) polymer insulators rated for nominal system voltage of 230 kV.
- Installation includes fitting accessories.

c) Gas Circuit Breakers
- Four (4) 245 kV, SF6 gas circuit breakers rated 3000 A, 63 kA interrupting capability, three (3) sets of bushing CTs, designed as per Transmission Owner specification SD0202.
- Includes installing control conduit to the circuit breakers, jumpers to the associated disconnect switches, and control cable to the control building.

d) 230 kV Disconnect Switches
- Six (6) three-phase vertical break disconnect switch is required to allow isolation of the circuit breaker that comprise the 230 kV main bus.
- Two (2) three-phase vertical break disconnect switch, with mechanical interlocked ground switch attachment, is required to allow isolation of the circuit breaker that comprise the 230 kV line terminals to the breaker for remote line isolation.
- All switches to be rated 230 kV, 3000 A continuous, 63 kA short term withstand capacity, 900 kV BIL.

e) Conductors
- The horizontal bus will be 4” aluminum schedule 40 rigid tubular bus.
- The equipment jumpers from the horizontal bus to the string bus shall be bundled 1780 ACSR “Chukar,” two conductors per phase.
- The equipment jumpers for switches to breakers shall be 1780 ACSR “Chukar,” two conductors per phase.
- The equipment jumpers from the horizontal bus to the coupling capacitor voltage transformers and surge arresters shall be 1780 ACSR “Chukar,” one conductor per phase.
- Include all necessary fittings.

f) Raceway & Conduit
- Four (4) new, two-inch (2”) conduits for the Transmission Owner-Interconnection fiber optic cable, routed from the new control house to the Interconnect Customer PCO Pole Location/POI.

i. Handhole / pull box installed at the PCO structure, according to Transmission Owner design specs.
ii. ADSS fiber between Smalling control house and the handhole / pull box installed at the PCO structure, including all associated fiber splicing.
iii. Excess slack of ADSS fiber left in the handhole / pull box located at the PCO structure such that the Interconnect Customer may pull to the generation control house.

- 2" PVC conduit with couplings, bends, adapters, liquid-tight fittings, and related hardware for breakers and switches.
- All conduit at road crossings and running outside station fence will be encased in concrete.

h) Existing Control Building
- Includes installing the panels in the control building, connection of control cable wiring checkout and commissioning of the associated systems.

Relay

a) Instrument Transformer
- Six (6) coupling capacitor voltage transformers (CCVTs), each with two (2) secondary windings, shall be installed. Scope includes installation of conduits to the CCVTs, jumpers to the associated bus, and control cables to the control building.

b) Miscellaneous equipment shall include:
- Two (2) three-phase CCVT/PT outdoor junction boxes capable of accommodating two (2) secondary windings.

c) Four (4) new relay panels are required for the new breakers in the Bay 5 & 8 at the Smalling 500/230kV substation.
- Four (4) breaker control panels for breakers RX311, RX312, RX316, and RX317 shall be provided with one (1) SEL-451 relay configured for breaker control, monitoring, and backup protection functions.
- Includes installing the panels inside the control building, de-terminating existing control cable wiring, reconnecting existing shielded control cable wiring, installing and connecting any additional control cable wiring as required, checkout and commissioning of the associated systems.

Relay Settings

a) Study and apply NERC/SERC Regulatory compliance requirements (FAC-008-3, PRC-027, PRC-023, PRC-025). Perform analysis based on Transmission Owner Standard compliance procedure for setting revisions and updates.

b) Develop new relay settings for two (2) new line protection panels associated with the 230kV interconnection gen-tie line coming from Unit#1 & Unit#2, incorporating two (2) SEL-411L relays utilizing a line current differential protection scheme.

c) Develop new relay settings for four (4) new breaker control panels associated with the 230kV breakers RX311, RX312, RX316, and RX317 incorporating one (1) SEL-451 relay for control and backup protection.
d) Develop revised relay settings for eight (8) bus protection panels associated with the 230kV Bus#1-4, each incorporating two (2) SEL-487B relays.
e) Prepare and support test plans for all newly developed and revised relay settings, ensuring complete functional and protection validation.
f) Provide both off-site and on-site support during the construction and commissioning phases, addressing relay setting database issues, relay software compatibility, and firmware version alignment.
g) Upgrade existing relays to the latest approved firmware in accordance with Transmission Owner standards and verify compatibility with relay settings and communication protocols.
h) Perform relay settings logistics and documentation tasks, including maintenance of relay database files (.rdbs), generation of viewable relay setting documents (.xls), organization of project folders for web posting (IPS), and relay model development in CAPE®.
i) All relay settings work shall be completed in strict accordance with Transmission Owner protection standards, project-specific design drawings, and applicable system studies.

Communications and SCADA

a) Provision underground (UG) fiber connections between Smalling 500/230kV Substation and the Franklin Farms Plant. Fiber shall be routed via dedicated conduits and splice points as coordinated with Transmission Owner IT Telecom.
b) Install one (1) 96-strand single mode fiber cable from Smalling Substation to the Plant Process Data Centers (PDCs), including link or fiber tie through the Admin Building to the Plant Control Building.
c) Provide a 144-strand fiber cable through the Admin Building for redundancy and future expansion.
d) Install Optical Ground Wire (OPGW) on the Gen-Tie line to provide a redundant telecommunications path between Smalling Substation and the Franklin Farms Plant, ensuring diverse and reliable routing.
e) Provide fiber panels and fiber connectors in the Smalling 500/230-kV Substation Electrical Building and Plant Electrical Building to maintain continuity of the fiber ring design.
f) Establish fully redundant singlemode direct fiber relay paths from Smalling 230kV Substation to both Plant relaying, ensuring physically diverse redundant routes for reliability.
g) Coordinate with Transmission Owner Telecom and Relay Design to define patching, port assignments, and multiplexed channel usage consistent with Transmission Owner standards.
h) Transmission Owner will complete fiber installation and splicing at the Smalling 230kV substation.

i) Complete fiber installation and splicing at the Smalling 230-kV Substation in coordination with Transmission Owner Telecom standards.
j) Transmission Owner Telecom's responsibility is to provide Direct Fiber assignments for Relay-Channels, Relay and Power Generation counterparts (on Power Gen side of Transmission) install relay communications via these channels. Transmission Owner Telecom (internal) will splice/OTDR test fibers and provide results to Relay/Power Gen. Relay and Power Gen resources responsible for testing Relays themselves. Update RTU configuration files as required to support new relay communication paths.
k) Perform SCADA integration and testing for all new fiber channels, including relay communications, telemetry, and alarm/status points.

Metering

a) No metering upgrades required.

ii. Underground ADSS Fiber

General

a) New underground fiber to be installed on this T-line section between the Franklin Farms CCCT and Smalling 500/230 kV substation.

UG Fiber

a) Approximately a total of 0.3 miles shall be installed between the Franklin Farms CCCT and Smalling 500/230 kV substation to provide communications to both stations.

(c) Shared Network Upgrade(s) to be funded by Interconnection Customer.
None.

(d) Substation Network Upgrades to be installed by Transmission Owner.
None.

4. System Protection Facilities

(a) System Protection Facilities not listed in Section 2 or 3 to be constructed by Interconnection Customer. None.

(b) System Protection Facilities not listed in 2 or 3 to be constructed by Transmission Owner.

Smalling 500 kV Substation

a) Develop new relay settings for one (1) line protection panel associated with the 500 kV Smalling–Baxter Wilson Line, incorporating two (2) SEL-411L relays utilizing a line current differential protection scheme.
b) Develop new relay settings for three (3) line protection panels associated with the 500 kV Smalling–Car Gas Rd Lines #1, #2, and #3, each incorporating two (2) SEL-411L relays utilizing a line current differential protection scheme.

Car Gas Rd 500 kV Substation

a) Develop new relay settings for three (3) line protection panels associated with the 500 kV Car Gas Rd–Smalling Lines #1, #2, and #3, each incorporating two (2) SEL-411L relays.
b) Develop new relay settings for three (3) line protection panels associated with the 500 kV Car Gas Rd–Perryville Lines #1, #2, and #3, each incorporating two (2) SEL-411L relays.
c) Develop new relay settings for two (2) line protection panels associated with the 500 kV Car Gas Rd–Sterlington Lines #1 and #2, each incorporating two (2) SEL-411L relays.
d) Develop new relay settings for one (1) line protection panel associated with the 500 kV Car Gas Rd–Mt Olive Line, incorporating two (2) SEL-411L relays.

Perryville 500 kV Substation

a) Develop new relay settings for three (3) line protection panels associated with the 500 kV Perryville–Car Gas Rd Lines #1, #2, and #3, each incorporating two (2) SEL-411L relays.
b) Develop new relay settings for one (1) backup protection panel associated with Perryville Unit #1, incorporating one (1) SEL-311C relay.
c) Develop new relay settings for one (1) backup protection panel associated with Perryville Unit #2, incorporating one (1) SEL-311C relay.

Sterlington 500 kV Substation

a) Develop new relay settings for two (2) line protection panels associated with the 500 kV Sterlington–Car Gas Rd Lines #1 and #2, each incorporating two (2) SEL-411L relays.
b) Develop new relay settings for one (1) line protection panel associated with the 500 kV Sterlington–Ouachita Line, incorporating two (2) SEL-411L relays.
c) Develop new relay settings for one (1) line protection panel associated with the 500 kV Sterlington–Ouachita Line, incorporating one (1) SEL-321 relay with POTT/DTT scheme.
d) Develop new relay settings for one (1) line protection panel associated with the 500 kV Sterlington–El Dorado Line, incorporating one (1) SEL-411L relay (OPT Modified C5).
e) Develop new relay settings for one (1) line protection panel associated with the 500 kV Sterlington–El Dorado Line, incorporating SEL-421 and SEL-311C relays.

Ouachita 500 kV Substation

a) Develop new relay settings for two (2) line protection panels associated with the 500 kV Ouachita–Sterlington Line (three-terminal configuration), each incorporating two (2) SEL-411L relays.
b) Develop new relay settings for one (1) line protection panel associated with the 500 kV Ouachita–Sterlington Line (three-terminal configuration), incorporating one (1) SEL-321 relay.

El Dorado 500 kV Substation

a) Develop new relay settings for one (1) line protection panel associated with the 500 kV El Dorado–Sterlington Line, incorporating one (1) SEL-411L relay (OPT Modified C5).
b) Develop new relay settings for one (1) line protection panel associated with the 500 kV El Dorado–Sterlington Line, incorporating SEL-421 and SEL-321 relays.

Baxter Wilson 500 kV Substation

a) Develop new relay settings for one (1) line protection panel associated with the 500 kV Baxter Wilson–Smalling Line, incorporating two (2) SEL-411L relays.

Catahoula 230 kV Substation

a) Develop new relay settings for two (2) line protection panels associated with the 230 kV Catahoula–Smalling Lines #1 and #2, each incorporating two (2) SEL-411L relays.

Eagle 230 kV Substation

a) Develop new relay settings for one (1) line protection panel associated with the 230 kV Eagle–Smalling Line, incorporating two (2) SEL-411L relays.
b) Develop new relay settings for one (1) line protection panel associated with the 230 kV Eagle–Chotard Line, incorporating two (2) SEL-411L relays.

Chotard 230 kV Substation

a) Develop new relay settings for one (1) line protection panel associated with the 230 kV Chotard–Smalling Line, incorporating two (2) SEL-411L relays.
b) Develop new relay settings for one (1) line protection panel associated with the 230 kV Chotard–Eagle Line, incorporating two (2) SEL-411L relays.

Yucatan 230 kV Substation

a) Develop new relay settings for one (1) line protection panel associated with the 230 kV Yucatan–Smalling Line #1, incorporating two (2) SEL-411L relays.
b) Develop new relay settings for one (1) line protection panel associated with the 230 kV Yucatan–Smalling Line #2, incorporating two (2) SEL-411L relays.

Concordia 230 kV Substation

a) Develop new relay settings for one (1) line protection panel associated with the 230 kV Concordia–Smalling Line, incorporating two (2) SEL-411L relays.
b) Develop new relay settings for one (1) line protection panel associated with the 230 kV Concordia–Marengo Line, incorporating two (2) SEL-411L relays.

Marengo 230 kV Substation

a) Develop new relay settings for one (1) line protection panel associated with the 230 kV Marengo–Smalling Line, incorporating two (2) SEL-411L relays.
b) Develop new relay settings for one (1) line protection panel associated with the 230 kV Marengo–Concordia Line, incorporating two (2) SEL-411L relays.

5. Distribution Upgrades.

(a) Distribution Upgrades to be constructed by Transmission Owner. None.

6. Contingency List. See Exhibit A10.

7. Affected System Upgrades List.
Affected Systems Studies have not concluded as of the date of this EGIA. Interconnection Customer is responsible for executing and fulfilling the obligations of any agreements for the study, construction, or funding of Affected System network upgrades identified by the Affected System after execution of this GIA.

8. JTIQ Upgrades.
None.

9. Common Use Upgrades. Interconnection Customer is responsible for entering into Facilities Construction Agreements and/or Multi-Party Facilities Construction Agreement with transmission owner for Interconnection Customer's share of the following upgrades:

10. Exhibits – The following exhibits are included:

A1. Interconnection Customer One-Line & Site Map
A1-1: Interconnection Customer One-Line Diagram (1 of 2)
A1-2: Interconnection Customer One-Line Diagram (2 of 2)
A1-3: Interconnection Project Site Map
A2. Transmission Owner One-Lines
A2-1: Transmission Owner One-Line
A3. Transmission Owner Substation General Arrangement
A3-1: General Arrangement Drawing
A4. Transmission Line Plan and Profile
A4-1: Tangent Structure Type
A4-2: Dead End Structure Types
A4-3: 3-D Interconnection Layout
A5. Facilities to be Constructed by Transmission Owner
A6. Detailed Cost of Facilities to be Constructed by Transmission Owner
A7. Facilities to be Constructed by Interconnection Customer
A8. Detailed Cost of Facilities to be Constructed by Interconnection Customer
A9. Facilities Subject to Transmission Owner Reimbursement
A10. Contingent Facilities
A11. Interconnection Customer Milestones
A12. Construction & Coordination Schedules
A13. Permits, Licenses, Regulatory Approvals and Authorization
A14. Interconnection and Operating Guidelines

Exhibit A1. Interconnection Customer One-Line & Site Map

A1-1: Interconnection Customer One-Line Diagram (1 of 2)

CUI//CEII MATERIAL – DO NOT RELEASE

A1-2: Interconnection Customer One-Line Diagram (2 of 2)

CUI//CEII MATERIAL – DO NOT RELEASE

A1-3: Interconnection Project Site Map




Exhibit A2. Transmission Owner One-Lines
A2-1: Transmission Owner One-Line




Exhibit A3. Transmission Owner Substation General Arrangement
A3-1: General Arrangement Drawing






Exhibit A4. Transmission Line Plan and Profile
A4-1: Tangent Structure Type



A4-2: Dead End Structure Types

0°–5°, SELF SUPPORTING, DE, JUMPER, VERTICAL, SINGLE CIRCUIT, DE POLYMER, STEEL 230kV



ASSEMBLY LIST		
ITEM	QTY.	ASSEMBLY/DRAWING
1	3	BLT–P–S
2	6	DEP/TRB–230–XX
3	3	JLP–230–XX
4	2	OHG–DE–XX
REFERENCE DRAWINGS		
7	1	SGN–S
8	–	GND–S–XX
9	–	POLE INDEX
10	1	FOOTING
11	–	PVO, SHT 1, VW PV–19
12	–	ANODE–XX (IF REQ.)

NOTES:

1) All dimensions are to Centerline of top attachment or BLT–XX.
2) See Pole Fabricator's drawings for attachment details.
3) See Staking Sheet and CU Drawings for line angles, pole, footing, grounding, and sign requirements.
4) Refer to Assembly drawings for part details.
5) Conductor attachment vangs shall be placed within 5 degrees of Ahead and Back locations.
6) This structure shall not be used for single insulator bundled conductor applications unless the combined phase tension is less than 19.4 kips. For two insulator attachment bundled conductor applications, use the appropriate bundled framing.

Set:Phase

NO.	DATE:	REVISION	BY:	APPR:

SDJA–V–DEP–S 230

ENTERGY STANDARD DWG.

DESIGN APPROVAL	STANDARDS APPROVAL
SIGNED / DATE	SIGNED / DATE

DEADEND STEEL 230kV
0°–5° SINGLE CIRCUIT

APPROVED BY:	DATE: 8–15–03
CHECKED BY:	SCALE: NONE
DRAWN BY: LINESOFT	ESI NO. TDS559A0


Entergy

No.

PLOT 1=130 SH. 1 OF 1

70'–120', SELF SUPPORTING, DE, VERTICAL,
SINGLE CIRCUIT, DE POLMER, STEEL 230kV

ASSEMBLY LIST		
ITEM	QTY.	ASSEMBLY/DRAWING
1	6	DEP/TRB–230–XX
2	2	OHG–DE–XX
REFERENCE DRAWINGS		
7	1	SGN–S
8	–	GND–S–XX
9	–	POLE INDEX
10	1	FOOTING
11	–	PVO, SHT 2, VW PV–15
12	–	ANODE–XX (IF REQ.)



NOTES:

1) All dimensions are to Centerline of top attachment.
2) See Pole Fabricator's drawings for attachment details.
3) See Staking Sheet and CU Drawings for line angles, pole, footing, grounding, and sign requirements.
4) Refer to Assembly drawings for part details.
5) Conductor attachment vangs shall be placed within 5 degrees of Ahead and Back locations.
6) This structure shall not be used for single insulator bundled conductor applications unless the combined phase tension is less than 19.4 kips. For two insulator attachment bundled conductor applications, use the appropriate bundled framing.

Set:Phase

NO.	DATE:	REVISION	BY:	APPR:
2	8–18–04	REVISED DIMENSION FOR SIGN	ITRON	
1	4–28–03	REV., DIM., GND., NOTE 1, ADD ITEM 12, NOTE 6	ITRON	

SD–V–DEP–S 230

ENTERGY STANDARD DWG.

DESIGN APPROVAL	STANDARDS APPROVAL
SIGNED / DATE	SIGNED / DATE

DEADEND STEEL 230kV
70'–120' SINGLE CIRCUIT

APPROVED BY:	DATE:	10–18–96
CHECKED BY:	SCALE:	NONE
DRAWN BY:	ESI NO.	TDS419A2

Entergy

No.

PLOT 1=130 SH. 1 OF 1

A4-3: 3-D Interconnection Layout




Exhibit A5. Facilities to be Constructed by Transmission Owner

Description of Upgrade	Upgrade Classification	Estimated Cost*
J3841 500/230 kV Substation: Transmission Owner Interconnection Facilities shall consist of a high bus dead-end structure, a section of tubular bus tapping off the breaker and a half bay, a disconnect switch with a ground switch attachment, (3) 230 kV surge arresters, and (6) coupling capacitor voltage transformers, and (1) Line Protection Panel with associated wiring . The facilities shall include associated support structures and associated foundations, as shown on Exhibit A4 which is a preliminary electrical profile view of the TOIFs.	TOIF	$875,000
J3842 500/230 kV Substation: Transmission Owner Interconnection Facilities shall consist of a high bus dead-end structure, a section of tubular bus tapping off the breaker and a half bay, a disconnect switch with a ground switch attachment, (3) 230 kV surge arresters, (6) coupling capacitor voltage transformer, and (1) Line Protection Panel with associated wiring. The facilities shall include associated support structures and associated foundations, as shown on Exhibit A4 which is a preliminary electrical profile view of the TOIFs.	TOIF	$865,000
J3841 Transmission Line: Entergy's Interconnection Facilities shall consist on installing new 954 ACSS "Cardinal", DNO-12776 OPGW 96, and 7#7 Alumowled shield wires, along with all attachment hardware. Self supported steel monopole tangent (1) and dead-end (3) structures, along with all attachment hardware.	TOIF	$1,765,000
J3842 Transmission Line: Entergy's Interconnection Facilities shall consist on installing new 954 ACSS "Cardinal", DNO-12776 OPGW 96, and 7#7 Alumowled shield wires, along with all attachment hardware. Self supported steel monopole tangent (1) and dead-end (3) structures, along with all attachment hardware.	TOIF	$1,735,000
J3841 500/230 kV Substation Equipment Upgrade(s): Network upgrade shall include (2) 245 kV, 63kA Circuit, Breakers, (4) 230kV, 3000A Switches, (17) 230 kV Bus Supports, (2) Breaker Control Panels and associated wiring.	NU	$4,263,300

J3842 500/230 kV Substation Equipment Upgrade(s): Network upgrade shall include (2) 245 kV, 63kA Circuit, Breakers, (4) 230kV, 3000A Switches, (17) 230 kV Bus Supports, (2) Breaker Control Panels and associated wiring.	NU	$4,263,300
J3841/J3842 Telecom: Installation of new UG fiber to establish redundant communication paths, including all materials, engineering, technician labor, fiber termination panels, and transition splicing at Smalling Substation and Franklin Farms Plant.	NU	$213,400
	Total Cost:	**$13,980,000**

***Estimated Costs are in 2025 dollars**

Exhibit A6. Detailed Cost of Facilities to be Constructed by Transmission Owner

Table A6-1: Detailed Cost Estimate*

Item Description	Estimated Total	TOIF	SANU	NU
Contract Construction	$7,290,000	$2,990,000	$0	$4,300,000
Contract Project Management	$570,000	$0	$0	$570,000
ROW, Permitting Support & Environmental	$0	$0	$0	$0
Materials	$3,510,000	$1,530,000	$0	$1,980,000
Contract Engineering	$590,000	$210,000	$0	$380,000
Telecom	$200,000	$0	$0	$200,000
Payroll	$500,000	$0	$0	$500,000
Distribution	$0	$0	$0	$0
Expense	$40,000	$20,000	$0	$20,000
Total Direct Cost:	**$12,700,000**	**$4,750,000**	**$0**	**$7,950,000**
Capital Suspense:	$850,000	$320,000	$0	$530,000
AFUDC:	$390,000	$150,000	$0	$250,000
Other Overheads:	$40,000	$20,000	$0	$10,000
Total In-direct Cost:	**$1,280,000**	**$490,000**	**$0**	**$790,000**
Total Cost:	**$13,980,000**	**$5,240,000**	**$0**	**$8,740,000**

***Estimated Costs are in 2025 dollars**

Exhibit A7. Facilities to be Constructed by Interconnection Customer

Interconnection Customer facilities are not included in this Facilities Study report. To be provided by the Interconnection Customer.

Exhibit A8. Detailed Cost of Facilities to be Constructed by Interconnection Customer

Interconnection Customer facilities are not included in this Facilities Study report. To be provided by the Interconnection Customer.

Exhibit A9. Facilities Subject to Transmission Owner Reimbursement

There is no transmission owner reimbursable scope associated with this project.

A10 Contingent Facilities

Table A10-1 describes transmission assumptions modeled in the studies that were deemed necessary to allow for the Interconnection Service as described in Appendix A of this GIA and is not related to Article 11.3.1, i.e., does not describe projects associated with a higher queued and/or similarly queued ERAS Interconnection Request. Nevertheless, if the transmission assumptions are not completed or significantly modified, the Interconnection Service granted under this GIA may be restricted until such time as the Interconnection Customer funds a study to determine the applicable ERIS and NRIS level that results due to the changes in Table A10-1.

A list of higher-queued and/or similarly queued ERAS study projects are in Tables A10-2 and A10-3. A project inclusion in this GIA does not necessarily mean that these facilities would be contingencies for the Interconnection Customer's Generating Facility. If any of the higher queued and/or same cycle ERAS generators were to drop out, then the Interconnection Customer may be subject to restudy pursuant to Article 11.3.2.

Table A10-1: Transmission Assumptions

MTEP ID	Facility ID	Facility	Description	Expected Completion Date	Status
25242	28277	WEBRE- COMMODORE 500kV Circuit 1	Amite South Reliability Project Phase 1 - alternative	8/1/2028	M2 - Appendix A Approved
15654	23667	DELHI-TALLULAH 115 kV Circuit 1	Delhi to Tallulah Rebuild	12/1/2026	M2 - Appendix A Approved
15654	23668	DELHI-DEHIL RX 115 kV Circuit 1	Delhi to Tallulah Rebuild	12/1/2026	M2 - Appendix A Approved
50093	50139	CHALKBLUFFPV – GALET 500kV Circuit 1	Galet 500/230kV New Substation	2/26/2027	M2 - Appendix A Approved

50093	50139	W.MEMPHIS – GALET 500 kV Circuit 1	Galet 500/230kV New Substation	2/26/2027	M2 - Appendix A Approved
17974	24744	STILLEYS – WEST FRANK FORT EAST 345kV Circuit 1	Crab Orchard: Install 345-138 kV transformer. Tap the Shawnee-West Frankfort east-4564 line and install 345kV ring bus to make the connection.	12/1/2026	M2 - Appendix A Approved
17974	24744	STILLEYS – SHAWNEE 345 kV Circuit 1	Crab Orchard: Install 345-138 kV transformer. Tap the Shawnee-West Frankfort east-4564 line and install 345kV ring bus to make the connection.	12/1/2026	M2 - Appendix A Approved
50556	50936	S HILLS - EAST ADAIR 345 kV Circuit T2	LRTP 23 – Lakefield Junction – East Adair	6/1/2034	M2 - Appendix A Approved
50556	50931	ORIENT - EAST ADAIR 345 kV Circuit T2	LRTP 23 – Lakefield Junction – East Adair	6/1/2034	M2 - Appendix A Approved
AFS	AFS	SPP	Build New Beckham to Potter 345 kV Line	TBD	TBD

Table A10-2: Prior Queued Projects

MISO Higher Queued Project #	Service Type	TO	County, State	Point Of Interconnection	Pmax (MW)	Fuel Type
None						

Table A10-3: Similarly Queued Projects

MISO Queue Project #	Service Type	TO	County, State	Point Of Interconnection	ERIS MW	Fuel Type
None						

Exhibit A11. Interconnection Customer Milestones

This exhibit is provided for reference only. Binding dates are in Appendix B.

The customer milestones include, but are not limited to those shown in the table below:

Table A11-1: Milestone Schedule

IC Milestone Schedule	
Task Name	**Proposed Finish**
GIA Execution:	TBD
GIA Payment:	TBD
Landowner Access Approval (soil borings):	N/A
Site Acquisition (servitude agreements):	N/A
Receipt of Environmental Permitting:	Complete

Exhibit A12. Construction & Coordination Schedules

This exhibit is provided for reference only. Binding dates are in Appendix B.

The proposed schedule is dependent on obtaining a suitable substation site, on timely receipt of all approvals associated with constructing the Transmission Owner interconnection substation and lines, outage availability, equipment lead-time, and resource availability. This schedule does not include upgrades that may be required because of the system impact studies. An Engineering and Procurement Agreement between the parties could potentially be utilized to begin work before the generation interconnection agreement is executed.
A detailed schedule will be prepared subsequent to customer approval to proceed with the project. Based on the Task duration schedules listed below, the overall project in-service date is projected to be Feb 2028.

Table A12-1: Milestone Schedule

Task Name	Proposed Start	Proposed Finish
GIA Execution:	TBD	
Customer Approval & Funding:	TBD	
Complete Project Execution Plan:	Complete	
Update/ Baseline Schedule:	Complete	
Detail Design:	Complete	Complete
Order Material:	Complete	Complete
Receive Material:	Complete	Complete
Issue for Construction Design Packages:	Complete	Complete
Environmental Permits:	Complete	
Construction:	Oct 2025	Oct 2026
In-Service:	Feb 2028	

Milestone Schedule Notes:

1. This schedule does not account for adverse weather conditions or major weather events.
2. All construction work requiring outages will be performed during acceptable periods of system load, which most often is the off-peak load season. Line outages will be discussed with the SOC and TCC and the assumption is made that line outages will be executed as planned. However, last minute denial of outages by the SOC/TCC along with resulting schedule delay is possible.
3. Substation construction will be coordinated with the transmission line outages when possible.
4. The above milestone schedule assumes construction resources will be available when required.

Exhibit A13. Permits, Licenses, Regulatory Approvals and Authorization

Permits, licenses, and approvals required to construct the Transmission Owner facilities may include, but are not limited to:

1. MISO questionnaire to be submitted to MISO, TCC, and TOP for review and approval
2. Revised station one line to be submitted to MISO, TCC, and TOP for review and approval
3. Wetland delineation of servitudes and proposed construction access points
4. US Corps of Engineers permitting/approval for wetlands
5. US Corps of Engineers permitting/approval for river/levee permits
6. Environmental sampling and disposal of displaced soils
7. Develop and implement a Storm Water Pollution Prevention Plan (SWPPP)
8. Temporary landowner easements
9. Pipeline Letters of No Objection
10. Access Road Permits for Public Roads

Exhibit A14. Interconnection and Operating Guidelines / Requirement

A14.1 Interconnection

The Interconnection Customer will comply with the Interconnection Guidelines for Transmission Interconnection Producer-Owned Generation Greater Than 20 MW dated March 2007, as amended from time to time and available at: https://www.entergy.com/transmission/requirements ("ENTERGY FACILITY CONNECTION REQUIREMENTS").

A14.2 Power Factor

In accordance with FERC Order No. 827, all newly-interconnected generators (synchronous or non-synchronous) are required to provide dynamic reactive power support within the range of +/- 0.95 power factor at the transmission voltage side of the generator step-up transformer at all dispatch levels. Static reactive power devices can only be used to make up for reactive losses that occur between the inverters and the transmission voltage side of the generator step-up transformer. Any additional reactive power must be supplied by a dynamic reactive power device.

The +/-0.95 power factor requirement corresponds to a triangle-shaped reactive power capability with proportional reduction in reactive power capability at lower active power (i.e. real power) output, as shown in Figure 14.1. However, reactive power capability outside the triangular-shaped requirement yet within the reactive power capability of the plant should be utilized to the greatest extent possible. Inverters shall not have artificial settings imposed to limit reactive power output to the triangular boundary.




Figure A14-1: Inverter-based Resource Plant Reactive Power Capability

A14.3 Primary Frequency Response

In accordance with FERC Order No. 842, the Interconnection Customer shall ensure the primary frequency response capability of its Generating Facility by installing, maintaining, and operating a functioning governor or equivalent controls. The hardware and/or software that provides frequency responsive active power control shall be able to sense changes in system frequency and autonomously adjust the Generating Facility's power output in accordance with the droop and deadband parameters provided by Entergy Transmission and to the extent the Generating Facility has operating capability in the direction needed to correct the frequency deviation. The Interconnection Customer is required to install a governor or equivalent controls with the

capability of operating with a maximum 5% droop and a maximum ± 0.036 Hz deadband. This response must be timely and sustained rather than injected for a short period and then withdrawn. The primary frequency response requirements shall apply to all inverter-based generating resources including energy storage during both charging and discharging states.

The Generator Owner shall provide the status and settings of the governor or equivalent controls to Entergy Transmission upon request. If the Generator Owner needs to operate the Generating Facility with its governor or equivalent controls not in service, the Generator Owner shall immediately notify Entergy Transmission and make reasonable efforts to return its governor or equivalent controls to service as soon as practical.

A14.3.1 Dynamic Frequency Response Requirements for Inverter-Based Resources

For a step change in frequency at the Point of Interconnection (POI), inverter-based resources (IBR) shall have the capability to meet the dynamic characteristics shown in Table A14.1. The active power-frequency response shall be sustained by the resource until such time that the control signals (e.g., Balancing Authority automatic generation control (AGC)) return the generator to a new set point value.

Table A14.1: Dynamic Active Power-Frequency Performance

Parameter	Description	Performance Requirement
Reaction Time	Time between the step change in frequency and the time when the IBR's active power output begins responding to the change.	< 500 ms
Rise Time	Time in which the IBR has reached 90% of the new steady-state (target) active power output command.	< 4 s
Settling Time	Time in which the IBR has entered into, and remains within, the settling band of the new steady-state active power output command.	< 10 s
Overshoot	Percentage of rated active power output that the IBR can exceed while reaching the settling band.	< 5%
Settling Band	Percentage of rated active power output that the resource should settle to within the settling time.	< 2.5%

A14.4 Frequency and Voltage Ride Through

The frequency and voltage ride-through curves described in NERC Reliability Standard PRC-024 and PRC-029 apply to the POI and not the inverter terminals themselves. The Interconnection Customer, in coordination with their inverter manufacturer, shall reflect the ride-through requirements at the POI to the inverter terminals to ensure that the inverters can ride through and continue current injection during disturbances.

The PRC-024 and PRC-029 voltage and frequency ride-through curves specify a "No Trip Zone". Operations outside of the "No Trip Zone" shall not be interpreted as a "Must Trip Zone" but rather a "May Trip Zone".

A14.4.1 Frequency Measurements and Protection

Frequency shall be calculated over a period of time (no less than 6 cycles) and filtered to

take control action on the fundamental frequency component of the calculated signal. Calculated frequency shall not be susceptible to spikes caused by phase jumps on the Bulk Electric System (BES).

Inverter-based resources shall also inhibit frequency tripping during and immediately after low voltage conditions. Inverter-based resources shall ensure that the frequency measurement and protection settings are set such that these resources are able to ride through and not trip for phase jumps or other grid disturbances where calculated frequency is affected but grid frequency is within the ride-through curves of PRC-024 and PRC-029.

A14.4.2 Momentary Cessation

Inverter-based resources interconnected to the transmission system are expected to continue current injection inside the "No Trip" zone of the PRC-024 and PRC-029 frequency and voltage ride through curves. Newly interconnecting inverter-based resources should eliminate the use of momentary cessation unless necessary in areas of the BES with low short circuit strength (SCR < 3).

A14.5 Voltage Control

BES-connected resources are required to operate in automatic voltage control mode as per NERC Reliability Standard VAR-002. All resources, including inverter-based resources, shall operate in a closed-loop, automatic voltage control mode to maintain voltage at the POI to within the specified voltage schedule tolerance band provided by the Transmission Operator as per NERC Reliability Standard VAR-002.

A14.5.1 Small Disturbance Reactive Power-Voltage Control Performance

Individual inverters shall always operate in automatic voltage control to support BES voltage schedules, post-contingency voltage recovery, and voltage stability. Each inverter shall continually respond to all changes in terminal voltage in a closed loop fashion to maintain the set point voltage level.

Inverter-based resources shall have the capability to meet the performance characteristics shown in Table A14.2. These characteristics are specified for the response of reactive power of the overall closed-loop response of the inverter-based resource plant.

Table A14.2: Dynamic Reactive Power-Voltage Performance for Small Disturbance

Parameter	Description	Performance Requirement
Reaction Time	Time between the step change in voltage and when the IBR's reactive power output begins responding to the change. Shall not include any intentional time delay.	< 500 ms
Rise Time	Time between a step change in control signal input (reference voltage) and when the reactive power output changes by 90% of its final value.	< 2-30 s
Overshoot	Percentage of rated reactive power output that the IBR can exceed while reaching the settling band.	< 5%

A14.5.2 Large Disturbance Reactive Power-Voltage Performance

The reactive power-voltage control shall be stable over all expected operating and grid conditions and be tuned to provide this stable response. The dynamic response of inverter-based resources shall be programmable by the Interconnection Customer (in coordination with the inverter manufacturer) to enable changes based on changing grid conditions once installed in the field.

Inverter response to fault events on the BES shall abide by the following principles:

- **Fault Inception**: During the inception of a fault, priority shall be given to delivering as much current to the system as quickly as possible to support protective relay systems to detect and clear the fault.
- **On-Fault Current Injection**: For the remaining on-fault period after the first couple cycles up to fault clearing, priority shall be given to accurately detecting and controlling the type of current needed based on terminal conditions and providing a combination of active and reactive current as necessary.
- **Post Fault Current Injection**: Priority shall be given to ensuring sufficient local voltage support before attempting to maintain or return to pre-disturbance active current injection.
- **Post-Fault Voltage Overshoot Mitigation**: Inverter reactive current response shall not exacerbate transient overvoltage conditions on the BES.

Inverters shall be designed to have the capability to meet the performance specifications shown in Table A14.3.

Table A14.3: Dynamic Reactive Power-Voltage Performance for Large Disturbance

Parameter	Description	Performance Requirement
Reaction Time	Time between the step change in voltage and when the IBR's reactive power output begins responding to the change.	< 200 ms
Rise Time	Time between a step change in control signal input (reference voltage) and when the reactive power output changes by 90% of its final value.	< 30 s

A14.6 Transmission System Studies

NERC Reliability Standard FAC-002 requires each Transmission Planner to assess the reliability impact of interconnecting new generation as well as any material modifications to existing interconnections of generation. Steady-state, dynamic, and short circuit studies are performed as part of the MISO Definitive Planning Phase (DPP) process. However, there are other considerations that may need to be assessed based on the interconnection location, IBR control functionality, and nearby resources (SVCs, series capacitors, synchronous generation, IBR generation, etc.).

A14.6.1 Controls Interactions and Controls Instability

Inter-plant coordination is increasingly important as the penetration of inverter-based resources continues to grow. When multiple resources attempt to control the same location on the BES (e.g., controlling voltage at the same POI or close proximity), their control systems need to be coordinated with one another to avoid reactive power output imbalance,

circular reactive power flows, controls overshoot, voltage control hunting, and unstable oscillations. Coordination issues shall be evaluated prior to the resource connecting to the BES. Prior to performing this analysis, the consultant selected by the Interconnection Customer shall be approved by Entergy Transmission. This analysis shall be performed during the plant design phase prior to plant backfeed. The results of the analysis shall be provided to Entergy Transmission with the cost of the study borne by the Interconnection Customer.

A14.6.2 Weak Grid Analysis (SCR < 3)

The changing nature of the electric grid and the growing complexity of IBR control systems can impact the performance of inverter-based resources and shall be assessed to ensure reliable operation of the BES. One of these changes is the continued reduction of short circuit levels in areas of high penetration of inverter-based resources. For interconnections with a short circuit ratio < 3, an EMTP study is required to assess potential SSR/SSCI and the proposed control design. Prior to performing this analysis, the consultant selected by the Interconnection Customer shall be approved by Entergy Transmission. This analysis shall be performed during the plant design phase prior to plant backfeed. The results of the analysis shall be provided to Entergy Transmission with the cost of the study borne by the Interconnection Customer.

A14.6.3 Power Quality

A14.6.3.1 Harmonic Distortion

Due to converter characteristics associated with IBR generation, there is an increased possibility of generating harmonic currents; therefore, Entergy shall install power quality monitoring devices at the POI. Entergy will install CCVTs with PQ sensors or Harmonic Measuring Devices (HMDs) to enhance accuracy of the Power Quality measurements. The harmonic current distortion at the POI shall be monitored for compliance with the IEEE 2800-2022 standard with the proposed generation. The harmonic distortion voltages at the POI shall also be monitored for compliance with the IEEE 519 standard with the proposed generation. Entergy will use IEEE 519, Table 1 to evaluate compliance with the voltage distortion limits. The table below is excerpted from the IEEE 519 standard for the transmission supply voltage levels. Entergy's evaluation of compliance with harmonic voltage distortion limits at the POI considers both the proposed generation and background harmonics present at the POI.

Table A14.4: Weekly 95th percentile (10 mins) Voltage Distortion Limits

Bus Voltage, V, at the POI	Individual harmonic (%) h ≤ 50	Total harmonic distortion THD (%)
1 kV < V ≤ 69 kV	3.0	5.0
69 kV < V ≤ 161 kV	1.5	2.5
161 kV < V	1.0	1.5[a]

[a] High-voltage systems are allowed to have up to 2.0% THD where the cause is an HVDC terminal whose effects are found to be attenuated at points in the network where future users may be connected.

If the PQ meter at the POI records harmonic voltage distortions that exceed the limits of the IEEE 519-2022, and if such conditions result in customer complaints or Entergy equipment performance issues attributable to the interconnection customer generator, Entergy may impose operating restrictions on the IBR until the issue is resolved. In the event that further studies are required, the costs to conduct such studies will be the responsibility of the Interconnection Customer.

A14.6.3.2 Flicker

Entergy has adopted subclause 8.1.3 (Flicker), including Table 16, of the IEEE Standard 2800-2022, without modification. The IBR plant contribution to the flicker at the POI shall not exceed EPst and EPlt of 0.35 and 0.25 respectively based on the 95th percentile value for a one-week measurements period. Assessment and measurement methods for flicker are defined in IEEE Std 1453 (subclause 6.3) and IEC 61000-3-7 (subclause 6.3). Entergy will monitor the flicker at the POI and work with the customer to take corrective action when this limit is exceeded.

A14.6.3.3 Rapid Voltage Changes (RVC)

The IBR plant shall not cause the rapid voltage changes at the POI to exceed 2.5% of nominal voltage.

This RVC limit shall apply to sudden changes due to frequent energization of transformers, frequent switching of capacitors, or from abrupt output variations caused by IBR plant misoperation. These RVC limits shall not apply to infrequent events such as switching, unplanned tripping, or transformer energization related to commissioning, fault restoration, or maintenance.

A14.7 Modeling

The steady-state and dynamic models used to represent inverter-based resources shall accurately capture the small and large disturbance aspects of the resource. The following modeling information shall be provided to Entergy Transmission within 60 calendar days prior to plant backfeed.

- Steady state model including collector system equivalent as recommended by NREL, collector station transformer, padmount transformer, and transmission gen-tie line.
- Dynamic models using the 2nd Generation Renewable Energy Models [PSS/E Models REPC, REGC, and REEC].
- Frequency and voltage ride through characteristics and corresponding dynamic models [PSS/E VTGTPA, FRQTPA]. The low-voltage ride-through capability of the PV plant shall be demonstrated either through detailed modeling of the PV controls or by field/ factory tests.
- Inverter PQ curve.
- CAPE short circuit model using a Voltage Controlled Current Source Model or short circuit modeling documentation from the inverter manufacturer.
- PSCAD model of the IBR plant.

Model verification shall be performed in compliance with NERC Reliability Standards MOD-026 and MOD-027 and transmitted to the Transmission Planner within 365 calendar days after the commissioning date.

A14.8 Inverter Negative Sequence Requirements

For unbalanced faults, in addition to increased positive sequence reactive current, the IBR unit shall inject negative sequence:

- Dependent on the IBR unit terminal (POI) negative sequence voltage, and
- Leads the IBR unit terminal (POI) negative sequence voltage by an allowable range as specified below. The allowable range is provided in lieu of tolerance band specified in the definition of a settling time.
    - 90-100 degrees, for full converter-based IBR Units
    - 90-150 degrees, for type III WTGs

A14.9 Disturbance Monitoring

The IBR owner is required to comply with the disturbance monitoring and reporting requirements in PRC-028-1.

A14.10 Communication Paths

The Interconnection Customer shall coordinate with the Transmission Owner to ensure that Transmission Owner's microwave paths are not obstructed by wind turbines, as applicable, associated with the Generating Facility. Obstruction shall be defined as any encroachment on the 3D cylindrical ellipse, as determined by the Worst-Case Fresnel Zone calculation, that would interfere with communication signals propagating between the transmitter and receiver. At a minimum, this coordination shall consist of one of the following:

The Interconnection Customer shall provide the Transmission Owner with geographical coordinates, along with tower heights and blade diameters, of each proposed wind turbine associated with the Generating Facility for review against the Transmission Owner's Licensed Microwave Paths. The Transmission Owner may elect to hire an RF Consultant to determine whether the proposed turbine locations will obstruct its Licensed Microwave Paths Costs, such a study shall be allocated to the Interconnection Customer and shall not be subject to reimbursement.

The Interconnection Customer shall provide the Transmission Owner with a microwave path study, including evaluation of the Transmission Owner's Licensed Microwave Paths. The Transmission Owner will review and approve or deny the completed study within 10 business days after the study is submitted, where the approval of the Transmission Owner is not to be unreasonably withheld or denied. The Interconnection Customer shall gain approval of the submitted study prior to constructing the Generating Facility.

A14.11 Generic Requirements for Fiber Optic Construction in Support of MISO Generation Projects

- All fiber shall be single mode, and its performance shall meet or exceed ITU-TG.657A1 specifications for Single-mode Optical Fiber, Dispersion Unshifted, with Low Water Peak.

- Minimum per-cable fiber count shall be forty-eight (48) strands.
    - To facilitate inter-company splicing, this count shall be incorporated into the fiber optic cable in four (4) bundles/tubes of twelve (12) fibers each, for a total of 48 fibers.
    - Higher count cables may be coordinated with Entergy.
- Fiber cable design shall be appropriate for the intended purpose (OPGW versus ADSS versus all-dielectric duct).
- All fiber optic joinery shall be accomplished via fusion splicing. Minimum standards for finished fusion splice performance are found in Table 1, below.
    - Mechanical fiber splicing is not permitted.
    - All fibers in the cable shall be spliced through at all intermediate splice points.
- Fiber termination connector type shall be SC ultra-polished physical contact or LC ultra-polished physical contact.
    - Mechanical fiber terminations are not permitted.
    - Connector Pigtails shall be attached to entrance cable via fusion splicing.
    - All fibers in the cable shall be terminated.
- At the designated meet point(s), Entergy will provide an all-dielectric fiber optic cable stub of sufficient length, to which the customer shall splice their fiber optic cable in a customer-provided splice enclosure appropriate to the cable and construction type.
    - This interface will be the point of demarcation for ownership and operational responsibility of the new fiber optic cable construction.
    - All fibers in the cable shall be spliced through at the point of demarcation.
- Entergy reserves the right to inspect customer-owned fiber optic facilities for compliance with these minimum requirements to ensure reliable operation of inter-company relay and communication systems.

- T**able A14.5: Summarized Fiber Optic Splice Performance Grid**

Summarized Fiber Optic Splice Performance Grid (all measurements to be recorded at 1550 nm)		
Parameter	**Measured Value**	**Action Required**
Splice Loss as estimated by Fusion Splicer:	loss ≤0.05 dB*loss ≤0.05 dB*	TARGET
	0.05 dB<loss<0.10 dB*0.05 dB<loss<0.10 dB*	acceptable
	loss ≥0.10 dB*loss ≥0.10 dB*	Break and re-splice up to three times; if no improvement, note the splice location and the fiber number for communication to Entergy.
Splice Loss as measured by OTDR:	loss ≤0.05 dB*loss ≤0.05 dB*	TARGET
	0.05 dB<loss<0.10 dB*0.05 dB<loss<0.10 dB*	acceptable
	loss ≥0.10 dB*loss ≥0.10 dB*	Note the splice location and fiber number for communication to Entergy.

Appendix B to GIA
Milestones

1. Selected Option pursuant to Article 5.1: Interconnection Customer selects the Standard Option as described in Article 5.1.1. Articles 5.1.2, 5.1.3, and 5.1.4 shall not apply to this GIA.

2. Milestones: The description and date entries listed in the following tables are provided solely for the convenience of the Parties in establishing their applicable Milestones consistent with the provisions of this GIA and the GIP.

A. Interconnection Customer Milestones

No.	Description	Date
1a.	Provide initial payment to Transmission Owner (GIA 11.5) in form of security for $ 13,980,000 (100% of total cost of Transmission Owner Interconnection Facilities and Network Upgrades). Coordinate Initial Payment confirmation with Transmission Owner and notify Transmission Provider via email notice to gifinance@misoenergy.org.	Because Interconnection Customer and Transmission Owner are the same Party, no security is being transferred . -Completed.
1b.	Provide security, *i.e.*, a guarantee, surety bond, letter of credit or other reasonably acceptable form of security to Transmission Owner (GIA 11.6).	Not Applicable.
1c.	Enter into a Facilities Service Agreement ("FSA") as may be applicable, with Transmission Owner for the Network Upgrades associated with this GIA.	Not Applicable.
1d.	Enter into amendment of this GIA, if required, for Interconnection Requests that did not elect optional negotiation period adjustment for Interconnection Facilities Study pursuant to GIA Section 11.3.1.	Within 90 days of the posting of the final Interconnection Facilities report.
1e.	Enter into SPP JTIQ Service Agreement (if included in JTIQ Participation Group) pursuant to GIP Section 11.1.	Not Applicable.
1f.	Enter into any agreement required by an Affected System for the study, construction, or funding of a network upgrade to mitigate impacts (for Interconnection Requests processed through ERAS) pursuant to GIP Section 3.5.2.	Within 15 Calendar Days after tender.
1g.	Demonstrate 100% Site Control (if not provided earlier due to qualifying regulatory limitations) or the GIA may be terminated per Article 2 of this GIA and the Interconnection Customer may be subject to Withdrawal Penalties per Section 7.6.2.1.1 of the GIP (Calculation of the Automatic Withdrawal Penalty).	Within 180 Calendar Days of the Effective Date.
2.	Provide Certificate of Insurance (GIA 18.4.9).	The earlier of the construction work

		commencement date or the milestone date; thereafter, within 90 Calendar Days of end of fiscal year or insurance renewal date.
3.	Provide evidence of one or more of the following milestones being achieved: (1) execution of contract for (a) fuel supply or transport; (b) cooling water supply; (c) engineering procurement of major equipment or construction; (d) execution of a contract for the sale of electric energy or capacity from the Generating Facility, or a statement signed by an officer or authorized agent of Interconnection Customer attesting that the Generating Facility is included in an applicable state resource adequacy plan; or other information that Transmission Provider deems to be reasonable evidence that the Generating Facility will qualify as a designated network resource; or (2) documentation of application for state or local air, water, land, or federal nuclear or hydroelectric permits and that the application is proceeding per regulations (GIP 11.3).	Within 180 Calendar Days of Effective Date.
4.	Cash Payment and security obligations are subject to quarterly review and update by Transmission Owner; who will take into account actual costs, updated cost projections and schedule revisions and make changes to the Interconnection Customer's Cash Payments and security obligations as required.	Because Interconnection Customer and Transmission Owner are the same Party, no security or cash is being provided.
5.	Invoice Transmission Owner for the estimated amount to be expended by the Interconnection Customer to construct any Stand Alone Network Upgrades for which the Interconnection Customer has exercised its Option to Build if the Transmission Owner has elected to Self Fund (GIA 5.2.13).	Not Applicable.
6.	Pre-construction meeting.	As may be agreed to by the Parties.
7.	Provide initial design and specifications for Interconnection Customer's Interconnection Facilities to Transmission Owner and Transmission Provider for comment (GIA 5.10.1).	180 Calendar Days prior to initial synchronization date.
8.	Provide final design and specifications for Interconnection Customer's Interconnection Facilities to Transmission Owner and Transmission Provider for comment (GIA 5.10.1).	90 Calendar Days prior to initial synchronization date.
9.	Deliver to Transmission Owner and Transmission Provider "as-built" drawings, information and documents	Within 120 Calendar Days of Commercial Operation

	regarding Interconnection Customer's Interconnection Facilities (GIA 5.10.3).	Date.
10.	Provide Transmission Owner final cost invoices to construct Stand Alone Network Upgrades for which the Interconnection Customer has exercised its Option to Build if the Transmission Owner has elected to Self Fund (GIA 5.2.13).	Not Applicable.
11.	Notify Transmission Provider and Transmission Owner in writing of Local Balancing Authority where Generating Facility is located (GIA 9.2).	Nine months prior to Initial Synchronization Date.
12.	Pre-energization meeting.	As may be agreed to by the Parties.
13.	Initial Synchronization Date.	08/05/2028
14.	Commercial Operation Date.	08/06/2028
15.	Interconnection Customer shall provide the Parties with notice on the status of the Generating Facility, including COD, under Article 15 of this GIA and shall also send such notice by email to ResourceIntegration@misoenergy.org. Notification shall include Interconnection Customer's name, and as applicable Market Participant(s) name(s), and project number.	6 months prior to Initial Synchronization Date.
16.	Interconnection Customer shall provide notice to the Parties of a test plan in advance of conducting tests for the Generating Facility. The notice shall be in the form below and should be provided under Article 15 of this GIA, and a copy of such notice should be emailed to ResourceIntegration@misoenergy.org**.**	5 Business Days prior to testing.
17.	In the event the Interconnection Customer makes any modifications to the design of the site layouts or interconnection facility routes after execution of this GIA, Interconnection Customer shall notify the Parties of such changes immediately upon identifying the need for such changes. After providing such notification, the Interconnection Customer shall provide to Transmission Provider evidence of continued Site Control for land sufficient to accommodate the changes in site layouts and/or interconnection facility routes (GIP 7.2.2).	90 Calendar Days after Interconnection Customer provides notice to Parties.

18.	Provide TO a PSCAD Model and a PSCAD Model Parameter Verification Report. This report shall provide evidence that tunable parameters match what is implemented in the field. Evidence can take the form of screenshots, nameplate photographs, signed manufacturer commissioning reports, parameter dump file, etc. All of these must be cross referenced with the settings in the PSCAD model. Field tunable parameters should be identified by the manufacturer but should include at a minimum, protection settings, ride through settings and any tunable control gains. Evidence must also be provided that proves the PSCAD PPC model has all communication delays, any sample and hold type outputs and all gains that are in the field. This must be confirmed with voltage step tests in the field and in PSCAD. The PPC must be tuned to work over a range of expected SCRs.	30 days prior to Commercial Operation Date.

B. Transmission Owner Milestones

No.	Description	Date
0.	Transmission Owner to enter Network Upgrade information into Transmission Provider's MTEP database and model on demand.	10 Business Days after Effective Date.
1.	Provide Certificate of Insurance (GIA 18.4.9).	The earlier of the construction work commencement date or the milestone date; within 90 Calendar Days of end of fiscal year or insurance renewal date.
2.	• Commence design of Interconnection Facilities (GIA 5.5 et seq.). • Commence equipment procurement.	As agreed to by the Parties (after completion of Interconnection Facilities Study, receipt of written authorization from Interconnection Customer and Interconnection Customer's deposit of security.
3.	Commence construction of Interconnection Facilities (GIA 5.6 et seq.).	As agreed to by the Parties (after receiving approval of

		Governmental Authority, receipt of written authorization and security from Interconnection Customer).
4.	Comment on Interconnection Customer's final design and specifications.	Within 30 Calendar Days of Interconnection Customer's submission of final design and specifications.
5.	Deliver to Interconnection Customer and Transmission Provider "as-built" drawings, information and documents regarding Transmission Owner's Interconnection Facilities (GIA 5.11).	Within 120 Calendar Days of Commercial Operation Date.
6.	Provide payment for invoiced estimated costs to construct for which the Interconnection Customer has exercised its Option to Build if the Transmission Owner has elected to Self Fund (GIA 5.2.13).	Not Applicable.
7.	Provide Interconnection Customer final cost invoices (GIA 12.2 *et seq.*).	Within (6) six months of completion.
8.	Refund overpayment of estimated costs (GIA 12.2).	Refunds within 30 Calendar Days after final invoice.
9.	In-Service Date/Backfeed Date.	08/04/2028

C. Affected System Owner Milestones

No.	Description	Date
1	Affected Systems Studies have not concluded as of the date of this EGIA. Interconnection Customer is responsible for executing and fulfilling the obligations of any agreements for the study, construction, or funding of Affected System network upgrades identified by the Affected System after execution of this GIA.	Execute agreements tendered by the affected system within fifteen (15) Calendar Days of tender.

Appendix B-1 to GIA
Pre-Certification Generation Test Notification Form

The following form would need to be submitted to MISO Real Time Operations at least five (5) Business Days prior to the first date of testing.

Project Number:

Project Name:

Point of Interconnection:

Dispatcher Contact Information:

Date	Start Time (in EST)	End Time (in EST)	Expected MW Output	Expected MVAR Output (Only needed if beyond normal power factor)

Appendix C to GIA
Interconnection Details

This Appendix C is a part of this GIA among Interconnection Customer, Transmission Owner and Transmission Provider.

1. The unique requirements of each generation interconnection will dictate the establishment of mutually agreeable Interconnection and/or Operating Guidelines that further define the requirements of this GIA. The Interconnection and/or Operating Guidelines applicable to this GIA consist of the following information. Additional detail may be provided through attachment to this Appendix C or through electronic means via the web address specified.

    (a) System Protection Facilities;
    (b) Communication requirements;
    (c) Metering requirements;
    (d) Grounding requirements;
    (e) Transmission Line and Substation Connection configurations;
    (f) Unit Stability requirements;
    (g) Equipment ratings;
    (h) Short Circuit requirements;
    (i) Synchronizing requirements;
    (j) Generation and Operation Control requirements;
    (k) Data provisions;
    (l) Energization inspection and testing requirements; and
    (m) Control equipment, if any.

    Entergy Facility Connection Requirements website:
    http://www.entergy.com/energydelivery/facility_requirements.aspx

    Reference material regarding the Entergy Facility Connection Requirements can be found on the two (2) links below located on the above mentioned web address.

    (1) Entergy Facilities Connection Requirements Document, March 2007; and
    (2) Entergy Facilities Connection Spreadsheet, October 2008.

    In the event that the Interconnection and/or Operating Guidelines conflict with this GIA, this GIA will govern.

2. Information required pursuant to Section 8.4 for Variable Energy Resource Generating Facilities: _____. Not Applicable

Appendix D to GIA
Security Arrangements Details

Infrastructure security of Transmission or Distribution System equipment and operations, as applicable, and control hardware and software is essential to ensure day-to-day Transmission and Distribution System reliability and operational security. The Commission will expect all Transmission Providers, market participants, and Interconnection Customers interconnected to the Transmission or Distribution System, as applicable, to comply with the recommendations provided by Governmental Authorities regarding Critical Energy Infrastructure Information ("CEII") as that term is defined in 18 C.F.R. Section 388.113(c) and best practice recommendations from the electric reliability authority. All public utilities will be expected to meet basic standards for system infrastructure and operational security, including physical, operational, and cyber-security practices.

Appendix E to GIA
Commercial Operation Date

This Appendix E is a part of this GIA between Transmission Provider, Transmission Owner and Interconnection Customer.

[Date]

Midcontinent Independent System Operator, Inc.
Attn: Director, Transmission Access Planning
720 City Center Drive
Carmel, IN 46032

Re: _____ Generating Facility

Dear _____:

On **[Date] [Interconnection Customer]** has completed Trial Operation of Unit No. ___. This letter confirms that **[Interconnection Customer]** commenced commercial operation of Unit No. ___ at the Generating Facility, effective as of **[Date plus one Calendar Day]**.

Thank you.

[Signature]

[Interconnection Customer Representative]

cc: Transmission Owner

Appendix F to GIA
Addresses for Delivery of Notices and Billings

Notices:

Transmission Provider:

MISO
Attn: Director, Transmission Access Planning
720 City Center Drive
Carmel, IN 46032

Transmission Owner:

Entergy Services, LLC
Attn: Sr Manager, Interconnection Planning and Customer Service
9585 Pecue Blvd
Baton Rouge, LA 70818

Interconnection Customer:

Entergy Services, LLC
Attn: Power Development/Jonathan Alvis
2107 Research Forest Drive
The Woodlands, TX 77380

Billings and Payments:

Transmission Provider:

MISO
Attn: Director, Transmission Access Planning
720 City Center Drive
Carmel, IN 46032

Transmission Owner:

Entergy Louisiana, LLC
P.O. Box 679505
Dallas, TX 75267-9505

Interconnection Customer:

Entergy Louisiana, LLC
Attn: Miscellaneous Accounts Receivable
P.O. Box 679505
Dallas, TX 75267-9505

Alternative Forms of Delivery of Notices (telephone, facsimile or email):

Transmission Provider:

Phone: (317) 249-5700
Email: misotap@misoenergy.org or
MISOTransmissionAccessPlanning@misoenergy.org

Transmission Owner:

Entergy Services, LLC
Voice telephone: (504)-576-7940
Email address: GIA@entergy.com

Interconnection Customer:

Entergy Louisiana, LLC
Voice telephone: (281) 719-7109
Email: jalvis@entergy.com

Entergy Louisiana, LLC
Attn: Sr Manager, Resource Planning
4809 Jefferson Highway
Jefferson LA 70121

Appendix G to GIA
Interconnection Requirements for Inverter-Based Resource Plants

Appendix G sets forth requirements and provisions specific to inverter-based resource (IBR) plants. Transmission Owner Local Planning Criteria for IBR performance may differ from Appendix G requirements. In such cases, Transmission Owner Local Planning Criteria shall supersede the Appendix G requirements and be documented in Appendix C of this GIA[1]. All other requirements of this GIA also apply to IBR plant interconnections. *IBR plants* shall meet both Applicable Reliability Standards and Appendix G requirements. Battery energy storage systems required to furnish grid-forming controls shall be exempt from specific IEEE 2800 requirements as outlined in the BPM for Generator Interconnection. Italicized terms indicate IEEE 2800-2022 defined terms[2]. IEEE 2800-2022's definitions will govern these italicized terms unless otherwise defined herein.

A. General

The *IBR plant* shall adhere to IEEE 2800-2022 Clause 4 requirements, except for subclauses 4.1 (introduction), 4.5 (operational measurement and communication capability), 4.6 (control capability requirements), 4.8 (isolation devices), 4.9 (inadvertent energization of TS), 4.11 (interconnection integrity), and 4.12 (integration with TS grounding).

Within the adopted IEEE 2800-2022 Subclauses, the following requirements shall be incorporated as Transmission Provider and Transmission Owner[3] specification options noted in IEEE 2800-2022.

- Subclause 4.2.1: The *reference point of applicability* (RPA) shall be at the *point of measurement* (POM) bus with the exception of requirements specified in Clauses 7.2.2.3.4 and 7.2.2.3.5 of the standard to have the RPA at the *point of connection* (POC).

- Subclause 4.3: The Transmission Owner shall specify the nominal voltage and frequency at the RPA in Appendix C of this GIA.

- Subclause 4.10.2: The *enter service* criteria shall use the default values for *applicable voltages* and *applicable frequency* specified in the table below unless otherwise specified in Appendix C of this GIA[4].

---

[1] IEEE 2800-2022 points to "weak grid" issues requiring exceptions to default values and ranges of available settings for various types of performance. IEEE 2800-2022 Annex C.2 contains discussion on characterizing weak grid areas.

[2] "IEEE Standard for Interconnection and Interoperability of Inverter-Based Resources (IBRs) Interconnecting with Associated Transmission Electric Power Systems," in IEEE Std 2800-2022 , vol., no., pp.1-180, 22 April 2022, doi: 10.1109/IEEESTD.2022.9762253.

[3] For the purpose of this GIA, the IEEE 2800 term of *TS operator* is synonymous with Transmission Owner and the IEEE 2800 term of *TS owner* is synonymous with Transmission Planner or Transmission Owner, as applicable.

[4] MISO default values may be modified within the IEEE 2800 range of allowable settings by Transmission Owner Local Planning Criteria.

Enter service criteria	Default setting
Applicable voltage, minimum value	0.9 p.u.
Applicable voltage, maximum value	1.05 p.u.
Applicable frequency, minimum value	58.8 Hz
Applicable frequency, maximum value	60.12 Hz.

- Subclause 4.10.3: The performance during *enter service* shall use the default values specified below unless otherwise specified in Appendix C of this GIA.
    - The minimum intentional delay performance, as defined in Subclause 4.10.3, b), shall be 0 seconds.
    - The duration of the *enter service* period, as defined in Subclause 4.10.3, c), shall be 300 seconds.

B. Response to Abnormal Conditions

The *IBR plant* shall adhere to IEEE 2800-2022 Clause 7 requirements, except for subclauses 7.2.1 (voltage protection) and 7.3.1 (mandatory frequency tripping). Where Applicable Reliability Standards require more stringent ride-through requirements compared to IEEE 2800-2022 Clause 7 requirements, those standards shall take precedence[5].

Within the adopted IEEE 2800-2022 Subclauses, the following requirements shall be incorporated as the Transmission Provider and Transmission Owner decision points[6] noted in IEEE 2800-2022.

- Subclause 7.2.2.1: The Transmission Owner shall specify the nominal voltage for use by this clause. Nominal voltages may include nominal transmission system voltages that are different from standard ANSI C84.1-2016 voltages.
- Subclause 7.2.2.2: If the *IBR plant* cannot deliver both active and reactive power due to its current limit (or apparent power limit), when the *applicable voltage* is below 95%, then preference shall be given to reactive power while minimizing any reductions in active power.
- Subclause 7.2.2.3: The *IBR plant* shall give preference to reactive power unless otherwise specified in Appendix C of this GIA. In addition, the *IBR plant* shall minimize reductions in active power while carrying out the reactive current priority mode response.

[5] More stringent ride-through requirements include, but are not limited to, expanded voltage and frequency conditions or extended cumulative times under which *IBR plants* must ride-through.

[6] Decision points refer to language in the IEEE 2800-2022 standard that leaves default values, application of requirements, and other details open for the *TS Owner* or *TS Operator* to define.

- Subclause 7.2.2.3.4: The Interconnection Customer shall submit the *IBR plant* controls default relationship between the magnitude of incremental positive and negative sequence reactive currents. The Transmission Provider and Transmission Owner, through this agreement, may specify a required *IBR plant* response relationship between the incremental positive and negative sequence reactive currents.

C. Reactive Power

The *IBR plant* shall adhere to IEEE 2800-2022 Clause 5 requirements.

Within the adopted IEEE 2800-2022 Subclauses, the following requirements shall be incorporated as the Transmission Provider and Transmission Owner decision points noted in IEEE 2800-2022.

- Subclause 5.1: The *IBR plant* shall have the reactive power capabilities outlined in this clause. Consistent with section 9.6.1 of this GIA, an *IBR plant* shall maintain a power factor within the range of 0.95 leading to 0.95 lagging, unless Transmission Provider has established different requirements that apply to all Generating Facilities in the Local Balancing Authority on a comparable basis, measured at the high side of the generator substation.

- Subclause 5.2.2: The voltage control dynamic performance requirements in Table 5 shall apply when the system short-circuit strength at the RPA is equal to or above the minimum short-circuit strength identified by the Transmission Provider or Transmission Owner.

- Subclause 5.2.2: The *reaction time*, as defined in Subclause 5.2.2 Table 5, shall be 250 milliseconds or less.

- Subclause 5.2.2: The maximum *step response time*, as defined in Subclause 5.2.2 Table 5, shall be 30 seconds.

- Subclause 5.2.3: The power factor control mode shall appropriately operate at all active power levels from the Inverter Based Resource Continuous Rating ("ICR") down to, but not including, zero.

D. Primary Frequency Response

The *IBR plant* shall adhere to IEEE 2800-2022 Clause 6 requirements, except for Subclause 6.2 (fast frequency response).

Within the adopted IEEE 2800-2022 Subclauses, the following requirements shall be incorporated as the Transmission Provider and Transmission Owner decision points noted in IEEE 2800-2022.

- Subclause 6.1.1: The use of primary frequency response capabilities shall be required for all *IBR plants.*
- Subclause 6.1.1: Frequency droop shall be based on the difference between nameplate capacity and zero output such that the slopes of the droop curves are always constant.
- Subclause 6.1.2: The *settling band* default value in Table 8 shall be based on the maximum of 2.5% of change or 0.5% of nameplate capacity.

The exceptions to primary frequency response requirements provided to electric storage resources in Article 9.6.4.4 of this GIA shall still apply.

TABLE 2. SUMMARY OF ADOPTION TREATMENT OF IEEE 2800-2022 SUBCLAUSES

IEEE 2800-2022 Subclause	Required by Appendix G for DPP-2022 and later	Required by Appendix G for DPP-2023 and later	Exception
4.1 Introduction			**X**
4.2 Reference Point of Applicability	**X**		
4.3 Applicable Voltages and Frequencies	**X**		
4.4 Measurement Accuracy	**X**		
4.5 Operational Measurement and Communication Capability			**X**
4.6 Control Capability			**X**
4.7 Prioritization of IBR Responses	**X**		
4.8 Isolation Devices			**X**
4.9 Inadvertent Energization of TS			**X**
4.10 Enter Service	**X**		
4.11 Interconnection Integrity			**X**
4.12 Integration with TS grounding			**X**
5.1 Reactive Power Capability		**X**	
5.2 Voltage and Reactive Power Modes		**X**	
6.1 Primary Frequency Response		**X**	
6.2 Fast Frequency Response			**X**
7.1 Introduction	**X**		
7.2.1 Voltage protection			**X**
7.2.2.1 Voltage disturbance ride-through: General	**X**		
7.2.2.2 Voltage disturbances within continuous operation	**X**		

7.2.2.3 Low- and high-voltage ride-through	**X**		
7.2.2.4 Consecutive voltage deviations ride-through		**X**	
7.2.2.5 Dynamic voltage support	**X**		
7.2.2.6 Restore output after voltage ride-through	**X**		
7.2.3 Transient overvoltage	**X**		
7.3.1 Mandatory frequency tripping			**X**
7.3.2 Frequency disturbance ride-through	**X**		
7.4 Return to service	**X**		

E. Supervisory Control and Data Acquisition (SCADA) Capability

The *IBR plant* shall provide SCADA capability to transmit data and receive instructions from Transmission Provider to protect system reliability. Transmission Provider and Interconnection Customer shall determine what SCADA information is essential for the proposed *IBR plant*, taking into account the size of the plant and its characteristics, location, and importance in maintaining generation resource adequacy and transmission system reliability in its area.

F. Disturbance Monitoring and Reporting Requirements

IBR plants with generating capacities of more than 20 MW must monitor and record data for all frequency ride-through events, transient low-voltage disturbances that initiated reactive current injection, reactive current injection or momentary cessation for transient high-voltage disturbances, and inverter trips. Dynamic Disturbance Recording ("DDR") data must be recorded continuously. The data may be recorded and stored in a central plant control system. The following data must be recorded:

Plant Level

(1) Plant three-phase voltage, current and power factor

(2) Status of ancillary reactive devices

(3) Status of all plant circuit breakers

(4) Status of plant controller

(5) Plant control set points

(6) Status of main plant transformer no load taps

(7) Status of main plant transformer tap changer (if applicable)

(8) Protective relay trips (relay target data)

Inverter Level Data

(1) Frequency, current, and voltage during frequency ride-through events

(2) Voltage and current during momentary cessation for transient high-voltage events (when used)

(3) Voltage and current during reactive current injection for transient low or high-voltage events

(4) Inverter alarm and fault codes

(5) DC current

(6) DC voltage

DDR Data – Plant Level

(1) One phase-to-neutral or positive sequence voltage on high-side of the main power transformer(s)

(2) Positive sequence current or phase current for the same phase as (1)

(3) Real and reactive power flows expressed on a three-phase basis corresponding to each main power transformer(s) where current measurements are required

(4) Frequency of any one of the voltages in (1)

The data must be time synchronized to a one millisecond level of resolution. All data except DDR data must be sampled at least every 10 milliseconds. DDR data must have an input sampling rate of at least 960 samples per second and an output recording rate of electrical quantities of at least 60 times per second.

The *IBR plant* shall store this data for a minimum of 60 calendar days. The *IBR plant*, upon request from MISO or the transmission owner, shall make this data available within 10 calendar days of the request.

Phasor measurement unit ("PMU") capabilities shall be used to facilitate the DDR data.

G. Applicability

IBR plants that are, or have been, interconnected to the network at the effective date of the Appendix G abnormal voltage ride-through standard are exempt from meeting the Appendix G abnormal voltage ride-through standard for the remaining life of the existing generation

equipment. Except for *IBR plants* actively undergoing a Generating Facility Replacement at the effective date of this GIA that have equipment on order where the OEM has documented performance that differs from what is required in this GIA, all individual IBR units that are replaced are required to meet the Appendix G performance requirements.

The IEEE 2800-2022 requirements cited in Section A (IEEE 2800-2022 Clause 4) and Section B (IEEE 2800-2022 Clause 7, except Subclause 7.2.2.4) of Appendix G shall apply to *IBR plants* in the DPP-2022-Cycle and beyond. For the DPP-2022-Cycle, Interconnection Customers may request exceptions confined to these sections only if specific limitations or uncertainties of equipment or plant capabilities prevent implementation of these requirements. GIAs signed or amended with inverter changes on or after January 1, 2025, are not eligible for requirement exceptions. Further, the process for establishing exceptions for these requirements shall not apply beyond the DPP-2022-Cycle.

The IEEE 2800-2022 requirements cited in Section B (IEEE 2800-2022 Subclause 7.2.2.4), Section C (IEEE 2800-2022 Clause 5), and Section D (IEEE 2800.2022 Clause 6) of Appendix G shall apply to *IBR plants* in the DPP-2023-Cycle and beyond. For the DPP-2023-Cycle, Generating Facilities Replacements, and Surplus Interconnections, Interconnection Customers may request exceptions confined to these sections only if specific limitations or uncertainties of equipment or plant capabilities prevent implementation of these requirements. GIAs signed or amended with inverter changes on or after January 1, 2026, are not eligible for requirement exceptions. Further, the process for establishing exceptions for these requirements shall not apply beyond the DPP-2023-Cycle.

Interconnection Customers requesting exceptions shall submit documentation to the Transmission Provider outlining the specific IEEE 2800-2022 subclauses pertinent to the request along with information from the manufacturer regarding the nature of the issue conforming to or assessing conformance with requirements herein. The Transmission Provider will, in good faith, accept Original Equipment Manufacturer (OEM)-documented requirement exceptions and document these exceptions in Appendix C of this GIA.

If the performance or capability exception can be mitigated through equipment firmware upgrades still under development, the Interconnection Customer shall use commercially reasonable efforts to implement the firmware upgrade within sixty (60) calendar days of commercial availability of such firmware.

The DDR and PMU requirements in the Section F, Disturbance Monitoring and Reporting Requirements of Appendix G shall apply to *IBR plants* in the DPP-2023-Cycle and beyond.

Appendix H to GIA – Not Applicable
Interconnection Requirements for Provisional GIA

Provisional Agreement

This GIA is being provided in accordance with Section 11.5 of the Transmission Provider's GIP, which provides among other things, that an Interconnection Customer may request that Transmission Provider provide Interconnection Customer with a Provisional Generator Interconnection Agreement that limits the transfer of energy by Interconnection Customer commensurate with that allowed for Energy Resource Interconnection Service. Interconnection Customer requested Transmission Provider to provide a Provisional Generator Interconnection Agreement for limited operation at the discretion of Transmission Provider based upon the results of available studies (by Interconnection Customer and by Transmission Provider).

A Provisional Interconnection Study, the results of which are posted on the confidential portion of the Transmission Provider's internet website, was performed by Transmission Provider in order to confirm the facilities that are required for provisional Interconnection Service and to require them to be in place prior to commencement of service under the GIA.

Interconnection Customer represents that the Interconnection Customer facilities (including Network Upgrades, Interconnection Facilities, Distribution Upgrades, System Protection Upgrades and/or Generator Upgrades) that are necessary to commence provisional Interconnection Service and meet the requirements of the Electric Reliability Organization, or any applicable regional entity for the interconnection of a new generator are in place prior to the commencement of generation from the Generating Facility and will remain in place during the term of the service. The requisite Interconnection Studies were performed for the Generating Facility. Interconnection Customer shall meet any additional requirements (including reactive power requirements) pursuant to the results of applicable future Interconnection System Impact Studies. Until such time as the applicable Interconnection Studies and any identified facilities are completed, the output of the Generating Facility will operate within the output limit prescribed in a future, if applicable, operating guide.

The maximum permissible output of the Generating Facility under Appendix A will be updated by Transmission Provider on a quarterly basis, determined in accordance with Section 11.5 of the GIP, by finding the transfer limit of energy commensurate with the analysis for Energy Resource Interconnection Service ("ERIS"). This study shall be performed assuming the system topology represented by the base cases used to calculate Available Flowgate Capability, as described in Attachment C of the Tariff, with dispatch and optimization algorithms posted on the MISO internet site and operation above those limits will be deemed as unauthorized use of the Transmission System and subject to provisions in the Tariff surrounding that use.

Use of interim operating guide

Implementation of interim operating guide, if applicable, will constitute an interim solution that will permit Interconnection Customer to operate the Generating Facility under conditional Interconnection Service until planned Network Upgrades are constructed. Any interim operating

guide will be subject to the approval of Transmission Owner and Transmission Provider. Minimum requirements for an interim operating guide are as indicated below.

* Transmission Operator will have control of breaker(s) dedicated to the Generating Facility and will be able to trip the Interconnection Customer's Generating Facility
* Protection schemes must be tested and operative
* Interconnection Customer will provide continuous communication capability with the Generator Operator
* Interconnection Customer and the owner of the Existing Generating Facility will enter into an operating agreement or similar agreement which designates, among other things, the responsibilities and authorities of each of the parties and shall be subject to the acceptance of Transmission Provider and Transmission Owner.
* A termination date consistent with completion of construction of Network Upgrades will be included as part of all operating guides accepted by Transmission Owner and Transmission Provider.

Interconnection Customer assumes all risks and liabilities with respect to changes, which may impact the Generator Interconnection Agreement including, but not limited to, change in output limits and responsibilities for future Network Upgrade and cost responsibilities that have not yet been identified on the direct connect Transmission System as well as all affected Transmission, Distribution or Generation System(s) including non-Transmission Provider Systems. Such upgrades will be determined pursuant to the Tariff and Policies in effect at the time of the Interconnection Studies.

Appendix I to GIA – Not Applicable
Requirements Applicable to Surplus Interconnection Service

Where this GIA provides for Surplus Interconnection Service, Interconnection Customer acknowledges, agrees to, and will be required to operate under the following conditions:

1) The combined Real-Time Offers, including Energy and Operating Reserves, of the Generating Facility and the Existing Generating Facility with which Interconnection Customer has an executed Energy Displacement Agreement must be less than or equal to Interconnection Service limit (MW, MVAR, MVA output) provided in Exhibit I-1 (Monitoring and Consent Agreement) (hereinafter, "Interconnection Service limit"). In the event that the sum of the simultaneous energy output of the Surplus Interconnection Service Generating Facility and the Existing Generating Facility exceeds such Interconnection Service limit, MISO reserves the right to curtail and/or disconnect the Generating Facility immediately.

   In the event that the sum of the emergency and/or economic maximum offer limits of the Generating Facility and the Existing Generating Facility exceeds the Interconnection Service limit, MISO reserves the right to curtail and/or disconnect the Generating Facility immediately.
2) The total MW, MVAR, MVA output at the Point of Interconnection resulting from the combined output of the Generating Facility with Surplus Interconnection Service and the Existing Generating Facility with which Interconnection Customer has an executed Energy Displacement Agreement shall not at any time exceed the Interconnection Service limit.

3) The Existing Generating Facility with which Interconnection Customer has an executed Energy Displacement Agreement is not relieved of any applicable requirements under the RAR of the Tariff.

4) The Interconnection Customer shall submit to the Transmission Provider a report by the seventh Calendar Day of each month showing the prior month's output, by 15 minute increment, the combined real-time offers and cleared energy injection. The Existing Generating Facility and the Interconnection Customer shall cooperate consistent with other provisions in the Tariff to the extent necessary to ensure accuracy of the report. Transmission Provider shall provide a template for this report.

Exhibit I-1 (Completed Monitoring and Consent Agreement - Appendix 11 of the GIP)

Exhibit I-2 (Completed Energy Displacement Agreement - Appendix 12 of the GIP)

Document Content(s)

Transmittal Letter - E0014 GIA.pdf.....1
Tab A_E0014 GIA _Public.pdf.....5
Tab B_Redlined E0014 GIA to pro forma_Public.pdf.....161
Tab C_ Protective Agreement.pdf.....325
FERC GENERATED TARIFF FILING.PDF.....333